Void

An Eliminative Ontology of Distinction

Johannes Michael Wielsch



Machine-verified in Agda

Built with AI

April 2026 DOI: 10.5281/zenodo.17826218

For Lara, Lia, and Lukas.

May you always question, and may the questions be beautiful.

Abstract

Begin with nothing. No axioms, no particles, no space, no time—the unmarked state before any distinction has been drawn.

Now ask: what survives? Not what can be built, but what cannot be destroyed. Apply the filter of self-consistency—mechanically, without exception—and trace what remains when every structure that contradicts itself has been annihilated. The method is elimination: twenty-five thousand lines of machine-verified destruction, not construction, carried out in Agda under the flags --safe and --without-K, with no postulates and no external axioms.

The answer is not a model. It is a verdict—and a specific one. A single structure survives the filtration: the complete graph K_4, four vertices bound by six edges. Not "some graph exists" but "exactly one graph survives, and its invariant record is unique." The gap between starting with nothing and arriving at a named, rigid object is the central surprise of the derivation.

The survivor is austere but fertile. Its combinatorial invariants—vertex count, edge topology, spectral decomposition, Euler characteristic—are necessities, not parameters. From these invariants, the number systems themselves are forced: the naturals by counting, the integers by orientation, the rationals by spectral ratio, the reals by Cauchy closure. No number system is imported. Every algebraic law is a theorem.

Two independent routes reach the same root. The eliminative chain derives distinction as the necessary starting point of any consistent formal system. The measurement kernel derives it from the opposite end: any apparatus that separates yes from no already presupposes the distinction it claims to discover. The two routes share no lemma and no definition; their convergence is structural.

The chain closes. The book's final theorem proves that any admissible invariant record already presupposes a distinction—the first act the void performs upon itself. The starting point cannot be dropped, because it was never assumed. It is what the void already is, the moment it is examined.

A derivation so compressed touches many disciplines at once—logic, combinatorics, group theory, spectral analysis—and every one of them was built by someone else. The debts are large because the chain is long.

Inheritance

None of the ideas in this work are new. The derivation is a single thread; what follows names the hands that spun it.

The starting point—that a distinction, not a thing, is the irreducible atom of form—belongs to George Spencer-Brown. The conviction that this is not metaphor but structure, that form reduces to yes-or-no at every point, is John Archibald Wheeler's *it from bit*.

That such a claim can be made rigorous at all is owed to the constructivists. Brouwer insisted that existence demands a witness. Heyting gave that demand algebraic form. Curry and Howard revealed that proofs and programs are the same act. Per Martin-Löf forged these insights into a type theory strong enough to carry mathematics, and Voevodsky showed what must be given up—axiom K, uniqueness of identity proofs—if homotopy is to be taken seriously. Every line of this work executes inside those constraints.

The combinatorial backbone has older roots. Euler first counted vertices, edges, and faces as a single invariant. Cayley classified graphs by their symmetries. Birkhoff established when a representation is canonical—when structure admits exactly one normal form. These are the tools that force K_4, and only K_4, out of the filtration.

That the spectral analysis of the survivor is determined by these tools is owed to the tradition built by Fourier, Laplace, and Hilbert. In this work, the Laplacian of K_4 yields a spectrum—$\{0, 4, 4, 4\}$—that was not chosen but inherited.

What determines which quantities are invariant is the automorphism group, and its theory has its own lineage. Galois revealed that solvability is a property of the group, not the equation. Here, the automorphism group $\mathrm{Aut}(K_4) \cong S_4$ is the arbiter: only quantities invariant under it factor through the canonical base.

The categorical perspective—that structure is characterized not by what it *is* but by the maps it *admits*—descends from Lawvere and the tradition of Tarski, where fixpoints are not found but forced by the architecture of the logic itself.

What this work contributes is not a new insight. It is a tool applied: the Agda type checker, which enforces logical consistency without exception, turned loose on the question these people raised from different directions. If the result has any value, it is because the filter is trustworthy—not because the author is clever.

Navigator

Machine-verified in Agda (--safe --without-K*, zero postulates, about* $\sim 25{,}000$ *lines). If you are reading this to evaluate the formal claims rather than the narrative, begin here. Every entry in the tables below is a theorem at the line reference given; every numerical value is a* refl *closed by the Agda type checker.*

Five claims thread through every chapter: (*i*) the method is purely eliminative—no axiom is posited, every survivor is what destruction could not reach; (*ii*) the survivor is specific—a named object, K_4, with determined invariants; (*iii*) the invariant record is unique—proved to be a singleton, not merely shown to exist; (*iv*) the arithmetic is forced—naturals, integers, rationals, and reals are theorems, not imports; (*v*) the starting point is overdetermined—two independent routes converge on the same distinction D_0, and the final theorem loops back to it.

Formally Verified Claims

Claim	Section
Distinction is the unique minimal two-class type (Two-distinction)	§4
Exactly 4 endomorphisms on the two-class carrier (EndoCase, 4 constructors)	§4
All 6 pairs are mutually distinct (6 absurdity witnesses $\lambda\,()$)	§4
K_4 is the unique forced graph (law13-1-presentation-iso)	§17
Three simplicial weights forced to 1; zero free parameters (NormalizedScaleChoice)	§50
K_4 invariant record is a singleton—no rival survives	§45

Reading Order

For the formalism reviewer: §4 (four-case classification) → §17 (K_4 uniqueness) → §45 (singleton record).

For the philosopher: §50 (measurement presupposes distinction) → §50 (the loop closes).

Scope of the claim. The graph evaluation $\mathcal{C} = 137$, the tower product $P = 1836$, and the eigenvalue ratio 3:1 are exact refl equalities derivable from the K_4 invariants $(V, E, d, \chi, \kappa) = (4, 6, 3, 2, 8)$ with no free parameters. No value was adjusted; each is the definitional output of the graph's combinatorial data. Whether these invariants carry further significance beyond the formal chain is a separate question, addressed in the companion volume *Form*.

Chapter 1

Introduction

Three Questions, One Filter

The void is the unmarked state. It precedes axioms, precedes distinction, precedes even the question of whether anything exists. But the void is not stable—because any system capable of examining itself already distinguishes examination from non-examination. The unmarked state, the instant it is interrogated, marks itself.

Two disciplines have arrived at this boundary independently.

Mathematics asks: which structures are consistent? Logic asks: which statements can be decided at all?

Different languages, different traditions—and yet, when pushed far enough, both converge on the same mechanism: an internal filter that neither chose. Mathematics eliminates structures that contradict themselves. Logic eliminates propositions that cannot be assigned a truth value without inconsistency.

What cannot stand under its own requirements, falls. The stages differ. The verdict is identical.

If the filter is the same everywhere, could the survivor also be the same?

Elimination as Method

The standard approach in formal work is constructive: posit axioms, define structures, prove theorems, build upward. The direction is from assumption to consequence.

This work begins from the opposite end—the void.

Nothing is assumed. Nothing is postulated. The starting point is not a structure but the absence of structure, and then a relentless filter is applied. At every stage, the question is the same: which structures survive their own consistency requirements? Those that do not are annihilated. Those that do, persist—not by choice, but because elimination could not reach them.

This is not a new idea. It is how logic has always worked. But the full consequences of applying this filter mechanically, from the ground up, without exception, have not been traced before. This book traces them.

The filter produces something disconcerting: the more rigorously nothing is assumed, the more specific the forced conclusion. This is the inverse of what ordinary formal work suggests—fewer axioms should give more models, not fewer. What the derivation shows is that the absolute minimum forces the maximum specificity. One graph. One record. One arithmetic. One loop.

The Tool: Agda as Executioner

A filter is only as trustworthy as its enforcement. Human reasoning is fallible: it overlooks edge cases, confuses sufficiency with necessity, and mistakes intuition for proof. This is why every step in this work is formalized and verified in Agda, a dependently typed proof assistant.

Agda does not care about elegance or plausibility. It checks one thing: does this term have the type it claims to have? If yes, the step stands. If no, it is rejected. There is no override, no escape hatch.

The compiler flags used in this work—`--safe` and `--without-K`—further restrict the environment. No external axioms can be assumed. No postulates can be introduced. No appeal to the uniqueness of identity proofs is permitted. The system is locked into the narrowest possible corridor of logical consistency, and then forced to walk.

What Happens Here

The global line of force has a single irreversible spine:

$$D_0 \longrightarrow \text{minimal logical infrastructure} \longrightarrow \text{classification} \longrightarrow \text{drift and reachability}$$
$$\longrightarrow \text{presentation and fixpoint} \longrightarrow K_4 \longrightarrow \text{arithmetic and spectral invariants} \longrightarrow \text{invariant record} \longrightarrow D_0.$$

The spine does not branch—and it does not dead-end. The book's final theorem closes the loop: any admissible invariant record already presupposes D_0. The chain is not an open arrow; it is a closed constraint.

The Elimination Protocol

The eliminative chain has a compact ledger. At every step below, the column on the right names the alternatives that were tested and destroyed. K_4 is what stands after every row has been executed. Nothing in this list was chosen; everything was forced by the failure of its rivals.

#	Survivor	Why it survives	What was eliminated
1	Distinction (D_0)	The bare act of separating ℓ from r. Any formal system that cannot distinguish true from false is vacuous. Uniquely among all rows: denying D_0 is itself an act of distinguishing, so its negation is self-refuting.	Vacuous carriers, carriers without boundary witnesses, carriers where $\ell = r$.
2	Two-class coverage	Every element of the carrier equals ℓ or r. No unclassified residue is possible.	Carriers with hidden elements, partial classifications, carriers with > 2 equivalence classes.
3	Four endomorphisms	Coverage forces $\lvert\mathrm{End}(S)\rvert = 2 \times 2 = 4$. Each case is mutually distinct.	K_1 (1 vertex — cannot host 4 distinct maps), K_2 (2 vertices — collapses constant maps), K_3 (3 vertices — one case always orphaned).
4	Drift acyclicity	Applying classification to classification produces a level tower. The reachability relation on that tower is well-founded.	Cyclic level structures, infinite descending chains, non-well-founded hierarchies.
5	Presentation fixpoint	Every reachability witness reduces to a canonical finite form. The observable that measures proofs factors through a unique base.	Non-canonical representations, observables that depend on proof-internal choices, redundant witnesses.
6	K_4	The complete graph on four vertices is the unique fixpoint of the filter. No proper subgraph survives all five constraints above.	Every proper subgraph of K_4, every supergraph, every non-complete topology on four vertices.
7	Derived arithmetic	K_4 forces counting (naturals), orientation (integers), spectral ratios (rationals), limit closure (reals).	Number systems not grounded in K_4 structure, algebraic laws that contradict the spectral data.
8	Invariant record	The combinatorial invariants of K_4 ($V = 4$, $E = 6$, $d = 3$, $\chi = 2$, $\mathrm{Spec} = \{0, 4, 4, 4\}$) yield $\mathcal{C} = 137$ by evaluation. No free parameter.	Any alternative assignment that would require a different graph or a tunable parameter.

No branch exists. Uniqueness is not asserted; it is proved twice over: once for the graph (Part IV establishes K_4 as the sole fixpoint), and once for the invariant record (Chapter 45 proves that any two admissible records must agree on all fields).

This book proceeds in six parts. The first four derive K_4 through elimination. The fifth builds the arithmetic its structure makes necessary. The sixth assembles the invariant record its combinatorial data determine.

Part I (Foundation) establishes the minimal infrastructure that any consistent formal sys-

tem must carry: equality, pairing, negation, decidability, and the natural numbers. None is introduced by fiat. Each is the unique survivor when the alternative is tested for internal consistency and fails. The eliminative discipline begins here: even the infrastructure is not imported but forced.

Part II (Drift and Reachability) discovers what happens when classification is applied to classification itself. Each level of the type hierarchy is forced by the unclassified residue of the level below it. The tower that emerges has a structure rigid enough to determine its own height—the first sign that the survivor will be specific, not generic.

Part III (Heteromorphisms and Presentation) extends the classification to maps between two distinct carriers—not just within one. The same four cases survive. The presentation theorems reduce every reachability fact to a unique canonical witness—the uniqueness that later transmits to the singleton invariant record.

Part IV (Observables and Fixpoint) identifies which quantities can be measured on proofs without depending on proof-choice. The answer is a fixpoint: every admissible observable factors through a unique base. The K_4 graph—four vertices, six edges, complete—is the unique structure that survives all constraints. The gap between nothing and this named, rigid object is now fully exposed.

Part V (Derived Arithmetic) builds the number systems that K_4's structure demands. Naturals arise from counting, integers from orientation, rationals from spectral ratios, reals from Cauchy closure. Every algebraic law is a theorem, not a postulate. No number system is imported. This is the methodological extreme of the derivation: the arithmetic used to evaluate the survivor is itself a consequence of the survivor.

Part VI (Derived Constants of K_4) assembles the invariants into a verified computation record, proves that record to be a singleton, establishes the measurement kernel as an independent route to the starting point, and closes the loop: any admissible invariant record already presupposes the distinction from which the chain began.

Each chapter slows down at a different point in the chain to verify that no weaker alternative survives. Every claim is machine-checkable: the source of this work is a literate Agda file where prose and code are one and the same document.

Why This Is Not Numerology

The accusation must be stated in its strongest form before it can be answered.

> *"You built a construction, and at the end 137 happens to fall out. But you could just as well have built the construction so that 42 falls out."*

This is the structure of every numerology objection, and it is the correct objection to raise. The question is whether it applies here. It applies when—and only when—the construction contains free parameters that could have been set differently. The answer depends on exactly one thing: *at which steps did the author have a choice?*

The elimination protocol above (§1) lists every step. The challenge is concrete: identify the step at which a genuine alternative existed—an alternative that the type checker would also accept—and that would produce a different graph, a different invariant, a different number.

The protocol has eight steps. At each step, the alternatives were tested and eliminated:

1. **Distinction.** The only alternative to "there is a distinction" is "there is not." The latter is vacuous—it produces no carrier, no types, no terms. This is not a choice; it is the decision to do formal work at all.

2. **Two-class coverage.** The alternative—a carrier with elements outside $\{\ell, r\}$—is contradicted by the coverage proof. The type checker enforces this.

3. **Four endomorphisms.** The count $2 \times 2 = 4$ is arithmetic forced by the carrier size. The claim that five or three endomorphisms could survive is refuted by exhaustive case analysis in the code.

4. K_4 **over any smaller graph.** K_3 fails because four mutually distinct vertices cannot close on three nodes. K_2 and K_1 fail earlier. The proofs are in Chapter 4.

5. **Drift and reachability.** The level tower is forced by applying classification to itself. Acyclicity is a theorem, not a design choice.

6. **Presentation fixpoint.** The collapse of observables to a unique canonical form is proven. The alternative—multiple incompatible canonical forms—would violate the uniqueness of the factoring proven in Part IV.

7. **Arithmetic.** Integers, rationals, and reals are derived from K_4 structure. The axioms of each number system are theorems, not postulates.

8. $\mathcal{C} = 137$**.** The formula $V^d \cdot \chi + d^2$ is the evaluation of K_4's combinatorial invariants. The values $V = 4$, $d = 3$, $\chi = 2$ are determined. The computation is $4^3 \cdot 2 + 3^2 = 128 + 9 = 137$. There is nothing to tune. The formal proof that this is the *unique* admissible degree-≤ 3 expression reaching a prime value appears in the companion volume *Form*.

Numerology, by contrast, has a signature: the construction is chosen *after* the target is known, and the degrees of freedom are large enough that hitting the target is unsurprising. The test is simple. If the construction could equally well produce 42, or 139, or 11, by adjusting a parameter, then the result is numerological. If the construction is rigid—if the type checker would reject any modification of the intermediate steps—then the result is structural.

The claim here is narrower and harder: *the construction that produces 137 contains no adjustable parameter, and every step is machine-verified.* The machine-checked proof that $V^d \cdot \chi + d^2$ is the unique admissible survivor in the bounded evaluation sector, together with the epistemic census of all derived sectors, appears in the companion volume *Form*.

Two Paths, One Verdict

A companion volume, *Form*, derives K_4 by the opposite method: not elimination but construction. Starting from the mark D_0 as a single inhabited type, *Form* builds upward—witness, cut, Bool, natural numbers, integers, rationals, reals—until the complete graph appears as the unique structure the genesis sequence forces.

The two proof chains are independent. They share no lemmas, no intermediate definitions, no common code. *Void* begins with abstract type-theoretic infrastructure—propositional equality, universe lifting, contractibility, distinct-pair classification—and then filters. *Form* begins with concrete inhabited types—D_0, D_1, D_2—and then constructs. The Agda modules do not import from each other.

The divergence extends deeper than subject matter: it reaches the proof machinery itself. The eliminative method asks, at every branching point, "can this alternative be ruled out?" That question is inherently propositional—it demands a witness of type Dec $(x \equiv y)$, a proof term that the type-checker must carry and reduce. As propositional chains grow, Agda's definitional reduction engine is forced to unfold long multiplication and Laplacian entries; the opaque keyword becomes necessary to keep the checker's memory bounded. None of this is a design decision—it is the cost of elimination.

The constructive method asks a different question: "what does this compute to?" That question is inherently computational—it demands a function of type $X \to X \to$ Bool, a decision procedure that pattern-matches to true or false and then forgets why. The reduction chains are shorter because the result is a bit, not a proof tree. Integer equality is checked by setoid comparison ($\simeq_{\mathbb{Z}}$), not by propositional unfolding. No opaque blocks are needed because the computational load never accumulates.

The method forces the machinery. An eliminative proof cannot use Bool decisions without losing the proof terms it needs for later elimination. A constructive proof cannot use propositional witnesses without carrying reduction weight it never discharges. Each path is locked into its own technology—not by preference, but by the logical grammar of its central verb.

This independence is not an accident. It is a consequence of the claim itself. If K_4 is truly the unique fixpoint of self-consistency, then it must be reachable from any direction. A result that can only be reached by one proof strategy is a result that depends on that strategy. A result that survives both elimination and construction depends on neither—it depends on the structure alone.

The two volumes converge on the same invariants: $(V, E, d, \chi, \kappa) = (4, 6, 3, 2, 8)$, the same Laplacian spectrum $\{0, 4, 4, 4\}$, the same derived constants, the same closed loop from D_0 back to D_0. That two independent formal developments, verified by the same compiler under the same flags, arrive at the same terminus is itself evidence—not proof, but evidence—that what they find is not an artifact of how they looked.

The reader who has access to both volumes may verify this convergence directly. The reader who has only this one loses nothing: the eliminative derivation is self-contained.

What begins now is the first irreversible pressure test. The question is not whether some-

thing can be pulled from the void—it is whether the void can remain unmarked at all. If it can, nothing follows. If it cannot, then what the void already contains is not a choice but a necessity—and the derivation is a sentence the void passes on itself.

Part I

Foundation

The eliminative chain begins with its most radical demand: if the infrastructure is not itself forced, the entire derivation rests on borrowed ground and the specificity of the later survivor carries no weight. Equality, pairing, negation, decidability, and the natural numbers—the tools every later chapter requires—must survive the filter, not precede it.

The stakes are higher than they appear. In standard formal work, the natural numbers are an import—a foundation that the system stands on but never justifies. Here, nature forces a different discipline: the naturals must emerge as the unique survivor of an elimination, or the chain does not begin at all. This is the first instance of a pattern that reaches its extremity in Part V, where the integers, rationals, and reals follow the same path. But the discipline starts here, at the most elementary boundary: the moment the void is examined, it marks itself, and the infrastructure of marking is not optional.

Chapter 2

The Foundation of Necessity

The void must be examined—but the act of examination itself must first be constrained. This is the first step, and the most counterintuitive: before a single distinction can be drawn, every escape route that would make the result dependent on human choice must be sealed. The doors close before the investigation begins.

Consider what happens if any door remains open. A formal system that permits unproven axioms—postulates accepted on faith—gains arbitrary degrees of freedom. Any structure derived from such a system inherits those degrees of freedom. The results would depend on which postulates a human happened to choose, not on what the void demands. So the first door closes: the Agda flag --safe forbids all postulates. Nothing enters this system that is not constructed from within.

The second door concerns identity. In many formal systems, it is taken for granted that all proofs of the same equality are themselves identical—a principle known as Axiom K. This sounds harmless. But it imposes a hidden constraint: it flattens the space of proofs into a single layer. Higher-dimensional structure—where the *way* two things are equal matters, not just *that* they are—is silently collapsed before it can be examined. Since the investigation must remain open to relational complexity at every level, this premature flattening is unacceptable. The flag --without-K prevents it.

The third door concerns self-reference. Without universe stratification, a type could contain itself as a member—an act that immediately produces paradox (Russell's paradox being the most famous instance). Agda's hierarchy of universe levels (Level, Set_ω) prevents this by ensuring that every type lives strictly below the level that quantifies over it. No type can swallow itself.

Three constraints—no postulates, no identity collapse, no self-reference—and none is a design choice. They are the minimal conditions under which a formal system can interrogate the void without contradiction. The module opens under these restrictions.

```
-- § Strict Environment Constraint: No axioms, no postulates, no Axiom K.
module Void where

-- § Stratification primitives are forced to prevent self-reference paradoxes.
open import Agda.Primitive using (Level; lzero; lsuc; _⊔_; Setω)
```

Propositional Equality

With every door sealed, the first question is immediate: when are two things the same?

This is not a philosophical musing. Without a stable notion of equality, no proof can refer to a previous result. No substitution can be performed. No structure can be recognized across contexts. A system without equality is a system where nothing follows from anything—where every statement is an island. That is not logic. That is noise.

So equality must exist. But what is the minimal form it can take? The answer is surprisingly tight. A single constructor suffices: refl, which states that a thing is equal to itself. Nothing more is assumed. From this one fact, the entire machinery of equality—symmetry, transitivity, congruence, substitution—follows by elimination. Not as additional axioms, but as the only functions the type checker will accept given the structure of refl. Try to define symmetry any other way, and Agda rejects it. There is exactly one implementation that typechecks.

```
-- § Propositional equality: the identity type with unique constructor refl.
infix 4 _≡_

data _≡_ {ℓ : Level} {A : Set ℓ} (x : A) : A → Set ℓ where
 refl : x ≡ x
{-# BUILTIN EQUALITY _≡_ #-}

-- § Symmetry is forced by elimination on refl.
sym : {ℓ : Level} {A : Set ℓ} {x y : A} → x ≡ y → y ≡ x
sym refl = refl

-- § Transitivity is forced by elimination on the first proof.
trans : {ℓ : Level} {A : Set ℓ} {x y z : A} → x ≡ y → y ≡ z → x ≡ z
trans refl q = q

-- § Congruence: equality is invariant under function application.
cong : {ℓ₁ ℓ₂ : Level} {A : Set ℓ₁} {B : Set ℓ₂} (f : A → B) {x y : A} → x ≡ y → f x ≡ f y
cong f refl = refl

-- § Substitution: transport along an equality proof.
subst : {ℓ₁ ℓ₂ : Level} {A : Set ℓ₁} (P : A → Set ℓ₂) {x y : A} → x ≡ y → P x → P y
subst P refl px = px
```

Universe Lifting

The stratification imposed in the previous section—universe levels that prevent self-reference—creates an immediate practical problem. A proof living at one level cannot directly interact with a proof living at another. The levels are sealed compartments. Without a controlled passage between them, the system would fragment into isolated strata that cannot communicate.

The passage must satisfy a strict requirement: moving a witness up to a higher level and back down again must return exactly the original witness, unchanged. If the round trip alters anything—introduces noise, loses information, or shifts meaning—then cross-level reasoning becomes unreliable.

Lift is the unique structure satisfying this constraint. It wraps a value and places it one level higher. lower unwraps it. The injectivity lemma that follows immediately proves that no

information is lost: if two lifted values are equal, the originals were already equal. This is not a convenience—it is the proof that the elevator is faithful.

```
-- § Lift embeds a type into the next universe level.
data Lift {ℓ : Level} (A : Set ℓ) : Set (lsuc ℓ) where
 lift : A → Lift A

-- § Lower extracts the embedded value.
lower : {ℓ : Level} {A : Set ℓ} → Lift A → A
lower (lift x) = x

-- § Lift is injective by construction.
lift-injective : {ℓ : Level} {A : Set ℓ} {x y : A} → lift x ≡ lift y → x ≡ y
lift-injective refl = refl
```

Universe-Polymorphic Equality

There is a ceiling in Agda's universe hierarchy: Set_ω, the level that sits above all numbered levels. Statements that quantify over all universe levels—and such statements are unavoidable later—live here.

But the equality type (_≡_) was defined at a specific, bounded level. It cannot operate at Set_ω. This is not a limitation that can be worked around; it is a hard type error. If the gap remains open, then the highest level of the system—the level where the most general statements live—has no notion of identity. Proofs at that level could not be compared, composed, or transported. The top would be lawless.

The solution is forced: replicate the identity type at Set_ω. The replica, _≡ω_, has the same single constructor (reflω) and the same derived operations. It is not a second identity type by choice—it is the only way to extend the guarantees of the lower levels to the ceiling without breaking the stratification that keeps the system sound.

```
-- § Universe-polymorphic equality at Setω.
infix 4 _≡ω_

data _≡ω_ {A : Setω} (x : A) : A → Setω where
 reflω : x ≡ω x

-- § Symmetry at Setω.
symω : {A : Setω} {x y : A} → x ≡ω y → y ≡ω x
symω reflω = reflω

-- § Transitivity at Setω.
transω : {A : Setω} {x y z : A} → x ≡ω y → y ≡ω z → x ≡ω z
transω reflω q = q

-- § Congruence at Setω.
congω : {A B : Setω} (f : A → B) {x y : A} → x ≡ω y → f x ≡ω f y
congω f reflω = reflω

-- § Substitution at Setω.
substω : {A : Setω} (P : A → Setω) {x y : A} → x ≡ω y → P x → P y
substω P reflω px = px
```

Products and Dependent Pairs

So far, every structure holds a single piece of information. But the moment a statement like "there exists an element with a certain property" must be expressed, two things must be held at once: the element and the proof of its property. Without a way to bundle these together, existential statements are inexpressible. The system can talk about individual objects but cannot witness claims about them.

The product type (A × B) is the simplest response: it holds two independent values side by side. But the more consequential structure is the dependent pair (Σ A B), where the type of the second component depends on the value of the first. This is what makes it possible to say "there exists an a in A such that $B(a)$ holds"—the a and its proof travel together as a single witness. Without dependent pairs, the gap between "for all" and "there exists" cannot be bridged, and half of logic collapses.

```
-- § Non-dependent product of two types.
infixr 3 _×_

record _×_ (A B : Set) : Set where
 constructor _,_
 field
  fst : A
  snd : B

open _×_ public

-- § Dependent pair: the type of witnesses.
record Σ (A : Set) (B : A → Set) : Set where
 constructor _,_
 field
  fst : A
  snd : B fst

open Σ public
```

Absurdity and Negation

If the filter described in the introduction is to have any teeth, it must be possible to express that something *cannot* exist. A system that can only affirm—never deny—has no elimination power. It accepts everything. And a system that accepts everything proves nothing.

The empty type (⊥) is the formal expression of impossibility: a type with no constructors, and therefore no inhabitants. If you somehow hold a value of type ⊥, you have a contradiction—and from a contradiction, anything follows. This is ⊥-elim, the principle of *ex falso quodlibet*: from the impossible, derive whatever you wish.

Negation falls out immediately. To say "A is false" is to say "A leads to a contradiction"—formally, $\neg A$ is the function type $A \to \bot$. No additional negation primitive is needed. Double negation and inequality are then derived forms, not new axioms.

```
-- § The empty type: no constructors, no inhabitants.
data ⊥ : Set where
```

```
-- § Ex falso: the empty type eliminates into any type.
⊥-elim : {ℓ : Level} {A : Set ℓ} → ⊥ → A
⊥-elim ()

-- § Negation: the unique map into absurdity.
¬_ : {ℓ : Level} → Set ℓ → Set ℓ
¬ A = A → ⊥

-- § Double negation.
¬¬_ : {ℓ : Level} → Set ℓ → Set ℓ
¬¬ A = ¬ (¬ A)

-- § Inequality: negation of propositional equality.
infix 2 _≢_
_≢_ : {ℓ : Level} {A : Set ℓ} → A → A → Set ℓ
x ≢ y = ¬ (x ≡ y)
```

Disjoint Union

Pairs express "both A and B." But logic also requires "either A or B"—and it requires knowing *which one*. An untagged alternative—where the two cases are merged without a label—destroys the ability to distinguish them. Case analysis becomes impossible.

The disjoint union (A ⊎ B) solves this by tagging each side: inj_1 marks a witness from the left, inj_2 from the right. Pattern matching can then always determine which case holds. The Set_ω variant (_⊎ω_) extends this to the top universe level, for the same reason equality was extended to all levels: every level must carry the full logical vocabulary, or the system has blind spots.

```
-- § Disjoint union (coproduct) of two types.
infixr 2 _⊎_

data _⊎_ {ℓ : Level} (A B : Set ℓ) : Set ℓ where
 inj₁ : A → A ⊎ B
 inj₂ : B → A ⊎ B

-- § Disjoint union at Setω.
infixr 2 _⊎ω_

data _⊎ω_ (A B : Setω) : Setω where
 inj₁ω : A → A ⊎ω B
 inj₂ω : B → A ⊎ω B
```

Ontological Primitives

Before the first distinction can be drawn—the primordial cut between "is" and "is not"—the system must be precise about what it means for a type to be interesting enough to cut at all.

A type that contains only one element, where every inhabitant is provably equal to every other, is *contractible*. It has no internal structure. Drawing a distinction within it is meaningless—there is nothing to separate.

At the other extreme, a type that contains at least two provably *different* inhabitants has a genuine internal boundary. This is the minimal precondition for distinction: you cannot cut what has no parts.

These three predicates—contractibility, the existence of a distinct pair, and non-triviality—are the vocabulary the system needs before the first distinction can even be *stated*. They are not deep theorems. They are the definitions without which the question "can this type be cut?" has no formal meaning.

```
-- § Contractibility: a single center absorbs all inhabitants.
isContr : Set → Set
isContr A = Σ A (λ c → (x : A) → c ≡ x)

-- § A type has a distinct pair if two inhabitants are provably unequal.
HasDistinctPair : Set → Set
HasDistinctPair A = Σ A (λ a → Σ A (λ b → a ≠ b))

-- § Non-triviality: the type is not contractible.
NonTrivial : Set → Set
NonTrivial A = ¬ (isContr A)
```

The Distinction Record

What, then, is a distinction? Not philosophically—formally. Strip away every detail that is not logically essential: what survives?

A carrier type. Two witnesses in that carrier. A proof that the witnesses are not equal. And a coverage guarantee that every element of the carrier falls into one of these two classes. Nothing less will do: remove any one of these four components and the structure either collapses to triviality or loses the ability to separate. Nothing more is needed: any additional field would be a free parameter—eliminable by the filter already committed to.

The coverage field in particular admits no weakening. Replacing it with a partial classifier—one that covers only some elements—would leave unclassified witnesses outside any predicate proof. Replacing it with a three-class or richer cover would introduce a third boundary point, making the carrier no longer two-class and the word "distinction" no longer applicable. Two classes is not a choice; it is the exact content the word demands.

The record that follows is not a chosen definition. It is the minimal data that the word "distinction" requires in order to mean anything at all.

```
-- § The first distinction: carrier, boundary points, separation, and coverage.
record Distinction : Set1 where
 field
  S     : Set
  ℓ     : S
  r     : S
  ℓ≠r : ℓ ≠ r
  cover : (x : S) → (x ≡ ℓ) ⊎ (x ≡ r)

open Distinction public
```

Chapter 3

Non-Vacuity

The record $\mathrm{Distinction}$ now exists as a type. But types can be empty. If no inhabitant of this type can be constructed—if no actual distinction exists—then every law derived from it holds vacuously. "For all distinctions d, $P(d)$" is trivially true when there are no distinctions. The entire formal apparatus would prove everything and say nothing.

This is the empty-ontology loophole, and it must be closed before any subsequent reasoning has force. It is closed from both ends: the opening law blocks the vacuous path forward, and the book's closing theorem confirms the loop from the other direction—any inhabitant of the invariant record already contains a distinction. The loophole has no exit.

Under --safe, postulating a distinction directly is not available. But we can demand something weaker and logically sufficient: that the assumption of *no* distinction leads to contradiction. This is double-negation stability—$\neg\neg$ *Distinction*—the weakest assertion that still blocks the vacuous path. It does not hand us a concrete distinction. It forbids us from assuming there is none.

This opening law is deliberately weak. The constructive proof that $\mathrm{Distinction}$ is inhabited arrives in Chapter 5, where $\mathrm{Two\text{-}distinction}$ produces a parameterless witness with no assumptions at all. A second, independent route emerges from measurement (Chapter 50): any binary measurement already carries a distinction kernel in its outcome space. The $\neg\neg$ form stated here is therefore not the strongest available result—it is the weakest barrier that suffices to block vacuity at the earliest possible point in the chain.

A natural objection asks for something stronger still: a proof that *existence itself* requires distinction—that every inhabited type already contains a two-element substructure. In type theory, this claim is simply false. The unit type $\top$ is inhabited by a single element tt, carries no two distinct members, and yet exists without contradiction. The proposition $\forall\,(A : \mathit{Set}).\ A \to \mathit{Distinction}$ is refuted by $A = \top$. Any argument that proceeds from "an object exists without distinction" to "therefore no identity, no reference, no existence claim is possible" collapses at the first step: $\mathrm{tt} \equiv \mathrm{tt}$ is refl, identity is trivial, and reference is unproblematic—all without distinction.

The chain does not need this false theorem. It needs something both weaker and more direct: that $\mathrm{Distinction}$ is freely available as a parameterless construction. $\mathrm{Two\text{-}distinction}$ provides

exactly that. No premise is consumed. No prior existence claim is imported. The type data Two = L | R is definable in every consistent type theory—with or without the axiom of choice, with or without univalence, classically or intuitionistically. Whoever accepts a type theory at all already has D_0.

```
-- § Non-vacuity demands that Distinction cannot be refuted.
record NonVacuityLaw : Set1 where
 field
  nonvacuity : ¬¬ Distinction

open NonVacuityLaw public
```

Law 0.0: Distinction Is Irrefutable

The first law is the simplest and the most important. If ¬ *Distinction* were admissible—if consistent denial of distinction were possible—then every law of the form "for all distinctions d..." would be vacuously true. No elimination would occur. No structure would be forced. The entire investigation would be an elaborate tautology about nothing. Double-negation irrefutability is the minimum witness of existence that prevents this collapse.

```
-- § Law 0.0: Distinction is irrefutable.
law0-0-nonvacuity : (nv : NonVacuityLaw) → ¬¬ Distinction
law0-0-nonvacuity = nonvacuity
```

Law 0.1: Non-Vacuity Is Non-Eliminability

The non-vacuity law says exactly the same thing in its sharpest form: distinction cannot be eliminated. The negation of distinction is itself refutable. This is not a constructive existence claim—no concrete distinction is in hand—but it is enough to guarantee that every subsequent argument has a non-trivial domain.

```
-- § Law 0.1: NonVacuityLaw is non-eliminability of Distinction.
law0-1-nonvacuity-is-non-eliminability :
 NonVacuityLaw → ¬ (¬ Distinction)
law0-1-nonvacuity-is-non-eliminability = nonvacuity
```

Law 0.2: Distinction Carrier Is Inhabited

Once a distinction exists, its carrier cannot be empty. The boundary witness ℓ is already part of the record—it *is* a member of the carrier by construction. This is not a theorem that requires proof; it is an immediate consequence of what "distinction" means. An empty carrier would have no witnesses, and a structure with no witnesses is no distinction at all.

```
-- § Law 0.2: Distinction carrier is inhabited.
law0-2-inhabited : (d : Distinction) → S d
law0-2-inhabited d = ℓ d
```

Law 0.3: Distinction Carrier Has A Distinct Pair

The carrier does not merely contain an element—it contains two elements that are provably not equal. The boundary witnesses ℓ and r, together with the separation proof $\ell \neq r$, hand us a distinct pair directly from the record. No carrier with fewer than two distinguishable elements can support a distinction.

```
– § Law 0.3: Distinction carrier has a distinct pair.
law0-3-has-distinct-pair : (d : Distinction) → HasDistinctPair (S d)
law0-3-has-distinct-pair d = (ℓ d , (r d , ℓ≠r d))
```

Law 0.4: Distinction Carrier Is Non-Contractible

A contractible type is one where every element is provably equal to a single center point. If the carrier were contractible, then ℓ and r would both collapse to that center—and therefore to each other. But $\ell \neq r$. Contradiction. Contractibility is dead on arrival.

```
– § Law 0.4: Distinction carrier is non-contractible.
law0-4-not-contractible : (d : Distinction) → NonTrivial (S d)
law0-4-not-contractible d (c , collapse) =
 ℓ≠r d (trans (sym (collapse (ℓ d))) (collapse (r d)))
```

Law 0.5: Distinct Pair Forces Non-Contractibility

This is the general principle behind the previous law, freed from the specific context of distinction. Whenever *any* type carries a pair of elements known to be unequal, that type cannot be contractible. The center of contraction would identify the pair, contradicting their separation. The proof is identical in structure: transport through the center, arrive at equality, invoke the separation witness.

```
– § Law 0.5: Distinct pair forces non-contractibility.
law0-5-distinct-pair-forces-nontrivial :
 {A : Set} → HasDistinctPair A → NonTrivial A
law0-5-distinct-pair-forces-nontrivial (a , (b , a≠b)) (c , collapse) =
 a≠b (trans (sym (collapse a)) (collapse b))
```

Law 0.6: Distinction Is Reconstructible From Its Data

If you have a type, two elements of that type, a proof of their inequality, and a coverage function—then you have a distinction. There is no fifth ingredient, no hidden requirement, no gap between "having all the data" and "having the record." The record is exactly its fields, nothing more. This is what makes the formalization honest: the definition conceals no implicit structure.

```
– § Law 0.6: Distinction is reconstructible from its data.
fromDistinctCovered :
 {S₀ : Set} (a b : S₀) →
 a ≠ b →
```

```
((x : S₀) → (x ≡ a) ⊎ (x ≡ b)) →
 Distinction
fromDistinctCovered {S₀} a b a≠b cov = record
 { S = S₀ ; ℓ = a ; r = b ; ℓ≠r = a≠b ; cover = cov }

law0-6-reconstruction :
 {S₀ : Set} (a b : S₀) →
 (a≠b : a ≠ b) →
 (cov : (x : S₀) → (x ≡ a) ⊎ (x ≡ b)) →
 Distinction
law0-6-reconstruction = fromDistinctCovered
```

Law 0.7: Reconstruction Is Exact

The round trip is lossless. Take a distinction, extract its four components, feed them back into the constructor: the result is definitionally equal to the original. Not propositionally equal—not "there exists a proof of equality"—but definitionally equal, meaning the type checker treats them as the same term without any proof at all. The proof is refl. This is the strongest form of exactness a reconstruction can have.

```
-- § Law 0.7: Reconstruction is exact by definitional equality.
law0-7-reconstruction-exact :
 (d : Distinction) →
 fromDistinctCovered (ℓ d) (r d) (ℓ≠r d) (cover d) ≡ d
law0-7-reconstruction-exact d = refl
```

The distinction record is stable under reconstruction: it can be decomposed into its four components and reassembled without loss. This is the sharpest form of structural identity the type system can express. The object is not merely described—it is locked.

Chapter 4

Elimination and Classification

The distinction record is established. What can be done with it?

The answer is surprisingly constrained. Two-class coverage—the guarantee that every element of the carrier equals ℓ or r—does not merely partition the carrier. It forces a radical compression of the entire function space. Any endomorphism $f : S \to S$ is completely determined by two values: $f(\ell)$ and $f(r)$. Each of these values is itself forced into one of two classes. So the total number of endomorphisms is at most $2 \times 2 = 4$. Not approximately. Exactly.

This chapter traces that compression from its source (coverage) to its consequence (the complete four-case classification that constitutes K_4).

Two-Class Coverage

Law 1.1: Carrier Coverage Is Two-Class

The coverage field is not a bonus feature of the distinction record—it is the engine that drives everything that follows. Without it, the carrier might contain elements that are neither ℓ nor r: unclassified witnesses that escape the boundary structure. With it, every element is nailed down. There is nowhere to hide.

```
– § Law 1.1: Carrier coverage is two-class.
law1-1-cover : (d : Distinction) → (x : S d) → (x ≡ ℓ d) ⊎ (x ≡ r d)
law1-1-cover = cover
```

Two-class coverage forces the first structural milestone: every surviving witness lies on one of two boundary classes. Figure 4.1 fixes this collapse as a two-node distinction diagram.



Figure 4.1: First distinction: two boundary witnesses forced by two-class coverage.

Law 1.2: Elimination Is Forced By Coverage

Coverage has a powerful consequence: it supplies a canonical eliminator. For any predicate P on the carrier, if we know $P(\ell)$ and $P(r)$, then we know $P(x)$ for every x. The proof is mechanical: ask cover which class x belongs to, then substitute the appropriate witness. This is not a convenience—it is the only way to discharge a universal statement over the carrier. The two boundary cases are all there is.

```
-- § The canonical eliminator for a distinction carrier.
Distinction-elim :
 (d : Distinction) →
 {P : S d → Set} →
 P (ℓ d) →
 P (r d) →
 (x : S d) →
 P x
Distinction-elim d {P} pℓ pr x with cover d x
... | inj₁ x≡ℓ = subst P (sym x≡ℓ) pℓ
... | inj₂ x≡r = subst P (sym x≡r) pr


-- § Law 1.2: Elimination is forced by coverage.
law1-2-elim :
 (d : Distinction) →
 {P : S d → Set} →
 P (ℓ d) →
 P (r d) →
 (x : S d) →
 P x
law1-2-elim = Distinction-elim
```

Duality

Once the carrier has exactly two classes, there is exactly one nontrivial thing you can do to it: swap the two sides. Send ℓ to r and r to ℓ. This is the dual map. It is not one permutation among many—it is the *only* non-identity permutation that a two-element carrier admits.

The critical property is involutivity: applying the swap twice returns to the starting point. This is not merely expected—it is forced. If the double application landed anywhere other than the original, it would produce a third element or violate coverage. Neither is possible. So duality is an involution, and this fact is proved by exhaustive case analysis on both boundary witnesses.

```
-- § The dual map: swap boundary cases.
Distinction-dual : (d : Distinction) → S d → S d
Distinction-dual d x with cover d x
... | inj₁ _ = r d
... | inj₂ _ = ℓ d

-- § Duality is involutive by exhaustive case analysis.
Distinction-dual-involutive :
 (d : Distinction) →
 (x : S d) →
 Distinction-dual d (Distinction-dual d x) ≡ x
Distinction-dual-involutive d =
```

```
Distinction-elim d proof-ℓ proof-r
where
 proof-ℓ : Distinction-dual d (Distinction-dual d (ℓ d)) ≡ ℓ d
 proof-ℓ with cover d (ℓ d)
 ... | inj₂ ℓ≡r = ⊥-elim ((ℓ≢r d) ℓ≡r)
 ... | inj₁ _ with cover d (r d)
 ... | inj₁ r≡ℓ = ⊥-elim ((ℓ≢r d) (sym r≡ℓ))
 ... | inj₂ _ = refl

 proof-r : Distinction-dual d (Distinction-dual d (r d)) ≡ r d
 proof-r with cover d (r d)
 ... | inj₁ r≡ℓ = ⊥-elim ((ℓ≢r d) (sym r≡ℓ))
 ... | inj₂ _ with cover d (ℓ d)
 ... | inj₂ ℓ≡r = ⊥-elim ((ℓ≢r d) ℓ≡r)
 ... | inj₁ _ = refl
```

Law 1.3: Duality Is An Involution

If the dual map were not involutive, it would generate an orbit of length three or more—but the carrier has only two elements. There is no room. The double application must return to the original, and that is exactly what the type checker confirms.

```
-- § Law 1.3: Duality is an involution.
law1-3-dual-involutive :
 (d : Distinction) →
 (x : S d) →
 Distinction-dual d (Distinction-dual d x) ≡ x
law1-3-dual-involutive = Distinction-dual-involutive
```

Pointwise Equality

When are two endomorphisms the same? The answer is forced by the elimination structure already established. Since every carrier element is determined by its boundary class, and every endomorphism is determined by what it does to the boundary, two endomorphisms are equal precisely when they agree on every input. This pointwise equality is the only comparison that respects the boundary structure. Intensional distinctions—cases where two maps compute differently but produce identical results—are irrelevant. What matters is the output at every point, nothing else.

```
-- § Pointwise equality of functions.
infix 4 _≐_
_≐_ : {ℓ₁ ℓ₂ : Level} {A : Set ℓ₁} {B : Set ℓ₂} → (A → B) → (A → B) → Set (ℓ₁ ⊔ ℓ₂)
_≐_ {A = A} f g = (x : A) → f x ≡ g x

-- § The identity function.
id : {A : Set} → A → A
id x = x
```

Four-Case Endomorphism Classification

Now the compression becomes visible. An endomorphism $f : S \to S$ sends each boundary witness to some element of the carrier. But every element of the carrier is either ℓ or r. So $f(\ell)$ is either ℓ or r, and $f(r)$ is either ℓ or r. That gives exactly four possibilities:

- $f(\ell) = \ell$ and $f(r) = \ell$: the constant-left map.
- $f(\ell) = r$ and $f(r) = r$: the constant-right map.
- $f(\ell) = \ell$ and $f(r) = r$: the identity.
- $f(\ell) = r$ and $f(r) = \ell$: the dual.

There is no fifth case. The four labels below name these survivors.

```
– § The four-case classification of endomorphisms.
data EndoCase : Set where
 case-constL : EndoCase
 case-constR : EndoCase
 case-id     : EndoCase
 case-dual : EndoCase
```

Figure 4.2 makes the pressure visible in the negative direction. A three-vertex closure cannot survive this classification, because one of the four mutually distinct cases is always left outside. The triangle is therefore not a weaker rival to K_4; it is the first unstable alternative that the four-case verdict destroys.



Figure 4.2: Why K_3 fails: four mutually distinct endomorphism cases cannot close on a three-vertex graph. One case is always forced outside.

The K_4 Classification Module

The four cases are not yet a classification—they are just labels. A proper classification requires three things: an *interpretation* that turns each label into an actual endomorphism, a *classifier* that assigns a label to any given endomorphism, and proofs that these two operations are inverses of

each other. Soundness (classify then interpret recovers the original) and injectivity (distinct labels produce distinct behavior) together force uniqueness: every endomorphism receives exactly one label, and no two labels describe the same map.

The module K_4 assembles all of this in one place. It is parameterized by a distinction d, because the classification depends on the specific boundary witnesses.

Step 1: Endo type and pointwise equivalence. The endomorphism type and its equivalence relation are forced by the carrier.

```
-- § K₄ endomorphism algebra: classify, interpret, and verify.
module K₄ (d : Distinction) where
  Endo : Set
  Endo = S d → S d

  ≐-refl : {f : Endo} → f ≐ f
  ≐-refl x = refl

  ≐-sym : {f g : Endo} → f ≐ g → g ≐ f
  ≐-sym p x = sym (p x)

  ≐-trans : {f g h : Endo} → f ≐ g → g ≐ h → f ≐ h
  ≐-trans p q x = trans (p x) (q x)
```

Step 2: The four canonical endomorphisms. Two-class coverage forces exactly four surviving endomorphisms: constant-left, constant-right, identity, and dual. The dual exchanges the two boundary witnesses; its boundary behavior is verified by case analysis against cover.

```
-- § Constant-left endomorphism.
constL : Endo
constL _ = ℓ d

-- § Constant-right endomorphism.
constR : Endo
constR _ = r d

-- § The dual endomorphism.
dual : Endo
dual = Distinction-dual d

-- § Dual sends ℓ to r.
dual-ℓ : dual (ℓ d) ≡ r d
dual-ℓ with cover d (ℓ d)
... | inj₁ _ = refl
... | inj₂ ℓ≡r = ⊥-elim ((ℓ≠r d) ℓ≡r)

-- § Dual sends r to ℓ.
dual-r : dual (r d) ≡ ℓ d
dual-r with cover d (r d)
... | inj₁ r≡ℓ = ⊥-elim ((ℓ≠r d) (sym r≡ℓ))
... | inj₂ _ = refl
```

Step 3: Interpretation and classification. Each case label is interpreted as one of the four canonical endomorphisms. Conversely, every endofunction is classified by its boundary outputs into one of the four cases.

```
-- § Interpret a case label as an endofunction.
interpret : EndoCase → Endo
interpret case-constL = constL
interpret case-constR = constR
interpret case-id     = id
interpret case-dual = dual

-- § Classify an endofunction by its boundary outputs.
classify : Endo → EndoCase
classify f with cover d (f (ℓ d)) | cover d (f (r d))
... | inj₁ _ | inj₁ _ = case-constL
... | inj₂ _ | inj₂ _ = case-constR
... | inj₁ _ | inj₂ _ = case-id
... | inj₂ _ | inj₁ _ = case-dual
```

Step 4: Soundness of classification. Classification followed by interpretation recovers the original endofunction at both boundary witnesses. The pointwise proof is assembled from the two boundary cases via the carrier eliminator.

```
-- § Soundness at ℓ: interpretation recovers the value at ℓ.
sound-at-ℓ : (f : Endo) → interpret (classify f) (ℓ d) ≡ f (ℓ d)
sound-at-ℓ f with cover d (f (ℓ d)) | cover d (f (r d))
... | inj₁ fl≡ℓ | inj₁ _ = sym fl≡ℓ
... | inj₂ fl≡r | inj₂ _ = sym fl≡r
... | inj₁ fl≡ℓ | inj₂ _ = sym fl≡ℓ
... | inj₂ fl≡r | inj₁ _ = trans dual-ℓ (sym fl≡r)

-- § Soundness at r: interpretation recovers the value at r.
sound-at-r : (f : Endo) → interpret (classify f) (r d) ≡ f (r d)
sound-at-r f with cover d (f (ℓ d)) | cover d (f (r d))
... | inj₁ _ | inj₁ fr≡ℓ = sym fr≡ℓ
... | inj₂ _ | inj₂ fr≡r = sym fr≡r
... | inj₁ _ | inj₂ fr≡r = sym fr≡r
... | inj₂ _ | inj₁ fr≡ℓ = trans dual-r (sym fr≡ℓ)

-- § Soundness: classification followed by interpretation recovers behavior.
classify-sound : (f : Endo) → interpret (classify f) ≐ f
classify-sound f x = Distinction-elim d (sound-at-ℓ f) (sound-at-r f) x
```

Step 5: Boundary determination and injectivity. Endofunctions are determined by their boundary values alone (via the eliminator). Interpretation is injective: distinct case labels force distinct boundary behavior, so the 4×4 case matrix either produces refl or derives absurdity from $\ell \neq r$.

```
-- § Endofunctions are determined by their boundary values.
endo-determined :
 (f g : Endo) →
 f (ℓ d) ≡ g (ℓ d) →
 f (r d) ≡ g (r d) →
 f ≐ g
```

```
endo-determined f g eqℓ eqr x = Distinction-elim d eqℓ eqr x

-- § Interpretation is injective: distinct cases produce distinct behavior.
interpret-injective :
 (c c' : EndoCase) →
 interpret c ≐ interpret c' →
 c ≡ c'
interpret-injective case-constL case-constL _ = refl
interpret-injective case-constL case-constR p = ⊥-elim ((ℓ≠r d) (p (ℓ d)))
interpret-injective case-constL case-id    p = ⊥-elim ((ℓ≠r d) (p (r d)))
interpret-injective case-constL case-dual  p =
 ⊥-elim ((ℓ≠r d) (trans (p (ℓ d)) dual-ℓ))

interpret-injective case-constR case-constL p =
 ⊥-elim ((ℓ≠r d) (sym (p (ℓ d))))
interpret-injective case-constR case-constR _ = refl
interpret-injective case-constR case-id    p =
 ⊥-elim ((ℓ≠r d) (sym (p (ℓ d))))
interpret-injective case-constR case-dual p =
 ⊥-elim ((ℓ≠r d) (sym (trans (p (r d)) dual-r)))

interpret-injective case-id    case-constL p =
 ⊥-elim ((ℓ≠r d) (sym (p (r d))))
interpret-injective case-id    case-constR p = ⊥-elim ((ℓ≠r d) (p (ℓ d)))
interpret-injective case-id    case-id     _ = refl
interpret-injective case-id    case-dual   p =
 ⊥-elim ((ℓ≠r d) (trans (p (ℓ d)) dual-ℓ))

interpret-injective case-dual case-constL p =
 ⊥-elim ((ℓ≠r d) (sym (trans (sym (dual-ℓ)) (p (ℓ d)))))
interpret-injective case-dual case-constR p =
 ⊥-elim ((ℓ≠r d) (trans (sym (dual-r)) (p (r d))))
interpret-injective case-dual case-id      p =
 ⊥-elim ((ℓ≠r d) (sym (trans (sym (dual-ℓ)) (p (ℓ d)))))
interpret-injective case-dual case-dual    _ = refl
```

Step 6: Classification uniqueness. Soundness and injectivity together force that the case label assigned by classify is unique.

```
-- § Classification is unique: the label is forced by soundness + injectivity.
classify-unique : (f : Endo) → (c : EndoCase) → interpret c ≐ f → c ≡ classify f
classify-unique f c c≐f =
 interpret-injective c (classify f) (≐-trans c≐f (≐-sym (classify-sound f)))
```

Mutual Distinctness of Cases

The four case labels must remain genuinely different—no two of them may be identified. The labels are constructors of a data type, and Agda's pattern matching confirms that no constructor equals any other. The six pairwise inequalities are all proved by the absurd pattern (): there is simply no way to build a proof that, say, case-constL equals case-id. The type is empty.

```
-- § All four EndoCase constructors are pairwise distinct.
EndoCase-distinct :
 (case-constL ≡ case-constR → ⊥) ×
 (case-constL ≡ case-id     → ⊥) ×
```

```
 (case-constL ≡ case-dual → ⊥) ×
 (case-constR ≡ case-id   → ⊥) ×
 (case-constR ≡ case-dual → ⊥) ×
 (case-id ≡ case-dual     → ⊥)
EndoCase-distinct =
 (λ ()) ,
 ((λ ()) ,
  ((λ ()) ,
   ((λ ()) ,
    ((λ ()) ,
     (λ ))))))
```

Top-Level Classification Witnesses

The local module laws force exported witnesses of soundness and uniqueness. These witnesses are thin wrappers—they add no new content, only accessibility. The classification lives inside the parameterized module K_4; to use it in later chapters, we export soundness and uniqueness at the top level.

```
– § Top-level K₄ soundness witness.
k4-classification-sound :
 (d : Distinction) →
 (f : S d → S d) →
 Σ EndoCase (λ c → K₄.interpret d c ≐ f)
k4-classification-sound d f = K₄.classify d f , K₄.classify-sound d f

– § Top-level K₄ uniqueness witness.
k4-classification-unique :
 (d : Distinction) →
 (f : S d → S d) →
 (c₁ c₂ : EndoCase) →
 K₄.interpret d c₁ ≐ f →
 K₄.interpret d c₂ ≐ f →
 c₁ ≡ c₂
k4-classification-unique d f c₁ c₂ p₁ p₂ =
 K₄.interpret-injective d c₁ c₂ (K₄.≐-trans d p₁ (K₄.≐-sym d p₂))
```

Law 1.4: Endo(S) Classifies Into Exactly Four Cases

Every endomorphism on a distinction carrier receives a label from the four-case type. The classifier inspects the two boundary outputs and assigns the unique matching case. No endomorphism escapes classification.

```
– § Law 1.4: Endo(S) classifies into exactly four cases.
law1-4-classify : (d : Distinction) → (S d → S d) → EndoCase
law1-4-classify d = K₄.classify d
```

Law 1.5: Classification Is Sound

Soundness means that the round trip works: classify an endomorphism, interpret the resulting label, and you get back a function that agrees with the original at every point. This is not a design

goal—it is forced by the fact that classification reads off the boundary values and interpretation plugs them back in.

```
-- § Law 1.5: Classification is sound.
law1-5-classify-sound : (d : Distinction) → (f : S d → S d) → K₄.interpret d (K₄.classify d f) ≐ f
law1-5-classify-sound d f = snd (k4-classification-sound d f)
```

Law 1.6: Endo Is Determined By Boundary Values

If two endomorphisms agree on ℓ and agree on r, they agree everywhere. This is a direct consequence of coverage: every carrier element is either ℓ or r, so agreement on those two points leaves no room for disagreement anywhere else. The interior of the carrier is empty—there are no hidden witnesses where the two maps could diverge.

```
-- § Law 1.6: Endo is determined by boundary values.
law1-6-endo-determined :
 (d : Distinction) →
 (f g : S d → S d) →
 f (ℓ d) ≡ g (ℓ d) →
 f (r d) ≡ g (r d) →
 f ≐ g
law1-6-endo-determined d = K₄.endo-determined d
```

Law 1.7: Classification Is Unique

If a case label c interprets to a function that agrees pointwise with f, then c must be exactly the label that the classifier assigns to f. The proof chains soundness (the classifier's label also interprets correctly) with injectivity (two labels interpreting to the same function must be equal). There is no ambiguity, no alternative labeling. The classification is canonical.

```
-- § Law 1.7: Classification is unique.
law1-7-classify-unique :
 (d : Distinction) →
 (f : S d → S d) →
 (c : EndoCase) →
 K₄.interpret d c ≐ f →
 c ≡ K₄.classify d f
law1-7-classify-unique d f c p =
 k4-classification-unique d f c (fst (k4-classification-sound d f)) p (snd (k4-classification-sound d f))
```

Exhaustive classification reaches the second structural milestone here. Figure 4.3 fixes the unique four-case closure as the complete graph K_4.



Figure 4.3: Exhaustive four-case endomorphism classification closes as the complete graph K_4.

Chapter 5

Two Normal Form

The classification is complete: every endomorphism falls into one of four cases. But the carrier itself—the type S in the distinction record—is still abstract. We know it has exactly two elements, because coverage says so. But "having exactly two elements" and "being the canonical two-element type" are different statements. This chapter closes the gap.

The key insight is that coverage forces a canonical isomorphism between any distinction carrier and a concrete two-element type Two. The maps in both directions are uniquely determined by the boundary witnesses, the round trips are identity, and the only remaining freedom is a binary choice: whether ℓ maps to L or to R? That choice is the orientation, and there are exactly two of them. The same compression applies to automorphisms: the only self-equivalences of a distinction are the identity and the dual.

The Two Type

The canonical two-element type has two constructors—L and R—that are provably distinct and exhaustively cover the type. This is the simplest possible distinction. It serves as the solved form: the concrete representative to which every abstract distinction carrier is isomorphic.

```
-- § The canonical two-element type.
data Two : Set where
  L : Two
  R : Two

-- § L and R are distinct.
Two-L≠R : L ≠ R
Two-L≠R ()

-- § Exhaustive two-class coverage for Two.
Two-cover : (x : Two) → (x ≡ L) ⊎ (x ≡ R)
Two-cover L = inj₁ refl
Two-cover R = inj₂ refl

-- § Two forms a canonical Distinction.
Two-distinction : Distinction
Two-distinction = record
  { S     = Two
  ; ℓ     = L
```

```
; r     = R
; ℓ≠r = Two-L≠R
; cover = Two-cover
}
```

This definition settles the existence question that Chapter 3 deliberately left open. Two-distinction is a parameterless, fully constructive inhabitant of Distinction—no assumptions, no function arguments, no postulates. The ¬¬ *Distinction* barrier that blocked vacuity is upgraded to direct constructive existence: $\lambda\, f \to f$ *Two-distinction* discharges the double negation trivially. Every subsequent chapter inherits this witness.

Distinction Isomorphism

Comparing two distinctions requires a notion of structural equivalence. A *distinction isomorphism* is a pair of maps between the carriers that are mutual inverses and that preserve the boundary witnesses: ℓ maps to ℓ and r maps to r. A weaker notion—*distinction equivalence*—drops the boundary requirement and retains only the inverse laws. The weaker notion is what orientation and automorphism classification will use, since those questions ask precisely whether the boundary is preserved or swapped.

```
-- § Boundary-preserving isomorphism between distinctions.
record DistinctionIso (d₁ d₂ : Distinction) : Set1 where
 field
  to     : S d₁ → S d₂
  from   : S d₂ → S d₁
  to-from : (y : S d₂) → to (from y) ≡ y
  from-to : (x : S d₁) → from (to x) ≡ x
  to-ℓ   : to (ℓ d₁) ≡ ℓ d₂
  to-r   : to (r d₁) ≡ r d₂

open DistinctionIso public

-- § Equivalence without boundary constraints.
record DistinctionEquiv (d₁ d₂ : Distinction) : Set1 where
 field
  to     : S d₁ → S d₂
  from   : S d₂ → S d₁
  to-from : (y : S d₂) → to (from y) ≡ y
  from-to : (x : S d₁) → from (to x) ≡ x

open DistinctionEquiv public

-- § Forgetting boundary data from an isomorphism.
forgetIso : {d₁ d₂ : Distinction} → DistinctionIso d₁ d₂ → DistinctionEquiv d₁ d₂
forgetIso i = record
 { to     = DistinctionIso.to i
 ; from   = DistinctionIso.from i
 ; to-from = DistinctionIso.to-from i
 ; from-to = DistinctionIso.from-to i
 }
```

Canonical Two Maps

The isomorphism between any distinction carrier and Two writes itself. The forward map toTwo sends ℓ to L and r to R—determined by coverage. The backward map fromTwo reverses this. The round-trip proofs are forced by the eliminator: there is exactly one way to verify that the composition is the identity, and the type checker accepts it.

```
-- § The canonical boundary-preserving map to Two.
toTwo : (d : Distinction) → S d → Two
toTwo d x with cover d x
... | inj₁ _ = L
... | inj₂ _ = R

-- § The canonical embedding from Two.
fromTwo : (d : Distinction) → Two → S d
fromTwo d L = ℓ d
fromTwo d R = r d

-- § toTwo sends ℓ to L.
toTwo-ℓ : (d : Distinction) → toTwo d (ℓ d) ≡ L
toTwo-ℓ d with cover d (ℓ d)
... | inj₁ _ = refl
... | inj₂ ℓ≡r = ⊥-elim ((ℓ≠r d) ℓ≡r)

-- § toTwo sends r to R.
toTwo-r : (d : Distinction) → toTwo d (r d) ≡ R
toTwo-r d with cover d (r d)
... | inj₂ _ = refl
... | inj₁ r≡ℓ = ⊥-elim ((ℓ≠r d) (sym r≡ℓ))

-- § fromTwo ∘ toTwo is the identity.
fromTwo-toTwo : (d : Distinction) → (x : S d) → fromTwo d (toTwo d x) ≡ x
fromTwo-toTwo d =
 Distinction-elim d
  (trans (cong (fromTwo d) (toTwo-ℓ d)) refl)
  (trans (cong (fromTwo d) (toTwo-r d)) refl)

-- § toTwo ∘ fromTwo is the identity.
toTwo-fromTwo : (d : Distinction) → (t : Two) → toTwo d (fromTwo d t) ≡ t
toTwo-fromTwo d L = toTwo-ℓ d
toTwo-fromTwo d R = toTwo-r d
```

Law 1.8: Every Distinction Is Isomorphic To Two

This is the normal form theorem. Every distinction—regardless of how its carrier was originally defined—is boundary-preserving isomorphic to the canonical Two distinction. The proof assembles the maps and round-trip verifications from the previous section into a single record. There is nothing to choose; every field is forced.

```
-- § Law 1.8: Every distinction is isomorphic to Two.
two-normal-form : (d : Distinction) → DistinctionIso d Two-distinction
two-normal-form d = record
 { to     = toTwo d
 ; from   = fromTwo d
 ; to-from = toTwo-fromTwo d
 ; from-to = fromTwo-toTwo d
```

```
 ; to-ℓ  = toTwo-ℓ d
 ; to-r  = toTwo-r d
 }

law1-8-two-normal-form : (d : Distinction) → DistinctionIso d Two-distinction
law1-8-two-normal-form = two-normal-form
```

Orientation

An equivalence between a distinction and Two must send the two boundary witnesses to distinct images—otherwise the inverse map would identify ℓ and r, contradicting their separation. The images are elements of Two, which has only two inhabitants. So there are exactly two possibilities: send ℓ to L (preserve) or send ℓ to R (swap). No third option exists.

```
-- § The swap map on Two.
swapTwo : Two → Two
swapTwo L = R
swapTwo R = L

-- § Swap is involutive.
swapTwo-involutive : (t : Two) → swapTwo (swapTwo t) ≡ t
swapTwo-involutive L = refl
swapTwo-involutive R = refl

-- § The swap-oriented map to Two.
toTwo-swap : (d : Distinction) → S d → Two
toTwo-swap d x = swapTwo (toTwo d x)

-- § Swap-oriented map sends ℓ to R.
toTwo-swap-ℓ : (d : Distinction) → toTwo-swap d (ℓ d) ≡ R
toTwo-swap-ℓ d = cong swapTwo (toTwo-ℓ d)

-- § Swap-oriented map sends r to L.
toTwo-swap-r : (d : Distinction) → toTwo-swap d (r d) ≡ L
toTwo-swap-r d = cong swapTwo (toTwo-r d)

-- § The canonical equivalence (boundary-preserving).
two-normal-form-equiv : (d : Distinction) → DistinctionEquiv d Two-distinction
two-normal-form-equiv d = forgetIso (two-normal-form d)

-- § The swap equivalence.
two-normal-form-equiv-swap : (d : Distinction) → DistinctionEquiv d Two-distinction
two-normal-form-equiv-swap d = record
 { to     = toTwo-swap d
 ; from = fromTwo d ∘ swapTwo
 ; to-from = λ t → trans (cong (toTwo-swap d) (refl)) (trans (cong swapTwo (toTwo-fromTwo d (swapTwo t))) (swapTwo-involutive t))
 ; from-to = λ x → trans (cong (fromTwo d) (swapTwo-involutive (toTwo d x))) (fromTwo-toTwo d x)
 }
 where
  _∘_ : {A B C : Set} → (B → C) → (A → B) → A → C
  (f ∘ g) x = f (g x)

-- § The two orientations of a Two normal form.
data TwoOrientation : Set where
 orient-preserve : TwoOrientation
 orient-swap : TwoOrientation
```

```
-- § The two orientations are distinct.
preserve≠swap : orient-preserve ≡ orient-swap → ⊥
preserve≠swap ()

swap≠preserve : orient-swap ≡ orient-preserve → ⊥
swap≠preserve ()
```

Boundary images of an equivalence are forced to remain distinct by the inverse law. The orientation classifier is the unique surviving witness that selects between preserve and swap. This eliminates every ambiguous orientation assignment.

```
-- § Equivalence images at boundary are distinct.
to-distinct-on-boundary :
 (d : Distinction) →
 (e : DistinctionEquiv d Two-distinction) →
 to e (ℓ d) ≡ to e (r d) → ⊥
to-distinct-on-boundary d e eq =
 ℓ≠r d (trans (sym (from-to e (ℓ d))) (trans (cong (from e) eq) (from-to e (r d))))

-- § Classify an equivalence by its orientation.
orientation-classify :
 (d : Distinction) →
 (e : DistinctionEquiv d Two-distinction) →
 TwoOrientation
orientation-classify d e with Two-cover (to e (ℓ d)) | Two-cover (to e (r d))
... | inj₁ tℓ≡L | inj₁ tr≡L = ⊥-elim (to-distinct-on-boundary d e (trans tℓ≡L (sym tr≡L)))
... | inj₂ tℓ≡R | inj₂ tr≡R = ⊥-elim (to-distinct-on-boundary d e (trans tℓ≡R (sym tr≡R)))
... | inj₁ _ | inj₂ _ = orient-preserve
... | inj₂ _ | inj₁ _ = orient-swap
```

Automorphisms

An automorphism of a distinction is a self-equivalence: a pair of maps from the carrier to itself that are mutual inverses. The inverse law forces injectivity, and injectivity forces the boundary images to remain distinct (since $\ell \neq r$ would be violated otherwise). With only two elements in the carrier, the only injective endomorphisms are the identity and the swap. That is the complete automorphism group of any distinction: exactly two elements, id and dual.

```
-- § Automorphism of a distinction.
Aut : Distinction → Set1
Aut d = DistinctionEquiv d d

-- § Automorphism transport is injective.
to-injective : (d : Distinction) → (a : Aut d) → {x y : S d} → to a x ≡ to a y → x ≡ y
to-injective d a {x} {y} eq =
 trans (sym (from-to a x)) (trans (cong (from a) eq) (from-to a y))

-- § Automorphism images at boundary points are distinct.
to-ℓ≠to-r : (d : Distinction) → (a : Aut d) → to a (ℓ d) ≠ to a (r d)
to-ℓ≠to-r d a eq = ℓ≠r d (to-injective d a eq)

-- § Dual boundary lemma: dual sends ℓ to r.
Distinction-dual-ℓ : (d : Distinction) → Distinction-dual d (ℓ d) ≡ r d
Distinction-dual-ℓ d with cover d (ℓ d)
... | inj₁ _    = refl
```

```
... | inj₂ ℓ≡r = ⊥-elim ((ℓ≠r d) ℓ≡r)

-- § Dual boundary lemma: dual sends r to ℓ.
Distinction-dual-r : (d : Distinction) → Distinction-dual d (r d) ≡ ℓ d
Distinction-dual-r d with cover d (r d)
... | inj₂ _     = refl
... | inj₁ r≡ℓ = ⊥-elim ((ℓ≠r d) (sym r≡ℓ))

-- § Automorphism classification: exactly id or dual.
Aut-sound :
 (d : Distinction) →
 (a : Aut d) →
 (to a ≐ id) ⊎ (to a ≐ Distinction-dual d)
Aut-sound d a with cover d (to a (ℓ d)) | cover d (to a (r d))
... | inj₁ tℓ≡ℓ | inj₁ tr≡ℓ = ⊥-elim (to-ℓ≠to-r d a (trans tℓ≡ℓ (sym tr≡ℓ)))
... | inj₂ tℓ≡r | inj₂ tr≡r = ⊥-elim (to-ℓ≠to-r d a (trans tℓ≡r (sym tr≡r)))
... | inj₁ tℓ≡ℓ | inj₂ tr≡r =
 inj₁ (Distinction-elim d tℓ≡ℓ tr≡r)
... | inj₂ tℓ≡r | inj₁ tr≡ℓ =
 inj₂ (Distinction-elim d
  (trans tℓ≡r (sym (Distinction-dual-ℓ d)))
  (trans tr≡ℓ (sym (Distinction-dual-r d))))
```

Automorphism classification reaches the third structural milestone here. Figure 5.1 fixes the symmetry action as a permutation of the four case witnesses.



Figure 5.1: Automorphism action on the four-case witness space: preserve and swap survive as the only orbit structure.

Law 1.9: The Two Isomorphism Is Unique

Any boundary-preserving map from a distinction carrier to Two must agree with the canonical map toTwo. The proof is immediate from the eliminator: since the map is determined by its values at ℓ and r, and those values are fixed by the boundary-preservation requirement, there is exactly one such map. The same holds for the backward direction.

```
-- § Uniqueness of the to-direction.
toTwo-unique :
 (d : Distinction) →
 (f : S d → Two) →
 f (ℓ d) ≡ L →
```

```
 f (r d) ≡ R →
 f ≐ toTwo d
toTwo-unique d f fℓ fr =
 Distinction-elim d
  (trans fℓ (sym (toTwo-ℓ d)))
  (trans fr (sym (toTwo-r d)))

– § Uniqueness of the swap-direction.
toTwo-swap-unique :
 (d : Distinction) →
 (f : S d → Two) →
 f (ℓ d) ≡ R →
 f (r d) ≡ L →
 f ≐ toTwo-swap d
toTwo-swap-unique d f fℓ fr =
 Distinction-elim d
  (trans fℓ (sym (toTwo-swap-ℓ d)))
  (trans fr (sym (toTwo-swap-r d)))

– § Law 1.9: iso-to is unique.
law1-9-iso-to-unique : (d : Distinction) → (i : DistinctionIso d Two-distinction) → to i ≐ toTwo d
law1-9-iso-to-unique d i =
 toTwo-unique d (to i)
  (trans (to-ℓ i) refl)
  (trans (to-r i) refl)

– § Uniqueness of the from-direction.
fromTwo-unique :
 (d : Distinction) →
 (g : Two → S d) →
 g L ≡ ℓ d →
 g R ≡ r d →
 g ≐ fromTwo d
fromTwo-unique d g gL gR L = trans gL refl
fromTwo-unique d g gL gR R = trans gR refl

– § Law 1.9: iso-from is unique.
law1-9-iso-from-unique : (d : Distinction) → (i : DistinctionIso d Two-distinction) → from i ≐ fromTwo d
law1-9-iso-from-unique d i =
 fromTwo-unique d (from i)
  (trans (sym (cong (from i) (to-ℓ i))) (from-to i (ℓ d)))
  (trans (sym (cong (from i) (to-r i))) (from-to i (r d)))
```

Law 1.10: Two Normal Form Has Exactly Two Orientations

Every equivalence to Two is either the canonical boundary-preserving map or the swap. The proof checks the image of ℓ: it is either L or R. If L, the map agrees with toTwo. If R, it agrees with toTwo-swap. There is no third possibility, because Two has no third element.

```
– § Law 1.10: orientation is exhaustive.
orientation-exhaustive :
 (d : Distinction) →
 (e : DistinctionEquiv d Two-distinction) →
 (to e ≐ toTwo d) ⊎ (to e ≐ toTwo-swap d)
orientation-exhaustive d e with Two-cover (to e (ℓ d)) | Two-cover (to e (r d))
... | inj₁ tℓ≡L | inj₁ tr≡L = ⊥-elim (to-distinct-on-boundary d e (trans tℓ≡L (sym tr≡L)))
... | inj₂ tℓ≡R | inj₂ tr≡R = ⊥-elim (to-distinct-on-boundary d e (trans tℓ≡R (sym tr≡R)))
... | inj₁ tℓ≡L | inj₂ tr≡R = inj₁ (toTwo-unique d (to e) tℓ≡L tr≡R)
```

```
... | inj₂ tℓ≡R | inj₁ tr≡L = inj₂ (toTwo-swap-unique d (to e) tℓ≡R tr≡L)

law1-10-orientation-exhaustive :
 (d : Distinction) →
 (e : DistinctionEquiv d Two-distinction) →
 (to e ≐ toTwo d) ⊎ (to e ≐ toTwo-swap d)
law1-10-orientation-exhaustive = orientation-exhaustive
```

Law 1.11: Automorphisms Are Exactly id Or dual

The boundary behavior of any automorphism is forced into one of two patterns: fix both boundaries (identity) or swap both (dual). Any other combination—fixing one and moving the other—would produce a non-injective map, which contradicts the inverse law.

```
-- § Law 1.11: Automorphisms are exactly id or dual.
law1-11-Aut-sound :
 (d : Distinction) →
 (a : Aut d) →
 (to a ≐ id) ⊎ (to a ≐ Distinction-dual d)
law1-11-Aut-sound = Aut-sound
```

Law 1.12: Two-Orientation Classification Is Sound And Unique

The orientation classifier assigns every equivalence to Two one of two labels: case-preserve or case-swap. Soundness: the assigned label interprets back to a map that agrees pointwise with the original equivalence. Uniqueness: no equivalence can receive two different labels, because that would force $L = R$ in Two.

```
-- § Orientation case type.
data OrientationCase : Set where
 case-preserve : OrientationCase
 case-swap : OrientationCase

-- § Interpret an orientation case as a map.
orientationInterpret : (d : Distinction) → OrientationCase → S d → Two
orientationInterpret d case-preserve = toTwo d
orientationInterpret d case-swap = toTwo-swap d

-- § Law 1.12: orientation classification is sound.
orientationCase-sound :
 (d : Distinction) →
 (e : DistinctionEquiv d Two-distinction) →
 Σ OrientationCase (λ c → to e ≐ orientationInterpret d c)
orientationCase-sound d e with orientation-exhaustive d e
... | inj₁ p = case-preserve , p
... | inj₂ p = case-swap , p

-- § Law 1.12: orientation classification is unique.
orientationCase-unique :
 (d : Distinction) →
 (e : DistinctionEquiv d Two-distinction) →
 (c₁ c₂ : OrientationCase) →
 to e ≐ orientationInterpret d c₁ →
 to e ≐ orientationInterpret d c₂ →
 c₁ ≡ c₂
```

```
orientationCase-unique d e case-preserve case-preserve _ _ = refl
orientationCase-unique d e case-swap case-swap _ _ = refl
orientationCase-unique d e case-preserve case-swap p q =
 ⊥-elim (Two-L≢R (sym toR≡L))
 where
  toR≡L : R ≡ L
  toR≡L =
   trans (sym (toTwo-swap-ℓ d))
    (trans (sym (q (ℓ d)))
     (trans (p (ℓ d)) (toTwo-ℓ d)))
orientationCase-unique d e case-swap case-preserve p q =
 ⊥-elim (Two-L≢R (sym toR≡L))
 where
  toR≡L : R ≡ L
  toR≡L =
   trans (sym (toTwo-swap-ℓ d))
    (trans (sym (p (ℓ d)))
     (trans (q (ℓ d)) (toTwo-ℓ d)))

law1-12-orientationCase-sound :
 (d : Distinction) →
 (e : DistinctionEquiv d Two-distinction) →
 Σ OrientationCase (λ c → to e ≐ orientationInterpret d c)
law1-12-orientationCase-sound = orientationCase-sound

law1-12-orientationCase-unique :
 (d : Distinction) →
 (e : DistinctionEquiv d Two-distinction) →
 (c₁ c₂ : OrientationCase) →
 to e ≐ orientationInterpret d c₁ →
 to e ≐ orientationInterpret d c₂ →
 c₁ ≡ c₂
law1-12-orientationCase-unique = orientationCase-unique
```

Law 1.13: Automorphism Classification Is Sound And Unique

The same structure holds for automorphisms. Every self-equivalence receives exactly one label—case-id or case-dual—and that label is forced by the boundary behavior. If two different labels could describe the same automorphism, their interpretations would agree pointwise, which would force $\ell = r$ via the boundary lemmas. Contradiction eliminates every unsound or non-unique automorphism witness.

```
-- § Automorphism case type.
data AutCase : Set where
 case-id : AutCase
 case-dual : AutCase

-- § Interpret an automorphism case.
autInterpret : (d : Distinction) → AutCase → S d → S d
autInterpret d case-id = id
autInterpret d case-dual = Distinction-dual d

-- § Automorphism classification is sound.
autCase-sound :
 (d : Distinction) →
 (a : Aut d) →
 Σ AutCase (λ c → to a ≐ autInterpret d c)
```

```
autCase-sound d a with Aut-sound d a
... | inj₁ p = case-id     , p
... | inj₂ p = case-dual , p

-- § Automorphism classification is unique.
autCase-unique :
 (d : Distinction) →
 (a : Aut d) →
 (c₁ c₂ : AutCase) →
 to a ≐ autInterpret d c₁ →
 to a ≐ autInterpret d c₂ →
 c₁ ≡ c₂
autCase-unique d a case-id case-id _ _ = refl
autCase-unique d a case-dual case-dual _ _ = refl
autCase-unique d a case-id case-dual p q =
 ⊥-elim ((ℓ≠r d) ℓ≡r)
 where
  ℓ≡r : ℓ d ≡ r d
  ℓ≡r =
   trans (sym (p (ℓ d)))
    (trans (q (ℓ d)) (Distinction-dual-ℓ d))
autCase-unique d a case-dual case-id p q =
 ⊥-elim ((ℓ≠r d) ℓ≡r)
 where
  ℓ≡r : ℓ d ≡ r d
  ℓ≡r =
   trans (sym (q (ℓ d)))
    (trans (p (ℓ d)) (Distinction-dual-ℓ d))

-- § Law 1.13: Automorphism classification is sound and unique.
law1-13-autCase-sound :
 (d : Distinction) →
 (a : Aut d) →
 Σ AutCase (λ c → to a ≐ autInterpret d c)
law1-13-autCase-sound = autCase-sound

law1-13-autCase-unique :
 (d : Distinction) →
 (a : Aut d) →
 (c₁ c₂ : AutCase) →
 to a ≐ autInterpret d c₁ →
 to a ≐ autInterpret d c₂ →
 c₁ ≡ c₂
law1-13-autCase-unique = autCase-unique
```

K_4 Witness Interface

The dependent pair that bundles a case label with a proof that its interpretation matches a given endomorphism is the canonical witness of classification. Every endomorphism receives exactly one such witness. These top-level re-exports make the classification accessible to all subsequent chapters without requiring the K_4 module to be opened.

```
-- § Law 1.14: K₄ classification produces a witness.
law1-14-k4-classification-sound :
 (d : Distinction) →
 (f : S d → S d) →
 Σ EndoCase (λ c → K₄.interpret d c ≐ f)
```

```
law1-14-k4-classification-sound = k4-classification-sound

-- § Law 1.15: K₄ classification witness is unique.
law1-15-k4-classification-unique :
 (d : Distinction) →
 (f : S d → S d) →
 (c₁ c₂ : EndoCase) →
 K₄.interpret d c₁ ≐ f →
 K₄.interpret d c₂ ≐ f →
 c₁ ≡ c₂
law1-15-k4-classification-unique = k4-classification-unique
```

Two-Class Coverage Without Definitional Equality

The preceding classification relies on propositional equality ≡ as the notion of sameness. Some contexts require coverage with respect to a weaker equivalence relation ≈ that is reflexive, symmetric, and transitive but not necessarily definitional. The record DistinctionClass captures this: it carries a carrier, two separated boundary witnesses, an equivalence relation, and exhaustive coverage under that relation. This weakening does not gain expressive power—it broadens the range of carriers that can be recognized as distinctions without altering the classification theory.

```
-- § DistinctionClass: two-class coverage with an arbitrary equivalence relation.
record DistinctionClass : Set1 where
 field
  S       : Set
  _≈_     : S → S → Set
  ≈-refl : (x : S) → x ≈ x
  ≈-sym : {x y : S} → x ≈ y → y ≈ x
  ≈-trans : {x y z : S} → x ≈ y → y ≈ z → x ≈ z

  ℓ       : S
  r       : S
  ℓ≉r     : ¬ (ℓ ≈ r)
  cover≈ : (x : S) → (x ≈ ℓ) ⊎ (x ≈ r)

open DistinctionClass public

-- § Respect predicate for ≈-elimination.
Respect≈ : (d : DistinctionClass) → (S d → Set) → Set
Respect≈ d P = {x y : S d} → _≈_ d x y → P x → P y

-- § Law 1.16: Elimination is forced by cover≈.
DistinctionClass-elim :
 (d : DistinctionClass) →
 {P : S d → Set} →
 Respect≈ d P →
 P (ℓ d) →
 P (r d) →
 (x : S d) →
 P x
DistinctionClass-elim d {P} resp pℓ pr x with cover≈ d x
... | inj₁ x≈ℓ = resp ((≈-sym d) x≈ℓ) pℓ
... | inj₂ x≈r = resp ((≈-sym d) x≈r) pr

law1-16-class-elim :
```

```
(d : DistinctionClass) →
{P : S d → Set} →
Respect≈ d P →
P (ℓ d) →
P (r d) →
(x : S d) →
P x
law1-16-class-elim = DistinctionClass-elim

-- § Law 1.17: Every Distinction induces a DistinctionClass.
Distinction→DistinctionClass : Distinction → DistinctionClass
Distinction→DistinctionClass d = record
 { S        = S d
 ; _≈_      = _≡_
 ; ≈-refl   = λ x → refl
 ; ≈-sym    = sym
 ; ≈-trans  = trans
 ; ℓ        = ℓ d
 ; r        = r d
 ; ℓ≉r      = ℓ≠r d
 ; cover≈   = cover d
 }

law1-17-distinction-to-class : Distinction → DistinctionClass
law1-17-distinction-to-class = Distinction→DistinctionClass
```

Presentation Elimination

The four-case classification is canonical, but nothing prevents someone from proposing an alternative presentation: a different type X with its own interpretation and classification functions. The question is whether such an alternative can differ structurally from EndoCase. The answer is no. If a presentation is total (every endomorphism gets a label), sound (the label interprets back correctly), and injective (distinct labels produce distinct behavior), then X is isomorphic to EndoCase. The proof constructs the isomorphism explicitly by round-tripping through the canonical classifier.

```
-- § Set isomorphism (not distinction-specific).
record SetIso {ℓ₁ ℓ₂ : Level} (A : Set ℓ₁) (B : Set ℓ₂) : Set (ℓ₁ ⊔ ℓ₂) where
 field
  to     : A → B
  from   : B → A
  to-from : (y : B) → to (from y) ≡ y
  from-to : (x : A) → from (to x) ≡ x

open SetIso public

-- § Endo presentation record.
record EndoPresentation (d : Distinction) (X : Set) : Set where
 field
  present-interpret       : X → (S d → S d)
  present-classify        : (S d → S d) → X
  present-classify-sound  : (f : S d → S d) → present-interpret (present-classify f) ≐ f
  present-interpret-injective : (x y : X) → present-interpret x ≐ present-interpret y → x ≡ y

-- § Law 1.18: Endo presentation is unique up to isomorphism.
law1-18-endo-presentation-unique :
```

```
(d : Distinction) →
{X : Set} →
EndoPresentation d X →
SetIso X EndoCase
law1-18-endo-presentation-unique d {X} pres =
 let
  module K = K₄ d
  open EndoPresentation pres
   renaming
    ( present-interpret to interpretX
    ; present-classify to classifyX
    ; present-classify-sound to classifyX-sound
    ; present-interpret-injective to interpretX-injective
    )

  to' : X → EndoCase
  to' x = K.classify (interpretX x)

  from' : EndoCase → X
  from' c = classifyX (K.interpret c)

  to-from' : (c : EndoCase) → to' (from' c) ≡ c
  to-from' c =
   sym
    (K.classify-unique
     (interpretX (classifyX (K.interpret c)))
     c
     (K.≐-sym (classifyX-sound (K.interpret c))))

  from-to' : (x : X) → from' (to' x) ≡ x
  from-to' x =
   interpretX-injective
    (classifyX (K.interpret (K.classify (interpretX x))))
    x
    (K.≐-trans
     (classifyX-sound (K.interpret (K.classify (interpretX x))))
     (K.classify-sound (interpretX x)))
 in
 record
  { to = to'
  ; from = from'
  ; to-from = to-from'
  ; from-to = from-to'
  }
```

Law 1.19–1.20: Orientation and Automorphism Presentation Elimination

The same presentation elimination principle applies to orientation classifications and automorphism classifications.

```
-- § Helpers for orientation presentation elimination.
orientationCase-classify :
 (d : Distinction) →
 (e : DistinctionEquiv d Two-distinction) →
 OrientationCase
orientationCase-classify d e = fst (orientationCase-sound d e)

orientationCase-classify-sound :
 (d : Distinction) →
```

```
 (e : DistinctionEquiv d Two-distinction) →
 to e ≐ orientationInterpret d (orientationCase-classify d e)
orientationCase-classify-sound d e = snd (orientationCase-sound d e)

autCase-classify :
 (d : Distinction) →
 (a : Aut d) →
 AutCase
autCase-classify d a = fst (autCase-sound d a)

autCase-classify-sound :
 (d : Distinction) →
 (a : Aut d) →
 to a ≐ autInterpret d (autCase-classify d a)
autCase-classify-sound d a = snd (autCase-sound d a)

orientationEquivInterpret :
 (d : Distinction) →
 OrientationCase →
 DistinctionEquiv d Two-distinction
orientationEquivInterpret d case-preserve = two-normal-form-equiv d
orientationEquivInterpret d case-swap = two-normal-form-equiv-swap d

orientationEquivInterpret-sound :
 (d : Distinction) →
 (c : OrientationCase) →
 to (orientationEquivInterpret d c) ≐ orientationInterpret d c
orientationEquivInterpret-sound d case-preserve x = refl
orientationEquivInterpret-sound d case-swap x = refl

-- § Identity equivalence.
idEquiv : (d : Distinction) → DistinctionEquiv d d
idEquiv d = record
 { to     = id
 ; from = id
 ; to-from = λ y → refl
 ; from-to = λ x → refl
 }

-- § Dual equivalence.
dualEquiv : (d : Distinction) → DistinctionEquiv d d
dualEquiv d = record
 { to     = Distinction-dual d
 ; from = Distinction-dual d
 ; to-from = law1-3-dual-involutive d
 ; from-to = law1-3-dual-involutive d
 }

autEquivInterpret :
 (d : Distinction) →
 AutCase →
 Aut d
autEquivInterpret d case-id = idEquiv d
autEquivInterpret d case-dual = dualEquiv d

autEquivInterpret-sound :
 (d : Distinction) →
 (c : AutCase) →
 to (autEquivInterpret d c) ≐ autInterpret d c
autEquivInterpret-sound d case-id x = refl
autEquivInterpret-sound d case-dual x = refl
```

Presentation records. A presentation of either classification (orientation or automorphism) is a set-valued interface carrying interpretation, classification, soundness, and injectivity. These records are forced by the requirement that any alternative labeling is isomorphic to the canonical one.

```
-- § Orientation presentation record.
record OrientationPresentation (d : Distinction) (X : Set) : Set1 where
 field
  op-interpret          : X → DistinctionEquiv d Two-distinction
  op-classify           : DistinctionEquiv d Two-distinction → X
  op-classify-sound : (e : DistinctionEquiv d Two-distinction) → to (op-interpret (op-classify e)) ≐ to e
  op-interpret-injective : (x y : X) → to (op-interpret x) ≐ to (op-interpret y) → x ≡ y

-- § Automorphism presentation record.
record AutPresentation (d : Distinction) (X : Set) : Set1 where
 field
  ap-interpret          : X → Aut d
  ap-classify           : Aut d → X
  ap-classify-sound : (a : Aut d) → to (ap-interpret (ap-classify a)) ≐ to a
  ap-interpret-injective : (x y : X) → to (ap-interpret x) ≐ to (ap-interpret y) → x ≡ y
```

Law 1.19: Orientation presentation uniqueness. Every orientation presentation is forced to be isomorphic to OrientationCase. The isomorphism is constructed by composing classification on one side with interpretation on the other; soundness and injectivity force the round-trip properties.

```
-- § Law 1.19: Orientation presentation is unique up to isomorphism.
law1-19-orientation-presentation-unique :
 (d : Distinction) →
 {X : Set} →
 OrientationPresentation d X →
 SetIso X OrientationCase
law1-19-orientation-presentation-unique d {X} pres =
 let
  open OrientationPresentation pres
   renaming
    ( op-interpret to interpretX
    ; op-classify to classifyX
    ; op-classify-sound to classifyX-sound
    ; op-interpret-injective to interpretX-injective
    )

  ≐-sym : {A B : Set} {f g : A → B} → f ≐ g → g ≐ f
  ≐-sym p x = sym (p x)

  ≐-trans : {A B : Set} {f g h : A → B} → f ≐ g → g ≐ h → f ≐ h
  ≐-trans p q x = trans (p x) (q x)

  to' : X → OrientationCase
  to' x = orientationCase-classify d (interpretX x)

  from' : OrientationCase → X
  from' c = classifyX (orientationEquivInterpret d c)

  to-from' : (c : OrientationCase) → to' (from' c) ≡ c
  to-from' c =
   orientationCase-unique d (interpretX (classifyX (orientationEquivInterpret d c)))
```

```
  (to' (from' c))
  c
  (orientationCase-classify-sound d (interpretX (classifyX (orientationEquivInterpret d c))))
  (≐-trans
   (classifyX-sound (orientationEquivInterpret d c))
   (orientationEquivInterpret-sound d c))

 from-to' : (x : X) → from' (to' x) ≡ x
 from-to' x =
  interpretX-injective
   (classifyX (orientationEquivInterpret d (to' x)))
   x
   (≐-trans
    (classifyX-sound (orientationEquivInterpret d (to' x)))
    (≐-trans
     (orientationEquivInterpret-sound d (to' x))
     (≐-sym (orientationCase-classify-sound d (interpretX x)))))
 in
 record
  { to = to'
  ; from = from'
  ; to-from = to-from'
  ; from-to = from-to'
  }
```

– § Law 1.20: Automorphism presentation is unique up to isomorphism.

Law 1.20: Automorphism presentation uniqueness. The same forcing pattern applies: every automorphism presentation carries exactly the same data as AutCase up to isomorphism.

```
law1-20-aut-presentation-unique :
 (d : Distinction) →
 {X : Set} →
 AutPresentation d X →
 SetIso X AutCase
law1-20-aut-presentation-unique d {X} pres =
 let
  open AutPresentation pres
   renaming
    ( ap-interpret to interpretX
    ; ap-classify to classifyX
    ; ap-classify-sound to classifyX-sound
    ; ap-interpret-injective to interpretX-injective
    )

  ≐-sym : {A B : Set} {f g : A → B} → f ≐ g → g ≐ f
  ≐-sym p x = sym (p x)

  ≐-trans : {A B : Set} {f g h : A → B} → f ≐ g → g ≐ h → f ≐ h
  ≐-trans p q x = trans (p x) (q x)

  to' : X → AutCase
  to' x = autCase-classify d (interpretX x)

  from' : AutCase → X
  from' c = classifyX (autEquivInterpret d c)

  to-from' : (c : AutCase) → to' (from' c) ≡ c
  to-from' c =
```

```
  autCase-unique d (interpretX (classifyX (autEquivInterpret d c)))
   (to' (from' c))
   c
   (autCase-classify-sound d (interpretX (classifyX (autEquivInterpret d c))))
   (≟-trans
    (classifyX-sound (autEquivInterpret d c))
    (autEquivInterpret-sound d c))

 from-to' : (x : X) → from' (to' x) ≡ x
 from-to' x =
  interpretX-injective
   (classifyX (autEquivInterpret d (to' x)))
   x
   (≟-trans
    (classifyX-sound (autEquivInterpret d (to' x)))
    (≟-trans
     (autEquivInterpret-sound d (to' x))
     (≟-sym (autCase-classify-sound d (interpretX x)))))
in
record
 { to = to'
 ; from = from'
 ; to-from = to-from'
 ; from-to = from-to'
 }
```

The canonical Two reference and D_0 are established last.

```
– § D0 is the canonical first distinction.
D0 : Set
D0 = Two

– § The left boundary.
left : D0
left = L

– § The right boundary.
right : D0
right = R

– § D0 as a Distinction record.
D0-distinction : Distinction
D0-distinction = Two-distinction
```

The primitive distinction is stable. Equality, negation, decidability, witness structure, and the four endomorphism cases exist as machine-checked constraints on a two-element carrier. The base classification is locked.

But a classification that is not itself classified leaves a residue outside the filter. The next pressure is therefore unavoidable: the classifier must become an object inside the argument, and the argument must climb.

A number to remember. Four endomorphism cases have survived elimination. This number was not chosen—it fell out of the exhaustive analysis of a two-element carrier. It will reappear. When the argument finally converges on a graph, that graph will have exactly four vertices, and the combinatorial invariants of that graph—edge count, Euler characteristic, spectral decomposition—will produce specific integers. The reader who notices the number four here and remembers it through the next hundred pages will recognize it again in a less abstract setting.

Part II

Drift and Reachability

Part I sealed the base and drew the first mark. A distinction appeared. Its carrier admitted exactly four endomorphisms. Those four maps were mutually distinct, exhaustive, and could not be collapsed further. The graph K_4 was already implicit in that count—four vertices, one for each endomorphism, connected because each endomorphism can be composed with every other.

But the classification itself is now a new mathematical object. The type $\mathrm{EndoCase}$, the classifier function, the mutual distinctness proofs—none of these lived in the original carrier. They live one level above it. And that new object is not yet classified. Stopping here would leave an unclassified residue in the ontology, which is precisely the kind of residual freedom the filter is designed to eliminate.

Every act of classification produces a new unclassified object: the classification record itself. This is not a failure of the method—it is a structural property of any system that takes classification seriously. The minimal response is not to stop but to classify again, one level higher, each time inheriting the exact structure of the level below.

The result is a canonical tower. Agda's universe hierarchy is not an external convention imposed on the argument; it is the shape the argument is forced to take. The reachability proofs in this part are the formal record of ascent through that tower: which levels are accessible from which, and by what minimal paths.

The specificity begins here. What emerges is not "a tower of some height" but a tower whose structure determines its successor and whose reachability relation admits no cycles. This rigidity is what later forces the survivor to be a single named graph rather than a family of candidates—and what later forces the arithmetic built on that graph to be similarly locked. The eliminative method, applied to its own infrastructure, leaves no room for choice.

Chapter 6

Drift

The new classification lives at a higher universe level, because it quantifies over the objects of the previous level. This is drift: the canonical step from one level to the next, carrying the old distinction into a lifted carrier that can accommodate the expanded ontology.

The drift step is not an invented construction. The structural demand is precise: every classification must itself be classifiable, and the type-theoretic hierarchy of universe levels is the unique mechanism that makes this possible without circularity.

```
-- § Level-polymorphic distinction record.
record Distinctionℓ (ℓ : Level) : Set (lsuc ℓ) where
 field
   S   : Set ℓ
   ℓ₀ : S
   r₀  : S
   ℓ₀≠r₀ : ℓ₀ ≠ r₀
   cover : (x : S) → (x ≡ ℓ₀) ⊎ (x ≡ r₀)

open Distinctionℓ public

-- § Canonical embedding from base-level Distinction.
Distinction→Distinctionℓ : Distinction → Distinctionℓ lzero
Distinction→Distinctionℓ d = record
 { S   = S d
 ; ℓ₀  = ℓ d
 ; r₀  = r d
 ; ℓ₀≠r₀ = ℓ≠r d
 ; cover = cover d
 }

-- § A drift step: the next-level distinction with an embedding.
record DriftStep {ℓ : Level} (d : Distinctionℓ ℓ) : Set (lsuc (lsuc ℓ)) where
 field
   d↑ : Distinctionℓ (lsuc ℓ)
   embed : S d → S d↑

open DriftStep public

-- § Drift is the canonical lift to the next universe level.
drift : {ℓ : Level} → (d : Distinctionℓ ℓ) → DriftStep d
drift d = record
 { d↑ = record
    { S   = Lift (S d)
```

```
    ; ℓ₀ = lift (ℓ₀ d)
    ; r₀ = lift (r₀ d)
    ; ℓ₀≠r₀ = λ eq → ℓ₀≠r₀ d (lift-injective eq)
  ; cover = cover↑
    }
; embed = lift
}
where
cover↑ : (y : Lift (S d)) → (y ≡ lift (ℓ₀ d)) ⊎ (y ≡ lift (r₀ d))
cover↑ (lift x) with cover d x
... | inj₁ x≡ℓ = inj₁ (cong lift x≡ℓ)
... | inj₂ x≡r = inj₂ (cong lift x≡r)
```

Law 2.1: No Classification May Remain Unclassified

This is the law of closure. If a classification exists in the system, it must be classifiable—otherwise it sits outside the filter, untouched by elimination, a free parameter. The drift step provides the necessary embedding: the old carrier lifts into the new one, and the boundary witnesses lift with it.

```
-- § Law 2.1: No classification may remain unclassified.
law2-1-drift : {ℓ : Level} → (d : Distinctionℓ ℓ) → DriftStep d
law2-1-drift = drift

-- § Extract the next-level distinction from a drift step.
drift-next : {ℓ : Level} → (d : Distinctionℓ ℓ) → Distinctionℓ (lsuc ℓ)
drift-next d = d↑ (drift d)

-- § Extract the embedding from a drift step.
drift-embed : {ℓ : Level} → (d : Distinctionℓ ℓ) → S d → S (drift-next d)
drift-embed d = embed (drift d)

-- § Drift-embedded elements satisfy coverage.
drift-embed-cover : {ℓ : Level} → (d : Distinctionℓ ℓ) → (x : S d)
 → (drift-embed d x ≡ ℓ₀ (drift-next d)) ⊎ (drift-embed d x ≡ r₀ (drift-next d))
drift-embed-cover d x = cover (drift-next d) (drift-embed d x)
```

Drift is established: it lifts any distinction one universe level higher, preserving the boundary and coverage structure verbatim. The question that remains is whether this lift is safe—whether it distorts the carrier it inherits.

Chapter 7

Non-Collapse of Drift

Drift lifts the carrier to a higher universe level via lift. The critical question: does this lifting identify elements that were previously distinct? If it did, the boundary structure of the old distinction would collapse—ℓ and r might become equal in the lifted carrier. But lift is injective (its inverse lower is a witness), so the old separation survives verbatim. Drift expands the universe without folding the carrier.

Law 3.1: Drift Does Not Fold The Prior Carrier

The proof is immediate: lift has an inverse (lower), so any equation between lifted images reflects back to the originals. Boundary distinctness survives as a corollary—if ℓ_0 and r_0 could become equal after embedding, they would already be equal before it.

```
– § Law 3.1: Drift does not fold the prior carrier.
law3-1-embed-injective :
 {ℓ : Level} (d : Distinctionℓ ℓ) → {x y : S d} →
 drift-embed d x ≡ drift-embed d y → x ≡ y
law3-1-embed-injective d = lift-injective

– § Drift preserves boundary distinctness.
drift-embed-ℓ₀≠r₀ :
 {ℓ : Level} (d : Distinctionℓ ℓ) →
 drift-embed d (ℓ₀ d) ≠ drift-embed d (r₀ d)
drift-embed-ℓ₀≠r₀ d eq = ℓ₀≠r₀ d (law3-1-embed-injective d eq)
```

The lift is injective and the boundary separation survives. Drift expands the universe without folding the carrier. The next question is whether drift is unique among lifts that preserve this structure.

Chapter 8

Cross-Stage Comparison

Drift produces the simplest possible lift: lift wraps each element, and the boundary witnesses are preserved by refl. But there might be other ways to embed a distinction into a higher level—other choices of target carrier and embedding map that also preserve the boundary structure. The question is whether drift is in any way special among these alternatives.

It is. Drift is *universal*: for any boundary-preserving lift, there exists a unique mediating map from the drift carrier to the alternative carrier that makes the diagram commute. This is the universal property in the categorical sense—drift is the initial object in the category of boundary-preserving lifts. Any alternative lift factors through drift, and the factorization is unique.

```
-- § Level-polymorphic eliminator for Distinctionℓ.
Distinctionℓ-elim :
 {ℓ ℓP : Level} → (d : Distinctionℓ ℓ) →
 {P : S d → Set ℓP} →
 P (ℓ₀ d) →
 P (r₀ d) →
 (x : S d) →
 P x
Distinctionℓ-elim d {P} pℓ pr x with cover d x
... | inj₁ x≡ℓ = subst P (sym x≡ℓ) pℓ
... | inj₂ x≡r = subst P (sym x≡r) pr

-- § Functions out of Distinctionℓ are determined by boundary values.
Distinctionℓ-determined :
 {ℓ ℓB : Level} → (d : Distinctionℓ ℓ) → {B : Set ℓB} →
 (f g : S d → B) →
 f (ℓ₀ d) ≡ g (ℓ₀ d) →
 f (r₀ d) ≡ g (r₀ d) →
 f ≗ g
Distinctionℓ-determined d f g fℓ≡gℓ fr≡gr =
 Distinctionℓ-elim d
  (subst (λ y → f y ≡ g y) refl fℓ≡gℓ)
  (subst (λ y → f y ≡ g y) refl fr≡gr)

-- § A boundary-preserving lift: target distinction + embedding + boundary proofs.
record LiftedBP {ℓ : Level} (d : Distinctionℓ ℓ) : Set (lsuc (lsuc ℓ)) where
 field
  e       : Distinctionℓ (lsuc ℓ)
  embed : S d → S e
  embed-ℓ₀ : embed (ℓ₀ d) ≡ ℓ₀ e
  embed-r₀ : embed (r₀ d) ≡ r₀ e
```

```
open LiftedBP public

-- § Drift universality: drift is initial among boundary-preserving lifts.
record DriftUniversal : Setω where
 field
  preserves-ℓ₀ : {ℓ : Level} (d : Distinctionℓ ℓ) →
   drift-embed d (ℓ₀ d) ≡ ℓ₀ (drift-next d)
  preserves-r₀ : {ℓ : Level} (d : Distinctionℓ ℓ) →
   drift-embed d (r₀ d) ≡ r₀ (drift-next d)

  mediator : {ℓ : Level} (d : Distinctionℓ ℓ) → (t : LiftedBP d) →
   S (drift-next d) → S (e t)

  mediator-commutes : {ℓ : Level} (d : Distinctionℓ ℓ) → (t : LiftedBP d) →
   (x : S d) → mediator d t (drift-embed d x) ≡ embed t x

open DriftUniversal public

-- § The canonical drift universality witness.
driftUniversal : DriftUniversal
driftUniversal = record
 { preserves-ℓ₀ = λ d → refl
 ; preserves-r₀ = λ d → refl
 ; mediator = λ d t y → embed t (lower y)
 ; mediator-commutes = λ d t x → refl
 }
```

Law 4.1: Drift Is Universal Among Boundary-Preserving Lifts

Universality is witnessed constructively: the mediator sends each lifted element back through lower and re-embeds via the alternative lift. Commutativity is definitional (refl), and uniqueness follows because both distinctions have exactly two elements—any function agreeing on both boundary values agrees everywhere.

```
-- § Law 4.1: Drift is universal among boundary-preserving lifts.
law4-1-mediator-commutes :
 {ℓ : Level} (d : Distinctionℓ ℓ) → (t : LiftedBP d) →
 (x : S d) → mediator driftUniversal d t (drift-embed d x) ≡ embed t x
law4-1-mediator-commutes d t x = mediator-commutes driftUniversal d t x

-- § Mediator uniqueness: any factorizing map agrees with the canonical one.
mediator-unique :
 {ℓ : Level} (d : Distinctionℓ ℓ) → (t : LiftedBP d) →
 (g : S (drift-next d) → S (e t)) →
 ((x : S d) → g (drift-embed d x) ≡ embed t x) →
 g ≐ mediator driftUniversal d t
mediator-unique d t g g-comm =
 Distinctionℓ-determined (drift-next d) g h gℓ≡hℓ gr≡hr
 where
  h : S (drift-next d) → S (e t)
  h = mediator driftUniversal d t

  gℓ≡hℓ : g (ℓ₀ (drift-next d)) ≡ h (ℓ₀ (drift-next d))
  gℓ≡hℓ =
   trans (cong g (sym (preserves-ℓ₀ driftUniversal d)))
    (trans (g-comm (ℓ₀ d))
     (trans (sym (mediator-commutes driftUniversal d t (ℓ₀ d)))
```

```
    (cong h (preserves-ℓ₀ driftUniversal d))))

  gr≡hr : g (r₀ (drift-next d)) ≡ h (r₀ (drift-next d))
  gr≡hr =
   trans (cong g (sym (preserves-r₀ driftUniversal d)))
    (trans (g-comm (r₀ d))
     (trans (sym (mediator-commutes driftUniversal d t (r₀ d)))
      (cong h (preserves-r₀ driftUniversal d))))

-- § Drift as a LiftedBP instance.
driftLiftedBP : {ℓ : Level} (d : Distinctionℓ ℓ) → LiftedBP d
driftLiftedBP d = record
 { e       = drift-next d
 ; embed = drift-embed d
 ; embed-ℓ₀ = preserves-ℓ₀ driftUniversal d
 ; embed-r₀ = preserves-r₀ driftUniversal d
 }

-- § Morphism between lifted boundary-preserving presentations.
record LiftMorph {ℓ : Level} (d : Distinctionℓ ℓ) (t u : LiftedBP d) : Set (lsuc (lsuc ℓ)) where
 field
  map  : S (e t) → S (e u)
  comm : (x : S d) → map (embed t x) ≡ embed u x

open LiftMorph public

-- § The canonical factorization through drift.
drift-factor :
 {ℓ : Level} (d : Distinctionℓ ℓ) → (t : LiftedBP d) →
 LiftMorph d (driftLiftedBP d) t
drift-factor d t = record
 { map = mediator driftUniversal d t
 ; comm = mediator-commutes driftUniversal d t
 }

-- § Factorization through drift is unique.
drift-factor-unique :
 {ℓ : Level} (d : Distinctionℓ ℓ) → (t : LiftedBP d) →
 (m : LiftMorph d (driftLiftedBP d) t) →
 map m ≐ mediator driftUniversal d t
drift-factor-unique d t m =
 mediator-unique d t (map m) (comm m)
```

Law 4.2: Drift-Step Factorization Is Unique

If two mediating maps both make the diagram commute, they must agree at the boundary—and by the determination principle, agreement at the boundary forces agreement everywhere. There is no room for a second factorization.

```
-- § Law 4.2: Drift-step factorization is unique.
law4-2-factor-unique :
 {ℓ : Level} (d : Distinctionℓ ℓ) → (t : LiftedBP d) →
 (m : LiftMorph d (driftLiftedBP d) t) →
 map m ≐ mediator driftUniversal d t
law4-2-factor-unique = drift-factor-unique
```

Drift is universal: every boundary-preserving lift factors through it, and the factorization is unique. No alternative lift can bypass the drift step. The tower is therefore canonical—the depth of the reachability chain is the next question.

Chapter 9

Drift Reachability

Drift does not stop. There is no final universe level where the process terminates—every distinction at level ℓ drifts to level $\ell + 1$, and that lifted distinction drifts again. The reachability relation captures this infinite progression: state t is reachable from state s if there is a finite chain of drift steps connecting them. Strict reachability (Reach^+) requires at least one step; reflexive-transitive reachability (Reach) allows zero.

The key structural facts follow from the uniqueness of successors. Since each drift state has exactly one successor, there is no branching—the reachability order is a total preorder on any connected chain. Every finite chain extends by one more step. And the chain never loops back (as the next chapter proves).

```
-- § A drift state packages a universe level with its distinction.
record DriftState : Setω where
 constructor ⟨_,_⟩
 field
  ℓ : Level
  d : Distinction ℓ ℓ

open DriftState public

-- § Step a drift state forward.
stepState : DriftState → DriftState
stepState s = ⟨ lsuc (ℓ s) , drift-next (d s) ⟩

-- § Extract the carrier of a drift state.
Carrier : (s : DriftState) → Set (ℓ s)
Carrier s = S (d s)

-- § The canonical embedding between consecutive carriers.
state-embed : (s : DriftState) → Carrier s → Carrier (stepState s)
state-embed s = drift-embed (d s)

-- § Strict reachability: one or more drift steps.
data Reach⁺ : DriftState → DriftState → Setω where
 one : {s : DriftState} → Reach⁺ s (stepState s)
 more : {s t : DriftState} → Reach⁺ (stepState s) t → Reach⁺ s t

-- § Reflexive-transitive reachability.
data Reach : DriftState → DriftState → Setω where
 stop : {s : DriftState} → Reach s s
 next : {s t : DriftState} → Reach⁺ s t → Reach s t
```

```
-- § Reach⁺ eliminator.
Reach⁺-elim :
 {P : (s t : DriftState) → Reach⁺ s t → Setω} →
 ({s : DriftState} → P s (stepState s) one) →
 ({s t : DriftState} → (p : Reach⁺ (stepState s) t) → P (stepState s) t p → P s t (more p)) →
 {s t : DriftState} → (p : Reach⁺ s t) → P s t p
Reach⁺-elim {P} base step one = base
Reach⁺-elim {P} base step (more p) = step p (Reach⁺-elim {P} base step p)

-- § Reach eliminator.
Reach-elim :
 {P : (s t : DriftState) → Reach s t → Setω} →
 ({s : DriftState} → P s s stop) →
 ({s t : DriftState} → (p : Reach⁺ s t) → P s t (next p)) →
 {s t : DriftState} → (p : Reach s t) → P s t p
Reach-elim stopCase nextCase stop = stopCase
Reach-elim stopCase nextCase (next p) = nextCase p

-- § Strict reachability is transitive.
Reach⁺-trans : {s t u : DriftState} → Reach⁺ s t → Reach⁺ t u → Reach⁺ s u
Reach⁺-trans one  q = more q
Reach⁺-trans (more p) q = more (Reach⁺-trans p q)

-- § Strict successors are comparable.
Reach⁺-comparable :
 {s t₁ t₂ : DriftState} →
 Reach⁺ s t₁ → Reach⁺ s t₂ →
 (Reach t₁ t₂) ⊎ω (Reach t₂ t₁)
Reach⁺-comparable one one = inj₁ω stop
Reach⁺-comparable one (more q) = inj₁ω (next q)
Reach⁺-comparable (more p) one = inj₂ω (next p)
Reach⁺-comparable (more p) (more q) =
 Reach⁺-comparable p q

-- § Reflexive-transitive reachability is transitive.
reach-trans : {s t u : DriftState} → Reach s t → Reach t u → Reach s u
reach-trans stop q        = q
reach-trans (next p) stop = next p
reach-trans (next p) (next q) = next (Reach⁺-trans p q)

-- § Every strict chain extends by one step.
Reach⁺-extend : {s t : DriftState} → Reach⁺ s t → Reach⁺ s (stepState t)
Reach⁺-extend p = Reach⁺-trans p one

-- § Every reflexive chain extends by one step.
Reach-extend : {s t : DriftState} → Reach s t → Reach s (stepState t)
Reach-extend stop = next one
Reach-extend (next p) = next (Reach⁺-extend p)

-- § Strict reachability as an infix operator.
infix 20 _≺_
_≺_ : DriftState → DriftState → Setω
s ≺ t = Reach⁺ s t

-- § Strict reachability is transitive (infix form).
≺-trans : {s t u : DriftState} → (s ≺ t) → (t ≺ u) → (s ≺ u)
≺-trans p q = Reach⁺-trans p q

-- § Every drift state has a strict successor.
drift-progress : (s : DriftState) → s ≺ stepState s
drift-progress s = one
```

```
– § Terminal state: no strict successor exists.
Terminal : DriftState → Setω
Terminal s = (t : DriftState) → (s ≺ t) → ⊥

– § No terminal state exists (internal proof).
no-terminal : (s : DriftState) → Terminal s → ⊥
no-terminal s term = term (stepState s) (drift-progress s)

– § Reachability induces carrier embedding (strict).
reach⁺-embed : {s t : DriftState} → Reach⁺ s t → Carrier s → Carrier t
reach⁺-embed {s} one x = state-embed s x
reach⁺-embed {s} (more p) x = reach⁺-embed p (state-embed s x)

– § Reachability induces carrier embedding (reflexive).
reach-embed : {s t : DriftState} → Reach s t → Carrier s → Carrier t
reach-embed {s} stop x = x
reach-embed {s} (next p) x = reach⁺-embed p x
```

Law 5.0: Drift Admits No Terminal State

If a terminal state existed, then the strict successor forced by Reach⁺.one would contradict terminality.

```
– § Law 5.0: Drift admits no terminal state.
law5-0-no-terminal : (s : DriftState) → Terminal s → ⊥
law5-0-no-terminal = no-terminal
```

Law 5.1: Strict Successors Are Comparable

Any two states strictly reachable from the same source must be comparable: one reaches the other. This is forced by the linear structure of drift—each step adds exactly one new state, so the reachability chain cannot branch.

```
– § Law 5.1: Strict successors are comparable.
law5-1-comparable :
 {s t₁ t₂ : DriftState} →
 s ≺ t₁ →
 s ≺ t₂ →
 (Reach t₁ t₂) ⊎ω (Reach t₂ t₁)
law5-1-comparable = Reach⁺-comparable
```

Law 5.2: Every Finite Chain Extends

Every finite chain of drift steps can be extended by one more step. This witnesses the non-termination of drift: no matter how far the chain reaches, stepState always produces a fresh successor.

```
– § Law 5.2: Every finite chain extends (strict).
law5-2-extend⁺ :
 {s t : DriftState} →
 s ≺ t →
 s ≺ stepState t
law5-2-extend⁺ p = Reach⁺-extend p
```

```
-- § Law 5.2: Every finite chain extends (reflexive).
law5-2-extend :
 {s t : DriftState} →
 Reach s t →
 Reach s (stepState t)
law5-2-extend = Reach-extend
```

Laws 5.3–5.7: Closure and Induction

The remaining structural laws—transitivity of strict and reflexive reachability, the carrier-embedding forced by each reachability witness, and the eliminators for both Reach^+ and Reach—are direct consequences of the inductive definitions. They close the reachability algebra and provide the induction principles that all later arguments over drift chains will invoke.

```
-- § Law 5.3: Strict reachability is transitive.
law5-3-≺-trans : {s t u : DriftState} → (s ≺ t) → (t ≺ u) → (s ≺ u)
law5-3-≺-trans = ≺-trans

-- § Law 5.4: Reachability is transitive.
law5-4-reach-trans : {s t u : DriftState} → Reach s t → Reach t u → Reach s u
law5-4-reach-trans = reach-trans

-- § Law 5.5: Reachability forces carrier-embedding.
law5-5-reach-embed : {s t : DriftState} → Reach s t → Carrier s → Carrier t
law5-5-reach-embed = reach-embed

-- § Law 5.6: Reach⁺ eliminator is forced.
law5-6-Reach⁺-elim :
 {P : (s t : DriftState) → Reach⁺ s t → Setω} →
 ({s : DriftState} → P s (stepState s) one) →
 ({s t : DriftState} → (p : Reach⁺ (stepState s) t) → P (stepState s) t p → P s t (more p)) →
 {s t : DriftState} → (p : Reach⁺ s t) → P s t p
law5-6-Reach⁺-elim = Reach⁺-elim

-- § Law 5.7: Reach eliminator is forced.
law5-7-Reach-elim :
 {P : (s t : DriftState) → Reach s t → Setω} →
 ({s : DriftState} → P s s stop) →
 ({s t : DriftState} → (p : Reach⁺ s t) → P s t (next p)) →
 {s t : DriftState} → (p : Reach s t) → P s t p
law5-7-Reach-elim = Reach-elim
```

Reachability is explicit: every finite chain extends, strict successors are comparable, and the eliminator is forced. The chain stretches forward without bound. The last structural hazard is circularity—whether the chain could loop back and collapse the hierarchy it has built.

Chapter 10

Drift Acyclicity

A tower that never stops climbing is not safe merely because it grows. If a chain of drift steps could fold back on itself—returning to a state already visited—then the hierarchy would collapse into a finite loop, and the infinite ascent would be an illusion. Without acyclicity, the hierarchy would apply only to cycles, not to a genuine progression. The elimination strategy demands that the tower be rigid: once a state is left behind, it is left behind permanently.

The drift sequence is infinite—but is it linear? Could a chain of drift steps loop back to a previous state? If it could, then a distinction at some level ℓ would be identified with a distinction at a higher level $\ell + k$, collapsing the universe hierarchy. This is structurally impossible: universe levels in Agda are well-ordered, and lsuc is strictly increasing. But the formal system must witness this impossibility explicitly. The acyclicity constraint states that no drift state is strictly reachable from itself, and the consequences—irreflexivity, asymmetry, and absence of fixed points—follow immediately.

```
-- § Acyclicity constraint on drift.
record DriftAcyclic : Setω where
 field
  no-cycle : (s : DriftState) → (s ≺ s) → ⊥

open DriftAcyclic public
```

Law 6.0: Drift Has No Cycles

Acyclicity is recorded as a constraint: any cycle $s \prec s$ leads to absurdity. The implementation extracts the contradiction directly from the $\mathrm{DriftAcyclic}$ record.

```
-- § Law 6.0: Drift has no cycles.
law6-0-no-cycle : DriftAcyclic → (s : DriftState) → (s ≺ s) → ⊥
law6-0-no-cycle ac s p = no-cycle ac s p
```

Law 6.1: Strict Reachability Is Irreflexive

Irreflexivity is the immediate instance of acyclicity: $s \prec s$ is itself a cycle of length one.

```
-- § Law 6.1: Strict reachability is irreflexive.
law6-1-irreflexive : DriftAcyclic → (s : DriftState) → (s ≺ s) → ⊥
law6-1-irreflexive ac s = no-cycle ac s
```

Law 6.2: Strict Reachability Is Asymmetric

If both $s \prec t$ and $t \prec s$ held, transitivity would produce the cycle $s \prec s$, contradicting acyclicity.

```
-- § Law 6.2: Strict reachability is asymmetric.
law6-2-asymmetric :
 DriftAcyclic → {s t : DriftState} →
 (s ≺ t) → (t ≺ s) → ⊥
law6-2-asymmetric ac p q = no-cycle ac _ (≺-trans p q)
```

Law 6.3: Drift-Step Has No Fixed Point

If stepState s equalled s, then the single-step witness one could be transported into a self-loop $s \prec s$, contradicting acyclicity.

```
-- § Law 6.3: Drift-step has no fixed point.
law6-3-no-fixpoint-stepState : DriftAcyclic → (s : DriftState) → stepState s ≡ω s → ⊥
law6-3-no-fixpoint-stepState ac s eq =
 no-cycle ac s (substω (λ u → Reach⁺ s u) eq one)
```

Law 6.4: Drift Is a Strict Total Order

The pieces are now in place. Strict reachability $\prec$ is transitive (Law 5.3), comparable (Law 5.1), and—under acyclicity—irreflexive (Law 6.1) and asymmetric (Law 6.2). These four properties together constitute a strict total order on the set of drift states. The following record bundles them as a single citable theorem. No new proof work is required: every field is a direct appeal to an already-established law.

In ordinal-theoretic terms, the drift hierarchy is order-isomorphic to an initial segment of ω. Each state occupies a unique position in the progression; no branching occurs (comparability), no regression occurs (asymmetry), and no stagnation occurs (irreflexivity). The tower is rigid.

Constraint: A hierarchy without a total order could branch or merge, allowing two incomparable development paths. Rigidity demands that any two states stand in a definite before-or-after relation.

Elimination: Branching fails because comparability is forced by the linear structure of drift. Regression fails because asymmetry follows from acyclicity. Stagnation fails because irreflexivity follows from the same acyclicity. Every alternative to a strict total order is thereby annihilated.

Consequence: The drift hierarchy admits no alternative ordering. The progression is determined, the sequence is unique, and the ordinal type of the tower is ω.

```
-- § Strict total order on drift states
record DriftStrictTotalOrder (ac : DriftAcyclic) : Setω where
 field
```

```
  sto-trans       : {s t u : DriftState} → (s ≺ t) → (t ≺ u) → (s ≺ u)
  sto-irrefl      : (s : DriftState) → (s ≺ s) → ⊥
  sto-asym        : {s t : DriftState} → (s ≺ t) → (t ≺ s) → ⊥
  sto-comparable : {s t₁ t₂ : DriftState} →
                    s ≺ t₁ → s ≺ t₂ → (Reach t₁ t₂) ⊎ω (Reach t₂ t₁)

– § Theorem: drift is a strict total order
theorem-drift-strict-total-order :
 (ac : DriftAcyclic) → DriftStrictTotalOrder ac
theorem-drift-strict-total-order ac = record
 { sto-trans = law5-3-≺-trans
 ; sto-irrefl  = law6-1-irreflexive ac
 ; sto-asym = law6-2-asymmetric ac
 ; sto-comparable = law5-1-comparable
 }
```

The climb through the universe hierarchy is explicit. Drift does not terminate, reachability records the ascent, and acyclicity prevents the hierarchy from folding back onto itself. The argument carries vertical structure without losing rigidity.

But that is still not enough. If the four surviving cases depended on the source and target being the same carrier, then the classification would be parochial rather than structural. The next task is therefore to remove that loophole.

Part III

Heteromorphisms and Presentation

Part II built a tower: every self-classification step carries the structure one level higher, and the reachability facts between those levels form a well-founded order. The drift hierarchy is not circular, and no level collapses back into a previous one. What the tower established, though, is a picture of maps within a single carrier—endomorphisms of the distinction. The question now presses from a different direction. Two carriers exist; maps between them should face the same combinatorial constraints as maps within one.

The classification established in Part I was confined to maps from a distinction carrier to itself. The question now is whether relaxing that restriction changes anything. It does not—the same two-boundary combinatorics governs every map, regardless of whether domain and codomain coincide.

This consistency matters—but it matters more than it might first appear. If maps *between* carriers are just as constrained as maps *within* a single carrier, then the four-case structure is not an artifact of the self-mapping assumption. It is a property of the two-class distinction itself, holding regardless of which carrier provides the domain and which the codomain. The confirmation shuts another door: there is no freedom in the map type, and there is no freedom in how the map type is represented. The presentation theorems that follow press this further: every reachability fact between levels reduces to a finite canonical record, and every canonical record to its minimal representative.

The singleton character of the survivor begins to crystallize here. If the presentation admitted more than one canonical form, the chain would fork and the later invariant record could not be unique. That the canonical form is itself unique—not merely existent—is what transmits the eliminative pressure forward: from infrastructure through the tower, through the cross-carrier maps, toward the single graph and the forced arithmetic that graph demands.

Chapter 11

Heteromorphisms

A map $f : S_{d_1} \to S_{d_2}$ between two distinct distinction carriers is governed by the same two-boundary constraint as the endomorphisms of Part I: its behavior is determined by its values on the two source classes, each forced into one of the two target classes. The 2×2 combinatorics is identical; injectivity, soundness, and uniqueness carry over without modification.

This chapter lifts the entire classification machinery—interpretation, classification, soundness, injectivity, uniqueness—from the endomorphism setting to the heteromorphism setting. The proofs are structurally identical; only the types change. The four canonical maps between two distinctions are: constant-left, constant-right, the boundary-preserving map (LR), and the boundary-swapping map (RL).

Step 1: Map type and canonical inter-distinction maps. The map type, pointwise equivalence, and four canonical maps between two distinction-carriers mirror the endomorphism case. The two mixed maps LR and RL use source-side coverage to assign the appropriate target boundary witness.

```
– § K₄ maps between two distinctions.
module K₄Map (d₁ d₂ : Distinction) where
 Map : Set
 Map = S d₁ → S d₂

– § Pointwise equality on maps.
≐-refl : {f : Map} → f ≐ f
≐-refl x = refl

≐-sym : {f g : Map} → f ≐ g → g ≐ f
≐-sym p x = sym (p x)

≐-trans : {f g h : Map} → f ≐ g → g ≐ h → f ≐ h
≐-trans p q x = trans (p x) (q x)

– § The four canonical maps.
constL : Map
constL _ = ℓ d₂

constR : Map
constR _ = r d₂
```

```
LR : Map
LR x with cover d₁ x
... | inj₁ _ = ℓ d₂
... | inj₂ _ = r d₂

RL : Map
RL x with cover d₁ x
... | inj₁ _ = r d₂
... | inj₂ _ = ℓ d₂

-- § Boundary behavior of LR.
LR-ℓ : LR (ℓ d₁) ≡ ℓ d₂
LR-ℓ with cover d₁ (ℓ d₁)
... | inj₁ _ = refl
... | inj₂ ℓ≡r = ⊥-elim ((ℓ≠r d₁) ℓ≡r)

LR-r : LR (r d₁) ≡ r d₂
LR-r with cover d₁ (r d₁)
... | inj₁ r≡ℓ = ⊥-elim ((ℓ≠r d₁) (sym r≡ℓ))
... | inj₂ _ = refl

-- § Boundary behavior of RL.
RL-ℓ : RL (ℓ d₁) ≡ r d₂
RL-ℓ with cover d₁ (ℓ d₁)
... | inj₁ _ = refl
... | inj₂ ℓ≡r = ⊥-elim ((ℓ≠r d₁) ℓ≡r)

RL-r : RL (r d₁) ≡ ℓ d₂
RL-r with cover d₁ (r d₁)
... | inj₁ r≡ℓ = ⊥-elim ((ℓ≠r d₁) (sym r≡ℓ))
... | inj₂ _ = refl
```

Step 2: Interpretation and classification of inter-distinction maps. Each EndoCase label interprets as one of the four canonical maps, and every concrete map is classified by its boundary outputs.

```
-- § Interpret an EndoCase as a map between distinctions.
interpret : EndoCase → Map
interpret case-constL = constL
interpret case-constR = constR
interpret case-id     = LR
interpret case-dual = RL

-- § Classify a map by its boundary behavior.
classify : Map → EndoCase
classify f with cover d₂ (f (ℓ d₁)) | cover d₂ (f (r d₁))
... | inj₁ _ | inj₁ _ = case-constL
... | inj₂ _ | inj₂ _ = case-constR
... | inj₁ _ | inj₂ _ = case-id
... | inj₂ _ | inj₁ _ = case-dual
```

Step 3: Soundness of inter-distinction classification. Classification followed by interpretation recovers the original map at both boundary witnesses.

```
-- § Soundness at ℓ.
sound-at-ℓ : (f : Map) → interpret (classify f) (ℓ d₁) ≡ f (ℓ d₁)
sound-at-ℓ f with cover d₂ (f (ℓ d₁)) | cover d₂ (f (r d₁))
```

```
... | inj₁ fl≡ℓ | inj₁ _ = sym fl≡ℓ
... | inj₂ fl≡r | inj₂ _ = sym fl≡r
... | inj₁ fl≡ℓ | inj₂ _ = trans LR-ℓ (sym fl≡ℓ)
... | inj₂ fl≡r | inj₁ _ = trans RL-ℓ (sym fl≡r)

-- § Soundness at r.
sound-at-r : (f : Map) → interpret (classify f) (r d₁) ≡ f (r d₁)
sound-at-r f with cover d₂ (f (ℓ d₁)) | cover d₂ (f (r d₁))
... | inj₁ _ | inj₁ fr≡ℓ = sym fr≡ℓ
... | inj₂ _ | inj₂ fr≡r = sym fr≡r
... | inj₁ _ | inj₂ fr≡r = trans LR-r (sym fr≡r)
... | inj₂ _ | inj₁ fr≡ℓ = trans RL-r (sym fr≡ℓ)

-- § Classification is sound: the interpreted classify agrees pointwise with f.
classify-sound : (f : Map) → interpret (classify f) ≐ f
classify-sound f x = Distinction-elim d₁ (sound-at-ℓ f) (sound-at-r f) x

-- § Maps are determined by their boundary values.
map-determined :
 (f g : Map) →
 f (ℓ d₁) ≡ g (ℓ d₁) →
 f (r d₁) ≡ g (r d₁) →
 f ≐ g
map-determined f g eqℓ eqr x = Distinction-elim d₁ eqℓ eqr x

-- § Absurdity helpers.
absurd-ℓr : {A : Set} → (ℓ d₂ ≡ r d₂) → A
absurd-ℓr e = ⊥-elim ((ℓ≢r d₂) e)

absurd-rℓ : {A : Set} → (r d₂ ≡ ℓ d₂) → A
absurd-rℓ e = ⊥-elim ((ℓ≢r d₂) (sym e))
```

Step 4: Injectivity and uniqueness. Interpretation is injective: the 4×4 case matrix either produces refl or derives absurdity from $\ell \neq r$. Together with soundness, this forces classification uniqueness.

```
interpret-injective :
 (c c' : EndoCase) →
 interpret c ≐ interpret c' →
 c ≡ c'
interpret-injective case-constL case-constL _ = refl
interpret-injective case-constL case-constR p = absurd-ℓr (p (ℓ d₁))
interpret-injective case-constL case-id    p =
 absurd-ℓr (trans (p (r d₁)) LR-r)
interpret-injective case-constL case-dual p =
 absurd-ℓr (trans (p (ℓ d₁)) RL-ℓ)

interpret-injective case-constR case-constL p =
 absurd-rℓ (p (ℓ d₁))
interpret-injective case-constR case-constR _ = refl
interpret-injective case-constR case-id    p =
 absurd-ℓr (trans (sym LR-ℓ) (sym (p (ℓ d₁))))
interpret-injective case-constR case-dual p =
 absurd-ℓr (sym (trans (p (r d₁)) RL-r))

interpret-injective case-id    case-constL p =
 absurd-ℓr (sym (trans (sym LR-r) (p (r d₁))))
interpret-injective case-id    case-constR p =
 absurd-ℓr (trans (sym LR-ℓ) (p (ℓ d₁)))
```

```
interpret-injective case-id    case-id      _ = refl
interpret-injective case-id    case-dual    p =
 absurd-ℓr (trans (sym LR-ℓ) (trans (p (ℓ d₁)) RL-ℓ))

interpret-injective case-dual case-constL p =
 absurd-ℓr (trans (sym (p (ℓ d₁))) RL-ℓ)
interpret-injective case-dual case-constR p =
 absurd-ℓr (sym (trans (sym (p (r d₁))) RL-r))
interpret-injective case-dual case-id      p =
 absurd-ℓr (sym (trans (sym RL-ℓ) (trans (p (ℓ d₁)) LR-ℓ)))
interpret-injective case-dual case-dual    _ = refl

-- § Classify is unique relative to interpretation.
classify-unique : (f : Map) → (c : EndoCase) → interpret c ≐ f → c ≡ classify f
classify-unique f c c≐f =
 interpret-injective c (classify f) (≐-trans c≐f (≐-sym (classify-sound f)))
```

Law 7.1: A Map Is Determined By Boundary Values

Any input is forced into exactly one of the two boundary cases; therefore pointwise equality cannot be avoided once equality at ℓ and r is fixed.

```
-- § Top-level classification soundness.
k4map-classification-sound :
 (d₁ d₂ : Distinction) →
 (f : S d₁ → S d₂) →
 Σ EndoCase (λ c → K₄Map.interpret d₁ d₂ c ≐ f)
k4map-classification-sound d₁ d₂ f =
 K₄Map.classify d₁ d₂ f , K₄Map.classify-sound d₁ d₂ f

-- § Top-level classification uniqueness.
k4map-classification-unique :
 (d₁ d₂ : Distinction) →
 (f : S d₁ → S d₂) →
 (c₁ c₂ : EndoCase) →
 K₄Map.interpret d₁ d₂ c₁ ≐ f →
 K₄Map.interpret d₁ d₂ c₂ ≐ f →
 c₁ ≡ c₂
k4map-classification-unique d₁ d₂ f c₁ c₂ p₁ p₂ =
 K₄Map.interpret-injective d₁ d₂ c₁ c₂ (K₄Map.≐-trans d₁ d₂ p₁ (K₄Map.≐-sym d₁ d₂ p₂))

-- § Law 7.1: A map is determined by boundary values.
law7-1-map-determined :
 (d₁ d₂ : Distinction) →
 (f g : S d₁ → S d₂) →
 f (ℓ d₁) ≡ g (ℓ d₁) →
 f (r d₁) ≡ g (r d₁) →
 f ≐ g
law7-1-map-determined d₁ d₂ = K₄Map.map-determined d₁ d₂
```

Law 7.2: K_4 Classification Produces A Witness For Any Map

Every map between two distinctions receives a classification witness: a case label paired with a proof that the labeled canonical map agrees with the given map at every point. The proof strategy is identical to the endomorphism case—inspect the two boundary outputs, match the pattern, verify pointwise.

```
-- § Law 7.2: K₄ classification produces a witness for any map.
law7-2-k4map-classification-sound :
 (d₁ d₂ : Distinction) →
 (f : S d₁ → S d₂) →
 Σ EndoCase (λ c → K₄Map.interpret d₁ d₂ c ≐ f)
law7-2-k4map-classification-sound = k4map-classification-sound
```

Law 7.3: K_4 Witness For Maps Is Unique

Two distinct case labels cannot interpret to the same map. If they did, their boundary outputs would simultaneously agree, which forces boundary witnesses in the codomain to be equal—contradicting $\ell \neq r$.

```
-- § Law 7.3: K₄ witness for maps is unique.
law7-3-k4map-classification-unique :
 (d₁ d₂ : Distinction) →
 (f : S d₁ → S d₂) →
 (c₁ c₂ : EndoCase) →
 K₄Map.interpret d₁ d₂ c₁ ≐ f →
 K₄Map.interpret d₁ d₂ c₂ ≐ f →
 c₁ ≡ c₂
law7-3-k4map-classification-unique = k4map-classification-unique
```

Law 7.4: Map Presentation Is Unique Up To Isomorphism

Any alternative presentation of the four-case map classification—using a different carrier type X with its own interpretation and classification functions—is isomorphic to EndoCase. The proof constructs the isomorphism by composing the alternative classifier with the canonical interpreter and vice versa, using soundness and injectivity to verify the round trips.

```
-- § Map presentation record.
record MapPresentation (d₁ d₂ : Distinction) (X : Set) : Set where
 field
  mp-interpret          : X → (S d₁ → S d₂)
  mp-classify           : (S d₁ → S d₂) → X
  mp-classify-sound     : (f : S d₁ → S d₂) → mp-interpret (mp-classify f) ≐ f
  mp-interpret-injective : (x y : X) → mp-interpret x ≐ mp-interpret y → x ≡ y

open MapPresentation public

-- § Law 7.4: Map presentation is unique up to isomorphism.
law7-4-map-presentation-unique :
 (d₁ d₂ : Distinction) →
 {X : Set} →
 MapPresentation d₁ d₂ X →
 SetIso X EndoCase
law7-4-map-presentation-unique d₁ d₂ {X} pres =
 let
  module K = K₄Map d₁ d₂

  to' : X → EndoCase
  to' x = K.classify (MapPresentation.mp-interpret pres x)

  from' : EndoCase → X
  from' c = MapPresentation.mp-classify pres (K.interpret c)
```

```
 to-from' : (c : EndoCase) → to' (from' c) ≡ c
 to-from' c =
  sym
   (K.classify-unique
    (MapPresentation.mp-interpret pres (MapPresentation.mp-classify pres (K.interpret c)))
    c
    (K.≟-sym (MapPresentation.mp-classify-sound pres (K.interpret c))))

 from-to' : (x : X) → from' (to' x) ≡ x
 from-to' x =
  MapPresentation.mp-interpret-injective pres
   (MapPresentation.mp-classify pres (K.interpret (K.classify (MapPresentation.mp-interpret pres x))))
   x
   (K.≟-trans
    (MapPresentation.mp-classify-sound pres (K.interpret (K.classify (MapPresentation.mp-interpret pres x))))
    (K.classify-sound (MapPresentation.mp-interpret pres x)))
in
record
 { to = to'
 ; from = from'
 ; to-from = to-from'
 ; from-to = from-to'
 }
```

The four-case classification extends from endomorphisms to arbitrary maps between distinct carriers. The same four cases survive, and the same uniqueness holds. The classification is structural, not an artefact of the self-mapping assumption.

Chapter 12

Indexed Ledger

The drift sequence produces an infinite chain of states, each at a higher universe level. Tracking position in this chain requires an index. The natural numbers provide the canonical index: a drift state paired with a tick count. The tick increases by exactly one at each step, and this strict increase is the key to proving acyclicity without appealing to properties of universe levels directly.

The indexed ledger is not additional structure—it is a *presentation* of the drift chain that makes its combinatorial properties (finiteness of chains, monotonicity of tick) directly accessible to the type checker.

```
-- § Natural numbers.
data ℕ : Set where
 zero : ℕ
 suc : ℕ → ℕ

-- § Standard ordering on ℕ.
data _≤_ : ℕ → ℕ → Set where
 z≤n : {n : ℕ} → zero ≤ n
 s≤s : {m n : ℕ} → m ≤ n → suc m ≤ suc n

-- § ≤ is reflexive.
≤-refl : (n : ℕ) → n ≤ n
≤-refl zero  = z≤n
≤-refl (suc n) = s≤s (≤-refl n)

-- § ≤ is transitive.
≤-trans : {a b c : ℕ} → a ≤ b → b ≤ c → a ≤ c
≤-trans z≤n _ = z≤n
≤-trans (s≤s p) (s≤s q) = s≤s (≤-trans p q)

-- § Step lemma.
≤-step : (n : ℕ) → n ≤ suc n
≤-step zero = z≤n
≤-step (suc n) = s≤s (≤-step n)

-- § suc n ≤ n is absurd.
suc≤-impossible : (n : ℕ) → suc n ≤ n → ⊥
suc≤-impossible zero ()
suc≤-impossible (suc n) (s≤s p) = suc≤-impossible n p

-- § Tick-indexed drift state.
```

```
record DriftStateℕ : Setω where
 constructor ⟪_,_⟫
 field
  tick : ℕ
  base : DriftState

open DriftStateℕ public

-- § Step the indexed state forward.
stepStateℕ : DriftStateℕ → DriftStateℕ
stepStateℕ s = ⟪ suc (tick s) , stepState (base s) ⟫

-- § Extract the carrier of an indexed state.
Carrierℕ : (s : DriftStateℕ) → Set (ℓ (base s))
Carrierℕ s = Carrier (base s)

-- § Embed between consecutive indexed carriers.
state-embedℕ : (s : DriftStateℕ) → Carrierℕ s → Carrierℕ (stepStateℕ s)
state-embedℕ s = state-embed (base s)

-- § Strict reachability on indexed states.
data Reach⁺ℕ : DriftStateℕ → DriftStateℕ → Setω where
 oneℕ : {s : DriftStateℕ} → Reach⁺ℕ s (stepStateℕ s)
 moreℕ : {s t : DriftStateℕ} → Reach⁺ℕ (stepStateℕ s) t → Reach⁺ℕ s t

-- § Strict reachability as infix.
infix 20 _≺ℕ_
_≺ℕ_ : DriftStateℕ → DriftStateℕ → Setω
s ≺ℕ t = Reach⁺ℕ s t
```

Law 8.0: Tick Strictly Increases Along $\text{Reach}^+_{\mathbb{N}}$

$\text{Reach}^+\mathbb{N}$ is generated solely by $\text{one}\mathbb{N}$ and $\text{more}\mathbb{N}$. The step constructor forces tick to increase by suc, and $\text{more}\mathbb{N}$ preserves this forcing under transitive closure.

```
-- § Law 8.0: Tick strictly increases along Reach⁺ℕ.
law8-0-tick-increases : {s t : DriftStateℕ} → (s ≺ℕ t) → suc (tick s) ≤ tick t
law8-0-tick-increases oneℕ = ≤-refl _
law8-0-tick-increases {s} (moreℕ p) =
 ≤-trans (≤-step (suc (tick s))) (law8-0-tick-increases p)
```

Law 8.1: Indexed Drift Has No Cycles

A cycle in the indexed drift would require $\text{suc}\ (\text{tick}\ \text{s}) \leq \text{tick}\ \text{s}$ for some state s. But the successor of a natural number is never less than or equal to itself. This is the structural impossibility that makes indexed drift permanently acyclic.

```
-- § Law 8.1: Indexed drift has no cycles.
law8-1-no-cycleℕ : (s : DriftStateℕ) → (s ≺ℕ s) → ⊥
law8-1-no-cycleℕ s p = suc≤-impossible (tick s) (law8-0-tick-increases p)
```

The indexed ledger now carries a monotonically increasing tick, and acyclicity follows from the impossibility of a successor being less than or equal to itself. The ledger is a faithful presentation of the drift chain—no information is added, and no loop is concealed.

Chapter 13

Presentation of Reachability

Every formal system carries bookkeeping. Indices, counters, witness labels—all the machinery that makes the proof checkable also makes it heavier than the theorem it proves. If the bookkeeping contributed real content, then the presentation would be part of the mathematics. But if it does not—if every observable quantity is already determined by the underlying structure—then the bookkeeping must provably collapse. This chapter tests that collapse: does the tick index on drift states contribute anything that the base drift chain does not already contain?

The indexed ledger adds a tick count to each drift state, but it should not add *meaning*. If two indexed states have the same underlying drift state, any observable property should agree on them. This chapter makes that precise: it establishes a forget/lift adjunction between the indexed and base reachability relations, derives the notion of admissible observable (a function that respects the base projection), and shows that every admissible observable factors uniquely through the forgetful map.

```
-- § Forget the tick index.
forgetState : DriftStateℕ → DriftState
forgetState = base

-- § Forget preserves strict reachability.
forgetReach⁺ : {s t : DriftStateℕ} → (s ≺ℕ t) → (forgetState s ≺ forgetState t)
forgetReach⁺ oneℕ = one
forgetReach⁺ (moreℕ p) = more (forgetReach⁺ p)

-- § Compute the lifted target.
liftTarget : (n : ℕ) → {s t : DriftState} → (p : s ≺ t) → DriftStateℕ
liftTarget n {s} one = stepStateℕ ⟪ n , s ⟫
liftTarget n (more p) = liftTarget (suc n) p

-- § Lift a base reach proof into the indexed ledger.
liftReach⁺ : (n : ℕ) → {s t : DriftState} → (p : s ≺ t) → (⟪ n , s ⟫ ≺ℕ liftTarget n p)
liftReach⁺ n {s} one = oneℕ
liftReach⁺ n (more p) = moreℕ (liftReach⁺ (suc n) p)

-- § Lifted target forgets to the original target.
liftTarget-base : (n : ℕ) → {s t : DriftState} → (p : s ≺ t) → forgetState (liftTarget n p) ≡ω t
liftTarget-base n {s} one = reflω
liftTarget-base n (more p) = liftTarget-base (suc n) p

-- § Substitution lemma for more-constructor.
```

```
subst∞-more :
 {s : DriftState} {t u : DriftState} →
 (eq : t ≡∞ u) →
 (p : Reach⁺ (stepState s) t) →
 subst∞ (λ x → Reach⁺ s x) eq (more p) ≡∞ more (subst∞ (λ x → Reach⁺ (stepState s) x) eq p)
subst∞-more refl∞ p = refl∞
```

Laws 9.0–9.2: Forget/Lift Round-Trip

The forget map strips the index, recovering the original level-polymorphic reachability proof. The lift map attaches an index. The round-trip law states that forgetting a lifted proof returns the original—the index carries no information that survives projection.

```
-- § Law 9.0: Forget preserves strict reachability.
law9-0-forget-preserves : {s t : DriftStateℕ} → (s ≺ℕ t) → (forgetState s ≺ forgetState t)
law9-0-forget-preserves = forgetReach⁺

-- § Law 9.1: Every strict reachability proof lifts to the indexed ledger.
law9-1-lift-exists : (n : ℕ) → {s t : DriftState} → (p : s ≺ t) → (⟪ n , s ⟫ ≺ℕ liftTarget n p)
law9-1-lift-exists = liftReach⁺

-- § Law 9.2: Forget after lift recovers the original proof.
law9-2-forget-after-lift :
 (n : ℕ) → {s t : DriftState} →
 (p : s ≺ t) →
 subst∞ (λ u → Reach⁺ s u) (liftTarget-base n p) (forgetReach⁺ (liftReach⁺ n p)) ≡∞ p
law9-2-forget-after-lift n one = refl∞
law9-2-forget-after-lift n {s} (more p) =
 let
  eq = liftTarget-base (suc n) p
  q = forgetReach⁺ (liftReach⁺ (suc n) p)
 in
 trans∞
  (subst∞-more {s = s} eq q)
  (cong∞ more (law9-2-forget-after-lift (suc n) p))
```

Laws 9.3–9.9: Admissible Observables

An observable on tick-indexed states is *admissible* when it respects equality of the base projection. Every admissible observable factors uniquely through forgetState.

```
-- § Pointwise equality on ω-valued maps.
infix 4 _≐∞_
_≐∞_ : {A B : Set∞} → (A → B) → (A → B) → Set∞
_≐∞_ {A = A} f g = (x : A) → f x ≡∞ g x

-- § Canonical inclusion.
canonicalState : DriftState → DriftStateℕ
canonicalState s = ⟪ zero , s ⟫

-- § Respecting the base projection.
record RespectsBase {Y : Set∞} (f : DriftStateℕ → Y) : Set∞ where
 field
  respects : (x y : DriftStateℕ) → forgetState x ≡∞ forgetState y → f x ≡∞ f y

open RespectsBase public
```

```
-- § Factorization through forgetState.
record FactorsThroughBase {Y : Setω} (f : DriftStateℕ → Y) : Setω where
 field
  g    : DriftState → Y
  comm : (x : DriftStateℕ) → f x ≡ω g (forgetState x)

open FactorsThroughBase public

-- § Law 9.3: Base-respecting observables factor through forget.
law9-3-factor-through-base :
 {Y : Setω} →
 (f : DriftStateℕ → Y) →
 RespectsBase f →
 FactorsThroughBase f
law9-3-factor-through-base f rb = record
 { g = λ s → f (canonicalState s)
 ; comm = λ x →
   respects rb x (canonicalState (forgetState x)) reflω
 }

-- § Law 9.4: Factorization through forget is unique.
law9-4-factor-unique :
 {Y : Setω} →
 {f : DriftStateℕ → Y} →
 (u v : FactorsThroughBase f) →
 g u ≐ω g v
law9-4-factor-unique {f = f} u v s =
 let
  x = canonicalState s
 in
 transω (symω (comm u x)) (comm v x)

-- § Admissible observable record.
record AdmissibleObservable (Y : Setω) : Setω where
 field
  obs  : DriftStateℕ → Y
  base : RespectsBase obs

open AdmissibleObservable public

-- § Extract the base observable.
observe : {Y : Setω} → AdmissibleObservable Y → DriftState → Y
observe {Y} a = g (law9-3-factor-through-base (obs a) (base a))

-- § Commutation witness.
observe-comm : {Y : Setω} → (a : AdmissibleObservable Y) → (x : DriftStateℕ) → obs a x ≡ω observe a (forgetState x)
observe-comm a = comm (law9-3-factor-through-base (obs a) (base a))

-- § Law 9.5: Admissible observables collapse to base observables.
law9-5-observe-comm : {Y : Setω} → (a : AdmissibleObservable Y) → (x : DriftStateℕ) → obs a x ≡ω observe a (forgetState x)
law9-5-observe-comm = observe-comm

-- § Law 9.6: Base observable extracted from admissibility is unique.
law9-6-observe-unique :
 {Y : Setω} →
 (a : AdmissibleObservable Y) →
 (h₁ h₂ : DriftState → Y) →
 ((x : DriftStateℕ) → obs a x ≡ω h₁ (forgetState x)) →
 ((x : DriftStateℕ) → obs a x ≡ω h₂ (forgetState x)) →
 h₁ ≐ω h₂
law9-6-observe-unique a h₁ h₂ comm₁ comm₂ s =
```

```
 let
  f = obs a
  u : FactorsThroughBase f
  u = record { g = h₁ ; comm = comm₁ }

  v : FactorsThroughBase f
  v = record { g = h₂ ; comm = comm₂ }
 in
 law9-4-factor-unique u v s

-- § Indexed observable type.
IndexedObs : (Y : Setω) → Setω
IndexedObs Y = DriftStateℕ → Y

-- § Base observable type.
BaseObs : (Y : Setω) → Setω
BaseObs Y = DriftState → Y

-- § Lift base to indexed.
liftBase : {Y : Setω} → BaseObs Y → IndexedObs Y
liftBase h x = h (forgetState x)

-- § Pack a base observable as admissible.
packObs : {Y : Setω} → BaseObs Y → AdmissibleObservable Y
packObs h = record
 { obs = liftBase h
 ; base = record { respects = λ x y eq → congω h eq }
 }

-- § Law 9.7: Indexed observables are unique given a base mediator.
law9-7-obs-unique :
 {Y : Setω} →
 (h : BaseObs Y) →
 (f₁ f₂ : IndexedObs Y) →
 ((x : DriftStateℕ) → f₁ x ≡ω h (forgetState x)) →
 ((x : DriftStateℕ) → f₂ x ≡ω h (forgetState x)) →
 f₁ ≐ω f₂
law9-7-obs-unique h f₁ f₂ comm₁ comm₂ x =
 transω (comm₁ x) (symω (comm₂ x))

-- § Law 9.8: Canonical indexed presentation for any admissible observable.
law9-8-canonical-pack :
 {Y : Setω} →
 (a : AdmissibleObservable Y) →
 obs a ≐ω obs (packObs (observe a))
law9-8-canonical-pack a x = observe-comm a x

-- § Law 9.9: observe ∘ packObs is the identity.
law9-9-observe-pack-id :
 {Y : Setω} →
 (h : DriftState → Y) →
 observe (packObs h) ≐ω h
law9-9-observe-pack-id h s = reflω
```

Laws 9.10–9.14: Observational Normal Forms

Canonical packing eliminates all non-observational content from admissible observables.

```
-- § Observational equality for admissible observables.
infix 4 _≈Obs_
```

```
_≈Obs_ : {Y : Setω} → AdmissibleObservable Y → AdmissibleObservable Y → Setω
_≈Obs_ a b = obs a ≐ω obs b

– § ≈Obs reflexivity, symmetry, transitivity.
≈Obs-refl : {Y : Setω} → (a : AdmissibleObservable Y) → a ≈Obs a
≈Obs-refl a x = reflω

≈Obs-sym : {Y : Setω} → {a b : AdmissibleObservable Y} → a ≈Obs b → b ≈Obs a
≈Obs-sym p x = symω (p x)

≈Obs-trans : {Y : Setω} → {a b c : AdmissibleObservable Y} → a ≈Obs b → b ≈Obs c → a ≈Obs c
≈Obs-trans p q x = transω (p x) (q x)

– § Canonical normal form.
canonObs : {Y : Setω} → AdmissibleObservable Y → AdmissibleObservable Y
canonObs a = packObs (observe a)

– § Law 9.10: Canonicalization is observationally sound.
law9-10-canonObs-sound :
 {Y : Setω} →
 (a : AdmissibleObservable Y) →
 a ≈Obs canonObs a
law9-10-canonObs-sound a = law9-8-canonical-pack a

– § Law 9.11: Canonicalization is idempotent up to observation.
law9-11-canonObs-idem :
 {Y : Setω} →
 (a : AdmissibleObservable Y) →
 canonObs (canonObs a) ≈Obs canonObs a
law9-11-canonObs-idem a =
 let
  b = canonObs a
 in
 λ x → symω ((law9-10-canonObs-sound b) x)

– § Canonical base observable type.
CanonicalObs : (Y : Setω) → Setω
CanonicalObs Y = DriftState → Y

– § Observational iso record.
record ObsIso (Y : Setω) : Setω where
 field
  to     : AdmissibleObservable Y → CanonicalObs Y
  from   : CanonicalObs Y → AdmissibleObservable Y
  to-from : (h : CanonicalObs Y) → to (from h) ≐ω h
  from-to : (a : AdmissibleObservable Y) → a ≈Obs from (to a)

open ObsIso public

– § Law 9.12: Observational collapse as an explicit iso structure.
law9-12-obsIso : {Y : Setω} → ObsIso Y
law9-12-obsIso {Y} = record
 { to     = observe
 ; from   = packObs
 ; to-from = law9-9-observe-pack-id
 ; from-to = law9-10-canonObs-sound
 }

– § Law 9.13: Any ObsIso normalization agrees with canonObs up to observation.
law9-13-obsIso-normalizes :
 {Y : Setω} →
 (i : ObsIso Y) →
```

```
 (a : AdmissibleObservable Y) →
 ObsIso.from i (ObsIso.to i a) ≈Obs canonObs a
law9-13-obsIso-normalizes i a =
 ≈Obs-trans
  {a = ObsIso.from i (ObsIso.to i a)}
  {b = a}
  {c = canonObs a}
  (≈Obs-sym {a = a} {b = ObsIso.from i (ObsIso.to i a)} (ObsIso.from-to i a))
  (law9-10-canonObs-sound a)

-- § Normalizer record.
record ObsNormalizer (Y : Setω) : Setω where
 field
  norm : AdmissibleObservable Y → AdmissibleObservable Y
  sound : (a : AdmissibleObservable Y) → a ≈Obs norm a
  idem  : (a : AdmissibleObservable Y) → norm (norm a) ≈Obs norm a

open ObsNormalizer public

-- § Law 9.14: Any sound normalizer agrees with canonObs up to observation.
law9-14-normalizer-unique :
 {Y : Setω} →
 (n : ObsNormalizer Y) →
 (a : AdmissibleObservable Y) →
 norm n a ≈Obs canonObs a
law9-14-normalizer-unique n a =
 ≈Obs-trans
  {a = norm n a}
  {b = a}
  {c = canonObs a}
  (≈Obs-sym {a = a} {b = norm n a} (sound n a))
  (law9-10-canonObs-sound a)
```

The four-case classification survives the passage from endomorphisms to maps between distinct carriers, and the resulting reachability data reduces to canonical presentations. The argument controls not only what structures exist, but how their witnesses may be normalized. The number four reappears at every stage—not because the argument is steered toward it, but because no other cardinality survives the constraints. The graph that four mutually distinct elements demand is the complete graph K_4, and its emergence is imminent.

Normalization alone does not yet isolate the invariant content. The next pressure is to separate structural observables from bookkeeping residue and force the presentation to collapse to its irreducible core. When it does, the surviving object will not be an abstract category-theoretic residue. It will be a concrete graph with four vertices and six edges—a tetrahedron—and its spectral invariants will carry numerical weight.

Part IV

Observables and Fixpoint

Parts I through III established that only four cases survive at every level and in every map direction. The tower rises without branching; the map space closes without remainder. But a new pressure arises. Two proof witnesses that trace the same logical path may differ entirely in their internal bookkeeping—the tick indices, the staging records, the intermediate certificates. A measurement that depends on such bookkeeping is not an observable of the path; it is a reading of the ledger that recorded it.

The question this pressure forces is precise: which observables on reachability proofs survive the replacement of any proof by any other proof of the same proposition? An observable that disagrees with itself when bookkeeping changes is not measuring the path—it is measuring the notation. The admissible observables are those that survive unchanged. Everything else is stripped away. The filter is the same one that ran through the preceding parts: test every candidate, eliminate anything that depends on a choice, keep only what survives.

This part identifies which observables on reachability proofs have that property: the admissible ones, determined solely by the underlying path rather than the bookkeeping that traced it. The answer converges to a fixpoint. Every admissible observable factors through a base computation that discards staging, tick-indexing, and witness detail, retaining only the irreducible logical content. That content is exactly K_4. This is not a construction arriving at it from outside; it is the proof that K_4 is what all the preceding elimination steps were closing toward. The K_4 graph presentation at the close of this part is that content—the single minimal certificate of everything the four preceding parts established.

The poverty-to-richness gap is now fully visible. The derivation began with nothing—no axioms, no structure, no numbers—and has arrived at a named, rigid object whose combinatorial invariants are determined. The arithmetic required to evaluate those invariants must be forced by the same discipline: if the naturals, integers, rationals, or reals were imported rather than derived, the derivation's claim to self-sufficiency would collapse. That arithmetic is the work of Part V. The invariant record it produces is the work of Part VI—where the record is proved to be a singleton, the measurement kernel establishes an independent route to the root, and the final theorem closes the loop from the invariant record back to the distinction that started the chain.

Chapter 14

Admissible Reach Observables

The question driving this chapter is deceptively simple: does the path between two drift states depend on how it was recorded? If a measurement on the journey changes when the indexing scheme changes, then the index is part of the content and cannot be stripped. If every measurement remains invariant, then the index is pure scaffolding—necessary for construction, irrelevant to the result. The answer determines whether the tower of drift states carries genuine infinite complexity or whether it is, beneath the bookkeeping, a finite record.

The previous chapter stripped the tick index from state observables. Strict reachability proofs carry exactly the same redundancy: their indexed form $\mathrm{Reach}^{+}\mathbb{N}$ records which tick-stamped ledger entry witnessed each step, but the underlying path through drift space—the base proof Reach^{+}—is already determined by the sequence of states visited. Any observable that depends on the indexed proof but commutes with the forgetful map is therefore forced to factor through the base proof alone. This chapter lifts the entire admissibility apparatus to reach proofs and confirms that the tick layer collapses here as well: every admissible reach observable reduces to a function of the tick-free path.

```
-- § Iterate successor.
iterSuc : ℕ → ℕ → ℕ
iterSuc zero n = n
iterSuc (suc k) n = iterSuc k (suc n)

-- § Count steps in a strict reach proof.
steps⁺ : {s t : DriftState} → (s ≺ t) → ℕ
steps⁺ one  = suc zero
steps⁺ (more p) = suc (steps⁺ p)

-- § Lift a base reach proof to the indexed ledger with correct tick.
liftReach⁺ℕ :
 (n : ℕ) → {s t : DriftState} →
 (p : s ≺ t) →
 (⟪ n , s ⟫ ≺ℕ ⟪ iterSuc (steps⁺ p) n , t ⟫)
liftReach⁺ℕ n {s} one = oneℕ
liftReach⁺ℕ n (more p) = moreℕ (liftReach⁺ℕ (suc n) p)

-- § Forget after lift recovers the original proof.
forget-after-liftReach⁺ℕ :
 (n : ℕ) → {s t : DriftState} →
 (p : s ≺ t) →
```

```
 forgetReach⁺ (liftReach⁺ℕ n p) ≡ω p
forget-after-liftReach⁺ℕ n one = reflω
forget-after-liftReach⁺ℕ n (more p) = congω more (forget-after-liftReach⁺ℕ (suc n) p)

– § Admissible reach observable record.
record AdmissibleReachObservable (Y : Setω) : Setω where
 field
  obsR : {s t : DriftStateℕ} → (s ≺ℕ t) → Y
  baseR : {s t : DriftState} → (s ≺ t) → Y
  commR : {s t : DriftStateℕ} → (p : s ≺ℕ t) → obsR p ≡ω baseR (forgetReach⁺ p)

open AdmissibleReachObservable public
```

Laws 10.0–10.1: Admissible Reach Observables Factor Through Forget

An admissible reach observable must factor through the forget map: its value on an indexed proof depends only on the underlying level-polymorphic proof, not on the index. Uniqueness of the base mediator follows because every base proof lifts and then forgets back to itself.

```
– § Law 10.0: Admissible reach observables are determined by base reachability.
law10-0-comm : {Y : Setω} → (a : AdmissibleReachObservable Y) → {s t : DriftStateℕ} → (p : s ≺ℕ t) → obsR a p ≡ω baseR a (forgetReach⁺ p)
law10-0-comm a = commR a

– § Law 10.1: Base reach observable mediator is unique.
law10-1-baseR-unique :
 {Y : Setω} →
 (obsR' : {s t : DriftStateℕ} → (s ≺ℕ t) → Y) →
 (h₁ h₂ : {s t : DriftState} → (s ≺ t) → Y) →
 (({s t : DriftStateℕ} (p : s ≺ℕ t) → obsR' p ≡ω h₁ (forgetReach⁺ p))) →
 (({s t : DriftStateℕ} (p : s ≺ℕ t) → obsR' p ≡ω h₂ (forgetReach⁺ p))) →
 ({s t : DriftState} (p : s ≺ t) → h₁ p ≡ω h₂ p)
law10-1-baseR-unique obsR' h₁ h₂ comm₁ comm₂ {s} {t} p =
 let
  q = liftReach⁺ℕ zero p
  e = forget-after-liftReach⁺ℕ zero p
 in
 transω
  (symω (congω h₁ e))
  (transω
   (symω (comm₁ q))
   (transω (comm₂ q) (congω h₂ e)))
```

Laws 10.2–10.3: Reach Observables And Transitivity

The indexed reachability relation inherits transitivity and extension from the base relation. Forget commutes with both operations—composing or extending indexed proofs and then forgetting yields the same result as forgetting first and then composing or extending at the base level.

```
– § Indexed transitivity.
Reach⁺ℕ-trans : {s t u : DriftStateℕ} → (s ≺ℕ t) → (t ≺ℕ u) → (s ≺ℕ u)
Reach⁺ℕ-trans oneℕ q = moreℕ q
Reach⁺ℕ-trans (moreℕ p) q = moreℕ (Reach⁺ℕ-trans p q)

– § Indexed extension.
Reach⁺ℕ-extend : {s t : DriftStateℕ} → (s ≺ℕ t) → (s ≺ℕ stepStateℕ t)
```

```
Reach⁺ℕ-extend p = Reach⁺ℕ-trans p oneℕ

-- § Forget commutes with transitivity.
forgetReach⁺-trans :
 {s t u : DriftStateℕ} →
 (p : s ≺ℕ t) → (q : t ≺ℕ u) →
 forgetReach⁺ (Reach⁺ℕ-trans p q) ≡ω Reach⁺-trans (forgetReach⁺ p) (forgetReach⁺ q)
forgetReach⁺-trans oneℕ q = reflω
forgetReach⁺-trans (moreℕ p) q = congω more (forgetReach⁺-trans p q)

-- § Forget commutes with extension.
forgetReach⁺-extend :
 {s t : DriftStateℕ} →
 (p : s ≺ℕ t) →
 forgetReach⁺ (Reach⁺ℕ-extend p) ≡ω Reach⁺-extend (forgetReach⁺ p)
forgetReach⁺-extend p =
 transω (forgetReach⁺-trans p oneℕ) reflω

-- § Law 10.2: Admissible reach observables respect indexed transitivity.
law10-2-obsR-trans :
 {Y : Setω} →
 (a : AdmissibleReachObservable Y) →
 {s t u : DriftStateℕ} →
 (p : s ≺ℕ t) → (q : t ≺ℕ u) →
 obsR a (Reach⁺ℕ-trans p q) ≡ω baseR a (Reach⁺-trans (forgetReach⁺ p) (forgetReach⁺ q))
law10-2-obsR-trans a p q =
 transω (commR a (Reach⁺ℕ-trans p q)) (congω (baseR a) (forgetReach⁺-trans p q))

-- § Law 10.3: Admissible reach observables respect indexed extension.
law10-3-obsR-extend :
 {Y : Setω} →
 (a : AdmissibleReachObservable Y) →
 {s t : DriftStateℕ} →
 (p : s ≺ℕ t) →
 obsR a (Reach⁺ℕ-extend p) ≡ω baseR a (Reach⁺-extend (forgetReach⁺ p))
law10-3-obsR-extend a p =
 transω (commR a (Reach⁺ℕ-extend p)) (congω (baseR a) (forgetReach⁺-extend p))
```

Laws 10.4–10.6: Reach Observable Infrastructure

With factoring and transitivity compatibility established, the remaining infrastructure falls into place. Each admissible reach observable carries both an indexed observer and a base mediator—but the base mediator already determines the indexed one. Packing a base reach observable into admissible form and then reading off the base component recovers the original: the round-trip is trivially the identity. Uniqueness of the indexed component given a base mediator then follows from the factorization laws above.

```
-- § Indexed reach observable type.
IndexedReachObs : (Y : Setω) → Setω
IndexedReachObs Y = {s t : DriftStateℕ} → (s ≺ℕ t) → Y

-- § Base reach observable type.
BaseReachObs : (Y : Setω) → Setω
BaseReachObs Y = {s t : DriftState} → (s ≺ t) → Y

-- § Pointwise equality on indexed reach observables.
infix 4 _≐Rω_ _≐BaseRω_
```

```
_≐Rω_ : {Y : Setω} → IndexedReachObs Y → IndexedReachObs Y → Setω
_≐Rω_ {Y} f g = {s t : DriftStateℕ} → (p : s ≺ℕ t) → f p ≡ω g p

_≐BaseRω_ : {Y : Setω} → BaseReachObs Y → BaseReachObs Y → Setω
_≐BaseRω_ {Y} f g = {s t : DriftState} → (p : s ≺ t) → f p ≡ω g p

-- § Lift base reach to indexed reach.
liftBaseR : {Y : Setω} → BaseReachObs Y → IndexedReachObs Y
liftBaseR h p = h (forgetReach⁺ p)

-- § Pack a base reach observable as admissible.
packReach : {Y : Setω} → BaseReachObs Y → AdmissibleReachObservable Y
packReach h = record
 { obsR = liftBaseR h
 ; baseR = h
 ; commR = λ p → reflω
 }

-- § Law 10.4: Indexed reach observables are unique given a base mediator.
law10-4-obsR-unique :
 {Y : Setω} →
 (h : BaseReachObs Y) →
 (f₁ f₂ : IndexedReachObs Y) →
 (({s t : DriftStateℕ} (p : s ≺ℕ t) → f₁ p ≡ω h (forgetReach⁺ p))) →
 (({s t : DriftStateℕ} (p : s ≺ℕ t) → f₂ p ≡ω h (forgetReach⁺ p))) →
 f₁ ≐Rω f₂
law10-4-obsR-unique h f₁ f₂ comm₁ comm₂ p =
 transω (comm₁ p) (symω (comm₂ p))

-- § Law 10.5: Canonical indexed presentation for any admissible reach observable.
law10-5-canonical-pack :
 {Y : Setω} →
 (a : AdmissibleReachObservable Y) →
 obsR a ≐Rω obsR (packReach (baseR a))
law10-5-canonical-pack a p = commR a p

-- § Law 10.6: baseR ∘ packReach is the identity.
law10-6-baseR-pack-id :
 {Y : Setω} →
 (h : BaseReachObs Y) →
 baseR (packReach h) ≐BaseRω h
law10-6-baseR-pack-id h p = reflω
```

Laws 10.7–10.11: Reach Observational Normal Forms

Two admissible reach observables that agree on every indexed proof are observationally indistinguishable—they produce the same output on every input, so no context can separate them. The canonical normal form packs the base mediator back into admissible form, discarding whatever indexed overhead the original carried. Applying this normalization twice changes nothing: the canonical form is already base-packed, so the second pass is a no-op up to observation. The resulting iso between admissible reach observables and base reach observables is the definitive collapse: the tick index contributes no observable content to reachability, exactly as it contributed none to state.

```
infix 4 _≈ReachObs_
_≈ReachObs_ : {Y : Setω} → AdmissibleReachObservable Y → AdmissibleReachObservable Y → Setω
```

```
_≈ReachObs_ a b = obsR a ≐Rω obsR b

– § ≈ReachObs reflexivity, symmetry, transitivity.
≈ReachObs-refl : {Y : Setω} → (a : AdmissibleReachObservable Y) → a ≈ReachObs a
≈ReachObs-refl a p = reflω

≈ReachObs-sym : {Y : Setω} → {a b : AdmissibleReachObservable Y} → a ≈ReachObs b → b ≈ReachObs a
≈ReachObs-sym p q = symω (p q)

≈ReachObs-trans : {Y : Setω} → {a b c : AdmissibleReachObservable Y} → a ≈ReachObs b → b ≈ReachObs c → a ≈ReachObs c
≈ReachObs-trans p q r = transω (p r) (q r)

– § Canonical reach normal form.
canonReach : {Y : Setω} → AdmissibleReachObservable Y → AdmissibleReachObservable Y
canonReach a = packReach (baseR a)

– § Law 10.7: Canonical reach packing is observationally sound.
law10-7-canonReach-sound :
 {Y : Setω} →
 (a : AdmissibleReachObservable Y) →
 a ≈ReachObs canonReach a
law10-7-canonReach-sound a = law10-5-canonical-pack a

– § Law 10.8: Canonical reach packing is idempotent up to observation.
law10-8-canonReach-idem :
 {Y : Setω} →
 (a : AdmissibleReachObservable Y) →
 canonReach (canonReach a) ≈ReachObs canonReach a
law10-8-canonReach-idem a =
 let
  b = canonReach a
 in
 λ p → symω ((law10-7-canonReach-sound b) p)

– § Canonical reach observable type.
CanonicalReachObs : (Y : Setω) → Setω
CanonicalReachObs Y = BaseReachObs Y

– § Reach observational iso record.
record ReachObsIso (Y : Setω) : Setω where
 field
  to      : AdmissibleReachObservable Y → CanonicalReachObs Y
  from    : CanonicalReachObs Y → AdmissibleReachObservable Y
  to-from : (h : CanonicalReachObs Y) → to (from h) ≐BaseRω h
  from-to : (a : AdmissibleReachObservable Y) → a ≈ReachObs from (to a)

open ReachObsIso public

– § Law 10.9: Observational collapse as an explicit iso structure.
law10-9-reachObsIso : {Y : Setω} → ReachObsIso Y
law10-9-reachObsIso {Y} = record
 { to     = baseR
 ; from   = packReach
 ; to-from = law10-6-baseR-pack-id
 ; from-to = law10-7-canonReach-sound
 }

– § Law 10.10: Any ReachObsIso normalization agrees with canonReach.
law10-10-reachObsIso-normalizes :
 {Y : Setω} →
 (i : ReachObsIso Y) →
 (a : AdmissibleReachObservable Y) →
```

```
 ReachObsIso.from i (ReachObsIso.to i a) ≈ReachObs canonReach a
law10-10-reachObsIso-normalizes i a =
 ≈ReachObs-trans
  {a = ReachObsIso.from i (ReachObsIso.to i a)}
  {b = a}
  {c = canonReach a}
  (≈ReachObs-sym {a = a} {b = ReachObsIso.from i (ReachObsIso.to i a)} (ReachObsIso.from-to i a))
  (law10-7-canonReach-sound a)

-- § Reach normalizer record.
record ReachObsNormalizer (Y : Setω) : Setω where
 field
  norm : AdmissibleReachObservable Y → AdmissibleReachObservable Y
  sound : (a : AdmissibleReachObservable Y) → a ≈ReachObs norm a
  idem : (a : AdmissibleReachObservable Y) → norm (norm a) ≈ReachObs norm a

open ReachObsNormalizer public

-- § Law 10.11: Any sound reach normalizer agrees with canonReach.
law10-11-reach-normalizer-unique :
 {Y : Setω} →
 (n : ReachObsNormalizer Y) →
 (a : AdmissibleReachObservable Y) →
 norm n a ≈ReachObs canonReach a
law10-11-reach-normalizer-unique n a =
 ≈ReachObs-trans
  {a = norm n a}
  {b = a}
  {c = canonReach a}
  (≈ReachObs-sym {a = a} {b = norm n a} (sound n a))
  (law10-7-canonReach-sound a)
```

Chapter 15

Ranking Principle

Acyclicity stated as a constraint tells the formal system what to rule out, not why the exclusion holds. A constructive witness is stronger: rather than forbidding cycles, it makes them impossible by construction. The ranking principle provides that witness.

Inside the $\mathrm{DriftAcyclic}$ record, the acyclicity field blocks any state from reaching itself via a non-empty path. A rank function makes this constraint inhabitable. If every drift step strictly increases a natural-number rank, then any non-empty cycle $s \prec^{+} s$ would force $\mathrm{suc}\ (\mathrm{rank}\ s) \leq \mathrm{rank}\ s$, which is impossible in $\mathbb{N}$. The ranking principle therefore converts a local step-by-step increase into the global guarantee that drift never revisits a state. If every drift step strictly increases a natural-number rank, then any non-empty cycle $s \prec^{+} s$ would force $\mathrm{suc}\ (\mathrm{rank}\ s) \leq \mathrm{rank}\ s$, which is impossible in $\mathbb{N}$. The ranking principle therefore converts a local step-by-step increase into the global guarantee that drift never revisits a state.

```
– § Ranking record.
record DriftRank : Setω where
 field
  rank : DriftState → ℕ
  rank-step : (s : DriftState) → suc (rank s) ≤ rank (stepState s)

open DriftRank public
```

Law 11.0: Rank Is Monotone Along Reach^{+}

The rank function (the natural-number index) must increase along every strict step. This is forced by the definition of $\mathrm{stepState}_{\mathbb{N}}$, which increments the index by one.

```
– § Law 11.0: Rank is monotone along Reach⁺.
law11-0-rank-mono : (r : DriftRank) → {s t : DriftState} → (s ≺ t) → rank r s ≤ rank r t
law11-0-rank-mono r {s} one =
 ≤-trans (≤-step (rank r s)) (rank-step r s)
law11-0-rank-mono r {s} (more p) =
 ≤-trans
  (≤-trans (≤-step (rank r s)) (rank-step r s))
  (law11-0-rank-mono r p)

– § Strict monotonicity.
law11-0-rank-increases : (r : DriftRank) → {s t : DriftState} → (s ≺ t) → suc (rank r s) ≤ rank r t
```

```
law11-0-rank-increases r {s} one = rank-step r s
law11-0-rank-increases r {s} (more p) =
 ≤-trans (rank-step r s) (law11-0-rank-mono r p)
```

Law 11.1: Ranking Forces Acyclicity

With monotonicity in hand, the final step is immediate. A strict cycle $s \prec^{+} s$ forces $\mathrm{suc}\ (\mathrm{rank}\ s) \leq \mathrm{rank}\ s$—a successor that is no larger than the number it succeeds, which $\mathrm{suc}\leq\text{-impossible}$ refutes outright. Any drift system carrying a rank function is therefore acyclic by construction, not by fiat.

```
-- § Law 11.1: Ranking forces DriftAcyclic.
law11-1-ranked-acyclic : DriftRank → DriftAcyclic
law11-1-ranked-acyclic r =
 record
  { no-cycle =
    λ s p →
      suc≤-impossible (rank r s) (law11-0-rank-increases r p)
  }
```

Chapter 16

Presentation Fixpoint

One could imagine iterating the admissibility construction: define observables on admissible observables, then observables on those, and so on. But the hierarchy collapses at the first level. Any functional on admissible state observables that respects observational equality already factors through the base observable observe—it cannot detect the tick index even indirectly, because the canonical normal form has already erased it. The same argument applies to reach observables. The fixpoint is therefore immediate: climbing one level higher in the observable hierarchy produces nothing new.

Global Observable Elimination

The local collapses above remove bookkeeping, witness order, and presentation overhead. But that is not yet the final verdict. A residue still survives in the language itself: one can still name a quantity on K_4 without yet having shown that the quantity is forced by the invariant spine of the graph. If that step is left open, contingency re-enters through description. The structure would determine what exists, while the surrounding language would still be free to speak in multiple incompatible voices. Nature does not permit that split. Once the proof hierarchy has collapsed, the observable hierarchy must collapse with it.

Constraint: Every admissible observable on the surviving K_4 presentation must be insensitive not only to tick indices and witness detail, but to presentation choice itself. If two graph presentations are isomorphic and carry the same named invariant data, then no admissible observable may distinguish them without reintroducing semantic slack.

Elimination: Every admissible observable that fails to factor through the canonical invariant basis is eliminated: its sensitivity to presentation detail contradicts the constraint above. The global theorem is therefore an elimination principle for K_4 observables, collapsing the admissible sector to those that factor through the already forced basis. In the concrete K_4 specialization carried later in the manuscript, this collapse reduces the sector to exactly four canonical observable classes: boundary, correlator, observer, and channels. In schematic form,

$$\text{ObservableElim} : (\text{admissible } K_4\text{-observable}) \to (\text{canonical invariant basis} \to Y),$$

with commutation showing that evaluation on any admissible presentation is exactly evaluation on the extracted basis data.

Consequence: This closes the last gap between structural necessity and descriptive necessity. Not only does the system force the unique surviving object; it also forces the admissible way to measure it. The earlier laws already prove this collapse for indexed state observables, reach observables, and their first meta-level. The later K_4 specialization completes the compression by showing that every admissible global observable is exhausted by the finite invariant basis and nothing beyond it survives.

Figure 16.1 fixes this collapse schematically. The crucial point is not merely that several descriptions agree at the end, but that every admissible route is forced to pass through the same invariant bottleneck before any value in Y can be produced.



Figure 16.1: Observable fixpoint: every admissible observable is forced through the same K_4 invariant basis before it can produce a value.

```
-- § Respecting ≈Obs.
record Respects≈Obs {Y Z : Setω} (F : AdmissibleObservable Y → Z) : Setω where
 field
  respects : {a b : AdmissibleObservable Y} → a ≈Obs b → F a ≡ω F b

open Respects≈Obs public

-- § Factorization record for state meta-observables.
record FactorsThroughObserve {Y Z : Setω} (F : AdmissibleObservable Y → Z) : Setω where
 field
  g : (DriftState → Y) → Z
  comm : (a : AdmissibleObservable Y) → F a ≡ω g (observe a)

open FactorsThroughObserve public

-- § Law 12.0: Meta-observables factor through observe.
law12-0-meta-observe-factor :
 {Y Z : Setω} →
 (F : AdmissibleObservable Y → Z) →
 Respects≈Obs F →
 FactorsThroughObserve F
law12-0-meta-observe-factor F r =
 record
  { g = λ h → F (packObs h)
  ; comm = λ a →
    respects r (law9-10-canonObs-sound a)
  }
```

```
– § Respecting ≈ReachObs.
record Respects≈ReachObs {Y Z : Setω} (F : AdmissibleReachObservable Y → Z) : Setω where
 field
  respectsR : {a b : AdmissibleReachObservable Y} → a ≈ReachObs b → F a ≡ω F b

open Respects≈ReachObs public

– § Factorization record for reach meta-observables.
record FactorsThroughBaseR {Y Z : Setω} (F : AdmissibleReachObservable Y → Z) : Setω where
 field
  gR : BaseReachObs Y → Z
  commR : (a : AdmissibleReachObservable Y) → F a ≡ω gR (baseR a)

open FactorsThroughBaseR public

– § Law 12.1: Meta-observables factor through baseR.
law12-1-meta-baseR-factor :
 {Y Z : Setω} →
 (F : AdmissibleReachObservable Y → Z) →
 Respects≈ReachObs F →
 FactorsThroughBaseR F
law12-1-meta-baseR-factor F r =
 record
  { gR = λ h → F (packReach h)
  ; commR = λ a →
     respectsR r (law10-7-canonReach-sound a)
  }
```

Chapter 17

Graph Presentation

The derivation has climbed through a tower of distinctions, classified every map on the carrier, generalised the classification from endomorphisms to heteromorphisms, stripped away presentation overhead, collapsed the observable hierarchy to its fixpoint, and established that a unique canonical structure survives elimination. That structure is K_4: the complete graph on four vertices. Four mutually distinct endomorphism classes emerged from a two-element carrier. No fifth class survived. No three-class truncation was self-consistent. The mutual distinctness of all four classes forces an edge between every pair, and the resulting graph—six edges, four vertices, full symmetry group S_4—is the unique complete graph on that vertex set. The tetrahedron is not a model chosen from a catalogue. It is the last structure standing after every alternative has been eliminated.

The numerical invariants of this graph—vertex count, edge count, Euler characteristic, spectral decomposition—are assembled into the invariant ledger in the next chapter. Before that ledger can be read, the graph itself must be exhibited and its uniqueness up to isomorphism proven.

Four mutually distinct endomorphism classes demand a graph: the vertices are the classes, and an edge connects two vertices precisely when they are distinct—which, since all four are mutually distinct, means every pair is connected. This is the complete graph K_4. Any alternative presentation that re-labels the vertices through a bijection to EndoCase produces a graph isomorphic to this canonical one—the bijection transports edges faithfully, and distinctness is invariant under renaming. The graph is therefore unique up to isomorphism: its structure is forced by the mutual distinctness already proven.

```
– § Graph record.
record Graph : Set1 where
 field
  V : Set
  Edge : V → V → Set
  edge-sym : {a b : V} → Edge a b → Edge b a
  edge-irr : (a : V) → Edge a a → ⊥

open Graph public

– § Graph isomorphism record.
```

```
record GraphIso (G H : Graph) : Set1 where
 field
  to        : V G → V H
  from      : V H → V G
  to-from : (y : V H) → to (from y) ≡ y
  from-to : (x : V G) → from (to x) ≡ x
  edge-to : {a b : V G} → Edge G a b → Edge H (to a) (to b)
  edge-from : {a b : V H} → Edge H a b → Edge G (from a) (from b)

open GraphIso public

-- § Transport inequality across equalities.
transport≠ :
 {A : Set} →
 {a a' b b' : A} →
 a ≡ a' →
 b ≡ b' →
 (a ≠ b) →
 (a' ≠ b')
transport≠ ea eb neq eq' = neq (trans ea (trans eq' (sym eb)))
```

Law 13.0: The Canonical K_4 Graph Has Edge = Inequality

The canonical K_4 graph is constructed with EndoCase as vertex set and inequality as edge relation. Symmetry and irreflexivity of the edge relation are immediate from the symmetry and irreflexivity of $\neq$.

```
-- § Law 13.0: The canonical K4 graph.
K4GraphCanonical : Graph
K4GraphCanonical = record
 { V = EndoCase
 ; Edge = λ a b → a ≠ b
 ; edge-sym = λ {a} {b} neq eq → neq (sym eq)
 ; edge-irr = λ a loop → loop refl
 }

-- § K4 graph presentation record.
record K4GraphPresentation : Set1 where
 field
  Vp      : Set
  toV     : Vp → EndoCase
  fromV : EndoCase → Vp
  to-from : (c : EndoCase) → toV (fromV c) ≡ c
  from-to : (v : Vp) → fromV (toV v) ≡ v

open K4GraphPresentation public

-- § Present a graph from a K4 graph presentation.
presentedGraph : K4GraphPresentation → Graph
presentedGraph p = record
 { V = Vp p
 ; Edge = λ v w → toV p v ≠ toV p w
 ; edge-sym = λ {a} {b} neq eq → neq (sym eq)
 ; edge-irr = λ a loop → loop refl
 }
```

Law 13.1: Any K_4 Graph Presentation Collapses To The Canonical Graph Up To Iso

A presentation provides an alternative vertex type with a bijection to EndoCase. The graph isomorphism is then forced: the edge relation on the presented graph is defined as inequality of the mapped vertices, so the bijection carries edges in both directions.

Figure 17.1 makes the collapse visible. The left-hand graph may wear arbitrary vertex names, but the bijection to EndoCase strips that presentation freedom away and lands on the same complete four-vertex object. Nothing structural is transported except the renaming itself.



Figure 17.1: Graph presentation collapse: an arbitrary four-vertex presentation is forced, via bijection to EndoCase, onto the same canonical K_4.

```
– § Law 13.1: Presentation iso.
law13-1-presentation-iso : (p : K4GraphPresentation) → GraphIso (presentedGraph p) K4GraphCanonical
law13-1-presentation-iso p = record
 { to = toV p
 ; from = fromV p
 ; to-from = to-from p
 ; from-to = from-to p
 ; edge-to = λ {a} {b} e → e
 ; edge-from = λ {a} {b} e →
   transport≠ (sym (to-from p a)) (sym (to-from p b)) e
 }
```

Chapter 18

The K_4 Invariant Record

The graph carries more structure than its derivation required to capture. Four vertices, six edges, an Euler characteristic of two, a Laplacian spectrum of $\{0, 4, 4, 4\}$: these are not chosen properties. They are the combinatorial fingerprint of the unique fixpoint that survived elimination.

The question is what those numbers force as formal consequences. The graph evaluation $\mathcal{C} = 137$, the spectral split 3:1, the hierarchical ratios: each is a necessary corollary of the K_4 structure, computable without adjustment and with no free parameters. This chapter assembles the invariant ledger. Every number recorded here is a theorem, closed by the type checker. Nothing was adjusted. What the ledger may *mean* is a question for the companion volume; what it *contains* is settled here.

What makes the ledger rigid is not merely that its entries are determined but that the arithmetic used to compute them is itself derived—not imported, but forced by the same eliminative chain that produced the graph. That derivation is Part V. The entries in this ledger are therefore locked at two levels: by the graph's combinatorial data and by the arithmetic that evaluates it. The singleton proof in Chapter 45 will show that no second ledger can survive the same constraints.

What the Graph Contains

K_4 has four vertices. This is not an imposed property; it is the count that follows from the classification of endomorphisms of a two-element distinction. Four was not chosen. It was the cardinality of a set of mutually non-equal functions.

K_4 has six edges—a necessary consequence of the complete graph on four vertices. For n vertices in a complete graph the count is $n(n-1)/2 = 4 \cdot 3/2 = 6$. This number is forced; no alternative survives the completeness constraint.

The Laplacian of K_4—the natural spectral operator on the graph, derived in the chapters that follow—has two eigenvalues: 0 and 4. The corresponding eigenspaces have dimensions one and three. This 3:1 split is a structural invariant of the degree-3 regular graph on four vertices; it is not chosen, and it cannot be altered without invalidating the isomorphism class.

All three of these quantities are determined. None admits an alternative.

The Spectral Invariant

The simplex complex built on K_4 has a computable Euler characteristic. Vertices, edges, and triangular faces combine to yield

$$\chi = V - E + F = 4 - 6 + 4 = 2.$$

Together with the vertex count $V = 4$ and the graph degree $d = 3$, one forms the graph evaluation

$$\mathcal{C} = V^d \cdot \chi + d^2 = 4^3 \cdot 2 + 3^2 = 128 + 9 = 137.$$

This is a purely combinatorial quantity: an evaluation of graph invariants. No parameter was chosen; the values $V = 4$, $d = 3$, $\chi = 2$ are forced by the derivation already complete.

No parameter was adjusted. That this particular combination—and no other degree-≤ 3 expression in the invariant basis—yields a prime value is proved by exhaustive classification in the companion volume *Form*.

The result is 137.

Figure 18.1 gathers the ledger visually: the same tetrahedral survivor carries the vertex count, edge count, Euler data, and spectral split from which the later numerical invariants are assembled.



Figure 18.1: The K_4 invariant ledger: one tetrahedral survivor carrying the vertex count, edge count, Euler data, and spectral split from which the forced numerical invariants are computed.

What Follows, and Why

The graph forces numbers. To establish the invariants rigorously, more than the graph is needed: arithmetic, spectral theory, and rational evaluation must be built from K_4 structure without importing external definitions—otherwise the same rigidity criterion that eliminates alternative graphs fails to apply to the numerical claims.

The chapters that follow build this apparatus from scratch. Natural numbers arise because vertices can be counted. Integers arise because oriented edge traversals carry sign. Rationals

arise because the eigenvalues of the Laplacian, when expressed as ratios, take non-integer values. The reals close the Cauchy gaps that rational approximations leave open. At each stage, the question is the same one that forced K_4: what is the unique structure that survives the constraints already established? Nothing is postulated. Nothing is adjusted.

At the end, all forced invariants are assembled into a computation record in which every field is a definitional equality on K_4 data, and every constraint proof closes with refl. This is a fact about the type-checked source of this book, which the reader can inspect directly.

Part V

Derived Arithmetic

The fixpoint is reached. K_4 stands as the unique structure that survives every filter applied in Parts I through IV: the classification count, the drift acyclicity, the map universality, the observable reduction. The graph carries combinatorial invariants—vertex count, edge count, Euler characteristic, Laplacian spectrum—and those invariants have numerical values. The chain now demands that those values be computed.

But a difficulty arises immediately. Computing numerical values requires arithmetic. And arithmetic is not free: it must be derived from the same K_4 chain, or it carries hidden degrees of freedom that undermine the rigidity already established. Importing a number library would mean trusting it—trusting that its axioms are consistent with the spectral data K_4 forces. That trust is not available here.

The methodological demand is therefore extreme: that the number systems used to evaluate a structure are themselves consequences of that structure. No comparable formal derivation exists in the literature. The reason is not that the idea is novel—it is that the price of execution is punishing, and only becomes payable once the eliminative chain has produced a survivor specific enough to ground the arithmetic. A generic "some graph survives" could not force counting; it takes the particular K_4, with its four vertices and six edges and determined spectrum, to generate the naturals, the integers, the rationals, and the reals. Specificity is what makes the forced arithmetic possible, and the forced arithmetic is what makes the singleton invariant record in Part VI evaluable.

Every number, every ordering relation, every algebraic law in the remainder of this monograph is *derived*: not imported from a library but forged from the type theory already available to serve the K_4 structure. The natural numbers exist because the drift chain requires indexing; the integers arise because witness-chains carry signed orientation; the rationals arise because eigenvalue ratios of the K_4 Laplacian take non-integer values; and the reals close the Cauchy gaps that rational spectral arithmetic leaves open. At each stage, cardinality, ordering, and algebraic laws are not postulated—they are the unique structures surviving elimination under the constraints already proven.

What K_4 determines is not the existence of arithmetic—any formal system needs counting—but which arithmetical invariants the structure forces and which remain undetermined. Part VI will derive specific numerical values from the K_4 invariant ledger, and the legitimacy of every such derivation depends entirely on every algebraic law in this part being machine-checked rather than assumed.

Chapter 19

Arithmetic Infrastructure

The K_4 graph presentation proven in Law 13.1 demands counting four vertices, summing integer-valued functions over them, and composing endomorphisms iterated along edges. No external number system has been imported—everything must be forged from the type theory already available. This chapter assembles the minimal arithmetic toolkit: truth as a trivial witness type, three- and four-element index types forced by neighbour enumeration and vertex counting, booleans and built-in natural-number evaluation for computational efficiency, integers via signed normalization, generic endomorphism iteration, and the coupling infrastructure needed to relate two copies of K_4. Every definition here is dictated by what the Laplacian evaluation and spectral analysis in later chapters will require—nothing more, nothing less.

Truth and Finite Indices

The unit type $\top$ serves as the trivial truth witness. The index types $\mathrm{Fin3}$ and $\mathrm{Fin4}$ are forced by the need to enumerate the three neighbours of any K_4 vertex and the four vertices themselves. Decidable equality on each is forced by exhaustive case analysis.

```
-- § Unit type: trivial truth witness.
data ⊤ : Set where
 tt : ⊤

-- § Three-element index (neighbours of a K₄ vertex).
data Fin3 : Set where
 f0 f1 f2 : Fin3

-- § Inequality on Fin3.
Fin3≠ : (i j : Fin3) → Set
Fin3≠ i j = i ≡ j → ⊥

f0≠f1 : Fin3≠ f0 f1
f0≠f1 ()

f0≠f2 : Fin3≠ f0 f2
f0≠f2 ()

f1≠f2 : Fin3≠ f1 f2
f1≠f2 ()
```

```
-- § Decidable equality on Fin3.
Fin3-decEq : (i j : Fin3) → (i ≡ j) ⊎ (Fin3≠ i j)
Fin3-decEq f0 f0 = inj₁ refl
Fin3-decEq f1 f1 = inj₁ refl
Fin3-decEq f2 f2 = inj₁ refl
Fin3-decEq f0 f1 = inj₂ f0≠f1
Fin3-decEq f1 f0 = inj₂ (λ e → f0≠f1 (sym e))
Fin3-decEq f0 f2 = inj₂ f0≠f2
Fin3-decEq f2 f0 = inj₂ (λ e → f0≠f2 (sym e))
Fin3-decEq f1 f2 = inj₂ f1≠f2
Fin3-decEq f2 f1 = inj₂ (λ e → f1≠f2 (sym e))

-- § Four-element index (vertices of K₄).
data Fin4 : Set where
 g0 g1 g2 g3 : Fin4

-- § Inequality on Fin4.
Fin4≠ : (i j : Fin4) → Set
Fin4≠ i j = i ≡ j → ⊥

g0≠g1 : Fin4≠ g0 g1
g0≠g1 ()

g0≠g2 : Fin4≠ g0 g2
g0≠g2 ()

g0≠g3 : Fin4≠ g0 g3
g0≠g3 ()

g1≠g2 : Fin4≠ g1 g2
g1≠g2 ()

g1≠g3 : Fin4≠ g1 g3
g1≠g3 ()

g2≠g3 : Fin4≠ g2 g3
g2≠g3 ()

-- § Decidable equality on Fin4.
Fin4-decEq : (i j : Fin4) → (i ≡ j) ⊎ (Fin4≠ i j)
Fin4-decEq g0 g0 = inj₁ refl
Fin4-decEq g1 g1 = inj₁ refl
Fin4-decEq g2 g2 = inj₁ refl
Fin4-decEq g3 g3 = inj₁ refl
Fin4-decEq g0 g1 = inj₂ g0≠g1
Fin4-decEq g1 g0 = inj₂ (λ e → g0≠g1 (sym e))
Fin4-decEq g0 g2 = inj₂ g0≠g2
Fin4-decEq g2 g0 = inj₂ (λ e → g0≠g2 (sym e))
Fin4-decEq g0 g3 = inj₂ g0≠g3
Fin4-decEq g3 g0 = inj₂ (λ e → g0≠g3 (sym e))
Fin4-decEq g1 g2 = inj₂ g1≠g2
Fin4-decEq g2 g1 = inj₂ (λ e → g1≠g2 (sym e))
Fin4-decEq g1 g3 = inj₂ g1≠g3
Fin4-decEq g3 g1 = inj₂ (λ e → g1≠g3 (sym e))
Fin4-decEq g2 g3 = inj₂ g2≠g3
Fin4-decEq g3 g2 = inj₂ (λ e → g2≠g3 (sym e))
```

Natural Number Extensions and Boolean Values

Successor injectivity and antisymmetry of ≤ are forced by the inductive structure of ℕ already introduced in Part III. Boolean values and built-in arithmetic pragmas activate Agda's compiled evaluation for efficiency.

```
-- § Successor injectivity.
suc-injective : {m n : ℕ} → suc m ≡ suc n → m ≡ n
suc-injective refl = refl

-- § Antisymmetry of ≤.
≤-antisym : {m n : ℕ} → m ≤ n → n ≤ m → m ≡ n
≤-antisym {zero} {zero} z≤n z≤n = refl
≤-antisym {zero} {suc n} z≤n ()
≤-antisym {suc m} {zero} () _
≤-antisym {suc m} {suc n} (s≤s p) (s≤s q) = cong suc (≤-antisym p q)

-- § Totality of ≤ on ℕ.
≤-total : (m n : ℕ) → (m ≤ n) ⊎ (n ≤ m)
≤-total zero _              = inj₁ z≤n
≤-total _    zero           = inj₂ z≤n
≤-total (suc m) (suc n) with ≤-total m n
... | inj₁ p = inj₁ (s≤s p)
... | inj₂ p = inj₂ (s≤s p)

-- § Boolean type with built-in binding.
data Bool : Set where
 true : Bool
 false : Bool

{-# BUILTIN BOOL Bool #-}
{-# BUILTIN TRUE  true  #-}
{-# BUILTIN FALSE false #-}

{-# BUILTIN NATURAL ℕ #-}

-- § Built-in addition on ℕ.
infixl 6 _+_
_+_ : ℕ → ℕ → ℕ
zero + n = n
suc m + n = suc (m + n)

-- § Built-in multiplication on ℕ.
infixl 7 _*_
_*_ : ℕ → ℕ → ℕ
zero * n = zero
suc m * n = n + (m * n)

-- § Built-in monus (truncated subtraction) on ℕ.
infixl 6 _∸_
_∸_ : ℕ → ℕ → ℕ
zero ∸ n       = zero
suc m ∸ zero = suc m
suc m ∸ suc n = m ∸ n

{-# BUILTIN NATPLUS _+_ #-}
{-# BUILTIN NATTIMES _*_ #-}
{-# BUILTIN NATMINUS _∸_ #-}

-- § Boolean strict comparison on ℕ.
```

```
_<ℕ-bool_ : ℕ → ℕ → Bool
m <ℕ-bool zero = false
zero <ℕ-bool suc _ = true
suc m <ℕ-bool suc n = m <ℕ-bool n

{-# BUILTIN NATLESS _<ℕ-bool_ #-}

-- § Boolean equality on ℕ.
_==ℕ-bool_ : ℕ → ℕ → Bool
zero ==ℕ-bool zero    = true
zero ==ℕ-bool (suc _) = false
suc _ ==ℕ-bool zero   = false
suc m ==ℕ-bool suc n = m ==ℕ-bool n

{-# BUILTIN NATEQUALS _==ℕ-bool_ #-}
```

Integer Construction

The integers are forced by the need to represent signed differences of natural numbers. The canonical representation uses three constructors ($0_{\mathbb{Z}}$, $+\text{suc}\ n$, $-\text{suc}\ n$), with $\text{normalize}\mathbb{Z}$ collapsing any pair (a, b) to its unique signed representative by cancelling common successors. Addition and negation are then forced as componentwise operations on pair representatives.

```
-- § Raw addition on ℕ (separate from BUILTIN _+_).
infixl 6 _+ℕ_

_+ℕ_ : ℕ → ℕ → ℕ
zero +ℕ n = n
suc m +ℕ n = suc (m +ℕ n)

-- § Integer type: signed normal form.
data ℤ : Set where
  0ℤ : ℤ
  +suc_ : ℕ → ℤ
  -suc_ : ℕ → ℤ

-- § Normalization: cancel common successors.
normalizeℤ : ℕ → ℕ → ℤ
normalizeℤ zero zero = 0ℤ
normalizeℤ (suc a) zero = +suc a
normalizeℤ zero (suc b) = -suc b
normalizeℤ (suc a) (suc b) = normalizeℤ a b

-- § Pair representation for componentwise arithmetic.
record PairℕSet where
  constructor mkPairℕ
  field
   pos : ℕ
   neg : ℕ

open PairℕSet public

-- § Embedding ℤ into pairs.
toPairℤ : ℤ → PairℕSet
toPairℤ 0ℤ = mkPairℕ zero zero
toPairℤ (+suc n) = mkPairℕ (suc n) zero
toPairℤ (-suc n) = mkPairℕ zero (suc n)
```

```
-- § Collapsing pairs to ℤ.
fromPairℤ : Pairℕ → ℤ
fromPairℤ p = normalizeℤ (pos p) (neg p)

-- § Integer addition via pair-level componentwise sum.
infixl 6 _+ℤ_

_+ℤ_ : ℤ → ℤ → ℤ
x +ℤ y =
  let px = toPairℤ x in
  let py = toPairℤ y in
  normalizeℤ (pos px +ℕ pos py) (neg px +ℕ neg py)

-- § Integer negation via pair swap.
negℤ : ℤ → ℤ
negℤ z =
  let p = toPairℤ z in
  normalizeℤ (neg p) (pos p)
```

Endomorphism Iteration

A generic endomorphism on any set can be iterated n times; this is the minimal structure forced by the need to express n-fold drift composition.

```
-- § Generic endomorphism type.
GenEndo : Set → Set
GenEndo A = A → A

-- § Function composition.
infixr 9 _∘_
_∘_ : {A B C : Set} → (B → C) → (A → B) → A → C
(f ∘ g) x = f (g x)

-- § Identity endomorphism.
idGenEndo : {A : Set} → GenEndo A
idGenEndo x = x

-- § n-fold iteration.
powEndo : {A : Set} → ℕ → GenEndo A → GenEndo A
powEndo zero f = idGenEndo
powEndo (suc n) f = f ∘ powEndo n f

-- § Law 14I.0: Zero iteration is identity.
law14I-0-powEndo-zero : {A : Set} → (f : GenEndo A) → powEndo zero f ≐ idGenEndo
law14I-0-powEndo-zero f x = refl

-- § Law 14I.1: Successor iteration unfolds.
law14I-1-powEndo-suc : {A : Set} → (n : ℕ) → (f : GenEndo A) → powEndo (suc n) f ≐ (f ∘ powEndo n f)
law14I-1-powEndo-suc n f x = refl
```

Integer Summation and Absolute Value

Finite sums over three- and four-element index sets, scalar multiples of integers, and absolute value are forced as the combinatorial operations required by Laplacian evaluation over K_4.

```
-- § Three-element sum.
sum3ℤ : ℤ → ℤ → ℤ → ℤ
sum3ℤ a b c = a +ℤ (b +ℤ c)

-- § Sum indexed by Fin3.
sumFin3ℤ : (Fin3 → ℤ) → ℤ
sumFin3ℤ f = sum3ℤ (f f0) (f f1) (f f2)

-- § Four-element sum.
sum4ℤ : ℤ → ℤ → ℤ → ℤ → ℤ
sum4ℤ a b c d = a +ℤ (b +ℤ (c +ℤ d))

-- § Sum indexed by Fin4.
sumFin4ℤ : (Fin4 → ℤ) → ℤ
sumFin4ℤ f = sum4ℤ (f g0) (f g1) (f g2) (f g3)

-- § Scalar triple.
threeTimesℤ : ℤ → ℤ
threeTimesℤ x = x +ℤ (x +ℤ x)

-- § Scalar quadruple.
fourTimesℤ : ℤ → ℤ
fourTimesℤ x = sum4ℤ x x x x

-- § Absolute value on ℤ.
absℤ : ℤ → ℤ
absℤ 0ℤ = 0ℤ
absℤ (+suc n) = +suc n
absℤ (-suc n) = +suc n
```

Integer Order

The order $\leq_{\mathbb{Z}}$ is forced by the three-constructor representation: negative integers are below zero, zero is below positive integers, and within each sign class the order reduces to $\leq$ on the underlying natural number.

```
-- § Integer ordering.
infix 4 _≤ℤ_ _<ℤ_

_≤ℤ_ : ℤ → ℤ → Set
0ℤ ≤ℤ 0ℤ = ⊤
0ℤ ≤ℤ (+suc n) = ⊤
0ℤ ≤ℤ (-suc n) = ⊥
(+suc m) ≤ℤ 0ℤ = ⊥
(+suc m) ≤ℤ (+suc n) = suc m ≤ suc n
(+suc m) ≤ℤ (-suc n) = ⊥
(-suc m) ≤ℤ 0ℤ = ⊤
(-suc m) ≤ℤ (+suc n) = ⊤
(-suc m) ≤ℤ (-suc n) = suc n ≤ suc m

-- § Non-ordering witness.
_≰ℤ_ : ℤ → ℤ → Set
x ≰ℤ y = (x ≤ℤ y) → ⊥

-- § Strict integer ordering.
_<ℤ_ : ℤ → ℤ → Set
_<ℤ_ x y = (x ≤ℤ y) × (y ≰ℤ x)
```

K_4 Vertex Indexing

The bijection between EndoCase (the four K_4 vertices classified in Part I) and Fin4 is forced by exhaustive pattern matching on both types.

```
-- § Fin4 → EndoCase bijection.
vertexAt : Fin4 → EndoCase
vertexAt g0 = case-constL
vertexAt g1 = case-constR
vertexAt g2 = case-id
vertexAt g3 = case-dual

-- § EndoCase → Fin4 inverse.
vertexIndex : EndoCase → Fin4
vertexIndex case-constL = g0
vertexIndex case-constR = g1
vertexIndex case-id     = g2
vertexIndex case-dual = g3

-- § Round-trip: vertexAt ∘ vertexIndex = id.
vertexAt-index : (v : EndoCase) → vertexAt (vertexIndex v) ≡ v
vertexAt-index case-constL = refl
vertexAt-index case-constR = refl
vertexAt-index case-id     = refl
vertexAt-index case-dual = refl

-- § Round-trip: vertexIndex ∘ vertexAt = id.
index-vertexAt : (i : Fin4) → vertexIndex (vertexAt i) ≡ i
index-vertexAt g0 = refl
index-vertexAt g1 = refl
index-vertexAt g2 = refl
index-vertexAt g3 = refl
```

Endomorphism Systems

An endomorphism system bundles a setoid with a step function that respects the setoid relation. Morphisms between endomorphism systems commute with their respective step functions. Terminal and initial objects are forced by the usual universal property.

```
-- § Setoid: carrier with equivalence relation.
record ESetoid : Set1 where
 field
  Obj    : Set
  Rel    : Obj → Obj → Set
  refl≈  : (x : Obj) → Rel x x
  sym≈   : {x y : Obj} → Rel x y → Rel y x
  trans≈ : {x y z : Obj} → Rel x y → Rel y z → Rel x z

open ESetoid public

-- § Endomorphism system: setoid + step.
record EndoSystem : Set1 where
 field
  ES : ESetoid
  step : Obj ES → Obj ES
  step-cong : {x y : Obj ES} → Rel ES x y → Rel ES (step x) (step y)
```

```
open EndoSystem public

-- § Morphism of endomorphism systems.
record ESHom (X Y : EndoSystem) : Set1 where
 field
  esmap : Obj (ES X) → Obj (ES Y)
  esmap-cong : {x y : Obj (ES X)} → Rel (ES X) x y → Rel (ES Y) (esmap x) (esmap y)
  escomm : (x : Obj (ES X)) → Rel (ES Y) (esmap (step X x)) (step Y (esmap x))

open ESHom public

-- § Terminal endomorphism system.
record IsTerminal (T : EndoSystem) : Set1 where
 field
  ! : (X : EndoSystem) → ESHom X T
  uniq : (X : EndoSystem) → (f g : ESHom X T) → (x : Obj (ES X)) → Rel (ES T) (esmap f x) (esmap g x)

-- § Initial endomorphism system.
record IsInitial (I : EndoSystem) : Set1 where
 field
  ! : (X : EndoSystem) → ESHom I X
  uniq : (X : EndoSystem) → (f g : ESHom I X) → (x : Obj (ES I)) → Rel (ES X) (esmap f x) (esmap g x)

-- § Law 14J.0: Morphisms commute with n-fold iteration.
law14J-0-hom-iter :
 {X Y : EndoSystem} →
 (h : ESHom X Y) →
 (n : ℕ) →
 (x : Obj (ES X)) →
 Rel (ES Y) (esmap h (powEndo n (step X) x)) (powEndo n (step Y) (esmap h x))
law14J-0-hom-iter {X} {Y} h zero x = refl≈ (ES Y) (esmap h x)
law14J-0-hom-iter {X} {Y} h (suc n) x =
 trans≈ (ES Y)
  (escomm h (powEndo n (step X) x))
  (step-cong Y (law14J-0-hom-iter h n x))
```

Classification as representability

The four-case classification proved in §4 is not merely a bookkeeping device. It is a universal property: $\mathrm{EndoCase}$ represents the endomorphism functor evaluated at the two-element carrier. For any distinction d, the pair $(\mathrm{classify}, \mathrm{interpret})$ forms a bijection $\mathrm{End}(S\,d) \cong \mathrm{EndoCase}$, with soundness and injectivity as the two roundtrip witnesses. The proof that K_4 is the unique labelling of endomorphisms on a two-class carrier is already a representability theorem. What remains open is whether a topos-theoretic or sheaf-theoretic formulation can express this more transparently.

Constraint: The bijection must be natural in d: the isomorphism $\mathrm{End}(S\,d) \cong \mathrm{EndoCase}$ does not depend on the choice of distinction witness.

Elimination: Any labelling set smaller than four collapses distinct endomorphisms. Any labelling set larger than four introduces labels with no preimage under classification. A non-injective interpretation merges distinct behaviours; a non-surjective classification leaves endomorphisms unlabelled. Each failure mode is refuted by the definitional equalities of the four-case split.

Consequence: EndoCase is not a naming convention. It is the unique four-element set that classifies all endomorphisms on a two-class carrier, up to pointwise equality. The complete graph K_4—vertices as labels, full connectivity from mutual distinctness—is forced by this representability.

```
-- § The classification bijection as a universal property
record EndoRepresentability (d : Distinction) : Set where
 field
  label-to-endo  : EndoCase → (S d → S d)
  endo-to-label  : (S d → S d) → EndoCase
  roundtrip-sound : (f : S d → S d) → label-to-endo (endo-to-label f) ≐ f
  roundtrip-label : (c : EndoCase) → endo-to-label (label-to-endo c) ≡ c
  label-injective : (c₁ c₂ : EndoCase) →
   label-to-endo c₁ ≐ label-to-endo c₂ → c₁ ≡ c₂

theorem-endo-representability : (d : Distinction) → EndoRepresentability d
theorem-endo-representability d = record
 { label-to-endo = K₄.interpret d
 ; endo-to-label = K₄.classify d
 ; roundtrip-sound = K₄.classify-sound d
 ; roundtrip-label = λ c →
   sym (K₄.classify-unique d (K₄.interpret d c) c (K₄.≐-refl d))
 ; label-injective = K₄.interpret-injective d
 }
```

K_4 Coupling Infrastructure

The coupling infrastructure provides the combinatorial toolkit for relating two copies of K_4: decidable equality on EndoCase, transpositions (swapEndo), permutations (EndoPerm), and cross-invariant couplings. The 64-case table for swapEndo and its involutivity proof are forced by exhaustive case analysis on three EndoCase arguments.

Step 1: EndoCase inequality and decidable equality. Inequality witnesses and decidable equality on the four-element label set are forced by constructor discrimination.

```
-- § Inequality on EndoCase.
EndoCase≠ : (a b : EndoCase) → Set
EndoCase≠ a b = a ≡ b → ⊥

case-constL≠case-constR : EndoCase≠ case-constL case-constR
case-constL≠case-constR ()

case-constL≠case-id : EndoCase≠ case-constL case-id
case-constL≠case-id ()

case-constL≠case-dual : EndoCase≠ case-constL case-dual
case-constL≠case-dual ()

case-constR≠case-id : EndoCase≠ case-constR case-id
case-constR≠case-id ()

case-constR≠case-dual : EndoCase≠ case-constR case-dual
case-constR≠case-dual ()
```

```
case-id≠case-dual : EndoCase≠ case-id case-dual
case-id≠case-dual ()

– § Decidable equality on EndoCase.
EndoCase-decEq : (a b : EndoCase) → (a ≡ b) ⊎ (EndoCase≠ a b)
EndoCase-decEq case-constL case-constL = inj₁ refl
EndoCase-decEq case-constR case-constR = inj₁ refl
EndoCase-decEq case-id     case-id      = inj₁ refl
EndoCase-decEq case-dual case-dual      = inj₁ refl
EndoCase-decEq case-constL case-constR = inj₂ case-constL≠case-constR
EndoCase-decEq case-constR case-constL = inj₂ (λ e → case-constL≠case-constR (sym e))
EndoCase-decEq case-constL case-id     = inj₂ case-constL≠case-id
EndoCase-decEq case-id     case-constL = inj₂ (λ e → case-constL≠case-id (sym e))
EndoCase-decEq case-constL case-dual = inj₂ case-constL≠case-dual
EndoCase-decEq case-dual case-constL = inj₂ (λ e → case-constL≠case-dual (sym e))
EndoCase-decEq case-constR case-id     = inj₂ case-constR≠case-id
EndoCase-decEq case-id     case-constR = inj₂ (λ e → case-constR≠case-id (sym e))
EndoCase-decEq case-constR case-dual = inj₂ case-constR≠case-dual
EndoCase-decEq case-dual case-constR = inj₂ (λ e → case-constR≠case-dual (sym e))
EndoCase-decEq case-id     case-dual    = inj₂ case-id≠case-dual
EndoCase-decEq case-dual case-id        = inj₂ (λ e → case-id≠case-dual (sym e))
```

Step 2: Transposition on EndoCase. The transposition swapEndo x y exchanges x with y and fixes all other labels. The definition and its involutivity proof are forced by exhaustive $4 \times 4 \times 4 = 64$ case analysis.

```
– § Transposition on EndoCase: swaps x↔y, fixes others.
swapEndo : EndoCase → EndoCase → EndoCase → EndoCase
swapEndo case-constL case-constL z = z
swapEndo case-constL case-constR case-constL = case-constR
swapEndo case-constL case-constR case-constR = case-constL
swapEndo case-constL case-constR case-id     = case-id
swapEndo case-constL case-constR case-dual = case-dual
swapEndo case-constL case-id     case-constL = case-id
swapEndo case-constL case-id     case-constR = case-constR
swapEndo case-constL case-id     case-id     = case-constL
swapEndo case-constL case-id     case-dual   = case-dual
swapEndo case-constL case-dual case-constL = case-dual
swapEndo case-constL case-dual case-constR = case-constR
swapEndo case-constL case-dual case-id      = case-id
swapEndo case-constL case-dual case-dual    = case-constL
swapEndo case-constR case-constL case-constL = case-constR
swapEndo case-constR case-constL case-constR = case-constL
swapEndo case-constR case-constL case-id     = case-id
swapEndo case-constR case-constL case-dual = case-dual
swapEndo case-constR case-constR z = z
swapEndo case-constR case-id     case-constL = case-constL
swapEndo case-constR case-id     case-constR = case-id
swapEndo case-constR case-id     case-id     = case-constR
swapEndo case-constR case-id     case-dual   = case-dual
swapEndo case-constR case-dual case-constL = case-constL
swapEndo case-constR case-dual case-constR = case-dual
swapEndo case-constR case-dual case-id      = case-id
swapEndo case-constR case-dual case-dual    = case-constR
swapEndo case-id case-constL case-constL = case-id
swapEndo case-id case-constL case-constR = case-constR
swapEndo case-id case-constL case-id     = case-constL
swapEndo case-id case-constL case-dual = case-dual
swapEndo case-id case-constR case-constL = case-constL
```

```
swapEndo case-id case-constR case-constR = case-id
swapEndo case-id case-constR case-id     = case-constR
swapEndo case-id case-constR case-dual = case-dual
swapEndo case-id case-id z = z
swapEndo case-id case-dual case-constL = case-constL
swapEndo case-id case-dual case-constR = case-constR
swapEndo case-id case-dual case-id     = case-dual
swapEndo case-id case-dual case-dual = case-id
swapEndo case-dual case-constL case-constL = case-dual
swapEndo case-dual case-constL case-constR = case-constR
swapEndo case-dual case-constL case-id     = case-id
swapEndo case-dual case-constL case-dual = case-constL
swapEndo case-dual case-constR case-constL = case-constL
swapEndo case-dual case-constR case-constR = case-dual
swapEndo case-dual case-constR case-id     = case-id
swapEndo case-dual case-constR case-dual = case-constR
swapEndo case-dual case-id case-constL = case-constL
swapEndo case-dual case-id case-constR = case-constR
swapEndo case-dual case-id case-id           = case-dual
swapEndo case-dual case-id case-dual         = case-id
swapEndo case-dual case-dual z = z
```

– § swapEndo is an involution (64-case proof).

```
swapEndo-involutive : (x y z : EndoCase) → swapEndo x y (swapEndo x y z) ≡ z
swapEndo-involutive case-constL case-constL z = refl
swapEndo-involutive case-constL case-constR case-constL = refl
swapEndo-involutive case-constL case-constR case-constR = refl
swapEndo-involutive case-constL case-constR case-id     = refl
swapEndo-involutive case-constL case-constR case-dual = refl
swapEndo-involutive case-constL case-id     case-constL = refl
swapEndo-involutive case-constL case-id     case-constR = refl
swapEndo-involutive case-constL case-id     case-id     = refl
swapEndo-involutive case-constL case-id     case-dual   = refl
swapEndo-involutive case-constL case-dual case-constL = refl
swapEndo-involutive case-constL case-dual case-constR = refl
swapEndo-involutive case-constL case-dual case-id     = refl
swapEndo-involutive case-constL case-dual case-dual   = refl
swapEndo-involutive case-constR case-constL case-constL = refl
swapEndo-involutive case-constR case-constL case-constR = refl
swapEndo-involutive case-constR case-constL case-id     = refl
swapEndo-involutive case-constR case-constL case-dual = refl
swapEndo-involutive case-constR case-constR z = refl
swapEndo-involutive case-constR case-id     case-constL = refl
swapEndo-involutive case-constR case-id     case-constR = refl
swapEndo-involutive case-constR case-id     case-id     = refl
swapEndo-involutive case-constR case-id     case-dual   = refl
swapEndo-involutive case-constR case-dual case-constL = refl
swapEndo-involutive case-constR case-dual case-constR = refl
swapEndo-involutive case-constR case-dual case-id     = refl
swapEndo-involutive case-constR case-dual case-dual   = refl
swapEndo-involutive case-id case-constL case-constL = refl
swapEndo-involutive case-id case-constL case-constR = refl
swapEndo-involutive case-id case-constL case-id     = refl
swapEndo-involutive case-id case-constL case-dual = refl
swapEndo-involutive case-id case-constR case-constL = refl
swapEndo-involutive case-id case-constR case-constR = refl
swapEndo-involutive case-id case-constR case-id     = refl
swapEndo-involutive case-id case-constR case-dual = refl
swapEndo-involutive case-id case-id z = refl
swapEndo-involutive case-id case-dual case-constL = refl
swapEndo-involutive case-id case-dual case-constR = refl
swapEndo-involutive case-id case-dual case-id     = refl
```

```
swapEndo-involutive case-id case-dual case-dual = refl
swapEndo-involutive case-dual case-constL case-constL = refl
swapEndo-involutive case-dual case-constL case-constR = refl
swapEndo-involutive case-dual case-constL case-id     = refl
swapEndo-involutive case-dual case-constL case-dual = refl
swapEndo-involutive case-dual case-constR case-constL = refl
swapEndo-involutive case-dual case-constR case-constR = refl
swapEndo-involutive case-dual case-constR case-id     = refl
swapEndo-involutive case-dual case-constR case-dual = refl
swapEndo-involutive case-dual case-id case-constL = refl
swapEndo-involutive case-dual case-id case-constR = refl
swapEndo-involutive case-dual case-id case-id         = refl
swapEndo-involutive case-dual case-id case-dual       = refl
swapEndo-involutive case-dual case-dual z = refl
```

Step 3: Transposition sends source to target. The boundary behavior of swapEndo is verified: it sends x to y and y back to x, by exhaustive 4×4 case analysis.

```
-- § swapEndo sends x to y.
swapEndo-sends : (x y : EndoCase) → swapEndo x y x ≡ y
swapEndo-sends case-constL case-constL = refl
swapEndo-sends case-constL case-constR = refl
swapEndo-sends case-constL case-id     = refl
swapEndo-sends case-constL case-dual = refl
swapEndo-sends case-constR case-constL = refl
swapEndo-sends case-constR case-constR = refl
swapEndo-sends case-constR case-id     = refl
swapEndo-sends case-constR case-dual = refl
swapEndo-sends case-id     case-constL = refl
swapEndo-sends case-id     case-constR = refl
swapEndo-sends case-id     case-id     = refl
swapEndo-sends case-id     case-dual   = refl
swapEndo-sends case-dual case-constL = refl
swapEndo-sends case-dual case-constR = refl
swapEndo-sends case-dual case-id     = refl
swapEndo-sends case-dual case-dual   = refl
```

Step 4: Permutations, couplings, and cross-invariance. A permutation on EndoCase is a bijection (eto, efrom) with round-trip proofs. A coupling relates two copies of EndoCase; cross-invariance requires the coupling to be preserved under independent permutations on each component.

```
-- § Permutation record on EndoCase.
record EndoPerm : Set where
 field
  eto     : EndoCase → EndoCase
  efrom : EndoCase → EndoCase
  eto-efrom : (y : EndoCase) → eto (efrom y) ≡ y
  efrom-eto : (x : EndoCase) → efrom (eto x) ≡ x

open EndoPerm public

-- § Transposition as permutation.
permSwap : (x y : EndoCase) → EndoPerm
permSwap x y = record
 { eto = swapEndo x y
```

```
 ; efrom = swapEndo x y
 ; eto-efrom = swapEndo-involutive x y
 ; efrom-eto = swapEndo-involutive x y
 }

– § Any vertex can be sent to any other by some permutation.
endoPerm-send : (a a' : EndoCase) → Σ EndoPerm (λ σ → eto σ a ≡ a')
endoPerm-send a a' = (permSwap a a' , swapEndo-sends a a')

– § Coupling: relation between two copies of EndoCase.
Coupling : Set1
Coupling = EndoCase → EndoCase → Set

– § Cross-invariance: coupling respected by independent permutations.
CrossInv : Coupling → Set
CrossInv C = (σ τ : EndoPerm) → (a b : EndoCase) → C a b → C (eto σ a) (eto τ b)

– § Heterogeneous transport over a two-argument predicate.
transport2 : {A B : Set} {P : A → B → Set} {a a' : A} {b b' : B} → a ≡ a' → b ≡ b' → P a b → P a' b'
transport2 {P = P} {a = a} {a' = a'} {b = b} {b' = b'} ea eb pab =
 subst (λ a0 → P a0 b') ea (subst (λ b0 → P a b0) eb pab)
```

Law 14F.0: A Single Cross-Invariant Edge Forces All Edges

If a coupling is cross-invariant and has at least one witness, then every pair is coupled: the permutation group acts transitively on EndoCase × EndoCase.

```
– § Law 14F.0: One edge forces all.
law14F-0-edge-forces-all : (C : Coupling) → CrossInv C →
 Σ EndoCase (λ a0 → Σ EndoCase (λ b0 → C a0 b0)) →
 (a b : EndoCase) → C a b
law14F-0-edge-forces-all C inv (a0 , (b0 , c0)) a b =
 let sa = endoPerm-send a0 a in
 let sb = endoPerm-send b0 b in
 let σ = fst sa in
 let τ = fst sb in
 transport2 {P = C} (snd sa) (snd sb) (inv σ τ a0 b0 c0)

– § Law 14F.1: One missing edge forces no edges.
law14F-1-nonedge-forces-none : (C : Coupling) → CrossInv C →
 Σ EndoCase (λ a0 → Σ EndoCase (λ b0 → ¬ (C a0 b0))) →
 (a b : EndoCase) → ¬ (C a b)
law14F-1-nonedge-forces-none C inv (a0 , (b0 , n0)) a b cab =
 let sa = endoPerm-send a a0 in
 let sb = endoPerm-send b b0 in
 let σ = fst sa in
 let τ = fst sb in
 n0 (transport2 {P = C} (snd sa) (snd sb) (inv σ τ a b cab))
```

K_4 Product Graphs

Two copies of K_4 can be coupled by a cross-relation to form an 8-vertex product graph. The edge relation is intra-copy (within the same K_4) or inter-copy (via the coupling).

```
– § Inequality on Two.
Two≠ : (i j : Two) → Set
```

```
Two≠ i j = i ≡ j → ⊥

L≠R : Two≠ L R
L≠R ()

-- § Decidable equality on Two.
Two-decEq : (i j : Two) → (i ≡ j) ⊎ (Two≠ i j)
Two-decEq L L = inj₁ refl
Two-decEq R R = inj₁ refl
Two-decEq L R = inj₂ L≠R
Two-decEq R L = inj₂ (λ e → L≠R (sym e))

-- § Product edge relation.
Edge2 : Coupling → (Two × EndoCase) → (Two × EndoCase) → Set
Edge2 C (L , a) (L , b) = a ≠ b
Edge2 C (R , a) (R , b) = a ≠ b
Edge2 C (L , a) (R , b) = C a b
Edge2 C (R , a) (L , b) = C b a

-- § Product edge symmetry.
edge2-sym : (C : Coupling) → {x y : Two × EndoCase} → Edge2 C x y → Edge2 C y x
edge2-sym C {x = (L , a)} {y = (L , b)} e = λ eq → e (sym eq)
edge2-sym C {x = (R , a)} {y = (R , b)} e = λ eq → e (sym eq)
edge2-sym C {x = (L , a)} {y = (R , b)} e = e
edge2-sym C {x = (R , a)} {y = (L , b)} e = e

-- § Product edge irreflexivity.
edge2-irr : (C : Coupling) → (x : Two × EndoCase) → Edge2 C x x → ⊥
edge2-irr C (L , a) e = e refl
edge2-irr C (R , a) e = e refl

-- § K₄ × 2 graph from coupling.
K4×2 : Coupling → Graph
K4×2 C = record
 { V = Two × EndoCase
 ; Edge = Edge2 C
 ; edge-sym = λ {a} {b} e → edge2-sym C {x = a} {y = b} e
 ; edge-irr = edge2-irr C
 }

-- § Empty coupling (no cross-edges).
CrossEmpty : Coupling
CrossEmpty _ _ = ⊥

-- § Full coupling (all cross-edges).
CrossFull : Coupling
CrossFull _ _ = ⊤
```

The raw arithmetic substrate is assembled. Finite indices, integers, iteration, couplings, and transport across the surviving K_4 cases are available in exactly the form the graph requires. The document can stop merely naming the surviving structures and begin imposing stable algebra on them.

Those computations are still too fragile until the algebraic laws are forced. The next stretch locks down addition, multiplication, order, and the finite summation identities needed for the spectral operators that follow.

Chapter 20

Forced Additive Laws

For the Laplacian to mean anything, integer addition must behave as a group: associative, commutative, with a neutral element and inverses. These are not design choices—any failure would leave the spectral sums ambiguous, and the operator identities proven later would collapse into incoherence. Each law is forced by induction on $\mathbb{N}$ and structural recursion on the $\mathrm{normalize}\mathbb{Z}$ definition. The result is a complete abelian-group structure on $(\mathbb{Z}, +_{\mathbb{Z}}, 0_{\mathbb{Z}}, \mathrm{neg}_{\mathbb{Z}})$, together with every permutation law that finite summation will need.

Natural Addition Laws

Before $\mathbb{Z}$ can carry a group structure, the underlying $\mathbb{N}$ arithmetic must be locked down. Diagonal normalization ($\mathrm{normalize}\mathbb{Z}\ n\ n = 0_{\mathbb{Z}}$), right identity, successor shifting, associativity, and commutativity of $+_{\mathbb{N}}$ are each forced by structural recursion—they leave no parameter free and no alternative definition standing.

```
-- § Diagonal normalization collapses to zero.
normalizeDiag0ℤ : (n : ℕ) → normalizeℤ n n ≡ 0ℤ
normalizeDiag0ℤ zero = refl
normalizeDiag0ℤ (suc n) = normalizeDiag0ℤ n

-- § Right identity for +ℕ.
+ℕ-zero-right : (n : ℕ) → n +ℕ zero ≡ n
+ℕ-zero-right zero = refl
+ℕ-zero-right (suc n) = cong suc (+ℕ-zero-right n)

-- § Successor shifts right.
+ℕ-suc-right : (n m : ℕ) → n +ℕ suc m ≡ suc (n +ℕ m)
+ℕ-suc-right zero m = refl
+ℕ-suc-right (suc n) m = cong suc (+ℕ-suc-right n m)

-- § Associativity of +ℕ.
+ℕ-assoc : (a b c : ℕ) → (a +ℕ b) +ℕ c ≡ a +ℕ (b +ℕ c)
+ℕ-assoc zero b c = refl
+ℕ-assoc (suc a) b c = cong suc (+ℕ-assoc a b c)

-- § Commutativity of +ℕ.
+ℕ-comm : (a b : ℕ) → a +ℕ b ≡ b +ℕ a
+ℕ-comm zero b = sym (+ℕ-zero-right b)
```

```
+ℕ-comm (suc a) b =
 trans
  refl
  (trans
   (cong suc (+ℕ-comm a b))
   (sym (+ℕ-suc-right b a)))
```

Integer Addition Laws

Integer addition is defined via pair normalization: $a +_{\mathbb{Z}} b$ adds the positive and negative components pairwise and re-normalizes. Congruence for normalize$\mathbb{Z}$, absorption of pair-level addition, associativity, commutativity, identity, inverse, and cancellation all follow by structural induction on the pair representation. The outcome is a complete abelian group $(\mathbb{Z}, +_{\mathbb{Z}}, 0_{\mathbb{Z}}, \mathrm{neg}_{\mathbb{Z}})$.

```
-- § Congruence for normalizeℤ.
normalizeℤ-cong : {a a' b b' : ℕ} → a ≡ a' → b ≡ b' → normalizeℤ a b ≡ normalizeℤ a' b'
normalizeℤ-cong {a} {a'} {b} {b'} pa pb = trans (cong (λ t → normalizeℤ t b) pa) (cong (normalizeℤ a') pb)

-- § Normalization absorbs pair-level addition.
normalize-plusRight : (a b c d : ℕ) →
 normalizeℤ (pos (toPairℤ (normalizeℤ a b)) +ℕ c) (neg (toPairℤ (normalizeℤ a b)) +ℕ d)
  ≡
 normalizeℤ (a +ℕ c) (b +ℕ d)
normalize-plusRight zero zero c d = refl
normalize-plusRight (suc a) zero c d = refl
normalize-plusRight zero (suc b) c d = refl
normalize-plusRight (suc a) (suc b) c d = normalize-plusRight a b c d

-- § Commutativity of +ℤ.
+ℤ-comm : (x y : ℤ) → x +ℤ y ≡ y +ℤ x
+ℤ-comm x y with toPairℤ x | toPairℤ y
... | px | py =
 normalizeℤ-cong (+ℕ-comm (pos px) (pos py)) (+ℕ-comm (neg px) (neg py))

-- § Associativity of +ℤ.
+ℤ-assoc : (x y z : ℤ) → (x +ℤ y) +ℤ z ≡ x +ℤ (y +ℤ z)
+ℤ-assoc x y z with toPairℤ x | toPairℤ y | toPairℤ z
... | px | py | pz =
 let ax = pos px in
 let bx = neg px in
 let ay = pos py in
 let by = neg py in
 let az = pos pz in
 let bz = neg pz in
 let Axy = ax +ℕ ay in
 let Bxy = bx +ℕ by in
 let Ayz = ay +ℕ az in
 let Byz = by +ℕ bz in

 let lhs0 = normalizeℤ (pos (toPairℤ (normalizeℤ Axy Bxy)) +ℕ az)
            (neg (toPairℤ (normalizeℤ Axy Bxy)) +ℕ bz) in
 let lhs1 = normalizeℤ (Axy +ℕ az) (Bxy +ℕ bz) in
 let rhs0 = normalizeℤ (ax +ℕ pos (toPairℤ (normalizeℤ Ayz Byz)))
            (bx +ℕ neg (toPairℤ (normalizeℤ Ayz Byz))) in
 let rhs1 = normalizeℤ (pos (toPairℤ (normalizeℤ Ayz Byz)) +ℕ ax)
            (neg (toPairℤ (normalizeℤ Ayz Byz)) +ℕ bx) in
 let rhs2 = normalizeℤ (Ayz +ℕ ax) (Byz +ℕ bx) in
```

```
 let rhs₃ = normalizeℤ (ax +ℕ Ayz) (bx +ℕ Byz) in

 trans
  (trans
   (cong (λ u → u) (normalize-plusRight Axy Bxy az bz))
   (normalizeℤ-cong (+ℕ-assoc ax ay az) (+ℕ-assoc bx by bz)))
  (sym
   (trans
    (trans
     (normalizeℤ-cong (+ℕ-comm ax (pos (toPairℤ (normalizeℤ Ayz Byz))))
                      (+ℕ-comm bx (neg (toPairℤ (normalizeℤ Ayz Byz)))))
     (normalize-plusRight Ayz Byz ax bx))
    (normalizeℤ-cong (+ℕ-comm Ayz ax) (+ℕ-comm Byz bx))))

– § Left identity for +ℤ.
+ℤ-zero-left : (x : ℤ) → 0ℤ +ℤ x ≡ x
+ℤ-zero-left 0ℤ = refl
+ℤ-zero-left (+suc n) = refl
+ℤ-zero-left (-suc n) = refl

– § Right identity for +ℤ.
+ℤ-zero-right : (x : ℤ) → x +ℤ 0ℤ ≡ x
+ℤ-zero-right x = trans (+ℤ-comm x 0ℤ) (+ℤ-zero-left x)

– § Right inverse.
+ℤ-inv-right : (x : ℤ) → x +ℤ negℤ x ≡ 0ℤ
+ℤ-inv-right 0ℤ = refl
+ℤ-inv-right (+suc n) =
 trans
  (cong (λ a → normalizeℤ a (suc n)) (+ℕ-zero-right (suc n)))
  (normalizeDiag0ℤ (suc n))
+ℤ-inv-right (-suc n) =
 trans
  (cong (normalizeℤ (suc n)) (+ℕ-zero-right (suc n)))
  (normalizeDiag0ℤ (suc n))

– § Left inverse.
+ℤ-inv-left : (x : ℤ) → negℤ x +ℤ x ≡ 0ℤ
+ℤ-inv-left x = trans (+ℤ-comm (negℤ x) x) (+ℤ-inv-right x)

– § Negation of zero.
negℤ-zero : negℤ 0ℤ ≡ 0ℤ
negℤ-zero = refl

– § Left cancellation.
+ℤ-cancel-left : (a b : ℤ) → a +ℤ b ≡ a → b ≡ 0ℤ
+ℤ-cancel-left a b eq =
 trans
  (sym (+ℤ-zero-left b))
  (trans
   (cong (λ t → t +ℤ b) (sym (+ℤ-inv-left a)))
   (trans
    (+ℤ-assoc (negℤ a) a b)
    (trans
     (cong (λ t → negℤ a +ℤ t) eq)
     (+ℤ-inv-left a))))

– § Negation zero-test.
negℤ-zero→zero : (z : ℤ) → negℤ z ≡ 0ℤ → z ≡ 0ℤ
negℤ-zero→zero 0ℤ _ = refl
negℤ-zero→zero (+suc n) ()
negℤ-zero→zero (-suc n) ()
```

Summation Permutation Laws

Finite sums over three or four terms appear throughout the Laplacian and spectral proofs. Each permutation identity—swapping the first two summands, swapping adjacent pairs, or commuting the last two—reduces to associativity and commutativity of $+_{\mathbb{Z}}$. These lemmas eliminate every ordering ambiguity before it can infect later calculations.

```
-- § Swap first two summands in a three-term sum.
swapHeadℤ : (a b t : ℤ) → a +ℤ (b +ℤ t) ≡ b +ℤ (a +ℤ t)
swapHeadℤ a b t =
 trans (sym (+ℤ-assoc a b t))
       (trans (cong (λ s → s +ℤ t) (+ℤ-comm a b))
              (+ℤ-assoc b a t))

sum3ℤ-swap01 : (a b c : ℤ) → sum3ℤ a b c ≡ sum3ℤ b a c
sum3ℤ-swap01 a b c = swapHeadℤ a b c

sum4ℤ-swap01 : (a b c d : ℤ) → sum4ℤ a b c d ≡ sum4ℤ b a c d
sum4ℤ-swap01 a b c d = swapHeadℤ a b (c +ℤ d)

sum4ℤ-swap12 : (a b c d : ℤ) → sum4ℤ a b c d ≡ sum4ℤ a c b d
sum4ℤ-swap12 a b c d = cong (λ t → a +ℤ t) (sum3ℤ-swap01 b c d)

sum4ℤ-swap23 : (a b c d : ℤ) → sum4ℤ a b c d ≡ sum4ℤ a b d c
sum4ℤ-swap23 a b c d = cong (λ t → a +ℤ (b +ℤ t)) (+ℤ-comm c d)
```

Negation Laws

The pair representation of $\mathbb{Z}$ makes negation a simple component swap: $\mathrm{neg}(a, b) = (b, a)$. From this, involutivity ($\mathrm{neg}(\mathrm{neg}\ z) = z$) is definitional, and distributivity of negation over sums, three-term sums, four-term sums, and the $4\times$ scaling all follow by induction on the structure. Normalization commutes with the swap, so every identity lifts cleanly from pairs to signed integers.

```
-- § Swap pair components.
swapPairℕ : Pairℕ → Pairℕ
swapPairℕ p = mkPairℕ (neg p) (pos p)

-- § Negation as pair swap.
toPair-negℤ : (z : ℤ) → toPairℤ (negℤ z) ≡ swapPairℕ (toPairℤ z)
toPair-negℤ 0ℤ = refl
toPair-negℤ (+suc n) = refl
toPair-negℤ (-suc n) = refl

-- § Negation is involutive.
negℤ-involutive : (z : ℤ) → negℤ (negℤ z) ≡ z
negℤ-involutive 0ℤ = refl
negℤ-involutive (+suc n) = refl
negℤ-involutive (-suc n) = refl

-- § Positive component of negation.
pos-toPair-negℤ : (z : ℤ) → pos (toPairℤ (negℤ z)) ≡ neg (toPairℤ z)
pos-toPair-negℤ z = cong pos (toPair-negℤ z)

-- § Negative component of negation.
```

```
neg-toPair-negℤ : (z : ℤ) → neg (toPairℤ (negℤ z)) ≡ pos (toPairℤ z)
neg-toPair-negℤ z = cong neg (toPair-negℤ z)

-- § Normalization commutes with negation.
neg-normalizeℤ : (a b : ℕ) → negℤ (normalizeℤ a b) ≡ normalizeℤ b a
neg-normalizeℤ zero zero = refl
neg-normalizeℤ (suc a) zero = refl
neg-normalizeℤ zero (suc b) = refl
neg-normalizeℤ (suc a) (suc b) = neg-normalizeℤ a b

-- § Negation distributes over componentwise addition.
negAdd-normalizeSwap : (x y : ℤ) →
 negℤ x +ℤ negℤ y ≡
 normalizeℤ (neg (toPairℤ x) +ℕ neg (toPairℤ y)) (pos (toPairℤ x) +ℕ pos (toPairℤ y))
negAdd-normalizeSwap x y =
 let A₁ = pos (toPairℤ (negℤ x)) +ℕ pos (toPairℤ (negℤ y)) in
 let B₁ = neg (toPairℤ (negℤ x)) +ℕ neg (toPairℤ (negℤ y)) in
 let A₂ = neg (toPairℤ x) +ℕ neg (toPairℤ y) in
 let B₂ = pos (toPairℤ x) +ℕ pos (toPairℤ y) in
 let eqA₁ =
       trans
        (cong (λ t → t +ℕ pos (toPairℤ (negℤ y))) (pos-toPair-negℤ x))
        (cong (λ t → neg (toPairℤ x) +ℕ t) (pos-toPair-negℤ y))
    in
 let eqB₁ =
       trans
        (cong (λ t → t +ℕ neg (toPairℤ (negℤ y))) (neg-toPair-negℤ x))
        (cong (λ t → pos (toPairℤ x) +ℕ t) (neg-toPair-negℤ y))
    in
 trans (cong (λ a → normalizeℤ a B₁) eqA₁)
       (cong (normalizeℤ A₂) eqB₁)

-- § Negation distributes over +ℤ.
neg-+ℤ : (x y : ℤ) → negℤ (x +ℤ y) ≡ negℤ x +ℤ negℤ y
neg-+ℤ x y =
 let A = pos (toPairℤ x) +ℕ pos (toPairℤ y) in
 let B = neg (toPairℤ x) +ℕ neg (toPairℤ y) in
 trans (neg-normalizeℤ A B) (sym (negAdd-normalizeSwap x y))

-- § Negation distributes over sum3ℤ.
neg-sum3ℤ : (a b c : ℤ) → negℤ (sum3ℤ a b c) ≡ sum3ℤ (negℤ a) (negℤ b) (negℤ c)
neg-sum3ℤ a b c =
 trans (neg-+ℤ a (b +ℤ c))
       (cong (λ t → negℤ a +ℤ t) (neg-+ℤ b c))

-- § Negation distributes over sum4ℤ.
neg-sum4ℤ : (a b c d : ℤ) → negℤ (sum4ℤ a b c d) ≡ sum4ℤ (negℤ a) (negℤ b) (negℤ c) (negℤ d)
neg-sum4ℤ a b c d =
 trans
  (neg-+ℤ a (b +ℤ (c +ℤ d)))
  (cong (λ t → negℤ a +ℤ t)
        (trans
         (neg-+ℤ b (c +ℤ d))
         (cong (λ t → negℤ b +ℤ t) (neg-+ℤ c d))))

-- § Negation distributes over fourTimesℤ.
neg-fourTimesℤ : (x : ℤ) → negℤ (fourTimesℤ x) ≡ fourTimesℤ (negℤ x)
neg-fourTimesℤ x = neg-sum4ℤ x x x x

-- § Negation distributes over sumFin3ℤ.
neg-sumFin3ℤ : (f : Fin3 → ℤ) → negℤ (sumFin3ℤ f) ≡ sumFin3ℤ (λ k → negℤ (f k))
neg-sumFin3ℤ f = neg-sum3ℤ (f f0) (f f1) (f f2)
```

Chapter 21

Multiplicative Structure and Integer Order

Spectral analysis of K_4 operators multiplies eigenvalues, compares magnitudes, and cancels common factors—all operations that demand a ring structure on $\mathbb{Z}$ and a total preorder compatible with it. Natural multiplication is forced by recursion on the left argument; integer multiplication lifts it through the pair representation; and the preorder $\leq_{\mathbb{Z}}$ inherits reflexivity, transitivity, and antisymmetry from $\leq$ on $\mathbb{N}$. Together they make $(\mathbb{Z}, +_{\mathbb{Z}}, *_{\mathbb{Z}}, \leq_{\mathbb{Z}})$ a commutative ordered ring—the minimal algebraic structure in which the Laplacian's spectral decomposition can be stated.

Natural Multiplication

Multiplication on $\mathbb{N}$ is defined by recursion on the left argument: $0 \cdot n = 0$ and $(1 + m) \cdot n = n + m \cdot n$. Right identity, left and right annihilation, and left identity for addition are immediate.

```
-- § Multiplication on ℕ (separate from BUILTIN _*_).
infixl 7 _*ℕ_

_*ℕ_ : ℕ → ℕ → ℕ
zero *ℕ n = zero
suc m *ℕ n = n +ℕ (m *ℕ n)

-- § Right identity for *ℕ.
*ℕ-one-right : (n : ℕ) → n *ℕ suc zero ≡ n
*ℕ-one-right zero = refl
*ℕ-one-right (suc n) = cong suc (*ℕ-one-right n)

-- § Right annihilation for *ℕ.
*ℕ-zero-right : (n : ℕ) → n *ℕ zero ≡ zero
*ℕ-zero-right zero = refl
*ℕ-zero-right (suc n) = *ℕ-zero-right n

-- § Left annihilation for *ℕ.
*ℕ-zero-left : (n : ℕ) → zero *ℕ n ≡ zero
*ℕ-zero-left n = refl

-- § Left identity for +ℕ.
+ℕ-zero-left : (n : ℕ) → zero +ℕ n ≡ n
+ℕ-zero-left n = refl
```

Integer Multiplication

Integer multiplication lifts pair-level multiplication through normalize$\mathbb{Z}$: $(a^+, a^-) \cdot (b^+, b^-) = (a^+b^+ + a^-b^-, a^+b^- + a^-b^+)$. Left and right annihilation, right identity, and the opaque wrapper $*\mathbb{Z}$ that controls definitional reduction are pinned down here.

```
-- § Pair-level multiplication.
Pairℕ-mul : Pairℕ → Pairℕ → Pairℕ
Pairℕ-mul p q =
 let a = pos p in
 let b = neg p in
 let c = pos q in
 let d = neg q in
 mkPairℕ ((a *ℕ c) +ℕ (b *ℕ d)) ((a *ℕ d) +ℕ (b *ℕ c))

-- § Integer one.
oneℤ : ℤ
oneℤ = +suc zero

-- § Natural one.
oneNat : ℕ
oneNat = suc zero

-- § Round-trip: fromPairℤ ∘ toPairℤ = id.
from-toPairℤ : (z : ℤ) → fromPairℤ (toPairℤ z) ≡ z
from-toPairℤ 0ℤ = refl
from-toPairℤ (+suc n) = refl
from-toPairℤ (-suc n) = refl

-- § Integer multiplication (opaque for reduction control).
infixl 7 _*ℤ_

opaque
 _*ℤ_ : ℤ → ℤ → ℤ
 x *ℤ y = fromPairℤ (Pairℕ-mul (toPairℤ x) (toPairℤ y))

opaque
 unfolding _*ℤ_
 -- § Left annihilation for *ℤ.
 *ℤ-zero-left : (y : ℤ) → 0ℤ *ℤ y ≡ 0ℤ
 *ℤ-zero-left y = refl

 -- § Right annihilation for *ℤ.
 *ℤ-zero-right : (x : ℤ) → x *ℤ 0ℤ ≡ 0ℤ
 *ℤ-zero-right 0ℤ = refl
 *ℤ-zero-right (+suc n) =
  normalizeℤ-cong
   (trans
    (+ℕ-zero-right (suc n *ℕ zero))
    (*ℕ-zero-right (suc n)))
   (trans
    (+ℕ-zero-right (suc n *ℕ zero))
    (*ℕ-zero-right (suc n)))
 *ℤ-zero-right (-suc n) =
  normalizeℤ-cong
   (*ℕ-zero-right (suc n))
   (*ℕ-zero-right (suc n))

 -- § Right identity for *ℤ.
 *ℤ-one-right : (x : ℤ) → x *ℤ oneℤ ≡ x
```

```
*ℤ-one-right 0ℤ = refl
*ℤ-one-right (+suc n) =
 normalizeℤ-cong
  (trans
   (+ℕ-zero-right (suc n *ℕ oneNat))
   (*ℕ-one-right (suc n)))
  (trans
   (+ℕ-zero-right (suc n *ℕ zero))
   (*ℕ-zero-right (suc n)))
*ℤ-one-right (-suc n) =
 normalizeℤ-cong
  (*ℕ-zero-right (suc n))
  (trans
   (+ℕ-zero-left (suc n *ℕ oneNat))
   (*ℕ-one-right (suc n)))
```

Integer Preorder

The preorder $\leq_{\mathbb{Z}}$ inherits reflexivity, transitivity, and antisymmetry from $\leq$ on $\mathbb{N}$. Case analysis over the three constructors of $\mathbb{Z}$ (zero, positive successor, negative successor) exhausts every comparison pair. Strict order implies weak order, and antisymmetry forces equality of the underlying natural predecessors.

```
-- § Reflexivity of ≤ℤ.
≤ℤ-refl : (x : ℤ) → x ≤ℤ x
≤ℤ-refl 0ℤ = tt
≤ℤ-refl (+suc n) = ≤-refl (suc n)
≤ℤ-refl (-suc n) = ≤-refl (suc n)

-- § Transitivity of ≤ℤ.
≤ℤ-trans : {x y z : ℤ} → x ≤ℤ y → y ≤ℤ z → x ≤ℤ z
≤ℤ-trans {0ℤ} {0ℤ} {0ℤ} _ _ = tt
≤ℤ-trans {0ℤ} {0ℤ} {+suc n} _ _ = tt
≤ℤ-trans {0ℤ} {0ℤ} { -suc n } _ ()
≤ℤ-trans {0ℤ} {+suc m} {0ℤ} _ ()
≤ℤ-trans {0ℤ} {+suc m} {+suc n} _ _ = tt
≤ℤ-trans {0ℤ} {+suc m} { -suc n } _ ()
≤ℤ-trans {0ℤ} { -suc m } {0ℤ} _ _ = tt
≤ℤ-trans {0ℤ} { -suc m } {+suc n} _ _ = tt
≤ℤ-trans {0ℤ} { -suc m } { -suc n } () _

≤ℤ-trans {+suc m} {0ℤ} {z} () _
≤ℤ-trans {+suc m} {+suc n} {0ℤ} p ()
≤ℤ-trans {+suc m} {+suc n} {+suc k} p q = ≤-trans p q
≤ℤ-trans {+suc m} {+suc n} { -suc k } _ ()
≤ℤ-trans {+suc m} { -suc n } {z} () _

≤ℤ-trans { -suc m } {0ℤ} {0ℤ} _ _ = tt
≤ℤ-trans { -suc m } {0ℤ} {+suc k} _ _ = tt
≤ℤ-trans { -suc m } {0ℤ} { -suc k } _ ()
≤ℤ-trans { -suc m } {+suc n} {0ℤ} _ ()
≤ℤ-trans { -suc m } {+suc n} {+suc k} _ _ = tt
≤ℤ-trans { -suc m } {+suc n} { -suc k } _ ()
≤ℤ-trans { -suc m } { -suc n } {0ℤ} _ _ = tt
≤ℤ-trans { -suc m } { -suc n } {+suc k} _ _ = tt
≤ℤ-trans { -suc m } { -suc n } { -suc k } p q = ≤-trans q p
```

```
-- § Strict order implies weak order.
<ℤ→≤ℤ : {x y : ℤ} → x <ℤ y → x ≤ℤ y
<ℤ→≤ℤ p = fst p

-- § Antisymmetry of ≤ℤ.
≤ℤ-antisym : {x y : ℤ} → x ≤ℤ y → y ≤ℤ x → x ≡ y
≤ℤ-antisym {0ℤ} {0ℤ} _ _ = refl
≤ℤ-antisym {0ℤ} {+suc n} _ ()
≤ℤ-antisym {0ℤ} { -suc n } () _
≤ℤ-antisym {+suc m} {0ℤ} () _
≤ℤ-antisym {+suc m} {+suc n} p q = cong +suc_ (suc-injective (≤-antisym p q))
≤ℤ-antisym {+suc m} { -suc n } () _
≤ℤ-antisym { -suc m } {0ℤ} _ ()
≤ℤ-antisym { -suc m } {+suc n} _ ()
≤ℤ-antisym { -suc m } { -suc n } p q = cong -suc_ (suc-injective (≤-antisym q p))

-- § Totality of ≤ℤ.
≤ℤ-total : (x y : ℤ) → (x ≤ℤ y) ⊎ (y ≤ℤ x)
≤ℤ-total 0ℤ 0ℤ = inj₁ tt
≤ℤ-total 0ℤ (+suc _) = inj₁ tt
≤ℤ-total 0ℤ (-suc _) = inj₂ tt
≤ℤ-total (+suc _) 0ℤ = inj₂ tt
≤ℤ-total (+suc m) (+suc n) with ≤-total (suc m) (suc n)
... | inj₁ p = inj₁ p
... | inj₂ p = inj₂ p
≤ℤ-total (+suc _) (-suc _) = inj₂ tt
≤ℤ-total (-suc _) 0ℤ = inj₁ tt
≤ℤ-total (-suc _) (+suc _) = inj₁ tt
≤ℤ-total (-suc m) (-suc n) with ≤-total (suc n) (suc m)
... | inj₁ p = inj₁ p
... | inj₂ p = inj₂ p
```

Chapter 22

K_4 Neighborhood and Laplacian

Every vertex of K_4 is adjacent to exactly three others—completeness minus self-adjacency leaves no room for variation. The combinatorial Laplacian takes a function on vertices, computes three times the vertex value minus the sum over its neighbours, and returns the result. No parameter is chosen; the operator is dictated entirely by the graph's edge set. This chapter constructs the neighbour triples exhaustively and defines the Laplacian as degree minus adjacency sum.

Neighbourhood Structure

Step 1: Adjacency and symmetric inequality witnesses. Adjacency on K_4 is edge membership. The symmetric inequality witnesses are forced by sym applied to the already-established inequalities.

```
-- § Adjacency on K4.
Adj : EndoCase → EndoCase → Set
Adj a b = Edge K4GraphCanonical a b

-- § Complete neighbour triple: every K4 vertex has exactly 3 neighbours.
record NeighborTriple (v : EndoCase) : Set where
 field
  n1 n2 n3 : EndoCase
  adj1 : Adj v n1
  adj2 : Adj v n2
  adj3 : Adj v n3
  n1≠n2 : n1 ≠ n2
  n1≠n3 : n1 ≠ n3
  n2≠n3 : n2 ≠ n3
  complete : (u : EndoCase) → Adj v u → (u ≡ n1) ⊎ ((u ≡ n2) ⊎ (u ≡ n3))

open NeighborTriple public

-- § Symmetric inequality witnesses.
case-constR≠case-constL : case-constR ≠ case-constL
case-constR≠case-constL eq = case-constL≠case-constR (sym eq)

case-id≠case-constL : case-id ≠ case-constL
case-id≠case-constL eq = case-constL≠case-id (sym eq)

case-dual≠case-constL : case-dual ≠ case-constL
```

```
case-dual≠case-constL eq = case-constL≠case-dual (sym eq)

case-id≠case-constR : case-id ≠ case-constR
case-id≠case-constR eq = case-constR≠case-id (sym eq)

case-dual≠case-constR : case-dual ≠ case-constR
case-dual≠case-constR eq = case-constR≠case-dual (sym eq)

case-dual≠case-id : case-dual ≠ case-id
case-dual≠case-id eq = case-id≠case-dual (sym eq)
```

Step 2: Law 14.0 — Complete neighbour triple for each vertex. Each of the four vertices of K_4 has exactly three neighbours. The four record constructions are forced by completeness minus self-adjacency.

```
-- § Law 14.0: Every vertex has a complete neighbour triple.
law14-0-neighbor-triple : (v : EndoCase) → NeighborTriple v
law14-0-neighbor-triple case-constL = record
 { n₁ = case-constR
 ; n₂ = case-id
 ; n₃ = case-dual
 ; adj₁ = case-constL≠case-constR
 ; adj₂ = case-constL≠case-id
 ; adj₃ = case-constL≠case-dual
 ; n₁≠n₂ = case-constR≠case-id
 ; n₁≠n₃ = case-constR≠case-dual
 ; n₂≠n₃ = case-id≠case-dual
 ; complete = λ
   { case-constL adj → ⊥-elim (adj refl)
   ; case-constR adj → inj₁ refl
   ; case-id     adj → inj₂ (inj₁ refl)
   ; case-dual adj → inj₂ (inj₂ refl)
   }
 }
law14-0-neighbor-triple case-constR = record
 { n₁ = case-constL
 ; n₂ = case-id
 ; n₃ = case-dual
 ; adj₁ = case-constR≠case-constL
 ; adj₂ = case-constR≠case-id
 ; adj₃ = case-constR≠case-dual
 ; n₁≠n₂ = case-constL≠case-id
 ; n₁≠n₃ = case-constL≠case-dual
 ; n₂≠n₃ = case-id≠case-dual
 ; complete = λ
   { case-constL adj → inj₁ refl
   ; case-constR adj → ⊥-elim (adj refl)
   ; case-id     adj → inj₂ (inj₁ refl)
   ; case-dual adj → inj₂ (inj₂ refl)
   }
 }
law14-0-neighbor-triple case-id = record
 { n₁ = case-constL
 ; n₂ = case-constR
 ; n₃ = case-dual
 ; adj₁ = case-id≠case-constL
 ; adj₂ = case-id≠case-constR
 ; adj₃ = case-id≠case-dual
 ; n₁≠n₂ = case-constL≠case-constR
```

```
 ; n₁≠n₃ = case-constL≠case-dual
 ; n₂≠n₃ = case-constR≠case-dual
 ; complete = λ
   { case-constL adj → inj₁ refl
   ; case-constR adj → inj₂ (inj₁ refl)
   ; case-id     adj → ⊥-elim (adj refl)
   ; case-dual adj → inj₂ (inj₂ refl)
   }
 }
law14-0-neighbor-triple case-dual = record
 { n₁ = case-constL
 ; n₂ = case-constR
 ; n₃ = case-id
 ; adj₁ = case-dual≠case-constL
 ; adj₂ = case-dual≠case-constR
 ; adj₃ = case-dual≠case-id
 ; n₁≠n₂ = case-constL≠case-constR
 ; n₁≠n₃ = case-constL≠case-id
 ; n₂≠n₃ = case-constR≠case-id
 ; complete = λ
   { case-constL adj → inj₁ refl
   ; case-constR adj → inj₂ (inj₁ refl)
   ; case-id     adj → inj₂ (inj₂ refl)
   ; case-dual adj → ⊥-elim (adj refl)
   }
 }

-- § Neighbour lookup by Fin3 index.
neighborAt : (v : EndoCase) → Fin3 → EndoCase
neighborAt v f0 = n₁ (law14-0-neighbor-triple v)
neighborAt v f1 = n₂ (law14-0-neighbor-triple v)
neighborAt v f2 = n₃ (law14-0-neighbor-triple v)

-- § Neighbours are adjacent.
neighborAt-adj : (v : EndoCase) → (i : Fin3) → Adj v (neighborAt v i)
neighborAt-adj v f0 = adj₁ (law14-0-neighbor-triple v)
neighborAt-adj v f1 = adj₂ (law14-0-neighbor-triple v)
neighborAt-adj v f2 = adj₃ (law14-0-neighbor-triple v)

-- § Neighbour lookup is injective.
neighborAt-injective : (v : EndoCase) → {i j : Fin3} → neighborAt v i ≡ neighborAt v j → i ≡ j
neighborAt-injective v {f0} {f0} _ = refl
neighborAt-injective v {f1} {f1} _ = refl
neighborAt-injective v {f2} {f2} _ = refl
neighborAt-injective v {f0} {f1} eq = ⊥-elim (n₁≠n₂ (law14-0-neighbor-triple v) eq)
neighborAt-injective v {f1} {f0} eq = ⊥-elim (n₁≠n₂ (law14-0-neighbor-triple v) (sym eq))
neighborAt-injective v {f0} {f2} eq = ⊥-elim (n₁≠n₃ (law14-0-neighbor-triple v) eq)
neighborAt-injective v {f2} {f0} eq = ⊥-elim (n₁≠n₃ (law14-0-neighbor-triple v) (sym eq))
neighborAt-injective v {f1} {f2} eq = ⊥-elim (n₂≠n₃ (law14-0-neighbor-triple v) eq)
neighborAt-injective v {f2} {f1} eq = ⊥-elim (n₂≠n₃ (law14-0-neighbor-triple v) (sym eq))
```

Laplacian Operator

The combinatorial Laplacian L takes a function f on K_4 vertices, computes three times the vertex value minus the sum over its three neighbours, and returns the difference. The degree term and adjacency sum are extracted from the neighbour triple, and the Laplacian is their difference.

```
-- § Adjacency sum: sum of f over the three neighbours.
adjSumℤ : (EndoCase → ℤ) → EndoCase → ℤ
```

```
adjSumℤ f v = sumFin3ℤ (λ i → f (neighborAt v i))

– § Degree term: 3 × f(v).
deg3ℤ : (EndoCase → ℤ) → EndoCase → ℤ
deg3ℤ f v = sum3ℤ (f v) (f v) (f v)

– § Combinatorial Laplacian: deg − adj.
laplacianℤ : (EndoCase → ℤ) → EndoCase → ℤ
laplacianℤ f v = deg3ℤ f v +ℤ negℤ (adjSumℤ f v)
```

Chapter 23

Simplex Invariants and Natural Multiplication Laws

The K_4 graph *is* the 3-simplex: four vertices, degree 3, six edges, Euler characteristic 2. These are not parameters but definitional equalities forced by the graph already constructed. To push further into spectral territory, natural-number arithmetic must satisfy distributivity, associativity, commutativity, and cancellation—the full semiring package. Each of these ten laws is forced by induction on $\mathbb{N}$, building on the additive laws already proven. The result is $(\mathbb{N}, +_{\mathbb{N}}, *_{\mathbb{N}})$ as a commutative semiring with monotonicity and cancellation, ready to serve as the backbone of the integer ring proofs that follow.

Simplex Invariants

No number enters by hand. The carrier of any distinction has exactly two elements (ℓ and r); this is the content of the word "distinction" and the one irreducible datum. Every simplex constant is then forced by algebra and graph theory from that single input.

A distinction offers two boundary witnesses. The total endomorphism count on a two-element carrier is $2^2 = 4$ (each of two outputs chosen independently). This is the vertex count of the complete graph K_4—the same four that the four-case classification (Chapter 4) forced by exhaustive type-theoretic analysis. The remaining simplex constants follow from the vertex count alone: degree $V - 1$, edge count $T(V)$ (the Vth triangle number), face count of the 3-simplex (each triple of vertices spans a face, and for four vertices there are exactly four such triples—one per omitted vertex), and Euler characteristic $V - E + F$.

Constraint: Every simplex constant must be derived from the carrier size of distinction. A bare numeral that does not trace back to the two-class structure of D_0 would introduce a free parameter and break the elimination chain.

Construction: Set $|S| = 2$ (the carrier size of distinction). Then $V = |S|^2 = 4$ (endomorphism count, matching the four constructors of $\mathrm{EndoCase}$ via the $\mathrm{vertexAt}/\mathrm{vertexIndex}$ bijection). The complete-graph formulas $d = V - 1$, $E = T(V)$, $F = V$ (self-duality of the

tetrahedron), and $\chi = V - E + F$ close the chain. Every constant reduces by refl—no arithmetic gap remains.

Consequence: The combinatorial profile $(4, 3, 6, 2)$ is not a parameter set. It is the unique output of the chain $|\{\ell, r\}| = 2 \;\rightarrow\; 2^2 = 4 \;\rightarrow\; K_4$ invariants. Changing any single entry would require changing the carrier size of distinction itself.

```
– § Distinction carrier size: |{ℓ, r}| = 2.
– § This is the ONE irreducible input—the content of the word "distinction."
states-per-distinction : ℕ
states-per-distinction = 2

– § Triangle number: T(n) = n(n−1)/2 = 0 + 1 +  + (n−1).
– § Counts edges of the complete graph K  without needing division.
triangle : ℕ → ℕ
triangle zero = 0
triangle (suc n) = n + triangle n

– § Simplex vertex count: |End(S)| = |S|² = 2² = 4.
– § (Four constructors of EndoCase, verified by Fin4 bijection.)
simplex-vertices : ℕ
simplex-vertices = states-per-distinction * states-per-distinction

– § Simplex degree: K  is (n−1)-regular.
simplex-degree : ℕ
simplex-degree = simplex-vertices ∸ 1

– § Simplex edge count: T(V) = T(4) = 0+1+2+3 = 6.
simplex-edges : ℕ
simplex-edges = triangle simplex-vertices

– § Simplex face count: the tetrahedron is self-dual, F = V.
– § (Each face is the triangle opposite one vertex; 4 vertices → 4 faces.)
simplex-faces : ℕ
simplex-faces = simplex-vertices

– § Simplex Euler characteristic: χ = V − E + F.
simplex-chi : ℕ
simplex-chi = (simplex-vertices + simplex-faces) ∸ simplex-edges

– § Law 14C.0: Vertex count = 4 (derived from 2² = 4).
law14C-0-vertices : simplex-vertices ≡ 4
law14C-0-vertices = refl

– § Law 14C.1: Degree = 3 (derived from V − 1 = 3).
law14C-1-degree : simplex-degree ≡ 3
law14C-1-degree = refl

– § Law 14C.2: Edge count = 6 (derived from T(4) = 6).
law14C-2-edges : simplex-edges ≡ 6
law14C-2-edges = refl

– § Law 14C.2a: Face count = 4 (self-duality).
law14C-2a-faces : simplex-faces ≡ 4
law14C-2a-faces = refl

– § Law 14C.3: Euler characteristic = 2 (derived from V − E + F = 2).
law14C-3-chi : simplex-chi ≡ 2
law14C-3-chi = refl

– § The carrier size is forced by distinction and nothing else.
law14C-4-carrier-is-2 : states-per-distinction ≡ 2
law14C-4-carrier-is-2 = refl
```

Distributivity and Associativity

The semiring laws of $(\mathbb{N}, +_{\mathbb{N}}, *_{\mathbb{N}})$ are chain-forced from the recursive definitions. Head-swapping, four-way shuffling, right distributivity of $*_{\mathbb{N}}$ over $+_{\mathbb{N}}$, associativity of $*_{\mathbb{N}}$, and zero cancellation for a positive left factor are each proved by structural induction.

```
-- § Left distributivity of *ℕ over +ℕ.
*ℕ-distrib-left-+ℕ : (a b c : ℕ) → (a +ℕ b) *ℕ c ≡ (a *ℕ c) +ℕ (b *ℕ c)
*ℕ-distrib-left-+ℕ zero b c =
 trans
  refl
  (sym (+ℕ-zero-left (b *ℕ c)))
*ℕ-distrib-left-+ℕ (suc a) b c =
 trans
  refl
  (trans
   (cong (λ t → c +ℕ t) (*ℕ-distrib-left-+ℕ a b c))
   (sym (+ℕ-assoc c (a *ℕ c) (b *ℕ c))))

-- § Head swap for ℕ sums.
swapHeadℕ : (a b t : ℕ) → a +ℕ (b +ℕ t) ≡ b +ℕ (a +ℕ t)
swapHeadℕ a b t =
 trans
  (sym (+ℕ-assoc a b t))
  (trans
   (cong (λ s → s +ℕ t) (+ℕ-comm a b))
   (+ℕ-assoc b a t))

-- § Four-way shuffle for ℕ.
shuffleℕ : (b c x y : ℕ) → (b +ℕ c) +ℕ (x +ℕ y) ≡ (b +ℕ x) +ℕ (c +ℕ y)
shuffleℕ b c x y =
 trans
  (+ℕ-assoc b c (x +ℕ y))
  (trans
   (cong (λ t → b +ℕ t) (sym (+ℕ-assoc c x y)))
   (trans
    (cong (λ t → b +ℕ (t +ℕ y)) (+ℕ-comm c x))
    (trans
     (cong (λ t → b +ℕ t) (+ℕ-assoc x c y))
     (sym (+ℕ-assoc b x (c +ℕ y))))))

-- § Right distributivity of *ℕ over +ℕ.
*ℕ-distrib-right-+ℕ : (a b c : ℕ) → a *ℕ (b +ℕ c) ≡ (a *ℕ b) +ℕ (a *ℕ c)
*ℕ-distrib-right-+ℕ zero b c = refl
*ℕ-distrib-right-+ℕ (suc a) b c =
 trans
  refl
  (trans
   (cong (λ t → (b +ℕ c) +ℕ t) (*ℕ-distrib-right-+ℕ a b c))
   (trans
    (shuffleℕ b c (a *ℕ b) (a *ℕ c))
    refl))

-- § Associativity of *ℕ.
*ℕ-assoc : (a b c : ℕ) → (a *ℕ b) *ℕ c ≡ a *ℕ (b *ℕ c)
*ℕ-assoc zero b c = refl
*ℕ-assoc (suc a) b c =
 trans
  (*ℕ-distrib-left-+ℕ b (a *ℕ b) c)
  (trans
```

```
  (cong (λ t → (b *ℕ c) +ℕ t) (*ℕ-assoc a b c))
  refl)

-- § Zero cancellation for positive left factor.
*ℕ-pos-zero→zero : (a n : ℕ) → suc a *ℕ n ≡ zero → n ≡ zero
*ℕ-pos-zero→zero a zero _ = refl
*ℕ-pos-zero→zero a (suc n) ()
```

Commutativity and Monotonicity

Commutativity of $*_{\mathbb{N}}$ is forced by the successor-right law and induction on the left argument. Monotonicity of $+_{\mathbb{N}}$ and $*_{\mathbb{N}}$ and right cancellation by a positive factor complete the ordered-semiring structure that the integer ring proofs will lift through.

```
-- § Successor-right law for *ℕ.
*ℕ-suc-right-+ℕ : (n m : ℕ) → n *ℕ (suc m) ≡ n +ℕ (n *ℕ m)
*ℕ-suc-right-+ℕ zero m = refl
*ℕ-suc-right-+ℕ (suc n) m =
 trans
  refl
  (trans
   (cong (λ t → (suc m) +ℕ t) (*ℕ-suc-right-+ℕ n m))
   (cong suc (swapHeadℕ m n (n *ℕ m))))

-- § Commutativity of *ℕ.
*ℕ-comm : (m n : ℕ) → m *ℕ n ≡ n *ℕ m
*ℕ-comm zero n = sym (*ℕ-zero-right n)
*ℕ-comm (suc m) n =
 trans
  refl
  (trans
   (cong (λ t → n +ℕ t) (*ℕ-comm m n))
   (sym (*ℕ-suc-right-+ℕ n m)))

-- § +ℕ is monotone on the left.
≤-+ℕ-mono^l : {a b : ℕ} → a ≤ b → (c : ℕ) → (c +ℕ a) ≤ (c +ℕ b)
≤-+ℕ-mono^l p zero = p
≤-+ℕ-mono^l p (suc c) = s≤s (≤-+ℕ-mono^l p c)

-- § Left cancellation for +ℕ ordering.
≤-+ℕ-cancel^l : (c a b : ℕ) → (c +ℕ a) ≤ (c +ℕ b) → a ≤ b
≤-+ℕ-cancel^l zero a b p = p
≤-+ℕ-cancel^l (suc c) a b (s≤s p) = ≤-+ℕ-cancel^l c a b p

-- § *ℕ is monotone in the left factor.
≤-*ℕ-mono^r : {m n : ℕ} → m ≤ n → (t : ℕ) → (m *ℕ t) ≤ (n *ℕ t)
≤-*ℕ-mono^r z≤n t = z≤n
≤-*ℕ-mono^r (s≤s p) t = ≤-+ℕ-mono^l (≤-*ℕ-mono^r p t) t

-- § Right cancellation by a positive (successor) factor.
≤-*ℕ-cancel^r-suc : {m n : ℕ} → (k : ℕ) → (m *ℕ suc k) ≤ (n *ℕ suc k) → m ≤ n
≤-*ℕ-cancel^r-suc {zero} {zero} k _ = z≤n
≤-*ℕ-cancel^r-suc {suc m'} {zero} k ()
≤-*ℕ-cancel^r-suc {zero} {suc n} k _ = z≤n
≤-*ℕ-cancel^r-suc {suc m} {suc n} k p =
 let
  step : (suc k +ℕ (m *ℕ suc k)) ≤ (suc k +ℕ (n *ℕ suc k))
  step = p
```

```
  tail : (m *ℕ suc k) ≤ (n *ℕ suc k)
  tail = ≤-+ℕ-cancelˡ (suc k) (m *ℕ suc k) (n *ℕ suc k) step

  ih : m ≤ n
  ih = ≤-*ℕ-cancelʳ-suc k tail
 in
 s≤s ih
```

Positive Naturals

The type $\mathbb{N}^+$ packages a natural number in successor form, eliminating the possibility of a zero denominator when rationals are introduced later.

```
-- § Positive natural: predecessor + implicit successor.
record ℕ⁺ : Set where
 constructor mkℕ⁺
 field
  pred : ℕ

PosNat : Set
PosNat = ℕ⁺

open ℕ⁺ public

-- § Embedding into ℕ (always ≥ 1).
⁺toℕ : ℕ⁺ → ℕ
⁺toℕ n = suc (pred n)

-- § Positive one.
one⁺ : ℕ⁺
one⁺ = mkℕ⁺ zero

-- § Successor on ℕ⁺.
suc⁺ : ℕ⁺ → ℕ⁺
suc⁺ n = mkℕ⁺ (suc (pred n))

-- § Addition on ℕ⁺.
_+⁺_ : ℕ⁺ → ℕ⁺ → ℕ⁺
mkℕ⁺ a +⁺ mkℕ⁺ b = mkℕ⁺ (a +ℕ suc b)

-- § Multiplication on ℕ⁺: (1+a)(1+b) = 1 + (a·(1+b) + b).
_*⁺_ : ℕ⁺ → ℕ⁺ → ℕ⁺
mkℕ⁺ a *⁺ mkℕ⁺ b = mkℕ⁺ ((a *ℕ suc b) +ℕ b)

-- § Embedding ℕ⁺ into ℤ.
⁺toℤ : ℕ⁺ → ℤ
⁺toℤ (mkℕ⁺ k) = +suc k
```

Chapter 24

Integer Multiplication Laws

The operator-span composition on K_4 eigenvectors multiplies integer scalars, distributes them over sums, and cancels common nonzero factors. These operations demand the full ring axioms: distributivity of $*_{\mathbb{Z}}$ over $+_{\mathbb{Z}}$, associativity, commutativity, and torsion-freedom—no nonzero scalar may annihilate another nonzero scalar. Every law is first proven at the $\mathrm{Pair}\mathbb{N}$ level, where multiplication is componentwise and explicit, then lifted through $\mathrm{normalize}\mathbb{Z}$ to the signed representation. The result is $(\mathbb{Z}, +_{\mathbb{Z}}, *_{\mathbb{Z}})$ as an integral domain with no free parameters.

Pair-Level Addition and Normalization

The pair representation (a^+, a^-) for integers admits componentwise addition and a normalization step that strips equal components. The round-trip lemma—$\mathrm{fromPair}\mathbb{Z}$ absorbs normalizePair—and the factorization $\mathrm{toPair}\mathbb{Z} \circ \mathrm{normalize}\mathbb{Z} = \mathrm{normalizePair} \circ \mathrm{mkPair}_{\mathbb{N}}$ are the bridge between signed integers and their pair-level computation.

```
-- § Componentwise pair addition.
Pairℕ-add : Pairℕ → Pairℕ → Pairℕ
Pairℕ-add p q = (mkPairℕ (pos p +ℕ pos q) (neg p +ℕ neg q))

-- § Normalization: cancel equal components.
normalizePair : Pairℕ → Pairℕ
normalizePair (mkPairℕ zero zero) = (mkPairℕ zero zero)
normalizePair (mkPairℕ (suc a) zero) = (mkPairℕ (suc a) zero)
normalizePair (mkPairℕ zero (suc b)) = (mkPairℕ zero (suc b))
normalizePair (mkPairℕ (suc a) (suc b)) = normalizePair (mkPairℕ a b)

-- § normalizePair is identity on (x , 0).
normalizePair-right0 : (x : ℕ) → normalizePair (mkPairℕ x zero) ≡ (mkPairℕ x zero)
normalizePair-right0 zero = refl
normalizePair-right0 (suc a) = refl

-- § normalizePair is identity on (0 , y).
normalizePair-left0 : (y : ℕ) → normalizePair (mkPairℕ zero y) ≡ (mkPairℕ zero y)
normalizePair-left0 zero = refl
normalizePair-left0 (suc b) = refl

-- § fromPairℤ absorbs normalizePair.
fromPair-normalizePair : (p : Pairℕ) → fromPairℤ (normalizePair p) ≡ fromPairℤ p
```

```
fromPair-normalizePair (mkPairℕ zero zero) = refl
fromPair-normalizePair (mkPairℕ (suc a) zero) = refl
fromPair-normalizePair (mkPairℕ zero (suc b)) = refl
fromPair-normalizePair (mkPairℕ (suc a) (suc b)) = fromPair-normalizePair (mkPairℕ a b)

-- § toPairℤ ∘ normalizeℤ = normalizePair ∘ mkPairℕ.
toPair-normalizeℤ : (a b : ℕ) → toPairℤ (normalizeℤ a b) ≡ normalizePair (mkPairℕ a b)
toPair-normalizeℤ zero zero = refl
toPair-normalizeℤ (suc a) zero = refl
toPair-normalizeℤ zero (suc b) = refl
toPair-normalizeℤ (suc a) (suc b) = toPair-normalizeℤ a b

-- § toPairℤ ∘ fromPairℤ = normalizePair.
toPair-fromPair : (p : Pairℕ) → toPairℤ (fromPairℤ p) ≡ normalizePair p
toPair-fromPair (mkPairℕ a b) = toPair-normalizeℤ a b
```

Pair-Level Distributivity

Right distributivity of pair-level multiplication over pair-level addition is a componentwise identity involving four products and two sums. It is verified by expanding definitions and applying commutativity and distributivity of ℕ. This is the key bridge lemma: once it holds at the pair level, the signed-integer distributivity follows by normalization absorption.

```
-- § Right distributivity at pair level.
Pairℕ-mul-distrib-right-add : (p q r : Pairℕ) →
 Pairℕ-mul p (Pairℕ-add q r) ≡ Pairℕ-add (Pairℕ-mul p q) (Pairℕ-mul p r)
Pairℕ-mul-distrib-right-add p q r =
 let a = pos p in
 let b = neg p in
 let c = pos q in
 let d = neg q in
 let e = pos r in
 let f = neg r in
 pair-ext
  (pos-proof a b c d e f)
  (neg-proof a b c d e f)
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl

  pos-proof : (a b c d e f : ℕ) →
   ((a *ℕ (c +ℕ e)) +ℕ (b *ℕ (d +ℕ f)))
    ≡
   (((a *ℕ c) +ℕ (b *ℕ d)) +ℕ ((a *ℕ e) +ℕ (b *ℕ f)))
  pos-proof a b c d e f =
   trans
    (cong (λ t → t +ℕ (b *ℕ (d +ℕ f))) (*ℕ-distrib-right-+ℕ a c e))
    (trans
     (cong (λ t → (a *ℕ c +ℕ a *ℕ e) +ℕ t) (*ℕ-distrib-right-+ℕ b d f))
     (shuffleℕ (a *ℕ c) (a *ℕ e) (b *ℕ d) (b *ℕ f)))

  neg-proof : (a b c d e f : ℕ) →
   ((a *ℕ (d +ℕ f)) +ℕ (b *ℕ (c +ℕ e)))
    ≡
   (((a *ℕ d) +ℕ (b *ℕ c)) +ℕ ((a *ℕ f) +ℕ (b *ℕ e)))
  neg-proof a b c d e f =
   trans
```

```
    (cong (λ t → t +ℕ (b *ℕ (c +ℕ e))) (*ℕ-distrib-right-+ℕ a d f))
    (trans
     (cong (λ t → (a *ℕ d +ℕ a *ℕ f) +ℕ t) (*ℕ-distrib-right-+ℕ b c e))
     (shuffleℕ (a *ℕ d) (a *ℕ f) (b *ℕ c) (b *ℕ e)))

– § Left identity for *ℕ.
*ℕ-one-left : (n : ℕ) → oneNat *ℕ n ≡ n
*ℕ-one-left n = +ℕ-zero-right n

opaque
 unfolding _*ℤ_
 – § Left identity for *ℤ.
 *ℤ-one-left : (x : ℤ) → oneℤ *ℤ x ≡ x
 *ℤ-one-left 0ℤ = refl
 *ℤ-one-left (+suc n) =
  normalizeℤ-cong
   (trans
    (+ℕ-zero-right (oneNat *ℕ suc n))
    (*ℕ-one-left (suc n)))
   (trans
    (+ℕ-zero-right (oneNat *ℕ zero))
    (*ℕ-zero-right oneNat))
 *ℤ-one-left (-suc n) =
  normalizeℤ-cong
   (trans
    (+ℕ-zero-right (oneNat *ℕ zero))
    (*ℕ-zero-right oneNat))
   (trans
    (+ℕ-zero-right (oneNat *ℕ suc n))
    (*ℕ-one-left (suc n)))

– § Left distributivity at pair level.
Pairℕ-mul-distrib-left-add : (p q r : Pairℕ) →
 Pairℕ-mul (Pairℕ-add p q) r ≡ Pairℕ-add (Pairℕ-mul p r) (Pairℕ-mul q r)
Pairℕ-mul-distrib-left-add p q r =
 let a = pos p in
 let b = neg p in
 let c = pos q in
 let d = neg q in
 let e = pos r in
 let f = neg r in
 pair-ext
  (pos-proof a b c d e f)
  (neg-proof a b c d e f)
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl

  pos-proof : (a b c d e f : ℕ) →
   (((a +ℕ c) *ℕ e) +ℕ ((b +ℕ d) *ℕ f))
    ≡
   (((a *ℕ e) +ℕ (b *ℕ f)) +ℕ ((c *ℕ e) +ℕ (d *ℕ f)))
  pos-proof a b c d e f =
   trans
    (cong (λ t → t +ℕ ((b +ℕ d) *ℕ f)) (*ℕ-distrib-left-+ℕ a c e))
    (trans
     (cong (λ t → ((a *ℕ e) +ℕ (c *ℕ e)) +ℕ t) (*ℕ-distrib-left-+ℕ b d f))
     (shuffleℕ (a *ℕ e) (c *ℕ e) (b *ℕ f) (d *ℕ f)))

  neg-proof : (a b c d e f : ℕ) →
   (((a +ℕ c) *ℕ f) +ℕ ((b +ℕ d) *ℕ e))
    ≡
```

```
  (((a *ℕ f) +ℕ (b *ℕ e)) +ℕ ((c *ℕ f) +ℕ (d *ℕ e)))
 neg-proof a b c d e f =
  trans
   (cong (λ t → t +ℕ ((b +ℕ d) *ℕ e)) (*ℕ-distrib-left-+ℕ a c f))
   (trans
    (cong (λ t → ((a *ℕ f) +ℕ (c *ℕ f)) +ℕ t) (*ℕ-distrib-left-+ℕ b d e))
    (shuffleℕ (a *ℕ f) (c *ℕ f) (b *ℕ e) (d *ℕ e)))
```

Diagonal Cancellation and Normalization Stability

Adding a diagonal pair (k, k) to any pair does not change its normalized form, because normalizePair cancels equal components. This is the key lemma connecting pair-level multiplication with $\mathbb{Z}$-level multiplication through normalize$\mathbb{Z}$.

```
-- § Diagonal addition is absorbed by normalization.
normalizePair-addDiag : (p : Pairℕ) → (k : ℕ) →
 normalizePair (Pairℕ-add p (mkPairℕ k k)) ≡ normalizePair p
normalizePair-addDiag (mkPairℕ a b) zero =
 cong normalizePair (pair-ext (+ℕ-zero-right a) (+ℕ-zero-right b))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl
normalizePair-addDiag (mkPairℕ a b) (suc k) =
 trans
  (cong normalizePair (pair-ext (+ℕ-suc-right a k) (+ℕ-suc-right b k)))
  (trans
   refl
   (normalizePair-addDiag (mkPairℕ a b) k))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl

-- § Successor-right via +ℕ one.
+ℕ-one-right : (n : ℕ) → n +ℕ suc zero ≡ suc n
+ℕ-one-right n = trans (+ℕ-comm n (suc zero)) refl

-- § *ℕ successor-right.
*ℕ-suc-right : (a n : ℕ) → a *ℕ suc n ≡ (a *ℕ n) +ℕ a
*ℕ-suc-right a n =
 trans
  (cong (λ t → a *ℕ t) (sym (+ℕ-one-right n)))
  (trans
   (*ℕ-distrib-right-+ℕ a n (suc zero))
   (cong (λ t → (a *ℕ n) +ℕ t) (*ℕ-one-right a)))

-- § *ℕ successor-left.
*ℕ-suc-left : (n a : ℕ) → suc n *ℕ a ≡ (n *ℕ a) +ℕ a
*ℕ-suc-left n a =
 trans
  (cong (λ t → t *ℕ a) (sym (+ℕ-one-right n)))
  (trans
   (*ℕ-distrib-left-+ℕ n (suc zero) a)
   (cong (λ t → (n *ℕ a) +ℕ t) (*ℕ-one-left a)))
```

Step 2: Pair-Level Cancellation. The successor lemmas isolate how multiplication interacts with single increments. Cancellation shows that normalizing after multiplying by a successor pair $(suc\ c,\ suc\ d)$ reduces to normalizing after multiplying by (c, d): the extra diagonal component is absorbed by normalization.

```
– § Right cancellation at pair level: common successor adds a diagonal.
Pairℕ-mul-cancelRight : (p : Pairℕ) → (c d : ℕ) →
 normalizePair (Pairℕ-mul p (mkPairℕ (suc c) (suc d))) ≡ normalizePair (Pairℕ-mul p (mkPairℕ c d))
Pairℕ-mul-cancelRight p c d =
 let a = pos p in
 let b = neg p in
 trans
  (cong normalizePair (pair-ext (pos-step a b c d) (neg-step a b c d)))
  (normalizePair-addDiag (Pairℕ-mul p (mkPairℕ c d)) (a +ℕ b))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl

  pos-step : (a b c d : ℕ) →
   ((a *ℕ suc c) +ℕ (b *ℕ suc d))
    ≡
   (((a *ℕ c) +ℕ (b *ℕ d)) +ℕ (a +ℕ b))
  pos-step a b c d =
   trans
    (cong (λ t → t +ℕ (b *ℕ suc d)) (*ℕ-suc-right a c))
    (trans
     (cong (λ t → ((a *ℕ c) +ℕ a) +ℕ t) (*ℕ-suc-right b d))
     (trans
      (shuffleℕ (a *ℕ c) a (b *ℕ d) b)
      refl))

  neg-step : (a b c d : ℕ) →
   ((a *ℕ suc d) +ℕ (b *ℕ suc c))
    ≡
   (((a *ℕ d) +ℕ (b *ℕ c)) +ℕ (a +ℕ b))
  neg-step a b c d =
   trans
    (cong (λ t → t +ℕ (b *ℕ suc c)) (*ℕ-suc-right a d))
    (trans
     (cong (λ t → ((a *ℕ d) +ℕ a) +ℕ t) (*ℕ-suc-right b c))
     (trans
      (shuffleℕ (a *ℕ d) a (b *ℕ c) b)
      refl))

– § Left cancellation at pair level.
Pairℕ-mul-cancelLeft : (q : Pairℕ) → (a b : ℕ) →
 normalizePair (Pairℕ-mul (mkPairℕ (suc a) (suc b)) q) ≡ normalizePair (Pairℕ-mul (mkPairℕ a b) q)
Pairℕ-mul-cancelLeft q a b =
 let c = pos q in
 let d = neg q in
 trans
  (cong normalizePair (pair-ext (pos-step a b c d) (neg-step a b c d)))
  (normalizePair-addDiag (Pairℕ-mul (mkPairℕ a b) q) (c +ℕ d))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl

  pos-step : (a b c d : ℕ) →
   ((suc a *ℕ c) +ℕ (suc b *ℕ d))
    ≡
```

```
  (((a *ℕ c) +ℕ (b *ℕ d)) +ℕ (c +ℕ d))
 pos-step a b c d =
  trans
   (cong (λ t → t +ℕ (suc b *ℕ d)) (*ℕ-suc-left a c))
   (trans
    (cong (λ t → ((a *ℕ c) +ℕ c) +ℕ t) (*ℕ-suc-left b d))
    (trans
     (shuffleℕ (a *ℕ c) c (b *ℕ d) d)
     refl))

 neg-step : (a b c d : ℕ) →
  ((suc a *ℕ d) +ℕ (suc b *ℕ c))
   ≡
  (((a *ℕ d) +ℕ (b *ℕ c)) +ℕ (c +ℕ d))
 neg-step a b c d =
  trans
   (cong (λ t → t +ℕ (suc b *ℕ c)) (*ℕ-suc-left a d))
   (trans
    (cong (λ t → ((a *ℕ d) +ℕ d) +ℕ t) (*ℕ-suc-left b c))
    (trans
     (shuffleℕ (a *ℕ d) d (b *ℕ c) c)
     (cong (λ t → ((a *ℕ d) +ℕ (b *ℕ c)) +ℕ t) (+ℕ-comm d c))))
```

Step 3: Normalization Stability. Left and right cancellation combine to show normalization is stable under factor normalization: normalizing either factor before pair-multiplication does not change the normalized product.

```
– § Normalization absorbs right factor normalization.
Pairℕ-mul-normalize-right : (p q : Pairℕ) →
 normalizePair (Pairℕ-mul p (normalizePair q)) ≡ normalizePair (Pairℕ-mul p q)
Pairℕ-mul-normalize-right p (mkPairℕ zero zero) = refl
Pairℕ-mul-normalize-right p (mkPairℕ (suc a) zero) = refl
Pairℕ-mul-normalize-right p (mkPairℕ zero (suc b)) = refl
Pairℕ-mul-normalize-right p (mkPairℕ (suc a) (suc b)) =
 trans
  (Pairℕ-mul-normalize-right p (mkPairℕ a b))
  (sym (Pairℕ-mul-cancelRight p a b))

– § Normalization absorbs left factor normalization.
Pairℕ-mul-normalize-left : (p q : Pairℕ) →
 normalizePair (Pairℕ-mul (normalizePair p) q) ≡ normalizePair (Pairℕ-mul p q)
Pairℕ-mul-normalize-left (mkPairℕ zero zero) q = refl
Pairℕ-mul-normalize-left (mkPairℕ (suc a) zero) q = refl
Pairℕ-mul-normalize-left (mkPairℕ zero (suc b)) q = refl
Pairℕ-mul-normalize-left (mkPairℕ (suc a) (suc b)) q =
 trans
  (Pairℕ-mul-normalize-left (mkPairℕ a b) q)
  (sym (Pairℕ-mul-cancelLeft q a b))
```

Canonical Pair Products and ℤ-Level Bridge

Products of pairs coming from toPairℤ are already in normal form. This bridges pair-level multiplication to ℤ-level multiplication through normalizeℤ.

```
– § Products of canonical pairs are already normalized.
Pairℕ-mul-toPair-normal : (x y : ℤ) →
```

```
 normalizePair (Pairℕ-mul (toPairℤ x) (toPairℤ y)) ≡ Pairℕ-mul (toPairℤ x) (toPairℤ y)
Pairℕ-mul-toPair-normal 0ℤ y = refl
Pairℕ-mul-toPair-normal (+suc n) 0ℤ =
 let mulEq : Pairℕ-mul (toPairℤ (+suc n)) (toPairℤ 0ℤ) ≡ (mkPairℕ zero zero)
     mulEq =
      pair-ext
       (trans (cong (λ t → t +ℕ (zero *ℕ zero)) (*ℕ-zero-right (suc n))) refl)
       (trans (cong (λ t → t +ℕ (zero *ℕ zero)) (*ℕ-zero-right (suc n))) refl)
 in
 trans (cong normalizePair mulEq) (trans (normalizePair-right0 zero) (sym mulEq))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl
Pairℕ-mul-toPair-normal (-suc n) 0ℤ =
 let mulEq : Pairℕ-mul (toPairℤ (-suc n)) (toPairℤ 0ℤ) ≡ (mkPairℕ zero zero)
     mulEq =
      pair-ext
       (trans (cong (λ t → t +ℕ (suc n *ℕ zero)) refl) (*ℕ-zero-right (suc n)))
       (trans (cong (λ t → t +ℕ (suc n *ℕ zero)) refl) (*ℕ-zero-right (suc n)))
 in
 trans (cong normalizePair mulEq) (trans (normalizePair-right0 zero) (sym mulEq))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl
Pairℕ-mul-toPair-normal (+suc n) (+suc m) =
 let mulEq : Pairℕ-mul (toPairℤ (+suc n)) (toPairℤ (+suc m)) ≡ (mkPairℕ (suc n *ℕ suc m) zero)
     mulEq =
      pair-ext
       (+ℕ-zero-right (suc n *ℕ suc m))
       (trans
        (cong (λ t → t +ℕ (zero *ℕ suc m)) (*ℕ-zero-right (suc n)))
        refl)
 in
 trans (cong normalizePair mulEq)
  (trans (normalizePair-right0 (suc n *ℕ suc m)) (sym mulEq))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl
Pairℕ-mul-toPair-normal (+suc n) (-suc m) =
 let mulEq : Pairℕ-mul (toPairℤ (+suc n)) (toPairℤ (-suc m)) ≡ (mkPairℕ zero (suc n *ℕ suc m))
     mulEq =
      pair-ext
       (trans
        (cong (λ t → t +ℕ (zero *ℕ suc m)) (*ℕ-zero-right (suc n)))
        refl)
       (+ℕ-zero-right (suc n *ℕ suc m))
 in
 trans (cong normalizePair mulEq)
  (trans (normalizePair-left0 (suc n *ℕ suc m)) (sym mulEq))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl
Pairℕ-mul-toPair-normal (-suc n) (+suc m) =
 let mulEq : Pairℕ-mul (toPairℤ (-suc n)) (toPairℤ (+suc m)) ≡ (mkPairℕ zero (suc n *ℕ suc m))
     mulEq =
      pair-ext
       (trans
        (cong (λ t → (zero *ℕ suc m) +ℕ t) (*ℕ-zero-right (suc n)))
        (trans
         (cong (λ t → t +ℕ zero) (*ℕ-zero-left (suc m)))
         refl))
```

```
      (+ℕ-zero-left (suc n *ℕ suc m))
 in
 trans (cong normalizePair mulEq)
  (trans (normalizePair-left0 (suc n *ℕ suc m)) (sym mulEq))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl
Pairℕ-mul-toPair-normal (-suc n) (-suc m) =
 let mulEq : Pairℕ-mul (toPairℤ (-suc n)) (toPairℤ (-suc m)) ≡ (mkPairℕ (suc n *ℕ suc m) zero)
     mulEq =
      pair-ext
       (+ℕ-zero-left (suc n *ℕ suc m))
       (trans
        (cong (λ t → (zero *ℕ suc m) +ℕ t) (*ℕ-zero-right (suc n)))
        (trans
         (cong (λ t → t +ℕ zero) (*ℕ-zero-left (suc m)))
         refl))
 in
 trans (cong normalizePair mulEq)
  (trans (normalizePair-right0 (suc n *ℕ suc m)) (sym mulEq))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl

opaque
 unfolding _*ℤ_
 -- § Bridge: toPairℤ of *ℤ = Pairℕ-mul of canonical pairs.
 toPair-*ℤ : (x y : ℤ) → toPairℤ (x *ℤ y) ≡ Pairℕ-mul (toPairℤ x) (toPairℤ y)
 toPair-*ℤ x y =
  trans
    (toPair-fromPair (Pairℕ-mul (toPairℤ x) (toPairℤ y)))
    (Pairℕ-mul-toPair-normal x y)

-- § Bridge: toPairℤ of +ℤ = normalizePair of componentwise add.
toPair-+ℤ : (x y : ℤ) → toPairℤ (x +ℤ y) ≡ normalizePair (Pairℕ-add (toPairℤ x) (toPairℤ y))
toPair-+ℤ x y = toPair-fromPair (Pairℕ-add (toPairℤ x) (toPairℤ y))
```

Ring Laws: Distributivity, Torsion-Freedom, Negation

Distributivity of $*_{\mathbb{Z}}$ over $+_{\mathbb{Z}}$ is the foundation of the spectral calculus: eigenvalue sums, Laplacian decompositions, and operator expansions all rely on it. The proof lifts pair-level distributivity through normalization absorption, then symmetrizes from right to left distributivity.

```
opaque
 unfolding _*ℤ_
 -- § Right distributivity of *ℤ over +ℤ.
 *ℤ-distrib-right-+ℤ : (x y z : ℤ) → x *ℤ (y +ℤ z) ≡ (x *ℤ y) +ℤ (x *ℤ z)
 *ℤ-distrib-right-+ℤ x y z =
  let px = toPairℤ x in
  let py = toPairℤ y in
  let pz = toPairℤ z in
  let q = Pairℕ-add py pz in
  let rhs : fromPairℤ (Pairℕ-add (Pairℕ-mul px py) (Pairℕ-mul px pz)) ≡ (x *ℤ y) +ℤ (x *ℤ z)
      rhs =
       trans
        (cong (λ t → fromPairℤ (Pairℕ-add t (Pairℕ-mul px pz))) (sym (toPair-*ℤ x y)))
        (trans
         (cong (λ t → fromPairℤ (Pairℕ-add (toPairℤ (x *ℤ y)) t)) (sym (toPair-*ℤ x z)))
```

```
      refl)
 in
 trans
  (cong (λ t → fromPairℤ (Pairℕ-mul px t)) (toPair-+ℤ y z))
  (trans
    (trans
     (sym (fromPair-normalizePair (Pairℕ-mul px (normalizePair q))))
     (cong fromPairℤ (Pairℕ-mul-normalize-right px q)))
    (trans
     (trans
      (fromPair-normalizePair (Pairℕ-mul px q))
      (cong fromPairℤ (Pairℕ-mul-distrib-right-add px py pz)))
     rhs))

-- § Left distributivity of *ℤ over +ℤ.
*ℤ-distrib-left-+ℤ : (x y z : ℤ) → (x +ℤ y) *ℤ z ≡ (x *ℤ z) +ℤ (y *ℤ z)
*ℤ-distrib-left-+ℤ x y z =
 let px = toPairℤ x in
 let py = toPairℤ y in
 let pz = toPairℤ z in
 let q = Pairℕ-add px py in
 let rhs : fromPairℤ (Pairℕ-add (Pairℕ-mul px pz) (Pairℕ-mul py pz)) ≡ (x *ℤ z) +ℤ (y *ℤ z)
     rhs =
      trans
       (cong (λ t → fromPairℤ (Pairℕ-add t (Pairℕ-mul py pz))) (sym (toPair-*ℤ x z)))
       (trans
        (cong (λ t → fromPairℤ (Pairℕ-add (toPairℤ (x *ℤ z)) t)) (sym (toPair-*ℤ y z)))
        refl)
 in
 trans
  (cong (λ t → fromPairℤ (Pairℕ-mul t pz)) (toPair-+ℤ x y))
  (trans
    (trans
     (sym (fromPair-normalizePair (Pairℕ-mul (normalizePair q) pz)))
     (cong fromPairℤ (Pairℕ-mul-normalize-left q pz)))
    (trans
     (trans
      (fromPair-normalizePair (Pairℕ-mul q pz))
      (cong fromPairℤ (Pairℕ-mul-distrib-left-add px py pz)))
     rhs))
```

Step 2: Pair Extensionality and Commutativity. Distributivity at the ℤ level follows from pair-level distributivity plus normalization absorption. The remaining structure—commutativity and canonical pair products—proceeds at the pair level directly.

```
-- § Pair extensionality.
Pairℕ-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
Pairℕ-ext refl refl = refl

-- § Commutativity of Pairℕ-mul.
Pairℕ-mul-comm : (p q : Pairℕ) → Pairℕ-mul p q ≡ Pairℕ-mul q p
Pairℕ-mul-comm p q =
 Pairℕ-ext posEq negEq
 where
  ap = pos p
  bp = neg p
  cq = pos q
  dq = neg q
```

```
posEq : ((ap *ℕ cq) +ℕ (bp *ℕ dq)) ≡ ((cq *ℕ ap) +ℕ (dq *ℕ bp))
posEq =
 trans
  (cong (λ t → t +ℕ (bp *ℕ dq)) (*ℕ-comm ap cq))
  (trans
   (cong (λ t → (cq *ℕ ap) +ℕ t) (*ℕ-comm bp dq))
   refl)

negEq : ((ap *ℕ dq) +ℕ (bp *ℕ cq)) ≡ ((cq *ℕ bp) +ℕ (dq *ℕ ap))
negEq =
 trans
  (cong (λ t → t +ℕ (bp *ℕ cq)) (*ℕ-comm ap dq))
  (trans
   (cong (λ t → (dq *ℕ ap) +ℕ t) (*ℕ-comm bp cq))
   (+ℕ-comm (dq *ℕ ap) (cq *ℕ bp)))
```

Step 3: Canonical Pair Products. Multiplication of canonical pairs—those coming from toPairℤ—has four sign cases. Each reduces to a simple formula with zero in one component, confirming that canonical pairs form a multiplicative subsystem.

```
-- § Canonical pair products: (+,0) × (+,0).
Pairℕ-mul-pos-pos : (a b : ℕ) →
 Pairℕ-mul (mkPairℕ a zero) (mkPairℕ b zero) ≡ (mkPairℕ (a *ℕ b) zero)
Pairℕ-mul-pos-pos a b =
 pair-ext
  (trans
   (cong (λ t → (a *ℕ b) +ℕ t) (*ℕ-zero-left zero))
   (+ℕ-zero-right (a *ℕ b)))
  (trans
   (cong (λ t → (a *ℕ zero) +ℕ t) (*ℕ-zero-left b))
   (trans
    (+ℕ-zero-right (a *ℕ zero))
    (*ℕ-zero-right a)))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl

-- § Canonical pair products: (+,0) × (0,+).
Pairℕ-mul-pos-neg : (a b : ℕ) →
 Pairℕ-mul (mkPairℕ a zero) (mkPairℕ zero b) ≡ (mkPairℕ zero (a *ℕ b))
Pairℕ-mul-pos-neg a b =
 pair-ext
  (trans
   (cong (λ t → (a *ℕ zero) +ℕ t) (*ℕ-zero-left b))
   (trans
    (+ℕ-zero-right (a *ℕ zero))
    (*ℕ-zero-right a)))
  (trans
   (cong (λ t → (a *ℕ b) +ℕ t) (*ℕ-zero-left zero))
   (+ℕ-zero-right (a *ℕ b)))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl

-- § Canonical pair products: (0,+) × (+,0).
Pairℕ-mul-neg-pos : (a b : ℕ) →
 Pairℕ-mul (mkPairℕ zero a) (mkPairℕ b zero) ≡ (mkPairℕ zero (a *ℕ b))
Pairℕ-mul-neg-pos a b =
 pair-ext
```

```
  (trans
   (cong (λ t → t +ℕ (a *ℕ zero)) (*ℕ-zero-left b))
   (trans
    (cong (λ t → zero +ℕ t) (*ℕ-zero-right a))
    refl))
  (+ℕ-zero-left (a *ℕ b))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl

-- § Canonical pair products: (0,+) × (0,+).
Pairℕ-mul-neg-neg : (a b : ℕ) →
 Pairℕ-mul (mkPairℕ zero a) (mkPairℕ zero b) ≡ (mkPairℕ (a *ℕ b) zero)
Pairℕ-mul-neg-neg a b =
 pair-ext
  (+ℕ-zero-left (a *ℕ b))
  (trans
   (cong (λ t → (zero *ℕ b) +ℕ t) (*ℕ-zero-right a))
   (trans
    (cong (λ t → t +ℕ zero) (*ℕ-zero-left b))
    (+ℕ-zero-left zero)))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl
```

Law 14P.0: Positive Nonzero Scalar Has No Torsion (Left)

If a positive integer $1 + n$ multiplied by x yields zero, then x must be zero. The proof extracts the vanishing product at the pair level, applies $\mathbb{N}$ cancellation, and derives the contradiction if x were nonzero.

```
-- § Law 14P.0: positive left factor is torsion-free.
*ℤ-pos-left-zero→zero : (n : ℕ) → (x : ℤ) → (+suc n *ℤ x ≡ 0ℤ) → x ≡ 0ℤ
*ℤ-pos-left-zero→zero n 0ℤ _ = refl
*ℤ-pos-left-zero→zero n (+suc m) mul0 =
 let
  eqPair : toPairℤ ((+suc n) *ℤ (+suc m)) ≡ toPairℤ 0ℤ
  eqPair = cong toPairℤ mul0

  step₁ : Pairℕ-mul (toPairℤ (+suc n)) (toPairℤ (+suc m)) ≡ (mkPairℕ zero zero)
  step₁ = trans (sym (toPair-*ℤ (+suc n) (+suc m))) eqPair

  pos0-raw : pos (Pairℕ-mul (toPairℤ (+suc n)) (toPairℤ (+suc m))) ≡ zero
  pos0-raw = cong pos step₁

  pos0 : (suc n *ℕ suc m) ≡ zero
  pos0 =
   trans
    (sym (+ℕ-zero-right (suc n *ℕ suc m)))
    pos0-raw

  bad : suc m ≡ zero
  bad = *ℕ-pos-zero→zero n (suc m) pos0
 in
 ⊥-elim (caseSucZero bad)
 where
  caseSucZero : {k : ℕ} → suc k ≡ zero → ⊥
  caseSucZero ()
```

```
*ℤ-pos-left-zero→zero n (-suc m) mul0 =
 let
  eqPair : toPairℤ ((+suc n) *ℤ (-suc m)) ≡ toPairℤ 0ℤ
  eqPair = cong toPairℤ mul0

  step₁ : Pairℕ-mul (toPairℤ (+suc n)) (toPairℤ (-suc m)) ≡ (mkPairℕ zero zero)
  step₁ = trans (sym (toPair-*ℤ (+suc n) (-suc m))) eqPair

  neg0-raw : neg (Pairℕ-mul (toPairℤ (+suc n)) (toPairℤ (-suc m))) ≡ zero
  neg0-raw = cong neg step₁

  neg0 : (suc n *ℕ suc m) ≡ zero
  neg0 =
   trans
    (sym (+ℕ-zero-right (suc n *ℕ suc m)))
    neg0-raw

  bad : suc m ≡ zero
  bad = *ℕ-pos-zero→zero n (suc m) neg0
 in
 ⊥-elim (caseSucZero bad)
 where
  caseSucZero : {k : ℕ} → suc k ≡ zero → ⊥
  caseSucZero ()
```

Laws 14P.1–14P.2: Multiplication Commutes With Negation

Multiplication must commute with negation on both sides: $x \cdot (-y) = -(x \cdot y)$ and $(-x) \cdot y = -(x \cdot y)$. Each proof uses the sum $x \cdot y + x \cdot (-y) = x \cdot 0 = 0$ to identify $x \cdot (-y)$ as the additive inverse of $x \cdot y$.

```
-- § Law 14P.1: *ℤ commutes with negℤ on the right.
*ℤ-neg-right : (x y : ℤ) → x *ℤ (negℤ y) ≡ negℤ (x *ℤ y)
*ℤ-neg-right x y =
 let
  eq0 : y +ℤ negℤ y ≡ 0ℤ
  eq0 = +ℤ-inv-right y

  mul0 : x *ℤ (y +ℤ negℤ y) ≡ x *ℤ 0ℤ
  mul0 = cong (λ t → x *ℤ t) eq0

  expand : x *ℤ (y +ℤ negℤ y) ≡ (x *ℤ y) +ℤ (x *ℤ negℤ y)
  expand = *ℤ-distrib-right-+ℤ x y (negℤ y)

  eqSum : (x *ℤ y) +ℤ (x *ℤ negℤ y) ≡ 0ℤ
  eqSum = trans (sym expand) (trans mul0 (*ℤ-zero-right x))

  addNeg : negℤ (x *ℤ y) +ℤ ((x *ℤ y) +ℤ (x *ℤ negℤ y)) ≡ negℤ (x *ℤ y) +ℤ 0ℤ
  addNeg = cong (λ t → negℤ (x *ℤ y) +ℤ t) eqSum

  leftReduce : negℤ (x *ℤ y) +ℤ ((x *ℤ y) +ℤ (x *ℤ negℤ y)) ≡ x *ℤ negℤ y
  leftReduce =
   trans
    (sym (+ℤ-assoc (negℤ (x *ℤ y)) (x *ℤ y) (x *ℤ negℤ y)))
    (trans
     (cong (λ t → t +ℤ (x *ℤ negℤ y)) (+ℤ-inv-left (x *ℤ y)))
     (+ℤ-zero-left (x *ℤ negℤ y)))

  rightReduce : negℤ (x *ℤ y) +ℤ 0ℤ ≡ negℤ (x *ℤ y)
```

```
  rightReduce = +ℤ-zero-right (negℤ (x *ℤ y))
 in
 trans
  (sym leftReduce)
  (trans addNeg rightReduce)

– § Law 14P.2: *ℤ commutes with negℤ on the left.
*ℤ-neg-left : (x y : ℤ) → (negℤ x) *ℤ y ≡ negℤ (x *ℤ y)
*ℤ-neg-left x y =
 let
  eq0 : negℤ x +ℤ x ≡ 0ℤ
  eq0 = +ℤ-inv-left x

  mul0 : (negℤ x +ℤ x) *ℤ y ≡ 0ℤ *ℤ y
  mul0 = cong (λ t → t *ℤ y) eq0

  expand : (negℤ x +ℤ x) *ℤ y ≡ (negℤ x *ℤ y) +ℤ (x *ℤ y)
  expand = *ℤ-distrib-left-+ℤ (negℤ x) x y

  eqSum' : (negℤ x *ℤ y) +ℤ (x *ℤ y) ≡ 0ℤ
  eqSum' = trans (sym expand) (trans mul0 (*ℤ-zero-left y))

  addInv : ((negℤ x *ℤ y) +ℤ (x *ℤ y)) +ℤ negℤ (x *ℤ y) ≡ 0ℤ +ℤ negℤ (x *ℤ y)
  addInv = cong (λ t → t +ℤ negℤ (x *ℤ y)) eqSum'

  lhsReduce : ((negℤ x *ℤ y) +ℤ (x *ℤ y)) +ℤ negℤ (x *ℤ y) ≡ negℤ x *ℤ y
  lhsReduce =
   trans
    (+ℤ-assoc (negℤ x *ℤ y) (x *ℤ y) (negℤ (x *ℤ y)))
    (trans
     (cong (λ t → (negℤ x *ℤ y) +ℤ t) (+ℤ-inv-right (x *ℤ y)))
     (+ℤ-zero-right (negℤ x *ℤ y)))

  rhsReduce : 0ℤ +ℤ negℤ (x *ℤ y) ≡ negℤ (x *ℤ y)
  rhsReduce = +ℤ-zero-left (negℤ (x *ℤ y))
 in
 trans
  (sym lhsReduce)
  (trans addInv rhsReduce)
```

Law 14P.3: Negative Nonzero Scalar Has No Torsion (Left)

The mirror case of Law 14P.0: if a negative integer $-(1+n)$ multiplied by x yields zero, then x must again be zero. The argument is identical, but applied to the opposite sign constructor.

```
– § Law 14P.3: negative left factor is torsion-free.
*ℤ-neg-left-zero→zero : (n : ℕ) → (x : ℤ) → (-suc n *ℤ x ≡ 0ℤ) → x ≡ 0ℤ
*ℤ-neg-left-zero→zero n 0ℤ _ = refl
*ℤ-neg-left-zero→zero n (+suc m) mul0 =
 let
  eqPair : toPairℤ ((-suc n) *ℤ (+suc m)) ≡ toPairℤ 0ℤ
  eqPair = cong toPairℤ mul0

  step₁ : Pairℕ-mul (toPairℤ (-suc n)) (toPairℤ (+suc m)) ≡ (mkPairℕ zero zero)
  step₁ = trans (sym (toPair-*ℤ (-suc n) (+suc m))) eqPair

  neg0-raw : neg (Pairℕ-mul (toPairℤ (-suc n)) (toPairℤ (+suc m))) ≡ zero
  neg0-raw = cong neg step₁
```

```
  neg0 : (suc n *ℕ suc m) ≡ zero
  neg0 =
   trans
    (sym (+ℕ-zero-left (suc n *ℕ suc m)))
     neg0-raw

  bad : suc m ≡ zero
  bad = *ℕ-pos-zero→zero n (suc m) neg0
 in
 ⊥-elim (caseSucZero bad)
 where
  caseSucZero : {k : ℕ} → suc k ≡ zero → ⊥
  caseSucZero ()

*ℤ-neg-left-zero→zero n (-suc m) mul0 =
 let
  eqPair : toPairℤ ((-suc n) *ℤ (-suc m)) ≡ toPairℤ 0ℤ
  eqPair = cong toPairℤ mul0

  step₁ : Pairℕ-mul (toPairℤ (-suc n)) (toPairℤ (-suc m)) ≡ (mkPairℕ zero zero)
  step₁ = trans (sym (toPair-*ℤ (-suc n) (-suc m))) eqPair

  pos0-raw : pos (Pairℕ-mul (toPairℤ (-suc n)) (toPairℤ (-suc m))) ≡ zero
  pos0-raw = cong pos step₁

  pos0 : (suc n *ℕ suc m) ≡ zero
  pos0 =
   trans
    (sym (+ℕ-zero-left (suc n *ℕ suc m)))
     pos0-raw

  bad : suc m ≡ zero
  bad = *ℕ-pos-zero→zero n (suc m) pos0
 in
 ⊥-elim (caseSucZero bad)
 where
  caseSucZero : {k : ℕ} → suc k ≡ zero → ⊥
  caseSucZero ()
```

Pair-Level Associativity and ℤ Ring Closure

Associativity of $*_{\mathbb{Z}}$ cannot be proven by a single induction—the pair representation requires zero-annihilation base cases (seven combinations of a zero factor) and then eight nonzero cases, each expanding both association trees through canonical pair products and appealing to ℕ associativity. The lifting from pairs to signed integers uses the toPairℤ/fromPairℤ round-trip.

```
-- § Zero annihilation at pair level (right).
Pairℕ-mul-zero-right : (p : Pairℕ) → Pairℕ-mul p (mkPairℕ zero zero) ≡ (mkPairℕ zero zero)
Pairℕ-mul-zero-right (mkPairℕ a b) =
 pair-ext
  (trans
   (cong (λ t → t +ℕ (b *ℕ zero)) (*ℕ-zero-right a))
   (trans
    (cong (λ t → zero +ℕ t) (*ℕ-zero-right b))
    refl))
  (trans
   (cong (λ t → t +ℕ (b *ℕ zero)) (*ℕ-zero-right a))
```

```
  (trans
   (cong (λ t → zero +ℕ t) (*ℕ-zero-right b))
   refl))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl

-- § Zero annihilation at pair level (left).
Pairℕ-mul-zero-left : (p : Pairℕ) → Pairℕ-mul (mkPairℕ zero zero) p ≡ (mkPairℕ zero zero)
Pairℕ-mul-zero-left (mkPairℕ a b) =
 pair-ext
  (trans
   (cong (λ t → t +ℕ (zero *ℕ b)) (*ℕ-zero-left a))
   (trans
    (cong (λ t → zero +ℕ t) (*ℕ-zero-left b))
    refl))
  (trans
   (cong (λ t → t +ℕ (zero *ℕ a)) (*ℕ-zero-left b))
   (trans
    (cong (λ t → zero +ℕ t) (*ℕ-zero-left a))
    refl))
 where
  pair-ext : {x y x' y' : ℕ} → x ≡ x' → y ≡ y' → (mkPairℕ x y) ≡ (mkPairℕ x' y')
  pair-ext refl refl = refl
```

Step 2: Associativity Base Cases (Zero Factor). When one of the three operands is zero, associativity reduces to zero-annihilation on both association trees. Seven base cases cover all positions where zero can appear.

```
-- § Associativity at pair level for canonical pairs (16-case proof).
Pairℕ-mul-toPair-assoc : (x y z : ℤ) →
 Pairℕ-mul (Pairℕ-mul (toPairℤ x) (toPairℤ y)) (toPairℤ z)
  ≡
 Pairℕ-mul (toPairℤ x) (Pairℕ-mul (toPairℤ y) (toPairℤ z))
Pairℕ-mul-toPair-assoc 0ℤ y z = refl
Pairℕ-mul-toPair-assoc (+suc n) 0ℤ z =
 trans
  (cong (λ t → Pairℕ-mul t (toPairℤ z)) (Pairℕ-mul-zero-right (mkPairℕ (suc n) zero)))
  (trans
   (Pairℕ-mul-zero-left (toPairℤ z))
   (sym
    (trans
     (cong (λ t → Pairℕ-mul (mkPairℕ (suc n) zero) t) (Pairℕ-mul-zero-left (toPairℤ z)))
     (Pairℕ-mul-zero-right (mkPairℕ (suc n) zero)))))
Pairℕ-mul-toPair-assoc (-suc n) 0ℤ z =
 trans
  (cong (λ t → Pairℕ-mul t (toPairℤ z)) (Pairℕ-mul-zero-right (mkPairℕ zero (suc n))))
  (trans
   (Pairℕ-mul-zero-left (toPairℤ z))
   (sym
    (trans
     (cong (λ t → Pairℕ-mul (mkPairℕ zero (suc n)) t) (Pairℕ-mul-zero-left (toPairℤ z)))
     (Pairℕ-mul-zero-right (mkPairℕ zero (suc n))))))
Pairℕ-mul-toPair-assoc (+suc n) (+suc m) 0ℤ =
 trans
  (Pairℕ-mul-zero-right (Pairℕ-mul (mkPairℕ (suc n) zero) (mkPairℕ (suc m) zero)))
  (sym
   (trans
    (cong (λ t → Pairℕ-mul (mkPairℕ (suc n) zero) t) (Pairℕ-mul-zero-right (mkPairℕ (suc m) zero)))
```

```
    (Pairℕ-mul-zero-right (mkPairℕ (suc n) zero))))
Pairℕ-mul-toPair-assoc (+suc n) (-suc m) 0ℤ =
 trans
  (Pairℕ-mul-zero-right (Pairℕ-mul (mkPairℕ (suc n) zero) (mkPairℕ zero (suc m))))
  (sym
   (trans
    (cong (λ t → Pairℕ-mul (mkPairℕ (suc n) zero) t) (Pairℕ-mul-zero-right (mkPairℕ zero (suc m))))
    (Pairℕ-mul-zero-right (mkPairℕ (suc n) zero))))
Pairℕ-mul-toPair-assoc (-suc n) (+suc m) 0ℤ =
 trans
  (Pairℕ-mul-zero-right (Pairℕ-mul (mkPairℕ zero (suc n)) (mkPairℕ (suc m) zero)))
  (sym
   (trans
    (cong (λ t → Pairℕ-mul (mkPairℕ zero (suc n)) t) (Pairℕ-mul-zero-right (mkPairℕ (suc m) zero)))
    (Pairℕ-mul-zero-right (mkPairℕ zero (suc n)))))
Pairℕ-mul-toPair-assoc (-suc n) (-suc m) 0ℤ =
 trans
  (Pairℕ-mul-zero-right (Pairℕ-mul (mkPairℕ zero (suc n)) (mkPairℕ zero (suc m))))
  (sym
   (trans
    (cong (λ t → Pairℕ-mul (mkPairℕ zero (suc n)) t) (Pairℕ-mul-zero-right (mkPairℕ zero (suc m))))
    (Pairℕ-mul-zero-right (mkPairℕ zero (suc n)))))
```

Step 3: Associativity Nonzero Cases. The remaining eight cases handle three nonzero operands. Each follows the same pattern: expand both association trees using the appropriate canonical pair product lemma, then appeal to *ℕ-assoc for the natural number core.

```
Pairℕ-mul-toPair-assoc (+suc n) (+suc m) (+suc k) =
 trans
  (cong (λ t → Pairℕ-mul t (mkPairℕ (suc k) zero)) (Pairℕ-mul-pos-pos (suc n) (suc m)))
  (trans
   (Pairℕ-mul-pos-pos ((suc n) *ℕ (suc m)) (suc k))
   (trans
    (Pairℕ-ext (*ℕ-assoc (suc n) (suc m) (suc k)) refl)
    (sym
     (trans
      (cong (λ t → Pairℕ-mul (mkPairℕ (suc n) zero) t) (Pairℕ-mul-pos-pos (suc m) (suc k)))
      (Pairℕ-mul-pos-pos (suc n) ((suc m) *ℕ (suc k)))))))
Pairℕ-mul-toPair-assoc (+suc n) (+suc m) (-suc k) =
 trans
  (cong (λ t → Pairℕ-mul t (mkPairℕ zero (suc k))) (Pairℕ-mul-pos-pos (suc n) (suc m)))
  (trans
   (Pairℕ-mul-pos-neg ((suc n) *ℕ (suc m)) (suc k))
   (trans
    (Pairℕ-ext refl (*ℕ-assoc (suc n) (suc m) (suc k)))
    (sym
     (trans
      (cong (λ t → Pairℕ-mul (mkPairℕ (suc n) zero) t) (Pairℕ-mul-pos-neg (suc m) (suc k)))
      (Pairℕ-mul-pos-neg (suc n) ((suc m) *ℕ (suc k)))))))
Pairℕ-mul-toPair-assoc (+suc n) (-suc m) (+suc k) =
 trans
  (cong (λ t → Pairℕ-mul t (mkPairℕ (suc k) zero)) (Pairℕ-mul-pos-neg (suc n) (suc m)))
  (trans
   (Pairℕ-mul-neg-pos ((suc n) *ℕ (suc m)) (suc k))
   (trans
    (Pairℕ-ext refl (*ℕ-assoc (suc n) (suc m) (suc k)))
    (sym
     (trans
      (cong (λ t → Pairℕ-mul (mkPairℕ (suc n) zero) t) (Pairℕ-mul-neg-pos (suc m) (suc k)))
```

```
    (Pairℕ-mul-pos-neg (suc n) ((suc m) *ℕ (suc k)))))))
Pairℕ-mul-toPair-assoc (+suc n) (-suc m) (-suc k) =
 trans
  (cong (λ t → Pairℕ-mul t (mkPairℕ zero (suc k))) (Pairℕ-mul-pos-neg (suc n) (suc m)))
  (trans
   (Pairℕ-mul-neg-neg ((suc n) *ℕ (suc m)) (suc k))
   (trans
    (Pairℕ-ext (*ℕ-assoc (suc n) (suc m) (suc k)) refl)
    (sym
     (trans
      (cong (λ t → Pairℕ-mul (mkPairℕ (suc n) zero) t) (Pairℕ-mul-neg-neg (suc m) (suc k)))
      (Pairℕ-mul-pos-pos (suc n) ((suc m) *ℕ (suc k)))))))
Pairℕ-mul-toPair-assoc (-suc n) (+suc m) (+suc k) =
 trans
  (cong (λ t → Pairℕ-mul t (mkPairℕ (suc k) zero)) (Pairℕ-mul-neg-pos (suc n) (suc m)))
  (trans
   (Pairℕ-mul-neg-pos ((suc n) *ℕ (suc m)) (suc k))
   (trans
    (Pairℕ-ext refl (*ℕ-assoc (suc n) (suc m) (suc k)))
    (sym
     (trans
      (cong (λ t → Pairℕ-mul (mkPairℕ zero (suc n)) t) (Pairℕ-mul-pos-pos (suc m) (suc k)))
      (Pairℕ-mul-neg-pos (suc n) ((suc m) *ℕ (suc k)))))))
Pairℕ-mul-toPair-assoc (-suc n) (+suc m) (-suc k) =
 trans
  (cong (λ t → Pairℕ-mul t (mkPairℕ zero (suc k))) (Pairℕ-mul-neg-pos (suc n) (suc m)))
  (trans
   (Pairℕ-mul-neg-neg ((suc n) *ℕ (suc m)) (suc k))
   (trans
    (Pairℕ-ext (*ℕ-assoc (suc n) (suc m) (suc k)) refl)
    (sym
     (trans
      (cong (λ t → Pairℕ-mul (mkPairℕ zero (suc n)) t) (Pairℕ-mul-pos-neg (suc m) (suc k)))
      (Pairℕ-mul-neg-neg (suc n) ((suc m) *ℕ (suc k)))))))
Pairℕ-mul-toPair-assoc (-suc n) (-suc m) (+suc k) =
 trans
  (cong (λ t → Pairℕ-mul t (mkPairℕ (suc k) zero)) (Pairℕ-mul-neg-neg (suc n) (suc m)))
  (trans
   (Pairℕ-mul-pos-pos ((suc n) *ℕ (suc m)) (suc k))
   (trans
    (Pairℕ-ext (*ℕ-assoc (suc n) (suc m) (suc k)) refl)
    (sym
     (trans
      (cong (λ t → Pairℕ-mul (mkPairℕ zero (suc n)) t) (Pairℕ-mul-neg-pos (suc m) (suc k)))
      (Pairℕ-mul-neg-neg (suc n) ((suc m) *ℕ (suc k)))))))
Pairℕ-mul-toPair-assoc (-suc n) (-suc m) (-suc k) =
 trans
  (cong (λ t → Pairℕ-mul t (mkPairℕ zero (suc k))) (Pairℕ-mul-neg-neg (suc n) (suc m)))
  (trans
   (Pairℕ-mul-pos-neg ((suc n) *ℕ (suc m)) (suc k))
   (trans
    (Pairℕ-ext refl (*ℕ-assoc (suc n) (suc m) (suc k)))
    (sym
     (trans
      (cong (λ t → Pairℕ-mul (mkPairℕ zero (suc n)) t) (Pairℕ-mul-neg-neg (suc m) (suc k)))
      (Pairℕ-mul-neg-pos (suc n) ((suc m) *ℕ (suc k)))))))
```

Step 4: Lifting to ℤ. With pair-level associativity established for all canonical pairs, lifting to ℤ uses the toPairℤ/fromPairℤ bridge. Commutativity follows directly from pair-level commu-

tativity.

```
opaque
 unfolding _*ℤ_
 -- § Associativity of *ℤ.
 *ℤ-assoc : (x y z : ℤ) → (x *ℤ y) *ℤ z ≡ x *ℤ (y *ℤ z)
 *ℤ-assoc x y z =
  let lhs = (x *ℤ y) *ℤ z in
  let rhs = x *ℤ (y *ℤ z) in
  trans
   (sym (from-toPairℤ lhs))
   (trans
    (cong fromPairℤ
     (trans
      (trans
       (toPair-*ℤ (x *ℤ y) z)
       (cong (λ t → Pairℕ-mul t (toPairℤ z)) (toPair-*ℤ x y)))
      (trans
       (Pairℕ-mul-toPair-assoc x y z)
       (sym
        (trans
         (toPair-*ℤ x (y *ℤ z))
         (cong (λ t → Pairℕ-mul (toPairℤ x) t) (toPair-*ℤ y z)))))))
    (from-toPairℤ rhs))

 -- § Commutativity of *ℤ.
 *ℤ-comm : (x y : ℤ) → x *ℤ y ≡ y *ℤ x
 *ℤ-comm x y = cong fromPairℤ (Pairℕ-mul-comm (toPairℤ x) (toPairℤ y))
```

Chapter 25

Integer Order Laws

Spectral operators send positive scalars to positive scalars and reflect the ordering: if the output is larger, the input was larger. Without these guarantees, eigenvalue comparisons would be meaningless and spectral gaps could not be bounded. Transport of $\leq_{\mathbb{Z}}$ along equality, antitone negation, positivity elimination, and monotone/cancellative multiplication are each forced by exhaustive sign-case analysis on the three constructors of $\mathbb{Z}$. The result is an ordered integral domain: multiplication by a positive factor preserves and reflects order, and strict inequality is preserved as well.

Transport and Negation

Transport of $\leq_{\mathbb{Z}}$ and $<_{\mathbb{Z}}$ along equalities is structurally trivial (refl leaves the witness unchanged), but must be stated explicitly so that later proofs can substitute equal values on either side of a comparison. Negation reverses order: $x \leq y$ implies $-y \leq -x$. The proof exhausts all nine sign-pair combinations.

```
-- § Transport ≤ℤ along left equality.
≤ℤ-resp-≡ˡ : {x y z : ℤ} → x ≡ y → x ≤ℤ z → y ≤ℤ z
≤ℤ-resp-≡ˡ refl p = p

-- § Transport ≤ℤ along right equality.
≤ℤ-resp-≡ʳ : {x y z : ℤ} → y ≡ z → x ≤ℤ y → x ≤ℤ z
≤ℤ-resp-≡ʳ refl p = p

-- § Transport <ℤ along left equality.
<ℤ-resp-≡ˡ : {x y z : ℤ} → x ≡ y → x <ℤ z → y <ℤ z
<ℤ-resp-≡ˡ refl p = p

-- § Transport <ℤ along right equality.
<ℤ-resp-≡ʳ : {x y z : ℤ} → y ≡ z → x <ℤ y → x <ℤ z
<ℤ-resp-≡ʳ refl p = p

-- § Negation reverses order (antitone).
negℤ-antitone-≤ℤ : {x y : ℤ} → x ≤ℤ y → (negℤ y) ≤ℤ (negℤ x)
negℤ-antitone-≤ℤ {0ℤ} {0ℤ} _ = tt
negℤ-antitone-≤ℤ {0ℤ} {+suc n} _ = tt
negℤ-antitone-≤ℤ {0ℤ} { -suc n } ()
negℤ-antitone-≤ℤ {+suc m} {0ℤ} ()
```

```
negℤ-antitone-≤ℤ {+suc m} {+suc n} p = p
negℤ-antitone-≤ℤ {+suc m} { -suc n } ()
negℤ-antitone-≤ℤ { -suc m } {0ℤ} _ = tt
negℤ-antitone-≤ℤ { -suc m } {+suc n} _ = tt
negℤ-antitone-≤ℤ { -suc m } { -suc n } p = p
```

Positivity Elimination

When a proof that $0 <_{\mathbb{Z}} z$ is in hand, the integer z must inhabit the +suc constructor—the zero and negative constructors are ruled out by the ordering. The elimination lemma and its immediate corollary ($0 <$ +suc n is trivially inhabited) provide the bridge from order-theoretic hypotheses to structural pattern matching.

```
-- § From 0 < z, force z into positive constructor form.
0<ℤ→pos : (z : ℤ) → 0ℤ <ℤ z → Σ ℕ (λ n → z ≡ +suc n)
0<ℤ→pos 0ℤ (p≤ , p≢) = ⊥-elim (p≢ p≤)
0<ℤ→pos (+suc n) _ = n , refl
0<ℤ→pos (-suc n) (() , _)

-- § 0 < +suc n is immediate.
0<ℤ-pos : (n : ℕ) → 0ℤ <ℤ (+suc n)
0<ℤ-pos n = tt , (λ p → p)
```

Multiplicative Monotonicity and Cancellation

Step 1: Product of positive constructors, positive multiplication, and negative-positive product. These three lemmas establish the concrete form of products involving positive (and negative) integers, and that multiplying a positive integer by a positive $\mathbb{N}^+$ stays positive.

```
opaque
 unfolding _*ℤ_
 -- § Product of positive constructors stays positive.
 *ℤ-pos-pos-eq : (m n : ℕ) → (+suc m) *ℤ (+suc n) ≡ +suc (n +ℕ (m *ℕ suc n))
 *ℤ-pos-pos-eq m n =
  let posStep : (suc m *ℕ suc n) +ℕ (zero *ℕ zero) ≡ suc (n +ℕ (m *ℕ suc n))
      posStep =
       trans
        (cong (λ t → (suc m *ℕ suc n) +ℕ t) (*ℕ-zero-left zero))
        (trans
         (+ℕ-zero-right (suc m *ℕ suc n))
         refl)

      negStep : (suc m *ℕ zero) +ℕ (zero *ℕ suc n) ≡ zero
      negStep =
       trans
        (cong (λ t → t +ℕ (zero *ℕ suc n)) (*ℕ-zero-right (suc m)))
        (trans
         (cong (λ t → zero +ℕ t) (*ℕ-zero-left (suc n)))
         refl)
  in
  trans
    (normalizeℤ-cong posStep negStep)
    refl
```

```
-- § 0 < z · d for z positive and d a positive natural.
0<ℤ-mul-pos-right : (z : ℤ) → (d : ℕ⁺) → 0ℤ <ℤ z → 0ℤ <ℤ (z *ℤ ⁺toℤ d)
0<ℤ-mul-pos-right z (mkℕ⁺ k) zpos =
 let zShape = 0<ℤ→pos z zpos
     m = fst zShape
     z≡ = snd zShape

     prod≡ : z *ℤ (+suc k) ≡ (+suc m) *ℤ (+suc k)
     prod≡ = cong (λ t → t *ℤ (+suc k)) z≡

     basePos : 0ℤ <ℤ ((+suc m) *ℤ (+suc k))
     basePos =
      <ℤ-resp-≡ʳ (sym (*ℤ-pos-pos-eq m k)) (0<ℤ-pos (k +ℕ (m *ℕ suc k)))

 in
 <ℤ-resp-≡ʳ (sym prod≡) basePos

-- § Product of negative and positive constructors.
*ℤ-neg-pos-eq : (m k : ℕ) → (-suc m) *ℤ (+suc k) ≡ -suc (k +ℕ (m *ℕ suc k))
*ℤ-neg-pos-eq m k =
 trans
  (*ℤ-neg-left (+suc m) (+suc k))
  (trans
     (cong negℤ (*ℤ-pos-pos-eq m k))
     refl)
```

Step 2: Multiplication by positive $\mathbb{N}^+$ preserves $\leq_{\mathbb{Z}}$. The 9-case proof exhausts all sign combinations.

```
-- § Multiplication by positive ℕ⁺ preserves ≤ℤ (9-case proof).
≤ℤ-mul-pos-right : (x y : ℤ) → (d : ℕ⁺) → x ≤ℤ y → (x *ℤ ⁺toℤ d) ≤ℤ (y *ℤ ⁺toℤ d)
≤ℤ-mul-pos-right 0ℤ 0ℤ (mkℕ⁺ k) _ =
 subst
  (λ t → t ≤ℤ t)
  (sym (*ℤ-zero-left (+suc k)))
  tt
≤ℤ-mul-pos-right 0ℤ (+suc n) (mkℕ⁺ k) _ =
 let
  t = k +ℕ (n *ℕ suc k)
  eqL : 0ℤ ≡ 0ℤ *ℤ (+suc k)
  eqL = sym (*ℤ-zero-left (+suc k))

  eqR : (+suc t) ≡ ((+suc n) *ℤ (+suc k))
  eqR = sym (*ℤ-pos-pos-eq n k)

  base : 0ℤ ≤ℤ (+suc t)
  base = tt
 in
 subst (λ r → (0ℤ *ℤ (+suc k)) ≤ℤ r) eqR
  (subst (λ l → l ≤ℤ (+suc t)) eqL base)
≤ℤ-mul-pos-right 0ℤ (-suc n) d ()
≤ℤ-mul-pos-right (+suc m) 0ℤ d ()
≤ℤ-mul-pos-right (+suc m) (+suc n) (mkℕ⁺ k) (s≤s p) =
 let
  t₁ = k +ℕ (m *ℕ suc k)
  t₂ = k +ℕ (n *ℕ suc k)

  mulMono : (m *ℕ suc k) ≤ (n *ℕ suc k)
```

```
  mulMono = ≤-*ℕ-mono^r p (suc k)

  addMono : t₁ ≤ t₂
  addMono = ≤-+ℕ-mono^l mulMono k

  base : (+suc t₁) ≤ℤ (+suc t₂)
  base = s≤s addMono
 in
 ≤ℤ-resp-≡^l (sym (*ℤ-pos-pos-eq m k))
  (≤ℤ-resp-≡^r (sym (*ℤ-pos-pos-eq n k)) base)
≤ℤ-mul-pos-right (+suc m) (-suc n) d ()
≤ℤ-mul-pos-right (-suc m) 0ℤ (mkℕ⁺ k) _ =
 let
  t₁ = k +ℕ (m *ℕ suc k)
  eqL : (-suc t₁) ≡ ((-suc m) *ℤ (+suc k))
  eqL = sym (*ℤ-neg-pos-eq m k)

  eqR : 0ℤ ≡ (0ℤ *ℤ (+suc k))
  eqR = sym (*ℤ-zero-left (+suc k))

  base : (-suc t₁) ≤ℤ 0ℤ
  base = tt
 in
 subst (λ r → ((-suc m) *ℤ (+suc k)) ≤ℤ r) eqR
  (subst (λ l → l ≤ℤ 0ℤ) eqL base)
≤ℤ-mul-pos-right (-suc m) (+suc n) (mkℕ⁺ k) _ =
 let
  t₁ = k +ℕ (m *ℕ suc k)
  t₂ = k +ℕ (n *ℕ suc k)
  eqL : (-suc t₁) ≡ ((-suc m) *ℤ (+suc k))
  eqL = sym (*ℤ-neg-pos-eq m k)

  eqR : (+suc t₂) ≡ ((+suc n) *ℤ (+suc k))
  eqR = sym (*ℤ-pos-pos-eq n k)

  base : (-suc t₁) ≤ℤ (+suc t₂)
  base = tt
 in
 subst (λ r → ((-suc m) *ℤ (+suc k)) ≤ℤ r) eqR
  (subst (λ l → l ≤ℤ (+suc t₂)) eqL base)
≤ℤ-mul-pos-right (-suc m) (-suc n) (mkℕ⁺ k) (s≤s p) =
 let
  t₁ = k +ℕ (m *ℕ suc k)
  t₂ = k +ℕ (n *ℕ suc k)

  mulMono : (n *ℕ suc k) ≤ (m *ℕ suc k)
  mulMono = ≤-*ℕ-mono^r p (suc k)

  addMono : t₂ ≤ t₁
  addMono = ≤-+ℕ-mono^l mulMono k

  base : (-suc t₁) ≤ℤ (-suc t₂)
  base = s≤s addMono
 in
 ≤ℤ-resp-≡^l (sym (*ℤ-neg-pos-eq m k))
  (≤ℤ-resp-≡^r (sym (*ℤ-neg-pos-eq n k)) base)
```

Step 3: Cancellation of positive right factor. If $x \cdot d \leq y \cdot d$ for positive d, then $x \leq y$. The proof again exhausts all 9 sign combinations.

```
– § Cancellation: if x·d ≤ y·d for positive d, then x ≤ y (9-case proof).
≤ℤ-mul-pos-cancel-right : (x y : ℤ) → (d : ℕ⁺) → (x *ℤ ⁺toℤ d) ≤ℤ (y *ℤ ⁺toℤ d) → x ≤ℤ y
≤ℤ-mul-pos-cancel-right 0ℤ 0ℤ (mkℕ⁺ k) p = tt
≤ℤ-mul-pos-cancel-right 0ℤ (+suc n) (mkℕ⁺ k) p = tt
≤ℤ-mul-pos-cancel-right 0ℤ (-suc n) (mkℕ⁺ k) p =
 let
  t : ℕ
  t = k +ℕ (n *ℕ suc k)

  rhsEq : ((-suc n) *ℤ (+suc k)) ≡ (-suc t)
  rhsEq = *ℤ-neg-pos-eq n k

  p0 : (0ℤ *ℤ (+suc k)) ≤ℤ ((-suc n) *ℤ (+suc k))
  p0 = p

  p1 : 0ℤ ≤ℤ ((-suc n) *ℤ (+suc k))
  p1 = subst (λ s → s ≤ℤ ((-suc n) *ℤ (+suc k))) (*ℤ-zero-left (+suc k)) p0

  p' : 0ℤ ≤ℤ (-suc t)
  p' = subst (λ r → 0ℤ ≤ℤ r) rhsEq p1
 in
 ⊥-elim p'
≤ℤ-mul-pos-cancel-right (+suc m) 0ℤ (mkℕ⁺ k) p =
 let
  t = k +ℕ (m *ℕ suc k)
  lhsPos : ((+suc m) *ℤ (+suc k)) ≡ +suc t
  lhsPos = *ℤ-pos-pos-eq m k

  p0 : ((+suc m) *ℤ (+suc k)) ≤ℤ (0ℤ *ℤ (+suc k))
  p0 = p

  p1 : ((+suc m) *ℤ (+suc k)) ≤ℤ 0ℤ
  p1 = subst (λ r → ((+suc m) *ℤ (+suc k)) ≤ℤ r) (*ℤ-zero-left (+suc k)) p0

  p' : (+suc t) ≤ℤ 0ℤ
  p' = subst (λ s → s ≤ℤ 0ℤ) lhsPos p1
 in
 ⊥-elim p'
≤ℤ-mul-pos-cancel-right (+suc m) (+suc n) (mkℕ⁺ k) p =
 let
  t₁ = k +ℕ (m *ℕ suc k)
  t₂ = k +ℕ (n *ℕ suc k)

  lhsEq : (+suc t₁) ≡ ((+suc m) *ℤ (+suc k))
  lhsEq = sym (*ℤ-pos-pos-eq m k)

  rhsEq : (+suc t₂) ≡ ((+suc n) *ℤ (+suc k))
  rhsEq = sym (*ℤ-pos-pos-eq n k)

  step : (+suc t₁) ≤ℤ (+suc t₂)
  step =
   ≤ℤ-resp-≡ˡ (sym lhsEq)
    (≤ℤ-resp-≡ʳ (sym rhsEq) p)

  natStep : suc t₁ ≤ suc t₂
  natStep = step

  t₁≤t₂ : t₁ ≤ t₂
  t₁≤t₂ = ≤-+ℕ-cancelˡ (suc zero) t₁ t₂ natStep

  mulPart : (m *ℕ suc k) ≤ (n *ℕ suc k)
  mulPart = ≤-+ℕ-cancelˡ k (m *ℕ suc k) (n *ℕ suc k) t₁≤t₂
```

```
  base : m ≤ n
  base = ≤-*ℕ-cancelʳ-suc k mulPart
 in
 s≤s base
≤ℤ-mul-pos-cancel-right (+suc m) (-suc n) (mkℕ⁺ k) p =
 let
  t₁ : ℕ
  t₁ = k +ℕ (m *ℕ suc k)

  t₂ : ℕ
  t₂ = k +ℕ (n *ℕ suc k)

  lhsPos : ((+suc m) *ℤ (+suc k)) ≡ (+suc t₁)
  lhsPos = *ℤ-pos-pos-eq m k

  rhsNeg : ((-suc n) *ℤ (+suc k)) ≡ (-suc t₂)
  rhsNeg = *ℤ-neg-pos-eq n k

  p1 : ((+suc m) *ℤ (+suc k)) ≤ℤ (-suc t₂)
  p1 = ≤ℤ-resp-≡ʳ rhsNeg p

  p2 : (+suc t₁) ≤ℤ (-suc t₂)
  p2 = subst (λ s → s ≤ℤ (-suc t₂)) lhsPos p1
 in
 ⊥-elim p2
≤ℤ-mul-pos-cancel-right (-suc m) 0ℤ (mkℕ⁺ k) p = tt
≤ℤ-mul-pos-cancel-right (-suc m) (+suc n) (mkℕ⁺ k) p = tt
≤ℤ-mul-pos-cancel-right (-suc m) (-suc n) (mkℕ⁺ k) p =
 let
  t₁ = k +ℕ (m *ℕ suc k)
  t₂ = k +ℕ (n *ℕ suc k)

  lhsEq : (-suc t₁) ≡ ((-suc m) *ℤ (+suc k))
  lhsEq = sym (*ℤ-neg-pos-eq m k)

  rhsEq : (-suc t₂) ≡ ((-suc n) *ℤ (+suc k))
  rhsEq = sym (*ℤ-neg-pos-eq n k)

  step : (-suc t₁) ≤ℤ (-suc t₂)
  step =
   ≤ℤ-resp-≡ˡ (sym lhsEq)
    (≤ℤ-resp-≡ʳ (sym rhsEq) p)

  natStep : suc t₂ ≤ suc t₁
  natStep = step

  t₂≤t₁ : t₂ ≤ t₁
  t₂≤t₁ = ≤-+ℕ-cancelˡ (suc zero) t₂ t₁ natStep

  mulPart : (n *ℕ suc k) ≤ (m *ℕ suc k)
  mulPart = ≤-+ℕ-cancelˡ k (n *ℕ suc k) (m *ℕ suc k) t₂≤t₁

  base : n ≤ m
  base = ≤-*ℕ-cancelʳ-suc k mulPart
 in
 s≤s base
```

Step 2: Nonneg and Strict Factor Monotonicity. Nonneg and strict variants follow: nonneg right factor reduces to positive factor plus the zero case, strict factor combines monotonicity with cancellation.

```
-- § Nonneg right factor preserves ≤ℤ.
≤ℤ-mul-nonneg-right : (x y z : ℤ) → x ≤ℤ y → 0ℤ ≤ℤ z → (x *ℤ z) ≤ℤ (y *ℤ z)
≤ℤ-mul-nonneg-right x y 0ℤ x≤y _ =
 subst (λ t → t ≤ℤ (y *ℤ 0ℤ)) (sym (*ℤ-zero-right x))
  (subst (λ t → 0ℤ ≤ℤ t) (sym (*ℤ-zero-right y)) tt)
≤ℤ-mul-nonneg-right x y (+suc k) x≤y _ =
 let
  d : ℕ⁺
  d = mkℕ⁺ k

  step : (x *ℤ ⁺toℤ d) ≤ℤ (y *ℤ ⁺toℤ d)
  step = ≤ℤ-mul-pos-right x y d x≤y

  lhs : (x *ℤ (+suc k)) ≡ (x *ℤ ⁺toℤ d)
  lhs = refl

  rhs : (y *ℤ (+suc k)) ≡ (y *ℤ ⁺toℤ d)
  rhs = refl
 in
 ≤ℤ-resp-≡ˡ (sym lhs) (≤ℤ-resp-≡ʳ (sym rhs) step)
≤ℤ-mul-nonneg-right x y (-suc k) _ ()

-- § Integer squares are always nonneg: 0 ≤ a * a.
squareℤ-nonneg : (a : ℤ) → 0ℤ ≤ℤ a *ℤ a
squareℤ-nonneg 0ℤ =
 subst (0ℤ ≤ℤ_) (sym (*ℤ-zero-left 0ℤ)) tt
squareℤ-nonneg (+suc n) =
 subst (_≤ℤ ((+suc n) *ℤ (+suc n))) (*ℤ-zero-left (+suc n))
  (≤ℤ-mul-nonneg-right 0ℤ (+suc n) (+suc n) tt tt)
squareℤ-nonneg (-suc n) =
 let
  chain : (-suc n) *ℤ (-suc n) ≡ (+suc n) *ℤ (+suc n)
  chain = trans
   (*ℤ-neg-left (+suc n) (-suc n))
   (trans
    (cong negℤ (*ℤ-neg-right (+suc n) (+suc n)))
    (negℤ-involutive ((+suc n) *ℤ (+suc n))))
 in
 subst (0ℤ ≤ℤ_) (sym chain) (squareℤ-nonneg (+suc n))

-- § Strict order preserved by positive right factor.
<ℤ-mul-pos-right : {x y : ℤ} → (d : ℕ⁺) → x <ℤ y → (x *ℤ ⁺toℤ d) <ℤ (y *ℤ ⁺toℤ d)
<ℤ-mul-pos-right {x} {y} d (x≤y , y≰x) =
 let
  lePart : (x *ℤ ⁺toℤ d) ≤ℤ (y *ℤ ⁺toℤ d)
  lePart = ≤ℤ-mul-pos-right x y d x≤y

  notRev : (y *ℤ ⁺toℤ d) ≰ℤ (x *ℤ ⁺toℤ d)
  notRev ydx≤xdx = y≰x (≤ℤ-mul-pos-cancel-right y x d ydx≤xdx)
 in
 lePart , notRev
```

Chapter 26

Absolute Value Laws

The triangle inequality for the rational distance function $\mathrm{dist}_{\mathbb{Q}}$ rests on two pillars: subadditivity of the integer absolute value $|\cdot|_{\mathbb{Z}}$ and its compatibility with multiplication. Each law is forced by exhaustive sign-case analysis on the three constructors of $\mathbb{Z}$—no axiom, no choice, just pattern matching that the compiler verifies. The result is a forced norm: idempotent, nonnegative, subadditive, multiplicative, and injective at zero.

Basic Properties

The absolute value $|z|$ maps each integer to its nonneg representative. Nonnegativity of $|z|$, multiplicativity ($|z \cdot w| = |z| \cdot |w|$), the zero-test ($|z| = 0 \Rightarrow z = 0$), and compatibility with the order are the basic tools that all later distance and magnitude arguments will invoke.

```
– § abs of zero.
absℤ-zero : absℤ 0ℤ ≡ 0ℤ
absℤ-zero = refl

– § abs absorbs negation.
absℤ-neg : (z : ℤ) → absℤ (negℤ z) ≡ absℤ z
absℤ-neg 0ℤ = refl
absℤ-neg (+suc n) = refl
absℤ-neg (-suc n) = refl

– § abs is idempotent.
absℤ-idem : (z : ℤ) → absℤ (absℤ z) ≡ absℤ z
absℤ-idem 0ℤ = refl
absℤ-idem (+suc n) = refl
absℤ-idem (-suc n) = refl

– § abs is nonneg.
absℤ-nonneg : (z : ℤ) → 0ℤ ≤ℤ absℤ z
absℤ-nonneg 0ℤ = tt
absℤ-nonneg (+suc n) = tt
absℤ-nonneg (-suc n) = tt

– § Every integer is bounded by its absolute value.
≤ℤ-absℤ : (z : ℤ) → z ≤ℤ absℤ z
≤ℤ-absℤ 0ℤ = tt
≤ℤ-absℤ (+suc n) = ≤-refl (suc n)
≤ℤ-absℤ (-suc n) = tt
```

```
-- § abs zero implies zero.
absℤ-zero→zero : (z : ℤ) → absℤ z ≡ 0ℤ → z ≡ 0ℤ
absℤ-zero→zero 0ℤ _ = refl
absℤ-zero→zero (+suc n) ()
absℤ-zero→zero (-suc n) ()
```

Magnitude and Subadditivity

The natural magnitude $\mathrm{mag}_{\mathbb{Z}}$ returns the underlying natural number regardless of sign. The embedding $\mathrm{from}_{\mathbb{N}\mathbb{Z}}$ sends it back to $\mathbb{Z}$. Magnitude is bounded by the input sum in the pair representation, and from this bound the subadditivity of $|\cdot|$ under $+_{\mathbb{Z}}$ follows.

```
-- § Natural magnitude.
magℤ : ℤ → ℕ
magℤ 0ℤ = zero
magℤ (+suc n) = suc n
magℤ (-suc n) = suc n

-- § Embedding ℕ into ℤ.
fromℕℤ : ℕ → ℤ
fromℕℤ zero = 0ℤ
fromℕℤ (suc n) = +suc n

-- § abs equals fromℕℤ of magnitude.
absℤ-fromℕℤ-magℤ : (z : ℤ) → absℤ z ≡ fromℕℤ (magℤ z)
absℤ-fromℕℤ-magℤ 0ℤ = refl
absℤ-fromℕℤ-magℤ (+suc n) = refl
absℤ-fromℕℤ-magℤ (-suc n) = refl

-- § Transport ≤ along right equality.
≤-resp-≡ʳ : {a b c : ℕ} → a ≤ b → b ≡ c → a ≤ c
≤-resp-≡ʳ {a} p eq = subst (λ t → a ≤ t) eq p

-- § Successor weakening.
≤-weaken-sucʳ : {a b : ℕ} → a ≤ b → a ≤ suc b
≤-weaken-sucʳ {a} {b} p = ≤-trans p (≤-step b)

-- § Double successor weakening.
≤-weaken-suc²ʳ : {a b : ℕ} → a ≤ b → a ≤ suc (suc b)
≤-weaken-suc²ʳ p = ≤-weaken-sucʳ (≤-weaken-sucʳ p)
```

Step 2: Subadditivity Core. The magnitude of $\mathrm{normalize}\mathbb{Z}$ is bounded by the input sum. From this, subadditivity of $\mathrm{mag}\mathbb{Z}$ and $\mathrm{abs}\mathbb{Z}$ under $+_{\mathbb{Z}}$ follows by bridging through the pair representation.

```
-- § mag of normalizeℤ is bounded by input sum.
magNormalize≤sum : (a b : ℕ) → magℤ (normalizeℤ a b) ≤ (a +ℕ b)
magNormalize≤sum zero zero = ≤-refl zero
magNormalize≤sum (suc a) zero =
 ≤-resp-≡ʳ
  (≤-refl (suc a))
  (sym (+ℕ-zero-right (suc a)))
magNormalize≤sum zero (suc b) = ≤-refl (suc b)
magNormalize≤sum (suc a) (suc b) =
```

```
 ≤-resp-≡ʳ
  (≤-weaken-suc²ʳ (magNormalize≤sum a b))
  rhs
 where
  rhs : suc (suc (a +ℕ b)) ≡ (suc a +ℕ suc b)
  rhs = sym (cong suc (+ℕ-suc-right a b))

-- § Magnitude is subadditive for +ℤ.
magℤ-+ℤ-subadd : (x y : ℤ) → magℤ (x +ℤ y) ≤ (magℤ x +ℕ magℤ y)
magℤ-+ℤ-subadd x y =
 ≤-resp-≡ʳ
  (magNormalize≤sum (pos px +ℕ pos py) (neg px +ℕ neg py))
  sumReassoc
 where
  px : Pairℕ
  px = toPairℤ x

  py : Pairℕ
  py = toPairℤ y

  cong₂ : {A B C : Set} → (f : A → B → C) → {a a' : A} → {b b' : B} → a ≡ a' → b ≡ b' → f a b ≡ f a' b'
  cong₂ f refl refl = refl

  pairSumMag : (z : ℤ) → (pos (toPairℤ z) +ℕ neg (toPairℤ z)) ≡ magℤ z
  pairSumMag 0ℤ = refl
  pairSumMag (+suc n) = +ℕ-zero-right (suc n)
  pairSumMag (-suc n) = refl

  pairSumMagPx : (pos px +ℕ neg px) ≡ magℤ x
  pairSumMagPx = pairSumMag x

  pairSumMagPy : (pos py +ℕ neg py) ≡ magℤ y
  pairSumMagPy = pairSumMag y

  sumReassoc :
   ((pos px +ℕ pos py) +ℕ (neg px +ℕ neg py))
    ≡
   (magℤ x +ℕ magℤ y)
  sumReassoc =
   trans
    (shuffleℕ (pos px) (pos py) (neg px) (neg py))
    (cong₂ _+ℕ_ pairSumMagPx pairSumMagPy)

-- § Transport ℕ-≤ into ≤ℤ for nonneg integers.
fromℕℤ-mono : {m n : ℕ} → m ≤ n → fromℕℤ m ≤ℤ fromℕℤ n
fromℕℤ-mono {zero} {zero} _ = tt
fromℕℤ-mono {zero} {suc n} _ = tt
fromℕℤ-mono {suc m} {zero} ()
fromℕℤ-mono {suc m} {suc n} p = p

-- § fromℕℤ is additive.
fromℕℤ-+ℤ : (m n : ℕ) → fromℕℤ m +ℤ fromℕℤ n ≡ fromℕℤ (m +ℕ n)
fromℕℤ-+ℤ zero zero = refl
fromℕℤ-+ℤ zero (suc n) = refl
fromℕℤ-+ℤ (suc m) zero = refl
fromℕℤ-+ℤ (suc m) (suc n) = refl

-- § abs is subadditive on ℤ (triangle core).
absℤ-subadd : (x y : ℤ) → absℤ (x +ℤ y) ≤ℤ (absℤ x +ℤ absℤ y)
absℤ-subadd x y =
 ≤ℤ-resp-≡ˡ (sym lhsEq) (≤ℤ-resp-≡ʳ (sym rhsEq) step₁)
 where
```

```
step₁ : fromℕℤ (magℤ (x +ℤ y)) ≤ℤ fromℕℤ (magℤ x +ℕ magℤ y)
step₁ = fromℕℤ-mono (magℤ-+ℤ-subadd x y)

lhsEq : absℤ (x +ℤ y) ≡ fromℕℤ (magℤ (x +ℤ y))
lhsEq = absℤ-fromℕℤ-magℤ (x +ℤ y)

rhsEq : absℤ x +ℤ absℤ y ≡ fromℕℤ (magℤ x +ℕ magℤ y)
rhsEq =
 trans
  (cong (λ t → t +ℤ absℤ y) (absℤ-fromℕℤ-magℤ x))
  (trans
   (cong (λ t → fromℕℤ (magℤ x) +ℤ t) (absℤ-fromℕℤ-magℤ y))
   (fromℕℤ-+ℤ (magℤ x) (magℤ y)))
```

Multiplicative Compatibility

Absolute value must commute with multiplication by a positive right factor: $|z \cdot d| = |z| \cdot d$ for $d > 0$. The proof splits by the sign of z and applies the canonical product forms established in the preceding chapter. Full multiplicativity $|x \cdot y| = |x| \cdot |y|$ then follows by exhaustive sign-case analysis.

```
-- § abs commutes with multiplication by positive ℕ⁺.
absℤ-mul-pos-right : (z : ℤ) → (d : ℕ⁺) → absℤ (z *ℤ ⁺toℤ d) ≡ (absℤ z *ℤ ⁺toℤ d)
absℤ-mul-pos-right 0ℤ d =
 trans
  (cong absℤ (*ℤ-zero-left (⁺toℤ d)))
  (sym (*ℤ-zero-left (⁺toℤ d)))
absℤ-mul-pos-right (+suc n) (mkℕ⁺ k) =
 let mulPosForm : (+suc n) *ℤ (+suc k) ≡ +suc (k +ℕ (n *ℕ suc k))
     mulPosForm = *ℤ-pos-pos-eq n k
 in
 trans
  (trans (cong absℤ mulPosForm) refl)
  (sym mulPosForm)

absℤ-mul-pos-right (-suc n) (mkℕ⁺ k) =
 let mulNegForm : (-suc n) *ℤ (+suc k) ≡ -suc (k +ℕ (n *ℕ suc k))
     mulNegForm = *ℤ-neg-pos-eq n k
     mulPosForm : (+suc n) *ℤ (+suc k) ≡ +suc (k +ℕ (n *ℕ suc k))
     mulPosForm = *ℤ-pos-pos-eq n k
 in
 trans
  (trans (cong absℤ mulNegForm) refl)
  (sym mulPosForm)
```

Step 2: Full Multiplicativity. The full multiplicativity proof $|x \cdot y| = |x| \cdot |y|$ follows by exhaustive sign-case analysis. Each case reduces to the positive product lemma *ℤ-pos-pos-eq combined with negation absorption.

```
-- § abs is fully multiplicative.
absℤ-mul : (x y : ℤ) → absℤ (x *ℤ y) ≡ (absℤ x *ℤ absℤ y)
absℤ-mul 0ℤ y =
 let
  lhs : absℤ (0ℤ *ℤ y) ≡ absℤ 0ℤ
```

```
  lhs = cong absℤ (*ℤ-zero-left y)

  rhs : (absℤ 0ℤ *ℤ absℤ y) ≡ absℤ 0ℤ
  rhs = *ℤ-zero-left (absℤ y)
 in
 trans lhs (sym rhs)
absℤ-mul x 0ℤ =
 let
  lhs : absℤ (x *ℤ 0ℤ) ≡ absℤ 0ℤ
  lhs = cong absℤ (*ℤ-zero-right x)

  rhs : (absℤ x *ℤ absℤ 0ℤ) ≡ absℤ 0ℤ
  rhs =
   trans
    (cong (λ t → absℤ x *ℤ t) absℤ-zero)
    (*ℤ-zero-right (absℤ x))
 in
 trans lhs (sym rhs)
absℤ-mul (+suc m) (+suc n) =
 let
  prodEq : (+suc m) *ℤ (+suc n) ≡ +suc (n +ℕ (m *ℕ suc n))
  prodEq = *ℤ-pos-pos-eq m n
 in
 trans (cong absℤ prodEq) (sym prodEq)
absℤ-mul (+suc m) (-suc n) =
 let
  prodEq : (+suc m) *ℤ (+suc n) ≡ +suc (n +ℕ (m *ℕ suc n))
  prodEq = *ℤ-pos-pos-eq m n

  absProd : absℤ ((+suc m) *ℤ (+suc n)) ≡ (+suc m) *ℤ (+suc n)
  absProd = trans (cong absℤ prodEq) (sym prodEq)
 in
 trans
  (cong absℤ (*ℤ-neg-right (+suc m) (+suc n)))
  (trans (absℤ-neg ((+suc m) *ℤ (+suc n))) absProd)
absℤ-mul (-suc m) (+suc n) =
 let
  prodEq : (+suc m) *ℤ (+suc n) ≡ +suc (n +ℕ (m *ℕ suc n))
  prodEq = *ℤ-pos-pos-eq m n

  absProd : absℤ ((+suc m) *ℤ (+suc n)) ≡ (+suc m) *ℤ (+suc n)
  absProd = trans (cong absℤ prodEq) (sym prodEq)
 in
 trans
  (cong absℤ (*ℤ-neg-left (+suc m) (+suc n)))
  (trans (absℤ-neg ((+suc m) *ℤ (+suc n))) absProd)
absℤ-mul (-suc m) (-suc n) =
 let
  mulEq : (-suc m) *ℤ (-suc n) ≡ (+suc m) *ℤ (+suc n)
  mulEq =
   trans
    (*ℤ-neg-right (negℤ (+suc m)) (+suc n))
    (trans
     (cong negℤ (*ℤ-neg-left (+suc m) (+suc n)))
     (negℤ-involutive ((+suc m) *ℤ (+suc n))))

  prodEq : (+suc m) *ℤ (+suc n) ≡ +suc (n +ℕ (m *ℕ suc n))
  prodEq = *ℤ-pos-pos-eq m n

  absProd : absℤ ((+suc m) *ℤ (+suc n)) ≡ (+suc m) *ℤ (+suc n)
  absProd = trans (cong absℤ prodEq) (sym prodEq)
 in
```

```
trans (cong absℤ mulEq) absProd

-- § If -b ≤ a ≤ b then |a| ≤ b.
absℤ-within-bound : (a b : ℤ) → (negℤ b) ≤ℤ a → a ≤ℤ b → absℤ a ≤ℤ b
absℤ-within-bound 0ℤ 0ℤ _ _ = tt
absℤ-within-bound 0ℤ (+suc n) _ _ = tt
absℤ-within-bound 0ℤ (-suc n) _ neg-bound = neg-bound
absℤ-within-bound (+suc a) b _ upper = upper
absℤ-within-bound (-suc a) b lower _ =
 ≤ℤ-resp-≡ʳ (negℤ-involutive b) (negℤ-antitone-≤ℤ lower)
```

Chapter 27

Additive Monotonicity and Positive Natural Laws

The rational order infrastructure demands two ingredients that have not yet been established: general additive monotonicity for $\leq_{\mathbb{Z}}$, and the fact that the embedding of $\mathbb{N}^+$ into $\mathbb{Z}$ respects multiplication. Additive monotonicity is reduced, via the normalize/cross bridge, from $\mathbb{Z}$-order statements to $\mathbb{N}$-level cross-sum inequalities where the inductive structure does the work. The $\mathbb{N}^+$ laws then follow directly from their $\mathbb{N}$ counterparts. Together these close the last gaps: $+_{\mathbb{Z}}$ is monotone in both arguments, cancellative on the right, and the $\mathbb{N}^+$ multiplication homomorphism into $(\mathbb{Z}, *_{\mathbb{Z}})$ is exact.

Nonneg Monotonicity Bridge

The nonneg fragment of $\mathbb{Z}$ inherits the monotonicity of $\mathbb{N}$ addition through $\text{from}_{\mathbb{N}\mathbb{Z}}$. Left and right monotonicity, nonneg $+_{\mathbb{Z}}$ monotonicity, reflection of $\leq_{\mathbb{Z}}$ back to $\mathbb{N}$, and the nonnegativity elimination lemma are assembled here as the bridge between $\mathbb{N}$ arithmetic and $\mathbb{Z}$ order.

```
– § Nonneg left monotonicity via fromℕℤ.
≤ℤ-fromℕℤ-+ℕ-mono^l : {a b : ℕ} → a ≤ b → (c : ℕ) → fromℕℤ (c +ℕ a) ≤ℤ fromℕℤ (c +ℕ b)
≤ℤ-fromℕℤ-+ℕ-mono^l p c = fromℕℤ-mono (≤-+ℕ-mono^l p c)

– § Nonneg right monotonicity via fromℕℤ.
≤ℤ-fromℕℤ-+ℕ-mono^r : {a b : ℕ} → a ≤ b → (c : ℕ) → fromℕℤ (a +ℕ c) ≤ℤ fromℕℤ (b +ℕ c)
≤ℤ-fromℕℤ-+ℕ-mono^r {a} {b} p c =
 let
  lhs : fromℕℤ (a +ℕ c) ≡ fromℕℤ (c +ℕ a)
  lhs = cong fromℕℤ (+ℕ-comm a c)

  rhs : fromℕℤ (b +ℕ c) ≡ fromℕℤ (c +ℕ b)
  rhs = cong fromℕℤ (+ℕ-comm b c)

  base : fromℕℤ (c +ℕ a) ≤ℤ fromℕℤ (c +ℕ b)
  base = ≤ℤ-fromℕℤ-+ℕ-mono^l p c
 in
 ≤ℤ-resp-≡^l (sym lhs) (≤ℤ-resp-≡^r (sym rhs) base)

– § Nonneg +ℤ right monotonicity.
```

```
≤ℤ-+ℤ-mono^r-nonneg : {m n : ℕ} → m ≤ n → (k : ℕ) → (fromℕℤ m +ℤ fromℕℤ k) ≤ℤ (fromℕℤ n +ℤ fromℕℤ k)
≤ℤ-+ℤ-mono^r-nonneg {m} {n} p k =
 ≤ℤ-resp-≡^l (sym (fromℕℤ-+ℤ m k))
  (≤ℤ-resp-≡^r (sym (fromℕℤ-+ℤ n k))
   (≤ℤ-fromℕℤ-+ℕ-mono^r p k))

-- § Reflect ≤ℤ back to ℕ-≤ for nonneg integers.
≤ℤ-fromℕℤ-reflect : {m n : ℕ} → fromℕℤ m ≤ℤ fromℕℤ n → m ≤ n
≤ℤ-fromℕℤ-reflect {zero} {zero} _ = z≤n
≤ℤ-fromℕℤ-reflect {zero} {suc n} _ = z≤n
≤ℤ-fromℕℤ-reflect {suc m} {zero} ()
≤ℤ-fromℕℤ-reflect {suc m} {suc n} p = p

-- § Nonnegativity forces fromℕℤ form.
0≤ℤ→fromℕℤ : (z : ℤ) → 0ℤ ≤ℤ z → Σ ℕ (λ n → z ≡ fromℕℤ n)
0≤ℤ→fromℕℤ 0ℤ _ = zero , refl
0≤ℤ→fromℕℤ (+suc n) _ = suc n , refl
0≤ℤ→fromℕℤ (-suc n) ()

-- § Both-slot nonneg monotonicity.
≤ℤ-+ℤ-mono-nonneg₂ : {m m' n n' : ℕ} → m ≤ m' → n ≤ n' →
 (fromℕℤ m +ℤ fromℕℤ n) ≤ℤ (fromℕℤ m' +ℤ fromℕℤ n')
≤ℤ-+ℤ-mono-nonneg₂ {m} {m'} {n} {n'} m≤m' n≤n' =
 let
  step₁ : (fromℕℤ m +ℤ fromℕℤ n) ≤ℤ (fromℕℤ m' +ℤ fromℕℤ n)
  step₁ = ≤ℤ-+ℤ-mono^r-nonneg m≤m' n

  step₂ : (fromℕℤ m' +ℤ fromℕℤ n) ≤ℤ (fromℕℤ m' +ℤ fromℕℤ n')
  step₂ =
   ≤ℤ-resp-≡^l (+ℤ-comm (fromℕℤ n) (fromℕℤ m'))
    (≤ℤ-resp-≡^r (+ℤ-comm (fromℕℤ n') (fromℕℤ m'))
     (≤ℤ-+ℤ-mono^r-nonneg n≤n' m'))
 in
 ≤ℤ-trans step₁ step₂
```

Normalize–Cross Bridge

The order on ℤ (defined via normalizeℤ) reduces to a cross-sum inequality on ℕ: normalizeℤ a b $\leq_{\mathbb{Z}}$ normalizeℤ c d if and only if $a + d \leq c + b$.

```
-- § Forward: normalize order implies cross-sum inequality.
normalize≤→cross : (a b c d : ℕ) → normalizeℤ a b ≤ℤ normalizeℤ c d → (a +ℕ d) ≤ (c +ℕ b)
normalize≤→cross (suc a) (suc b) c d p =
 let ih : (a +ℕ d) ≤ (c +ℕ b)
     ih = normalize≤→cross a b c d p

     lifted : (suc (a +ℕ d)) ≤ (suc (c +ℕ b))
     lifted = s≤s ih

     rhsEq : (c +ℕ suc b) ≡ suc (c +ℕ b)
     rhsEq = +ℕ-suc-right c b
 in
 subst (λ t → (suc a +ℕ d) ≤ t) (sym rhsEq) lifted
normalize≤→cross a b (suc c) (suc d) p =
 let ih : (a +ℕ d) ≤ (c +ℕ b)
     ih = normalize≤→cross a b c d p

     lifted : (suc (a +ℕ d)) ≤ (suc (c +ℕ b))
```

```
    lifted = s≤s ih

    lhsEq : (a +ℕ suc d) ≡ suc (a +ℕ d)
    lhsEq = +ℕ-suc-right a d
  in
  subst (λ t → t ≤ (suc c +ℕ b)) (sym lhsEq) lifted

normalize≤→cross zero zero zero zero _ = z≤n
normalize≤→cross zero zero (suc c) zero _ = z≤n
normalize≤→cross zero zero zero (suc d) ()
normalize≤→cross (suc a) zero zero zero ()
normalize≤→cross (suc a) zero (suc c) zero p =
  let
   lhsEq : (suc a +ℕ zero) ≡ suc a
   lhsEq = cong suc (+ℕ-zero-right a)

   rhsEq : (suc c +ℕ zero) ≡ suc c
   rhsEq = cong suc (+ℕ-zero-right c)
  in
  subst (λ t → t ≤ (suc c +ℕ zero)) (sym lhsEq)
   (subst (λ t → (suc a) ≤ t) (sym rhsEq) p)
normalize≤→cross (suc a) zero zero (suc d) ()
normalize≤→cross zero (suc b) zero zero _ = z≤n
normalize≤→cross zero (suc b) (suc c) zero _ = z≤n
normalize≤→cross zero (suc b) zero (suc d) p = p

-- § Backward: cross-sum inequality implies normalize order.
cross→normalize≤ : (a b c d : ℕ) → (a +ℕ d) ≤ (c +ℕ b) → normalizeℤ a b ≤ℤ normalizeℤ c d
cross→normalize≤ (suc a) (suc b) c d p with subst (λ t → (suc a +ℕ d) ≤ t) (+ℕ-suc-right c b) p
... | s≤s q = cross→normalize≤ a b c d q
cross→normalize≤ a b (suc c) (suc d) p with subst (λ t → t ≤ (suc c +ℕ b)) (+ℕ-suc-right a d) p
... | s≤s q = cross→normalize≤ a b c d q

cross→normalize≤ zero zero zero zero _ = tt
cross→normalize≤ zero zero (suc c) zero _ = tt
cross→normalize≤ zero zero zero (suc d) ()
cross→normalize≤ (suc a) zero zero zero ()
cross→normalize≤ (suc a) zero (suc c) zero p =
  let
   lhsEq : (suc a +ℕ zero) ≡ suc a
   lhsEq = cong suc (+ℕ-zero-right a)

   rhsEq : (suc c +ℕ zero) ≡ suc c
   rhsEq = cong suc (+ℕ-zero-right c)

   p' : (suc a) ≤ (suc c)
   p' =
     subst (λ t → t ≤ (suc c)) lhsEq
      (subst (λ t → (suc a +ℕ zero) ≤ t) rhsEq p)
  in
  p'
cross→normalize≤ (suc a) zero zero (suc d) ()
cross→normalize≤ zero (suc b) zero zero _ = tt
cross→normalize≤ zero (suc b) (suc c) zero _ = tt
cross→normalize≤ zero (suc b) zero (suc d) p = p
```

General Additive Monotonicity

Right, left, and both-slot monotonicity of $+_{\mathbb{Z}}$, together with right additive cancellation, extend the nonneg bridge to all of $\mathbb{Z}$. The proofs normalize both sides through the cross-sum bridge and apply $\mathbb{N}$-level monotonicity.

```
-- § Right monotonicity of +ℤ (general).
≤ℤ-+ℤ-mono^r : {x y : ℤ} → x ≤ℤ y → (z : ℤ) → (x +ℤ z) ≤ℤ (y +ℤ z)
≤ℤ-+ℤ-mono^r {x} {y} x≤y z =
 let
  px = toPairℤ x
  py = toPairℤ y
  pz = toPairℤ z

  ax = pos px
  bx = neg px
  ay = pos py
  by = neg py
  az = pos pz
  bz = neg pz

  x≤y' : normalizeℤ ax bx ≤ℤ normalizeℤ ay by
  x≤y' =
   ≤ℤ-resp-≡^r (sym (from-toPairℤ y))
    (≤ℤ-resp-≡^l (sym (from-toPairℤ x)) x≤y)

  crossXY : (ax +ℕ by) ≤ (ay +ℕ bx)
  crossXY = normalize≤→cross ax bx ay by x≤y'

  k : ℕ
  k = az +ℕ bz

  base : (k +ℕ (ax +ℕ by)) ≤ (k +ℕ (ay +ℕ bx))
  base = ≤-+ℕ-mono^l crossXY k

  lhsEq : ((ax +ℕ az) +ℕ (by +ℕ bz)) ≡ (k +ℕ (ax +ℕ by))
  lhsEq =
   trans
    (shuffleℕ ax az by bz)
    (+ℕ-comm (ax +ℕ by) k)

  rhsEq : ((ay +ℕ az) +ℕ (bx +ℕ bz)) ≡ (k +ℕ (ay +ℕ bx))
  rhsEq =
   trans
    (shuffleℕ ay az bx bz)
    (+ℕ-comm (ay +ℕ bx) k)

  sumCross : ((ax +ℕ az) +ℕ (by +ℕ bz)) ≤ ((ay +ℕ az) +ℕ (bx +ℕ bz))
  sumCross =
   subst (λ t → t ≤ ((ay +ℕ az) +ℕ (bx +ℕ bz))) (sym lhsEq)
    (subst (λ t → (k +ℕ (ax +ℕ by)) ≤ t) (sym rhsEq) base)
 in
 cross→normalize≤ (ax +ℕ az) (bx +ℕ bz) (ay +ℕ az) (by +ℕ bz) sumCross

-- § Left monotonicity of +ℤ.
≤ℤ-+ℤ-mono^l : {x y : ℤ} → x ≤ℤ y → (z : ℤ) → (z +ℤ x) ≤ℤ (z +ℤ y)
≤ℤ-+ℤ-mono^l {x} {y} x≤y z =
 ≤ℤ-resp-≡^l (+ℤ-comm x z)
  (≤ℤ-resp-≡^r (+ℤ-comm y z)
   (≤ℤ-+ℤ-mono^r x≤y z))

-- § Both-slot monotonicity of +ℤ.
≤ℤ-+ℤ-mono : {x y u v : ℤ} → x ≤ℤ y → u ≤ℤ v → (x +ℤ u) ≤ℤ (y +ℤ v)
≤ℤ-+ℤ-mono {x} {y} {u} {v} x≤y u≤v =
 ≤ℤ-trans (≤ℤ-+ℤ-mono^r x≤y u) (≤ℤ-+ℤ-mono^l u≤v y)

-- § Right additive cancellation for ≤ℤ.
≤ℤ-+ℤ-cancel^r : (x y z : ℤ) → x ≤ℤ (z +ℤ y) → (x +ℤ negℤ y) ≤ℤ z
```

```
≤ℤ-+ℤ-cancelʳ x y z p =
 let
  step : (x +ℤ negℤ y) ≤ℤ ((z +ℤ y) +ℤ negℤ y)
  step = ≤ℤ-+ℤ-monoʳ p (negℤ y)

  rhsEq : ((z +ℤ y) +ℤ negℤ y) ≡ z
  rhsEq =
   trans
    (+ℤ-assoc z y (negℤ y))
    (trans
     (cong (λ t → z +ℤ t) (+ℤ-inv-right y))
     (+ℤ-zero-right z))
 in
 ≤ℤ-resp-≡ʳ rhsEq step
```

Step 2: $\mathbb{N}^+$ Multiplication Homomorphism. fromℕℤ is a multiplicative homomorphism for $\mathbb{N}^+$, and positive integers satisfy $1 < 2z$—the key lemma for half-line arguments in the rational order.

```
– § fromℕℤ is multiplicative for ℕ⁺.
fromℕℤ-mul-⁺ : (n : ℕ) → (d : ℕ⁺) → (fromℕℤ n *ℤ ⁺toℤ d) ≡ fromℕℤ (n *ℕ ⁺toℕ d)
fromℕℤ-mul-⁺ zero d =
 trans
  (*ℤ-zero-left (⁺toℤ d))
  (cong fromℕℤ (sym (*ℕ-zero-left (⁺toℕ d))))
fromℕℤ-mul-⁺ (suc n) (mkℕ⁺ k) =
 let
  natForm : (suc n *ℕ suc k) ≡ suc (k +ℕ (n *ℕ suc k))
  natForm = refl

  rhs : fromℕℤ (suc n *ℕ suc k) ≡ +suc (k +ℕ (n *ℕ suc k))
  rhs = cong fromℕℤ natForm
 in
 trans
  (*ℤ-pos-pos-eq n k)
  (sym rhs)

– § 1 < 2z for z positive.
oneℤ<twoTimes-pos : (z : ℤ) → 0ℤ <ℤ z → oneℤ <ℤ (z +ℤ z)
oneℤ<twoTimes-pos z zpos with 0<ℤ→pos z zpos
... | (m , z≡) =
 <ℤ-resp-≡ʳ (cong (λ t → t +ℤ t) (sym z≡)) (lePart , notRev)
 where
  twoTimes : (+suc m) +ℤ (+suc m) ≡ +suc (m +ℕ suc m)
  twoTimes =
   trans
    (fromℕℤ-+ℤ (suc m) (suc m))
    (cong fromℕℤ refl)

  lePart : oneℤ ≤ℤ ((+suc m) +ℤ (+suc m))
  lePart =
   let
    lePos : oneℤ ≤ℤ (+suc (m +ℕ suc m))
    lePos = s≤s z≤n
   in
    subst (λ t → oneℤ ≤ℤ t) (sym twoTimes) lePos

  no-suc≤zero : {t : ℕ} → suc t ≤ zero → ⊥
  no-suc≤zero ()
```

```
impossible : (+suc (m +ℕ suc m)) ≤ℤ oneℤ → ⊥
impossible (s≤s pNat) =
 let
  pNat' : suc (m +ℕ m) ≤ zero
  pNat' = subst (λ t → t ≤ zero) (+ℕ-suc-right m m) pNat
 in
 no-suc≤zero pNat'

notRev : ((+suc m) +ℤ (+suc m)) ≰ℤ oneℤ
notRev q = impossible (subst (λ t → t ≤ℤ oneℤ) twoTimes q)
```

Laws of $\mathbb{N}^+$

Commutativity of $\mathbb{N}^+$ multiplication and its homomorphism into $\mathbb{Z}$ are forced by the underlying $\mathbb{N}$ laws. These two lemmas close the positive-denominator arithmetic needed for rational cross-multiplication.

```
– § Commutativity of ℕ⁺ multiplication.
*⁺-comm : (x y : ℕ⁺) → x *⁺ y ≡ y *⁺ x
*⁺-comm (mkℕ⁺ a) (mkℕ⁺ b) =
 cong mkℕ⁺ (trans lhsNorm (sym rhsNorm))
 where
  lhsNorm : (a *ℕ suc b) +ℕ b ≡ (a +ℕ b) +ℕ (a *ℕ b)
  lhsNorm =
   trans
    (cong (λ t → t +ℕ b) (*ℕ-suc-right-+ℕ a b))
    (trans
     (+ℕ-assoc a (a *ℕ b) b)
     (trans
      (cong (λ t → a +ℕ t) (+ℕ-comm (a *ℕ b) b))
      (sym (+ℕ-assoc a b (a *ℕ b)))))

  rhsNorm : (b *ℕ suc a) +ℕ a ≡ (a +ℕ b) +ℕ (a *ℕ b)
  rhsNorm =
   trans
    (cong (λ t → t +ℕ a) (*ℕ-suc-right-+ℕ b a))
    (trans
     (cong (λ t → (b +ℕ t) +ℕ a) (*ℕ-comm b a))
     (trans
      (+ℕ-assoc b (a *ℕ b) a)
      (trans
       (cong (λ t → b +ℕ t) (+ℕ-comm (a *ℕ b) a))
       (trans
        (swapHeadℕ b a (a *ℕ b))
        (sym (+ℕ-assoc a b (a *ℕ b)))))))

– § ⁺toℤ is a multiplicative homomorphism.
⁺toℤ-*⁺ : (x y : ℕ⁺) → ⁺toℤ (x *⁺ y) ≡ (⁺toℤ x) *ℤ (⁺toℤ y)
⁺toℤ-*⁺ (mkℕ⁺ a) (mkℕ⁺ b) =
 sym
  (trans
   (*ℤ-pos-pos-eq a b)
   (cong (λ t → +suc t) (+ℕ-comm b (a *ℕ suc b))))
```

Integer arithmetic is rigid enough to support genuine spectral calculation. The K_4 neighbourhood structure, the Laplacian, simplex invariants, multiplication laws, and order laws are

all forced into place. The graph is not merely a topological survivor; it is an operator-bearing object.

Spectral ratios force quotient arithmetic: the integer combinatorics extends into the rational domain.

Chapter 28

Rational Numbers and Measurement

Eigenvalue quotients from the K_4 spectral analysis—ratios of integers that are not themselves integers—demand a quotient field. $\mathbb{Q}$ is defined as the forced quotient $\mathbb{Z}/\mathbb{N}^+$: an integer numerator over a positive denominator, with equality given by the cross-multiplication setoid $a{\cdot}d = c{\cdot}b$. Distance is the absolute difference of two rationals, and measurement acts on Distinctions are classified as K_4-maps into the two-element carrier. The simplex evaluation $\mathcal{C} = 137$ emerges as a forced combinatorial invariant of the graph, not a fitted parameter.

Rational Arithmetic

A rational number is an integer numerator over a positive denominator. Equality is the cross-multiplication setoid $a \cdot d = c \cdot b$, addition and multiplication lift through the common-denominator product, and distance is the absolute difference of the cross-products.

```
-- § Rational number: integer numerator over positive denominator.
record ℚ : Set where
 constructor _/_
 field
  num : ℤ
  den : ℕ⁺

open ℚ public

infix 4 _≃ℚ_

-- § Setoid equality: cross-multiplication.
_≃ℚ_ : ℚ → ℚ → Set
(a / b) ≃ℚ (c / d) = (a *ℤ ⁺toℤ d) ≡ (c *ℤ ⁺toℤ b)

infixl 6 _+ℚ_ _-ℚ_
infixl 7 _*ℚ_

-- § Rational addition.
_+ℚ_ : ℚ → ℚ → ℚ
(a / b) +ℚ (c / d) = ((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b)) / (b *⁺ d)

-- § Rational multiplication.
_*ℚ_ : ℚ → ℚ → ℚ
(a / b) *ℚ (c / d) = (a *ℤ c) / (b *⁺ d)
```

```
-- § Rational negation.
-ℚ_ : ℚ → ℚ
-ℚ (a / b) = negℤ a / b

-- § Rational subtraction.
_-ℚ_ : ℚ → ℚ → ℚ
p -ℚ q = p +ℚ (-ℚ q)

-- § Distinguished rationals.
0ℚ 1ℚ : ℚ
0ℚ = 0ℤ / one⁺
1ℚ = oneℤ / one⁺

infix 4 _≤ℚ_ _<ℚ_

-- § Rational order: cross-multiply and compare integers.
_≤ℚ_ : ℚ → ℚ → Set
(a / b) ≤ℚ (c / d) = (a *ℤ ⁺toℤ d) ≤ℤ (c *ℤ ⁺toℤ b)

-- § Strict rational order.
_<ℚ_ : ℚ → ℚ → Set
(a / b) <ℚ (c / d) = (a *ℤ ⁺toℤ d) <ℤ (c *ℤ ⁺toℤ b)

-- § Rational distance.
distℚ : ℚ → ℚ → ℚ
distℚ (a / b) (c / d) = absℤ ((a *ℤ ⁺toℤ d) +ℤ negℤ (c *ℤ ⁺toℤ b)) / (b *⁺ d)
```

Simplex Evaluation: $\mathcal{C} = 137$

The K_4 simplex invariants from the preceding chapter combine via the forced arithmetic to yield the integer 137. The canonicity of this particular combination—the proof that no other degree-$\leq$ 3 expression in the invariant basis reaches 137—is established in the companion volume *Form*. Agda requires the computation first and the classification later, because the classification depends on the full invariant ledger assembled across the intervening chapters.

```
-- § Natural exponentiation.
_^_ : ℕ → ℕ → ℕ
x ^ zero = suc zero
x ^ suc n = x * (x ^ n)

-- § Simplex evaluation from K₄ invariants.
simplex-eval : ℕ
simplex-eval = (simplex-vertices ^ simplex-degree) * simplex-chi + (simplex-degree * simplex-degree)

-- § Law 15A.0: the derived integer is exactly 137.
law15A-0-simplex-eval-137 : simplex-eval ≡ 137
law15A-0-simplex-eval-137 = refl

-- § Redundant witness (same computation, explicit name).
derived-integer : ℕ
derived-integer =
 (simplex-vertices ^ simplex-degree) * simplex-chi
 + (simplex-degree * simplex-degree)

law15A-0-derived-integer-137 : derived-integer ≡ 137
law15A-0-derived-integer-137 = refl
```

Measurement Acts

A measurement on a Distinction d is a K_4-map from d into the two-element distinction. The classification theorem forces every measurement into exactly one of the 16 endomorphism cases.

```
– § Measurement: map from d into Two-distinction.
Measurement : Distinction → Set
Measurement d = S d → S Two-distinction

– § Law 15B.0: measurements are determined by their action on two generators.
law15B-0-measurement-determined :
 (d : Distinction) →
 (m₁ m₂ : Measurement d) →
 m₁ (ℓ d) ≡ m₂ (ℓ d) →
 m₁ (r d) ≡ m₂ (r d) →
 m₁ ≐ m₂
law15B-0-measurement-determined d =
 law7-1-map-determined d Two-distinction

– § Law 15B.1: every measurement is realized by some EndoCase.
law15B-1-measurement-classification-sound :
 (d : Distinction) →
 (m : Measurement d) →
 Σ EndoCase (λ c → K₄Map.interpret d Two-distinction c ≐ m)
law15B-1-measurement-classification-sound d m =
 law7-2-k4map-classification-sound d Two-distinction m

– § Law 15B.2: the classifying EndoCase is unique.
law15B-2-measurement-classification-unique :
 (d : Distinction) →
 (m : Measurement d) →
 (c₁ c₂ : EndoCase) →
 K₄Map.interpret d Two-distinction c₁ ≐ m →
 K₄Map.interpret d Two-distinction c₂ ≐ m →
 c₁ ≡ c₂
law15B-2-measurement-classification-unique d m c₁ c₂ p q =
 law7-3-k4map-classification-unique d Two-distinction m c₁ c₂ p q
```

Triangle Inequality Infrastructure

The numerator of the rational distance $d(p, q)$ is the absolute value of the cross-difference. Non-negativity of this numerator is immediate from $|\cdot|$, and the scaled triangle inequality follows by factoring through the subadditivity of $|\cdot|$ on $\mathbb{Z}$.

```
– § Numerator of distℚ.
numDistℚ : ℚ → ℚ → ℤ
numDistℚ (a / b) (c / d) = absℤ ((a *ℤ ⁺toℤ d) +ℤ negℤ (c *ℤ ⁺toℤ b))

– § Distance numerator is nonneg.
numDistℚ-nonneg : (p q : ℚ) → 0ℤ ≤ℤ numDistℚ p q
numDistℚ-nonneg (a / b) (c / d) = absℤ-nonneg _
```

Step 2: Triangle Inequality Core. The scaled triangle inequality rewrites $d(p, r)$ as a cross-product dominated by $d(p, q) + d(q, r)$ via the absolute value subadditivity lemma.

```
-- § Triangle core: scaled distance numerator inequality.
numDistℚ-triangle-scaled : (p q r : ℚ) →
 (numDistℚ p r *ℤ ⁺toℤ (den q))
  ≤ℤ
 ((numDistℚ p q *ℤ ⁺toℤ (den r)) +ℤ (numDistℚ q r *ℤ ⁺toℤ (den p)))
numDistℚ-triangle-scaled (a / b) (c / d) (e / f) =
 ≤ℤ-resp-≡ˡ lhsAbs
 (≤ℤ-resp-≡ʳ rhsAbs
  absStep)
 where
  Wt : ℤ
  Wt = (a *ℤ ⁺toℤ f) +ℤ negℤ (e *ℤ ⁺toℤ b)

  Ut : ℤ
  Ut = (a *ℤ ⁺toℤ d) +ℤ negℤ (c *ℤ ⁺toℤ b)

  Vt : ℤ
  Vt = (c *ℤ ⁺toℤ f) +ℤ negℤ (e *ℤ ⁺toℤ d)

  swapScale : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
  swapScale x u v =
   trans
    (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
    (trans
     (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
     (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

  Wtd : ℤ
  Wtd = Wt *ℤ ⁺toℤ d

  Utf : ℤ
  Utf = Ut *ℤ ⁺toℤ f

  Vtb : ℤ
  Vtb = Vt *ℤ ⁺toℤ b

  cancelMid : (c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f ≡ (c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b
  cancelMid = swapScale c b f

  cancelEnd : (e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d ≡ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b
  cancelEnd = swapScale e b d

  cancelHead : (a *ℤ ⁺toℤ f) *ℤ ⁺toℤ d ≡ (a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f
  cancelHead = swapScale a f d

  -- § Algebra: Wt·d = Ut·f + Vt·b.
  Wtd≡sum : Wtd ≡ (Utf +ℤ Vtb)
  Wtd≡sum =
   trans WtdForm (sym sumForm)
   where
    WtdForm : Wtd ≡ ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) +ℤ negℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b)
    WtdForm =
     trans
      (*ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ f) (negℤ (e *ℤ ⁺toℤ b)) (⁺toℤ d))
      (trans
       (cong (λ t → ((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ d) +ℤ t)
             (*ℤ-neg-left (e *ℤ ⁺toℤ b) (⁺toℤ d)))
       (trans
```

```
    (cong (λ t → t +ℤ negℤ ((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d)) cancelHead)
    (cong (λ t → ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) +ℤ t)
          (cong negℤ cancelEnd))))

  UtfForm : Utf ≡ ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) +ℤ negℤ ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f)
  UtfForm =
   trans
    (*ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ d) (negℤ (c *ℤ ⁺toℤ b)) (⁺toℤ f))
    (cong (λ t → ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) +ℤ t)
          (*ℤ-neg-left (c *ℤ ⁺toℤ b) (⁺toℤ f)))

  VtbForm : Vtb ≡ ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b) +ℤ negℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b)
  VtbForm =
   trans
    (*ℤ-distrib-left-+ℤ (c *ℤ ⁺toℤ f) (negℤ (e *ℤ ⁺toℤ d)) (⁺toℤ b))
    (cong (λ t → ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b) +ℤ t)
          (*ℤ-neg-left (e *ℤ ⁺toℤ d) (⁺toℤ b)))

  sumForm :
   (Utf +ℤ Vtb) ≡ ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) +ℤ negℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b)
  sumForm =
   let
    Adf = (a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f
    CbF = (c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f
    CfB = (c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b
    EdB = (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b

    UtfRhs = Adf +ℤ negℤ CbF
    VtbRhs = CfB +ℤ negℤ EdB

    midRewrite : (negℤ CbF +ℤ CfB) ≡ (negℤ CfB +ℤ CfB)
    midRewrite =
     cong (λ t → negℤ t +ℤ CfB) cancelMid

    cancelMiddle : (negℤ CbF +ℤ CfB) ≡ 0ℤ
    cancelMiddle =
     trans midRewrite (+ℤ-inv-left CfB)

    sumCancel : (UtfRhs +ℤ VtbRhs) ≡ (Adf +ℤ negℤ EdB)
    sumCancel =
     trans
      (+ℤ-assoc Adf (negℤ CbF) VtbRhs)
      (trans
          (cong (λ t → Adf +ℤ t)
                (sym (+ℤ-assoc (negℤ CbF) CfB (negℤ EdB))))
          (trans
           (cong (λ t → Adf +ℤ (t +ℤ negℤ EdB)) cancelMiddle)
           (cong (λ t → Adf +ℤ t) (+ℤ-zero-left (negℤ EdB)))))
   in
   trans
    (cong (λ t → t +ℤ Vtb) UtfForm)
    (trans
     (cong (λ t → UtfRhs +ℤ t) VtbForm)
     sumCancel)

absStep : absℤ Wtd ≤ℤ (absℤ Utf +ℤ absℤ Vtb)
absStep =
 ≤ℤ-resp-≡ˡ (sym (cong absℤ Wtd≡sum)) (absℤ-subadd Utf Vtb)

lhsAbs : absℤ Wtd ≡ (absℤ Wt *ℤ ⁺toℤ d)
lhsAbs =
 trans
```

```
  (absℤ-mul-pos-right Wt d)
  refl

rhsAbs : (absℤ Utf +ℤ absℤ Vtb) ≡ ((absℤ Ut *ℤ ⁺toℤ f) +ℤ (absℤ Vt *ℤ ⁺toℤ b))
rhsAbs =
 trans
  (cong (λ t → t +ℤ absℤ Vtb) (absℤ-mul-pos-right Ut f))
  (cong (λ t → (absℤ Ut *ℤ ⁺toℤ f) +ℤ t) (absℤ-mul-pos-right Vt b))
```

Chapter 29

Rational Setoid and Order Laws

Spectral operator eigenvalues must be expressible as rational numbers and compared as such. This forces $\simeq_{\mathbb{Q}}$ to carry the full structure of an equivalence relation—reflexivity and symmetry are immediate from cross-multiplication, while transitivity requires cancellation of the intermediate denominator via torsion-freedom. The preorder $\leq_{\mathbb{Q}}$ then inherits its laws from multiplicative monotonicity of $\leq_{\mathbb{Z}}$. The outcome is a linearly preordered setoid with strict order compatible with the non-strict order: exactly the structure needed to state spectral gaps and eigenvector ordering.

Setoid Laws

Reflexivity and symmetry of $\simeq_{\mathbb{Q}}$ are inherited directly from propositional equality of the cross-products. Transitivity requires cancelling the intermediate denominator d: the hypothesis $a \cdot d = c \cdot b$ and $c \cdot f = e \cdot d$ are cross-multiplied and then d is removed via torsion-freedom of $\mathbb{Z}$.

```
– § Reflexivity of ≃ℚ.
≃ℚ-refl : (p : ℚ) → p ≃ℚ p
≃ℚ-refl (a / b) = refl

– § Symmetry of ≃ℚ.
≃ℚ-sym : {p q : ℚ} → p ≃ℚ q → q ≃ℚ p
≃ℚ-sym = sym

– § Right cancellation of *ℤ by positive factor.
*ℤ-cancel-right-pos : (x y : ℤ) → (d : ℕ⁺) → (x *ℤ ⁺toℤ d) ≡ (y *ℤ ⁺toℤ d) → x ≡ y
*ℤ-cancel-right-pos x y d eq =
 ≤ℤ-antisym
  (≤ℤ-mul-pos-cancel-right x y d (≤ℤ-resp-≡ʳ eq (≤ℤ-refl (x *ℤ ⁺toℤ d))))
  (≤ℤ-mul-pos-cancel-right y x d (≤ℤ-resp-≡ʳ (sym eq) (≤ℤ-refl (y *ℤ ⁺toℤ d))))

– § Transitivity of ≃ℚ (uses torsion-freedom to cancel intermediate denominator).
≃ℚ-trans : {p q r : ℚ} → p ≃ℚ q → q ≃ℚ r → p ≃ℚ r
≃ℚ-trans {a / b} {c / d} {e / f} eq₁ eq₂ =
 let
  B : ℤ
  B = ⁺toℤ b

  D : ℤ
```

```
  D = ⁺toℤ d

  F : ℤ
  F = ⁺toℤ f

  step₁ : ((a *ℤ D) *ℤ F) ≡ ((c *ℤ B) *ℤ F)
  step₁ = cong (λ t → t *ℤ F) eq₁

  step₂ : ((c *ℤ F) *ℤ B) ≡ ((e *ℤ D) *ℤ B)
  step₂ = cong (λ t → t *ℤ B) eq₂

  swapCBF : ((c *ℤ B) *ℤ F) ≡ ((c *ℤ F) *ℤ B)
  swapCBF =
   trans
    (*ℤ-assoc c B F)
    (trans
     (cong (λ t → c *ℤ t) (*ℤ-comm B F))
     (sym (*ℤ-assoc c F B)))

  mid : ((a *ℤ D) *ℤ F) ≡ ((e *ℤ D) *ℤ B)
  mid = trans step₁ (trans swapCBF step₂)

  regroupL : ((a *ℤ D) *ℤ F) ≡ (a *ℤ F) *ℤ D
  regroupL =
   trans
    (*ℤ-assoc a D F)
    (trans
     (cong (λ t → a *ℤ t) (*ℤ-comm D F))
     (sym (*ℤ-assoc a F D)))

  regroupR : ((e *ℤ D) *ℤ B) ≡ (e *ℤ B) *ℤ D
  regroupR =
   trans
    (*ℤ-assoc e D B)
    (trans
     (cong (λ t → e *ℤ t) (*ℤ-comm D B))
     (sym (*ℤ-assoc e B D)))

  eqD : ((a *ℤ F) *ℤ D) ≡ ((e *ℤ B) *ℤ D)
  eqD = trans (sym regroupL) (trans mid regroupR)
 in
 *ℤ-cancel-right-pos (a *ℤ F) (e *ℤ B) d eqD
```

Preorder Laws

Reflexivity of $\leq_{\mathbb{Q}}$ reduces to $\leq_{\mathbb{Z}}$-reflexivity of the common cross-product. Transitivity cross-multiplies both inequalities by the missing denominator, applies $\leq_{\mathbb{Z}}$-transitivity, and cancels the common factor via multiplicative monotonicity. The strict/non-strict compositions $\leq \circ <$ and $< \circ \leq$ are then derived from transitivity and irreflexivity.

```
– § Reflexivity of ≤ℚ.
≤ℚ-refl : (q : ℚ) → q ≤ℚ q
≤ℚ-refl (a / b) = ≤ℤ-refl (a *ℤ ⁺toℤ b)

– § Denominator scaling swap.
swapScaleℚ : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
swapScaleℚ x u v =
```

```
 trans
  (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
  (trans
   (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
   (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

– § Transitivity of ≤ℚ (uses multiplicative monotonicity + cancellation).
≤ℚ-trans : {x y z : ℚ} → x ≤ℚ y → y ≤ℚ z → x ≤ℚ z
≤ℚ-trans {x} {y} {z} p q with x | y | z
... | a / b | c / d | e / f =
 let
  p' : ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ≤ℤ ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f)
  p' = ≤ℤ-mul-pos-right (a *ℤ ⁺toℤ d) (c *ℤ ⁺toℤ b) f p

  q' : ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b) ≤ℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b)
  q' = ≤ℤ-mul-pos-right (c *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ d) b q

  midEq : ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) ≡ ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b)
  midEq = swapScaleℚ c b f

  p'' : ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ≤ℤ ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b)
  p'' = ≤ℤ-resp-≡ʳ midEq p'

  step : ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ≤ℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b)
  step = ≤ℤ-trans p'' q'

  lhsEq : ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ≡ ((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ d)
  lhsEq = swapScaleℚ a d f

  rhsEq : ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) ≡ ((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d)
  rhsEq = swapScaleℚ e d b

  step' : ((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ d) ≤ℤ ((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d)
  step' = ≤ℤ-resp-≡ˡ lhsEq (≤ℤ-resp-≡ʳ rhsEq step)

  done : (a *ℤ ⁺toℤ f) ≤ℤ (e *ℤ ⁺toℤ b)
  done = ≤ℤ-mul-pos-cancel-right (a *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ b) d step'
 in
 done

– § Negation of ≤ℚ.
_≰ℚ_ : ℚ → ℚ → Set
x ≰ℚ y = (x ≤ℚ y) → ⊥

– § ≤ composed with < yields <.
≤<ℚ→<ℚ : {x y z : ℚ} → x ≤ℚ y → y <ℚ z → x <ℚ z
≤<ℚ→<ℚ {a / b} {c / d} {e / f} x≤y (y≤z , z≰y) =
 let
  x≤z : (a / b) ≤ℚ (e / f)
  x≤z = ≤ℚ-trans {a / b} {c / d} {e / f} x≤y y≤z

  z≰x : (e / f) ≰ℚ (a / b)
  z≰x z≤x = z≰y (≤ℚ-trans {e / f} {a / b} {c / d} z≤x x≤y)
 in
 x≤z , z≰x

– § < composed with ≤ yields <.
<≤ℚ→<ℚ : {x y z : ℚ} → x <ℚ y → y ≤ℚ z → x <ℚ z
<≤ℚ→<ℚ {a / b} {c / d} {e / f} (x≤y , y≰x) y≤z =
 let
  x≤z : (a / b) ≤ℚ (e / f)
  x≤z = ≤ℚ-trans {a / b} {c / d} {e / f} x≤y y≤z
```

```
  z≰x : (e / f) ≰ℚ (a / b)
  z≰x z≤x =
   let
    y≤x : (c / d) ≤ℚ (a / b)
    y≤x = ≤ℚ-trans {c / d} {e / f} {a / b} y≤z z≤x
   in
   y≰x y≤x
 in
 x≤z , z≰x
```

Rational Order Base Laws

Strict order implies non-strict, setoid equality forces $\leq$ in both directions, positive denominators are strictly positive integers, $0 < 1$ in both $\mathbb{Z}$ and $\mathbb{Q}$, and a positive rational has a positive numerator. These base facts anchor every later spectral-gap and distance argument.

```
-- § Strict order implies non-strict.
<ℚ→≤ℚ : {x y : ℚ} → x <ℚ y → x ≤ℚ y
<ℚ→≤ℚ p = fst p

-- § Aliases for uniform naming.
ltZ_to_leZ : {x y : ℤ} → x <ℤ y → x ≤ℤ y
ltZ_to_leZ {x} {y} p = <ℤ→≤ℤ {x} {y} p

ltQ_to_leQ : {x y : ℚ} → x <ℚ y → x ≤ℚ y
ltQ_to_leQ {x} {y} p = <ℚ→≤ℚ {x} {y} p

-- § Setoid equality forces ≤ in both directions.
≃ℚ→≤ℚˡ : {p q : ℚ} → p ≃ℚ q → p ≤ℚ q
≃ℚ→≤ℚˡ {a / b} {c / d} eq =
 ≤ℤ-resp-≡ʳ eq (≤ℤ-refl (a *ℤ ⁺toℤ d))

≃ℚ→≤ℚʳ : {p q : ℚ} → p ≃ℚ q → q ≤ℚ p
≃ℚ→≤ℚʳ {a / b} {c / d} eq =
 ≤ℤ-resp-≡ʳ (sym eq) (≤ℤ-refl (c *ℤ ⁺toℤ b))

-- § Positive naturals are strictly positive integers.
den-posℤ : (d : ℕ⁺) → 0ℤ <ℤ ⁺toℤ d
den-posℤ (mkℕ⁺ k) =
 tt , (λ p → p)

-- § 0 < 1 in ℤ.
0ℤ<oneℤ : 0ℤ <ℤ oneℤ
0ℤ<oneℤ =
 tt , (λ p → p)

-- § 0 < 1 in ℚ.
0ℚ<1ℚ : 0ℚ <ℚ 1ℚ
0ℚ<1ℚ =
 <ℤ-resp-≡ˡ (sym (*ℤ-zero-left (⁺toℤ one⁺)))
  (<ℤ-resp-≡ʳ (sym (*ℤ-one-left (⁺toℤ one⁺)))
    0ℤ<oneℤ)

-- § 0 < ϵ forces 0 < num ϵ.
0ℚ<→0ℤ<num : (ϵ : ℚ) → 0ℚ <ℚ ϵ → 0ℤ <ℤ num ϵ
0ℚ<→0ℤ<num (a / b) p =
 let step₁ : 0ℤ <ℤ (a *ℤ ⁺toℤ one⁺)
```

```
    step₁ = <ℤ-resp-≡ˡ (*ℤ-zero-left (⁺toℤ b)) p

    step₂ : 0ℤ <ℤ a
    step₂ = <ℤ-resp-≡ʳ (*ℤ-one-right a) step₁
in
step₂
```

Chapter 30

Laplacian as Finite-Index Operator

The Laplacian, defined on EndoCase-indexed functions in the preceding chapter, must now be re-expressed as a matrix operator on the canonical four-element index Fin 4. The bijection vertexAt/vertexIndex forces the Vec4-level operator to coincide with its EndoCase counterpart, and the diagonal/off-diagonal split is fixed by Fin4-decidable equality. Multiple equivalent presentations—pre-action, post-action, row-sum, global-sum, coefficient-matrix—are proven identical by exhaustive case analysis, converging on the spectral identity $L = 4I - J$, the minimal polynomial $L^2 = 4L$, and the forced decomposition $4v = Lv + Jv$. Every coefficient is dictated by the graph; no matrix entry is chosen.

Vec4 Infrastructure

A $\text{Vec4}_{\mathbb{Z}}$ is an integer-valued function on four canonical indices. The coefficient type $\text{Coeff}_{\mathbb{Z}}$ is closed: exactly four actions (zero, identity, negation, triple) survive, corresponding to the four places a Laplacian matrix entry can land. Coefficient and action matrices lift these pointwise.

```
-- § Vec4ℤ: integer-valued functions on the four canonical indices.
Vec4ℤ : Set
Vec4ℤ = Fin4 → ℤ

-- § Actℤ: an action on integers.
Actℤ : Set
Actℤ = ℤ → ℤ

-- § Canonical integer actions.
zeroAct : Actℤ
zeroAct _ = 0ℤ

idAct : Actℤ
idAct x = x

negAct : Actℤ
negAct = negℤ

threeAct : Actℤ
threeAct = threeTimesℤ

fourAct : Actℤ
```

```
fourAct = fourTimesℤ

-- § Coefficient type: the four forced actions as a closed data type.
data Coeffℤ : Set where
 c0 : Coeffℤ
 c1 : Coeffℤ
 c-1 : Coeffℤ
 c3 : Coeffℤ

-- § Map coefficients to their canonical actions.
coeffAct : Coeffℤ → Actℤ
coeffAct c0 = zeroAct
coeffAct c1 = idAct
coeffAct c-1 = negAct
coeffAct c3 = threeAct

-- § Matrix types: coefficient-valued and action-valued.
Mat4Coeffℤ : Set
Mat4Coeffℤ = Fin4 → Fin4 → Coeffℤ

liftCoeffMatℤ : Mat4Coeffℤ → (Fin4 → Fin4 → Actℤ)
liftCoeffMatℤ m i j = coeffAct (m i j)

Mat4Actℤ : Set
Mat4Actℤ = Fin4 → Fin4 → Actℤ
```

Off-Diagonal Enumeration

For each index $i \in$ Fin4, the three neighbours are enumerated by others i. Summing over these three off-diagonal entries or over the full four-element orbit is deterministic: the permutation is fixed by the graph structure.

```
-- § others i k: the k-th index distinct from i (exhaustive by Fin3).
others : Fin4 → Fin3 → Fin4
others g0 f0 = g1
others g0 f1 = g2
others g0 f2 = g3
others g1 f0 = g0
others g1 f1 = g2
others g1 f2 = g3
others g2 f0 = g0
others g2 f1 = g1
others g2 f2 = g3
others g3 f0 = g0
others g3 f1 = g1
others g3 f2 = g2

-- § Sum over all four indices, starting from i.
sumFin4Aroundℤ : Fin4 → (Fin4 → ℤ) → ℤ
sumFin4Aroundℤ i f = sum4ℤ (f i) (f (others i f0)) (f (others i f1)) (f (others i f2))

-- § Sum over the three off-diagonal indices.
sumOthersℤ : Vec4ℤ → Fin4 → ℤ
sumOthersℤ v i = sumFin3ℤ (λ k → v (others i k))
```

Laplacian on Vec4

The Laplacian acts as $Lv_i = 3v_i - \Sigma_{j \neq i} v_j$. The pre-action matrix form places $3\times$ on the diagonal and the identity on off-diagonal entries, then subtracts the neighbour sum. Conversion between the EndoCase and Fin4 representations is mediated by the canonical bijection.

```
-- § Laplacian: 3·v_i minus neighbor sum.
laplacianVec4ℤ : Vec4ℤ → Vec4ℤ
laplacianVec4ℤ v i = threeTimesℤ (v i) +ℤ negℤ (sumOthersℤ v i)

-- § Matrix application (pre-action form).
applyLaplacianPreActℤ : Mat4Actℤ → Vec4ℤ → Vec4ℤ
applyLaplacianPreActℤ m v i =
 m i i (v i) +ℤ
 negℤ (sumFin3ℤ (λ k → m i (others i k) (v (others i k))))

-- § Pre-action Laplacian matrix: diagonal = 3×, off-diagonal = id.
laplacianPreMatActℤ : Mat4Actℤ
laplacianPreMatActℤ i j with Fin4-decEq i j
... | inj₁ _ = threeAct
... | inj₂ _ = idAct

-- § Matrix-applied Laplacian.
laplacianMatVec4ℤ : Vec4ℤ → Vec4ℤ
laplacianMatVec4ℤ = applyLaplacianPreActℤ laplacianPreMatActℤ

-- § Conversion between EndoCase and Fin4 representations.
vecFromEndo : (EndoCase → ℤ) → Vec4ℤ
vecFromEndo f i = f (vertexAt i)

endoFromVec : Vec4ℤ → (EndoCase → ℤ)
endoFromVec v x = v (vertexIndex x)
```

Compatibility Laws

Law 14E.0 verifies that the EndoCase Laplacian factors through Fin4 indexing: the round-trip through vertexAt/vertexIndex is the identity. Law 14E.1 confirms that the pre-action matrix agrees with the direct Laplacian on all four indices.

```
-- § Law 14E.0: EndoCase Laplacian factors through Fin4 indexing.
law14E-0-laplacian-factor : (f : EndoCase → ℤ) → (x : EndoCase) →
 laplacianVec4ℤ (vecFromEndo f) (vertexIndex x) ≡ laplacianℤ f x
law14E-0-laplacian-factor f case-constL = refl
law14E-0-laplacian-factor f case-constR = refl
law14E-0-laplacian-factor f case-id = refl
law14E-0-laplacian-factor f case-dual = refl

-- § Law 14E.1: pre-action matrix agrees with the Laplacian.
law14E-1-matrix-agrees : (v : Vec4ℤ) → (i : Fin4) →
 laplacianMatVec4ℤ v i ≡ laplacianVec4ℤ v i
law14E-1-matrix-agrees v g0 = refl
law14E-1-matrix-agrees v g1 = refl
law14E-1-matrix-agrees v g2 = refl
law14E-1-matrix-agrees v g3 = refl
```

Post-Action and Row-Sum Presentations

The post-action matrix moves the negation inside the off-diagonal entries, replacing identity with negation. Row-sum, global-sum, and coefficient-valued presentations are proven pairwise identical: each is a permutation or re-parenthesisation of the same four summands. Laws 14E.2–14E.9 confirm that all six matrix forms collapse to a single Laplacian operator.

```
-- § Alternative application forms.
applyMat4ActDiagOthersℤ : Mat4Actℤ → Vec4ℤ → Vec4ℤ
applyMat4ActDiagOthersℤ m v i =
 m i i (v i) +ℤ
 sumFin3ℤ (λ k → m i (others i k) (v (others i k)))

applyMat4ActRowSumℤ : Mat4Actℤ → Vec4ℤ → Vec4ℤ
applyMat4ActRowSumℤ m v i = sumFin4Aroundℤ i (λ j → m i j (v j))

applyMat4ActGlobalSumℤ : Mat4Actℤ → Vec4ℤ → Vec4ℤ
applyMat4ActGlobalSumℤ m v i = sumFin4ℤ (λ j → m i j (v j))

applyMat4CoeffGlobalSumℤ : Mat4Coeffℤ → Vec4ℤ → Vec4ℤ
applyMat4CoeffGlobalSumℤ m v i = sumFin4ℤ (λ j → coeffAct (m i j) (v j))

-- § Post-action: diagonal = 3×, off-diagonal = negation.
laplacianPostMatActℤ : Mat4Actℤ
laplacianPostMatActℤ i j with Fin4-decEq i j
... | inj₁ _ = threeAct
... | inj₂ _ = negAct

laplacianPostMatVec4ℤ : Vec4ℤ → Vec4ℤ
laplacianPostMatVec4ℤ = applyMat4ActDiagOthersℤ laplacianPostMatActℤ

laplacianRowSumMatVec4ℤ : Vec4ℤ → Vec4ℤ
laplacianRowSumMatVec4ℤ = applyMat4ActRowSumℤ laplacianPostMatActℤ

laplacianGlobalMatVec4ℤ : Vec4ℤ → Vec4ℤ
laplacianGlobalMatVec4ℤ = applyMat4ActGlobalSumℤ laplacianPostMatActℤ

-- § Coefficient Laplacian matrix: diagonal c3, off-diagonal c-1.
laplacianCoeffMatℤ : Mat4Coeffℤ
laplacianCoeffMatℤ i j with Fin4-decEq i j
... | inj₁ _ = c3
... | inj₂ _ = c-1

laplacianCoeffGlobalMatVec4ℤ : Vec4ℤ → Vec4ℤ
laplacianCoeffGlobalMatVec4ℤ = applyMat4CoeffGlobalSumℤ laplacianCoeffMatℤ

-- § Law 14E.3: row-sum unfolds to diagonal+others.
law14E-3-row-sum-unfolds : (m : Mat4Actℤ) → (v : Vec4ℤ) → (i : Fin4) →
 applyMat4ActRowSumℤ m v i ≡ applyMat4ActDiagOthersℤ m v i
law14E-3-row-sum-unfolds m v i = refl

-- § Law 14E.4: row-sum around i equals global sum (by permutation).
law14E-4-sumFin4Around-eq-sumFin4 : (f : Fin4 → ℤ) → (i : Fin4) →
 sumFin4Aroundℤ i f ≡ sumFin4ℤ f
law14E-4-sumFin4Around-eq-sumFin4 f g0 = refl
law14E-4-sumFin4Around-eq-sumFin4 f g1 = sum4ℤ-swap01 (f g1) (f g0) (f g2) (f g3)
law14E-4-sumFin4Around-eq-sumFin4 f g2 =
 trans (sum4ℤ-swap01 (f g2) (f g0) (f g1) (f g3))
       (sum4ℤ-swap12 (f g0) (f g2) (f g1) (f g3))
law14E-4-sumFin4Around-eq-sumFin4 f g3 =
```

```
 trans
  (trans (sum4ℤ-swap01 (f g3) (f g0) (f g1) (f g2))
         (sum4ℤ-swap12 (f g0) (f g3) (f g1) (f g2)))
  (sum4ℤ-swap23 (f g0) (f g1) (f g3) (f g2))

-- § Law 14E.2: post-action matrix agrees with Laplacian (negation placement).
law14E-2-matrix-neg-in-agrees : (v : Vec4ℤ) → (i : Fin4) →
 laplacianPostMatVec4ℤ v i ≡ laplacianVec4ℤ v i
law14E-2-matrix-neg-in-agrees v g0 =
 cong (λ t → threeTimesℤ (v g0) +ℤ t)
      (sym (neg-sumFin3ℤ (λ k → v (others g0 k))))
law14E-2-matrix-neg-in-agrees v g1 =
 cong (λ t → threeTimesℤ (v g1) +ℤ t)
      (sym (neg-sumFin3ℤ (λ k → v (others g1 k))))
law14E-2-matrix-neg-in-agrees v g2 =
 cong (λ t → threeTimesℤ (v g2) +ℤ t)
      (sym (neg-sumFin3ℤ (λ k → v (others g2 k))))
law14E-2-matrix-neg-in-agrees v g3 =
 cong (λ t → threeTimesℤ (v g3) +ℤ t)
      (sym (neg-sumFin3ℤ (λ k → v (others g3 k))))

-- § Law 14E.5: row-sum equals global-sum.
law14E-5-rowSum-eq-globalSum : (m : Mat4Actℤ) → (v : Vec4ℤ) → (i : Fin4) →
 applyMat4ActRowSumℤ m v i ≡ applyMat4ActGlobalSumℤ m v i
law14E-5-rowSum-eq-globalSum m v i =
 law14E-4-sumFin4Around-eq-sumFin4 (λ j → m i j (v j)) i

-- § Law 14E.6: global matrix application equals Laplacian.
law14E-6-global-matrix-agrees : (v : Vec4ℤ) → (i : Fin4) →
 laplacianGlobalMatVec4ℤ v i ≡ laplacianVec4ℤ v i
law14E-6-global-matrix-agrees v i =
 trans (sym (law14E-5-rowSum-eq-globalSum laplacianPostMatActℤ v i))
       (trans (law14E-3-row-sum-unfolds laplacianPostMatActℤ v i)
              (law14E-2-matrix-neg-in-agrees v i))

-- § Law 14E.7: coefficient lift agrees with post-action matrix (16 cases).
law14E-7-coeff-lift-agrees : (i j : Fin4) →
 liftCoeffMatℤ laplacianCoeffMatℤ i j ≡ laplacianPostMatActℤ i j
law14E-7-coeff-lift-agrees g0 g0 = refl
law14E-7-coeff-lift-agrees g0 g1 = refl
law14E-7-coeff-lift-agrees g0 g2 = refl
law14E-7-coeff-lift-agrees g0 g3 = refl
law14E-7-coeff-lift-agrees g1 g0 = refl
law14E-7-coeff-lift-agrees g1 g1 = refl
law14E-7-coeff-lift-agrees g1 g2 = refl
law14E-7-coeff-lift-agrees g1 g3 = refl
law14E-7-coeff-lift-agrees g2 g0 = refl
law14E-7-coeff-lift-agrees g2 g1 = refl
law14E-7-coeff-lift-agrees g2 g2 = refl
law14E-7-coeff-lift-agrees g2 g3 = refl
law14E-7-coeff-lift-agrees g3 g0 = refl
law14E-7-coeff-lift-agrees g3 g1 = refl
law14E-7-coeff-lift-agrees g3 g2 = refl
law14E-7-coeff-lift-agrees g3 g3 = refl

-- § Law 14E.8: coefficient global sum equals action global sum.
law14E-8-coeff-global-eq-act-global : (v : Vec4ℤ) → (i : Fin4) →
 laplacianCoeffGlobalMatVec4ℤ v i ≡ laplacianGlobalMatVec4ℤ v i
law14E-8-coeff-global-eq-act-global v g0 = refl
law14E-8-coeff-global-eq-act-global v g1 = refl
law14E-8-coeff-global-eq-act-global v g2 = refl
law14E-8-coeff-global-eq-act-global v g3 = refl
```

```
-- § Law 14E.9: coefficient global matrix equals Laplacian.
law14E-9-coeff-global-agrees : (v : Vec4ℤ) → (i : Fin4) →
 laplacianCoeffGlobalMatVec4ℤ v i ≡ laplacianVec4ℤ v i
law14E-9-coeff-global-agrees v i =
 trans (law14E-8-coeff-global-eq-act-global v i)
       (law14E-6-global-matrix-agrees v i)
```

Spectral Form: $L = 4I - J$

The around-sum splits into $v_i + \Sigma_{j \neq i} v_j$, yielding the identity $Lv_i = 4v_i - \Sigma v$.

```
-- § Split around-sum into diagonal + others.
sumFin4Around-split : (v : Vec4ℤ) → (i : Fin4) →
 sumFin4Aroundℤ i v ≡ v i +ℤ sumOthersℤ v i
sumFin4Around-split v g0 = refl
sumFin4Around-split v g1 = refl
sumFin4Around-split v g2 = refl
sumFin4Around-split v g3 = refl

-- § 4x = x + 3x.
fourTimes-split : (x : ℤ) → fourTimesℤ x ≡ x +ℤ threeTimesℤ x
fourTimes-split x = refl

-- § Law 14E.10: Laplacian equals 4·v_i minus global sum.
law14E-10-laplacian-four-minus-sumAll : (v : Vec4ℤ) → (i : Fin4) →
 laplacianVec4ℤ v i ≡ fourTimesℤ (v i) +ℤ negℤ (sumFin4ℤ v)
law14E-10-laplacian-four-minus-sumAll v i =
 let x = v i in
 let othersSum = sumOthersℤ v i in
 let around = sumFin4Aroundℤ i v in
 let a = threeTimesℤ x in
 let b = negℤ othersSum in
 let rhsAround = fourTimesℤ x +ℤ negℤ around in

 let rhsAround≡laplacian : rhsAround ≡ laplacianVec4ℤ v i
     rhsAround≡laplacian =
      trans
       (cong (λ t → t +ℤ negℤ around) (fourTimes-split x))
       (trans
        (cong (λ t → (x +ℤ a) +ℤ t) (trans (cong negℤ (sumFin4Around-split v i)) (neg-+ℤ x othersSum)))
        (trans
         (+ℤ-assoc x a (negℤ x +ℤ negℤ othersSum))
         (trans
          (cong (λ t → x +ℤ t) (sym (+ℤ-assoc a (negℤ x) (negℤ othersSum)))
          )
          (trans
           (cong (λ t → x +ℤ ((t) +ℤ negℤ othersSum)) (+ℤ-comm a (negℤ x)))
           (trans
            (cong (λ t → x +ℤ t) (+ℤ-assoc (negℤ x) a (negℤ othersSum)))
            (trans
             (sym (+ℤ-assoc x (negℤ x) (a +ℤ negℤ othersSum)))
             (trans
              (cong (λ t → t +ℤ (a +ℤ negℤ othersSum)) (+ℤ-inv-right x))
              (trans
               (+ℤ-zero-left (a +ℤ negℤ othersSum))
               refl))))))))
 in
```

```
 trans
  (sym rhsAround≡laplacian)
  (cong (λ s → fourTimesℤ x +ℤ negℤ s) (law14E-4-sumFin4Around-eq-sumFin4 v i))
```

Eigenvector Classification

Sum-zero vectors are 4-eigenvectors: when $\Sigma v = 0$, the $-\Sigma v$ term vanishes and $Lv = 4v$. Constant vectors are 0-eigenvectors: the $4v_i - 4v_i = 0$ cancellation is immediate. The J operator maps every vector to the constant vector at Σv, so $J \circ J = 4J$ and J as a coefficient matrix is the all-ones matrix.

```
-- § Law 14E.11: sum-zero vectors are 4-eigenvectors.
law14E-11-sum0-eigen4 : (v : Vec4ℤ) → (i : Fin4) → sumFin4ℤ v ≡ 0ℤ →
 laplacianVec4ℤ v i ≡ fourTimesℤ (v i)
law14E-11-sum0-eigen4 v i sum0 =
 trans
  (law14E-10-laplacian-four-minus-sumAll v i)
  (trans
   (cong (λ s → fourTimesℤ (v i) +ℤ negℤ s) sum0)
   (+ℤ-zero-right (fourTimesℤ (v i))))

-- § Constant vector and J operator.
constVec4ℤ : ℤ → Vec4ℤ
constVec4ℤ x _ = x

JVec4ℤ : Vec4ℤ → Vec4ℤ
JVec4ℤ v _ = sumFin4ℤ v

-- § Coefficient matrix for J: all ones.
onesCoeffMatℤ : Mat4Coeffℤ
onesCoeffMatℤ _ _ = c1

JCoeffGlobalMatVec4ℤ : Vec4ℤ → Vec4ℤ
JCoeffGlobalMatVec4ℤ = applyMat4CoeffGlobalSumℤ onesCoeffMatℤ

-- § Sum of constant vector is four times its value.
sumFin4-const : (x : ℤ) → sumFin4ℤ (constVec4ℤ x) ≡ fourTimesℤ x
sumFin4-const x = refl

-- § Law 14E.12: J as coefficient matrix.
law14E-12-ones-matrix-is-J : (v : Vec4ℤ) → (i : Fin4) →
 JCoeffGlobalMatVec4ℤ v i ≡ JVec4ℤ v i
law14E-12-ones-matrix-is-J v i = refl

-- § Law 14E.13: constant vectors are 0-eigenvectors.
law14E-13-const-eigen0 : (x : ℤ) → (i : Fin4) →
 laplacianVec4ℤ (constVec4ℤ x) i ≡ 0ℤ
law14E-13-const-eigen0 x i =
 trans
  (law14E-10-laplacian-four-minus-sumAll (constVec4ℤ x) i)
  (trans
   (cong (λ s → fourTimesℤ x +ℤ negℤ s) (sumFin4-const x))
   (+ℤ-inv-right (fourTimesℤ x)))
```

J Operator Properties

J is constant across indices, its sum is $4\Sigma v$, and J scales constants by 4. $J \circ J = 4J$ and the sum-zero criterion $\Sigma v = 0$ is equivalent to membership in the 4-eigenspace of L. These identities are assembled here as the spectral raw material for the decomposition $4v = Lv + Jv$.

```
-- § J is constant across indices.
J-constant : (v : Vec4ℤ) → (i j : Fin4) → JVec4ℤ v i ≡ JVec4ℤ v j
J-constant v i j = refl

-- § Sum of J v is four times the sum of v.
sumFin4-J : (v : Vec4ℤ) → sumFin4ℤ (JVec4ℤ v) ≡ fourTimesℤ (sumFin4ℤ v)
sumFin4-J v = refl

-- § J v is definitionally the constant vector at sum v.
J-is-constVec : (v : Vec4ℤ) → (i : Fin4) → JVec4ℤ v i ≡ constVec4ℤ (sumFin4ℤ v) i
J-is-constVec v i = refl

-- § Law 14E.17: J scales constants by 4.
law14E-17-J-const-four : (x : ℤ) → (i : Fin4) →
 JVec4ℤ (constVec4ℤ x) i ≡ fourTimesℤ x
law14E-17-J-const-four x i = sumFin4-const x

-- § Law 14E.18: J ∘ J = 4 · J.
law14E-18-JJ-fourJ : (v : Vec4ℤ) → (i : Fin4) →
 JVec4ℤ (JVec4ℤ v) i ≡ fourTimesℤ (JVec4ℤ v i)
law14E-18-JJ-fourJ v i =
 trans (sumFin4-J v) refl

-- § Law 14E.19: pointwise 4-eigenvectors force sum-zero.
law14E-19-eigen4→sum0 : (v : Vec4ℤ) → ((i : Fin4) → laplacianVec4ℤ v i ≡ fourTimesℤ (v i)) →
 sumFin4ℤ v ≡ 0ℤ
law14E-19-eigen4→sum0 v eigen4 =
 let a = fourTimesℤ (v g0) in
 let s = sumFin4ℤ v in
 let eq0 : a +ℤ negℤ s ≡ a
     eq0 =
      trans
       (sym (law14E-10-laplacian-four-minus-sumAll v g0))
       (eigen4 g0)
 in
 negℤ-zero→zero s (+ℤ-cancel-left a (negℤ s) eq0)

-- § Law 14E.20: sum-zero ↔ pointwise 4-eigenspace.
law14E-20-sum0→eigen4 : (v : Vec4ℤ) → sumFin4ℤ v ≡ 0ℤ → (i : Fin4) →
 laplacianVec4ℤ v i ≡ fourTimesℤ (v i)
law14E-20-sum0→eigen4 v sum0 i = law14E-11-sum0-eigen4 v i sum0

law14E-20-eigen4→sum0 : (v : Vec4ℤ) → ((i : Fin4) → laplacianVec4ℤ v i ≡ fourTimesℤ (v i)) →
 sumFin4ℤ v ≡ 0ℤ
law14E-20-eigen4→sum0 = law14E-19-eigen4→sum0
```

Operator Identity and Kernel

Law 14E.21 establishes $L = 4I - J$ pointwise. The kernel condition $Lv_i = 0$ is then equivalent to $4v_i = Jv_i$, which forces every component to equal $\frac{1}{4}\Sigma v$—the defining property of constant vectors. Laws 14E.23–14E.27 package this equivalence in both directions.

```
-- § Law 14E.21: L = 4I − J pointwise.
law14E-21-L-four-minus-J : (v : Vec4ℤ) → (i : Fin4) →
 laplacianVec4ℤ v i ≡ fourTimesℤ (v i) +ℤ negℤ (JVec4ℤ v i)
law14E-21-L-four-minus-J v i =
 trans (law14E-10-laplacian-four-minus-sumAll v i) refl

-- § Law 14E.22: kernel condition L v i = 0 ↔ 4·v_i = J v i.
law14E-22-L0→fourEqJ : (v : Vec4ℤ) → (i : Fin4) → laplacianVec4ℤ v i ≡ 0ℤ →
 fourTimesℤ (v i) ≡ JVec4ℤ v i
law14E-22-L0→fourEqJ v i L0 =
 let a = fourTimesℤ (v i) in
 let j = JVec4ℤ v i in
 let eq₀ : a +ℤ negℤ j ≡ 0ℤ
     eq₀ = trans (sym (law14E-21-L-four-minus-J v i)) L0
 in
 let step₁ : (a +ℤ negℤ j) +ℤ j ≡ 0ℤ +ℤ j
     step₁ = cong (λ t → t +ℤ j) eq₀
     step₂ : a +ℤ (negℤ j +ℤ j) ≡ 0ℤ +ℤ j
     step₂ = trans (sym (+ℤ-assoc a (negℤ j) j)) step₁
     step₃ : a +ℤ 0ℤ ≡ 0ℤ +ℤ j
     step₃ = trans (sym (cong (λ t → a +ℤ t) (+ℤ-inv-left j))) step₂
 in
 trans
  (sym (+ℤ-zero-right a))
  (trans step₃ (+ℤ-zero-left j))

law14E-22-fourEqJ→L0 : (v : Vec4ℤ) → (i : Fin4) → fourTimesℤ (v i) ≡ JVec4ℤ v i →
 laplacianVec4ℤ v i ≡ 0ℤ
law14E-22-fourEqJ→L0 v i fourEqJ =
 let a = fourTimesℤ (v i) in
 let j = JVec4ℤ v i in
 trans
  (law14E-21-L-four-minus-J v i)
  (trans
     (cong (λ t → a +ℤ t) (cong negℤ (sym fourEqJ)))
     (+ℤ-inv-right a))

-- § Pointwise vector equality.
Vec4Eq : Vec4ℤ → Vec4ℤ → Set
Vec4Eq v w = (i : Fin4) → v i ≡ w i

-- § Kernel predicate.
KernelL : Vec4ℤ → Set
KernelL v = (i : Fin4) → laplacianVec4ℤ v i ≡ 0ℤ

-- § Law 14E.23: L = 4I − J as Vec4Eq.
law14E-23-L-eq-four-minus-J : (v : Vec4ℤ) →
 Vec4Eq (laplacianVec4ℤ v) (λ i → fourTimesℤ (v i) +ℤ negℤ (JVec4ℤ v i))
law14E-23-L-eq-four-minus-J v i = law14E-21-L-four-minus-J v i

-- § Law 14E.24: kernel forces fourTimes-constant.
law14E-24-kernel→fourTimes-constant : (v : Vec4ℤ) → KernelL v → (i j : Fin4) →
 fourTimesℤ (v i) ≡ fourTimesℤ (v j)
law14E-24-kernel→fourTimes-constant v ker i j =
 let fi = law14E-22-L0→fourEqJ v i (ker i) in
 let fj = law14E-22-L0→fourEqJ v j (ker j) in
 trans fi (trans refl (sym fj))

-- § Law 14E.25: kernel ↔ fourEqJ pointwise.
law14E-25-kernel→fourEqJ : (v : Vec4ℤ) → KernelL v → (i : Fin4) →
 fourTimesℤ (v i) ≡ JVec4ℤ v i
law14E-25-kernel→fourEqJ v ker i = law14E-22-L0→fourEqJ v i (ker i)
```

```
law14E-25-fourEqJ→kernel : (v : Vec4ℤ) → ((i : Fin4) → fourTimesℤ (v i) ≡ JVec4ℤ v i) → KernelL v
law14E-25-fourEqJ→kernel v hyp i = law14E-22-fourEqJ→L0 v i (hyp i)

-- § Law 14E.26: kernel forces sum = 4·v_i.
law14E-26-kernel→sumEqFour : (v : Vec4ℤ) → KernelL v → (i : Fin4) →
 sumFin4ℤ v ≡ fourTimesℤ (v i)
law14E-26-kernel→sumEqFour v ker i =
 trans
  refl
  (trans
    (sym (law14E-25-kernel→fourEqJ v ker i))
    refl)

-- § Law 14E.27: sum = 4·v_i forces kernel.
law14E-27-sumEqFour→kernel : (v : Vec4ℤ) → ((i : Fin4) → sumFin4ℤ v ≡ fourTimesℤ (v i)) → KernelL v
law14E-27-sumEqFour→kernel v hyp =
 law14E-25-fourEqJ→kernel v (λ i → sym (trans refl (hyp i)))

-- § Law 14E.14: J is constant.
law14E-14-J-constant : (v : Vec4ℤ) → (i j : Fin4) →
 JVec4ℤ v i ≡ JVec4ℤ v j
law14E-14-J-constant = J-constant

-- § Law 14E.15: sum-zero ↔ J v = 0.
law14E-15-sum0-to-J0 : (v : Vec4ℤ) → (i : Fin4) → sumFin4ℤ v ≡ 0ℤ →
 JVec4ℤ v i ≡ 0ℤ
law14E-15-sum0-to-J0 v i sum0 = sum0

law14E-15-J0-to-sum0 : (v : Vec4ℤ) → JVec4ℤ v g0 ≡ 0ℤ →
 sumFin4ℤ v ≡ 0ℤ
law14E-15-J0-to-sum0 v J0 = J0

-- § Law 14E.16: L ∘ J = 0.
law14E-16-LJ-zero : (v : Vec4ℤ) → (i : Fin4) →
 laplacianVec4ℤ (JVec4ℤ v) i ≡ 0ℤ
law14E-16-LJ-zero v i =
 let s = sumFin4ℤ v in
 trans
  (law14E-10-laplacian-four-minus-sumAll (JVec4ℤ v) i)
  (trans
    (cong (λ t → fourTimesℤ s +ℤ negℤ t) (sumFin4-J v))
    (+ℤ-inv-right (fourTimesℤ s)))
```

Image of the Laplacian

Adding a constant c to every component shifts the global sum by $4c$. The core identity $\Sigma(Lv) = 0$ then follows from $L = 4I - J$ and the fact that $\Sigma(4v) = 4\Sigma v = \Sigma(Jv)$.

```
-- § Add constant to each component.
sumFin4-addConst : (v : Vec4ℤ) → (c : ℤ) →
 sumFin4ℤ (λ i → v i +ℤ c) ≡ sumFin4ℤ v +ℤ fourTimesℤ c
sumFin4-addConst v c =
 let
  a0 = v g0
  a1 = v g1
  a2 = v g2
  a3 = v g3
```

```
r23 = (a2 +ℤ c) +ℤ (a3 +ℤ c)
r1 = (a1 +ℤ c) +ℤ r23

step₁ : (a0 +ℤ c) +ℤ r1 ≡ a0 +ℤ (c +ℤ r1)
step₁ = +ℤ-assoc a0 c r1

step₂ : r1 ≡ a1 +ℤ (c +ℤ r23)
step₂ = +ℤ-assoc a1 c r23

step₃ : c +ℤ r1 ≡ a1 +ℤ (c +ℤ (c +ℤ r23))
step₃ =
 trans
   (cong (λ t → c +ℤ t) step₂)
   (swapHeadℤ c a1 (c +ℤ r23))

step₄ : (a0 +ℤ c) +ℤ r1 ≡ a0 +ℤ (a1 +ℤ (c +ℤ (c +ℤ r23)))
step₄ = trans step₁ (cong (λ t → a0 +ℤ t) step₃)

step₅ a : r23 ≡ a2 +ℤ (c +ℤ (a3 +ℤ c))
step₅ a = +ℤ-assoc a2 c (a3 +ℤ c)

step₅ b : c +ℤ r23 ≡ a2 +ℤ (c +ℤ (c +ℤ (a3 +ℤ c)))
step₅ b =
 trans
   (cong (λ t → c +ℤ t) step₅ a)
   (swapHeadℤ c a2 (c +ℤ (a3 +ℤ c)))

step₅ c : c +ℤ (c +ℤ r23) ≡ a2 +ℤ (c +ℤ (c +ℤ (c +ℤ (a3 +ℤ c))))
step₅ c =
 trans
   (cong (λ t → c +ℤ t) step₅ b)
   (swapHeadℤ c a2 (c +ℤ (c +ℤ (a3 +ℤ c))))

step₆ : a0 +ℤ (a1 +ℤ (c +ℤ (c +ℤ r23))) ≡ a0 +ℤ (a1 +ℤ (a2 +ℤ (c +ℤ (c +ℤ (c +ℤ (a3 +ℤ c))))))
step₆ = cong (λ t → a0 +ℤ (a1 +ℤ t)) step₅ c

step₇ a : c +ℤ (a3 +ℤ c) ≡ a3 +ℤ (c +ℤ c)
step₇ a = swapHeadℤ c a3 c

step₇ b : c +ℤ (c +ℤ (a3 +ℤ c)) ≡ a3 +ℤ (c +ℤ (c +ℤ c))
step₇ b =
 trans
   (cong (λ t → c +ℤ t) step₇ a)
   (swapHeadℤ c a3 (c +ℤ c))

step₇ c : c +ℤ (c +ℤ (c +ℤ (a3 +ℤ c))) ≡ a3 +ℤ (c +ℤ (c +ℤ (c +ℤ c)))
step₇ c =
 trans
   (cong (λ t → c +ℤ t) step₇ b)
   (swapHeadℤ c a3 (c +ℤ (c +ℤ c)))

step₈ : c +ℤ (c +ℤ (c +ℤ (a3 +ℤ c))) ≡ a3 +ℤ fourTimesℤ c
step₈ = trans step₇ c refl

step₉ : a0 +ℤ (a1 +ℤ (a2 +ℤ (c +ℤ (c +ℤ (c +ℤ (a3 +ℤ c)))))) ≡ a0 +ℤ (a1 +ℤ (a2 +ℤ (a3 +ℤ fourTimesℤ c)))
step₉ = cong (λ t → a0 +ℤ (a1 +ℤ (a2 +ℤ t))) step₈

step₁₀ a : a2 +ℤ (a3 +ℤ fourTimesℤ c) ≡ (a2 +ℤ a3) +ℤ fourTimesℤ c
step₁₀ a = sym (+ℤ-assoc a2 a3 (fourTimesℤ c))

step₁₀ b : a1 +ℤ (a2 +ℤ (a3 +ℤ fourTimesℤ c)) ≡ (a1 +ℤ (a2 +ℤ a3)) +ℤ fourTimesℤ c
step₁₀ b =
```

```
  trans
    (cong (λ t → a1 +ℤ t) step₁₀a)
    (sym (+ℤ-assoc a1 (a2 +ℤ a3) (fourTimesℤ c)))

 step₁₀c : a0 +ℤ (a1 +ℤ (a2 +ℤ (a3 +ℤ fourTimesℤ c))) ≡ (a0 +ℤ (a1 +ℤ (a2 +ℤ a3))) +ℤ fourTimesℤ c
 step₁₀c =
  trans
    (cong (λ t → a0 +ℤ t) step₁₀b)
    (sym (+ℤ-assoc a0 (a1 +ℤ (a2 +ℤ a3)) (fourTimesℤ c)))
 in
 trans
  refl
  (trans
   step₄
   (trans
     step₆
     (trans
      step₉
      (trans
       step₁₀c
       refl))))
```

Step 2: Distribution and Global Sum. fourTimesℤ distributes over $+_{\mathbb{Z}}$, commutes with sumFin4ℤ, and yields the global-sum-zero law for the Laplacian.

```
-- § fourTimes distributes over +ℤ.
fourTimes-+ℤ : (x y : ℤ) → fourTimesℤ (x +ℤ y) ≡ fourTimesℤ x +ℤ fourTimesℤ y
fourTimes-+ℤ x y =
 trans
  (sym (sumFin4-const (x +ℤ y)))
  (trans
   (sumFin4-addConst (constVec4ℤ x) y)
   (trans
    (cong (λ t → t +ℤ fourTimesℤ y) (sumFin4-const x))
    refl))

-- § Sum of fourTimes equals fourTimes of sum.
sumFin4-fourTimes : (v : Vec4ℤ) →
 sumFin4ℤ (λ i → fourTimesℤ (v i)) ≡ fourTimesℤ (sumFin4ℤ v)
sumFin4-fourTimes v =
 let
  a0 = v g0
  a1 = v g1
  a2 = v g2
  a3 = v g3
 in
 sym
  (trans
   refl
   (trans
    (fourTimes-+ℤ a0 (a1 +ℤ (a2 +ℤ a3)))
    (trans
     (cong (λ t → fourTimesℤ a0 +ℤ t) (fourTimes-+ℤ a1 (a2 +ℤ a3)))
     (trans
      (cong (λ t → fourTimesℤ a0 +ℤ (fourTimesℤ a1 +ℤ t)) (fourTimes-+ℤ a2 a3))
      refl))))

-- § Law 14E.28: global sum of the Laplacian is zero.
law14E-28-sumLaplacian0 : (v : Vec4ℤ) →
```

```
 sumFin4ℤ (laplacianVec4ℤ v) ≡ 0ℤ
law14E-28-sumLaplacian0 v =
 let
  s = sumFin4ℤ v

  step0 :
   sumFin4ℤ (laplacianVec4ℤ v) ≡
   sum4ℤ (fourTimesℤ (v g0) +ℤ negℤ s) (laplacianVec4ℤ v g1) (laplacianVec4ℤ v g2) (laplacianVec4ℤ v g3)
  step0 =
   cong
    (λ t0 → sum4ℤ t0 (laplacianVec4ℤ v g1) (laplacianVec4ℤ v g2) (laplacianVec4ℤ v g3))
    (law14E-10-laplacian-four-minus-sumAll v g0)

  step1 :
   sum4ℤ (fourTimesℤ (v g0) +ℤ negℤ s) (laplacianVec4ℤ v g1) (laplacianVec4ℤ v g2) (laplacianVec4ℤ v g3) ≡
   sum4ℤ (fourTimesℤ (v g0) +ℤ negℤ s) (fourTimesℤ (v g1) +ℤ negℤ s) (laplacianVec4ℤ v g2) (laplacianVec4ℤ v g3)
  step1 =
   cong
    (λ t1 → sum4ℤ (fourTimesℤ (v g0) +ℤ negℤ s) t1 (laplacianVec4ℤ v g2) (laplacianVec4ℤ v g3))
    (law14E-10-laplacian-four-minus-sumAll v g1)

  step2 :
   sum4ℤ (fourTimesℤ (v g0) +ℤ negℤ s) (fourTimesℤ (v g1) +ℤ negℤ s) (laplacianVec4ℤ v g2) (laplacianVec4ℤ v g3) ≡
   sum4ℤ (fourTimesℤ (v g0) +ℤ negℤ s) (fourTimesℤ (v g1) +ℤ negℤ s) (fourTimesℤ (v g2) +ℤ negℤ s) (laplacianVec4ℤ v g3)
  step2 =
   cong
    (λ t2 → sum4ℤ (fourTimesℤ (v g0) +ℤ negℤ s) (fourTimesℤ (v g1) +ℤ negℤ s) t2 (laplacianVec4ℤ v g3))
    (law14E-10-laplacian-four-minus-sumAll v g2)

  step3 :
   sum4ℤ (fourTimesℤ (v g0) +ℤ negℤ s) (fourTimesℤ (v g1) +ℤ negℤ s) (fourTimesℤ (v g2) +ℤ negℤ s) (laplacianVec4ℤ v g3) ≡
   sum4ℤ (fourTimesℤ (v g0) +ℤ negℤ s) (fourTimesℤ (v g1) +ℤ negℤ s) (fourTimesℤ (v g2) +ℤ negℤ s) (fourTimesℤ (v g3) +ℤ negℤ s)
  step3 =
   cong
    (λ t3 → sum4ℤ (fourTimesℤ (v g0) +ℤ negℤ s) (fourTimesℤ (v g1) +ℤ negℤ s) (fourTimesℤ (v g2) +ℤ negℤ s) t3)
    (law14E-10-laplacian-four-minus-sumAll v g3)

  rewriteSum :
   sumFin4ℤ (laplacianVec4ℤ v) ≡
   sumFin4ℤ (λ i → fourTimesℤ (v i) +ℤ negℤ s)
  rewriteSum =
   trans
    refl
    (trans step0 (trans step1 (trans step2 (trans step3 refl))))
 in
 trans
  rewriteSum
  (trans
   (sumFin4-addConst (λ i → fourTimesℤ (v i)) (negℤ s))
   (trans
    (cong (λ t → t +ℤ fourTimesℤ (negℤ s)) (sumFin4-fourTimes v))
    (trans
     (cong (λ t → fourTimesℤ s +ℤ t) (sym (neg-fourTimesℤ s)))
     (+ℤ-inv-right (fourTimesℤ s)))))
```

Minimal Polynomial and Operator Algebra

$L^2 = 4L$ is the minimal polynomial $x(x-4) = 0$: applying L twice to any vector reduces to four times the single application, because the image of L is sum-zero and therefore lies in the 4-eigenspace. $J \circ L = 0$ and $L + J = 4I$ close the operator algebra of K_4.

```
-- § Law 14E.29: L ∘ L = 4 · L (minimal polynomial x(x−4) = 0).
law14E-29-LL-fourL : (v : Vec4ℤ) → (i : Fin4) →
 laplacianVec4ℤ (laplacianVec4ℤ v) i ≡ fourTimesℤ (laplacianVec4ℤ v i)
law14E-29-LL-fourL v i =
 law14E-11-sum0-eigen4 (laplacianVec4ℤ v) i (law14E-28-sumLaplacian0 v)

-- § Law 14E.30: J ∘ L = 0.
law14E-30-JL-zero : (v : Vec4ℤ) → (i : Fin4) →
 JVec4ℤ (laplacianVec4ℤ v) i ≡ 0ℤ
law14E-30-JL-zero v i =
 law14E-15-sum0-to-J0 (laplacianVec4ℤ v) i (law14E-28-sumLaplacian0 v)

-- § Law 14E.31: L + J = 4I pointwise.
law14E-31-L-plus-J-eq-fourI : (v : Vec4ℤ) → (i : Fin4) →
 laplacianVec4ℤ v i +ℤ JVec4ℤ v i ≡ fourTimesℤ (v i)
law14E-31-L-plus-J-eq-fourI v i =
 let a = fourTimesℤ (v i) in
 let j = JVec4ℤ v i in
 trans
  (cong (λ t → t +ℤ j) (law14E-21-L-four-minus-J v i))
  (trans
   (+ℤ-assoc a (negℤ j) j)
   (trans
    (cong (λ t → a +ℤ t) (+ℤ-inv-left j))
    (+ℤ-zero-right a)))

-- § Zero vector.
zeroVec4ℤ : Vec4ℤ
zeroVec4ℤ = constVec4ℤ 0ℤ
```

Vec4Eq Packagings

The pointwise identities $L+J = 4I$, $L \circ J = 0$, $J \circ L = 0$, $L^2 = 4L$, and $J^2 = 4J$ are repackaged as Vec4Eq statements. The canonical decomposition $4v = Lv + Jv$ with Lv sum-zero and Jv constant is the spectral splitting that all later eigenvalue arguments invoke.

```
-- § Law 14E.32: L + J = 4I as Vec4Eq.
law14E-32-LplusJ-eq-fourI-Vec4Eq : (v : Vec4ℤ) →
 Vec4Eq (λ i → laplacianVec4ℤ v i +ℤ JVec4ℤ v i) (λ i → fourTimesℤ (v i))
law14E-32-LplusJ-eq-fourI-Vec4Eq v i = law14E-31-L-plus-J-eq-fourI v i

-- § Law 14E.33: L ∘ J = 0 as Vec4Eq.
law14E-33-LJ-zero-Vec4Eq : (v : Vec4ℤ) →
 Vec4Eq (laplacianVec4ℤ (JVec4ℤ v)) zeroVec4ℤ
law14E-33-LJ-zero-Vec4Eq v i = law14E-16-LJ-zero v i

-- § Law 14E.34: J ∘ L = 0 as Vec4Eq.
law14E-34-JL-zero-Vec4Eq : (v : Vec4ℤ) →
 Vec4Eq (JVec4ℤ (laplacianVec4ℤ v)) zeroVec4ℤ
law14E-34-JL-zero-Vec4Eq v i = law14E-30-JL-zero v i

-- § Law 14E.35: L and J commute (both composites = 0).
law14E-35-LJ-commute : (v : Vec4ℤ) →
 Vec4Eq (laplacianVec4ℤ (JVec4ℤ v)) (JVec4ℤ (laplacianVec4ℤ v))
law14E-35-LJ-commute v i =
 trans (law14E-16-LJ-zero v i) (sym (law14E-30-JL-zero v i))

-- § Law 14E.36: L² = 4L as Vec4Eq.
```

```
law14E-36-LL-fourL-Vec4Eq : (v : Vec4ℤ) →
 Vec4Eq (laplacianVec4ℤ (laplacianVec4ℤ v)) (λ i → fourTimesℤ (laplacianVec4ℤ v i))
law14E-36-LL-fourL-Vec4Eq v i = law14E-29-LL-fourL v i

-- § Law 14E.37: J² = 4J as Vec4Eq.
law14E-37-JJ-fourJ-Vec4Eq : (v : Vec4ℤ) →
 Vec4Eq (JVec4ℤ (JVec4ℤ v)) (λ i → fourTimesℤ (JVec4ℤ v i))
law14E-37-JJ-fourJ-Vec4Eq v i = law14E-18-JJ-fourJ v i

-- § Pointwise four-times and pointwise addition.
fourVec4ℤ : Vec4ℤ → Vec4ℤ
fourVec4ℤ v i = fourTimesℤ (v i)

_+Vec4ℤ_ : Vec4ℤ → Vec4ℤ → Vec4ℤ
(v +Vec4ℤ w) i = v i +ℤ w i

-- § Law 14E.38: image of L is sum-zero and 4-eigen.
law14E-38-imageL-sum0-and-eigen4 : (v : Vec4ℤ) →
 (sumFin4ℤ (laplacianVec4ℤ v) ≡ 0ℤ) × ((i : Fin4) → laplacianVec4ℤ (laplacianVec4ℤ v) i ≡ fourTimesℤ (laplacianVec4ℤ v i))
law14E-38-imageL-sum0-and-eigen4 v =
 law14E-28-sumLaplacian0 v , law14E-29-LL-fourL v

-- § Law 14E.39: image of J is constant and in kernel of L.
law14E-39-imageJ-const-and-kernelL : (v : Vec4ℤ) →
 (((i j : Fin4) → JVec4ℤ v i ≡ JVec4ℤ v j) × ((i : Fin4) → laplacianVec4ℤ (JVec4ℤ v) i ≡ 0ℤ))
law14E-39-imageJ-const-and-kernelL v =
 law14E-14-J-constant v , law14E-16-LJ-zero v

-- § Decomposition type: 4v = u + w with u sum-zero, w constant.
Decomp4 : Vec4ℤ → Set
Decomp4 v =
 Σ Vec4ℤ (λ u →
   Σ Vec4ℤ (λ w →
     (Vec4Eq (u +Vec4ℤ w) (fourVec4ℤ v)) ×
     (sumFin4ℤ u ≡ 0ℤ) ×
     ((i j : Fin4) → w i ≡ w j)))

-- § Law 14E.40: canonical decomposition 4v = Lv + Jv.
law14E-40-decomp4-canonical : (v : Vec4ℤ) → Decomp4 v
law14E-40-decomp4-canonical v =
 laplacianVec4ℤ v ,
 (JVec4ℤ v ,
   (law14E-32-LplusJ-eq-fourI-Vec4Eq v ,
    (law14E-28-sumLaplacian0 v ,
      law14E-14-J-constant v)))
```

Additivity of L and J

L and J are additive operators: $L(u+v) = Lu + Lv$ and $J(u+v) = Ju + Jv$. The proof proceeds by distributing the three-slot summation over pointwise addition and reassociating via sumFin3-linearity.

```
-- § sumFin3 distributes over pointwise addition.
sumFin3-+ℤ : (f g : Fin3 → ℤ) →
 sumFin3ℤ (λ k → f k +ℤ g k) ≡
 sumFin3ℤ f +ℤ sumFin3ℤ g
sumFin3-+ℤ f g =
 let
```

```
  a0 = f f0
  a1 = f f1
  a2 = f f2
  b0 = g f0
  b1 = g f1
  b2 = g f2

  X = a1 +ℤ b1
  Y = a2 +ℤ b2
  R = b0 +ℤ b2

  step₁ : sumFin3ℤ (λ k → f k +ℤ g k) ≡ a0 +ℤ (b0 +ℤ (X +ℤ Y))
  step₁ = +ℤ-assoc a0 b0 (X +ℤ Y)

  step₂ : a0 +ℤ (b0 +ℤ (X +ℤ Y)) ≡ a0 +ℤ (X +ℤ (b0 +ℤ Y))
  step₂ = cong (λ t → a0 +ℤ t) (swapHeadℤ b0 X Y)

  step₃ : a0 +ℤ (X +ℤ (b0 +ℤ Y)) ≡ a0 +ℤ (X +ℤ (a2 +ℤ R))
  step₃ = cong (λ t → a0 +ℤ (X +ℤ t)) (swapHeadℤ b0 a2 b2)

  step₄ : a0 +ℤ (X +ℤ (a2 +ℤ R)) ≡ a0 +ℤ (a1 +ℤ (b1 +ℤ (a2 +ℤ R)))
  step₄ = cong (λ t → a0 +ℤ t) (+ℤ-assoc a1 b1 (a2 +ℤ R))

  step₅ : a0 +ℤ (a1 +ℤ (b1 +ℤ (a2 +ℤ R))) ≡ a0 +ℤ (a1 +ℤ (a2 +ℤ (b1 +ℤ R)))
  step₅ = cong (λ t → a0 +ℤ (a1 +ℤ t)) (swapHeadℤ b1 a2 R)

  step₆ : a0 +ℤ (a1 +ℤ (a2 +ℤ (b1 +ℤ R))) ≡ a0 +ℤ ((a1 +ℤ a2) +ℤ (b1 +ℤ R))
  step₆ = cong (λ t → a0 +ℤ t) (sym (+ℤ-assoc a1 a2 (b1 +ℤ R)))

  step₇ : a0 +ℤ ((a1 +ℤ a2) +ℤ (b1 +ℤ R)) ≡ a0 +ℤ ((a1 +ℤ a2) +ℤ (b0 +ℤ (b1 +ℤ b2)))
  step₇ = cong (λ t → a0 +ℤ ((a1 +ℤ a2) +ℤ t)) (swapHeadℤ b1 b0 b2)

  step₈ : a0 +ℤ ((a1 +ℤ a2) +ℤ (b0 +ℤ (b1 +ℤ b2))) ≡ (a0 +ℤ (a1 +ℤ a2)) +ℤ (b0 +ℤ (b1 +ℤ b2))
  step₈ = sym (+ℤ-assoc a0 (a1 +ℤ a2) (b0 +ℤ (b1 +ℤ b2)))
 in
 trans
  refl
  (trans step₁
   (trans step₂
    (trans step₃
     (trans step₄
      (trans step₅
       (trans step₆
        (trans step₇
         (trans step₈ refl))))))))

-- § sumOthers distributes over pointwise addition.
sumOthers-+Vec4ℤ : (v w : Vec4ℤ) → (i : Fin4) →
 sumOthersℤ (v +Vec4ℤ w) i ≡ sumOthersℤ v i +ℤ sumOthersℤ w i
sumOthers-+Vec4ℤ v w i =
 sumFin3-+ℤ (λ k → v (others i k)) (λ k → w (others i k))
```

Step 2: Vec4ℤ and Laplacian Distribution. sumFin4 distributes over pointwise addition of Vec4ℤ, and the Laplacian distributes over vector sums.

```
-- § sumFin4 distributes over pointwise addition.
sumFin4-+Vec4ℤ : (v w : Vec4ℤ) →
 sumFin4ℤ (λ i → v i +ℤ w i) ≡ sumFin4ℤ v +ℤ sumFin4ℤ w
sumFin4-+Vec4ℤ v w =
 let
```

```
  split0 : (x : Vec4ℤ) → sumFin4ℤ x ≡ x g0 +ℤ sumOthersℤ x g0
  split0 x =
   trans
    (sym (law14E-4-sumFin4Around-eq-sumFin4 x g0))
    (sumFin4Around-split x g0)

  v0 = v g0
  w0 = w g0
  sv = sumOthersℤ v g0
  sw = sumOthersℤ w g0

  step₁ : sumFin4ℤ (v +Vec4ℤ w) ≡ (v0 +ℤ w0) +ℤ sumOthersℤ (v +Vec4ℤ w) g0
  step₁ = trans (split0 (v +Vec4ℤ w)) refl

  step₂ : (v0 +ℤ w0) +ℤ sumOthersℤ (v +Vec4ℤ w) g0 ≡ (v0 +ℤ w0) +ℤ (sv +ℤ sw)
  step₂ = cong (λ t → (v0 +ℤ w0) +ℤ t) (sumOthers-+Vec4ℤ v w g0)

  step₃ : (v0 +ℤ w0) +ℤ (sv +ℤ sw) ≡ (v0 +ℤ sv) +ℤ (w0 +ℤ sw)
  step₃ =
   trans
    (+ℤ-assoc v0 w0 (sv +ℤ sw))
    (trans
     (cong (λ t → v0 +ℤ t) (swapHeadℤ w0 sv sw))
     (sym (+ℤ-assoc v0 sv (w0 +ℤ sw))))
 in
 trans
  (trans refl step₁)
  (trans
   step₂
   (trans
    step₃
    (trans
     (cong (λ t → t +ℤ (w0 +ℤ sw)) (sym (split0 v)))
     (cong (λ t → sumFin4ℤ v +ℤ t) (sym (split0 w))))))

-- § Law 14E.41: J preserves pointwise addition.
law14E-41-J-add : (v w : Vec4ℤ) → (i : Fin4) →
 JVec4ℤ (v +Vec4ℤ w) i ≡ JVec4ℤ v i +ℤ JVec4ℤ w i
law14E-41-J-add v w i = sumFin4-+Vec4ℤ v w

-- § threeTimes distributes over +ℤ.
threeTimes-+ℤ : (x y : ℤ) → threeTimesℤ (x +ℤ y) ≡ threeTimesℤ x +ℤ threeTimesℤ y
threeTimes-+ℤ x y =
 sumFin3-+ℤ (λ _ → x) (λ _ → y)

-- § Law 14E.42: L preserves pointwise addition.
law14E-42-L-add : (v w : Vec4ℤ) → (i : Fin4) →
 laplacianVec4ℤ (v +Vec4ℤ w) i ≡ laplacianVec4ℤ v i +ℤ laplacianVec4ℤ w i
law14E-42-L-add v w i =
 let
  A = threeTimesℤ (v i)
  B = threeTimesℤ (w i)
  C = negℤ (sumOthersℤ v i)
  D = negℤ (sumOthersℤ w i)

  step₁ : laplacianVec4ℤ (v +Vec4ℤ w) i ≡ (A +ℤ B) +ℤ negℤ (sumOthersℤ (v +Vec4ℤ w) i)
  step₁ = cong (λ t → t +ℤ negℤ (sumOthersℤ (v +Vec4ℤ w) i)) (threeTimes-+ℤ (v i) (w i))

  step₂ : negℤ (sumOthersℤ (v +Vec4ℤ w) i) ≡ C +ℤ D
  step₂ =
   trans
    (cong negℤ (sumOthers-+Vec4ℤ v w i))
```

```
  (neg-+ℤ (sumOthersℤ v i) (sumOthersℤ w i))

 step₃ : (A +ℤ B) +ℤ (C +ℤ D) ≡ (A +ℤ C) +ℤ (B +ℤ D)
 step₃ =
  trans
   (+ℤ-assoc A B (C +ℤ D))
   (trans
    (cong (λ t → A +ℤ t) (swapHeadℤ B C D))
    (sym (+ℤ-assoc A C (B +ℤ D))))
in
trans
 step₁
 (trans
  (cong (λ t → (A +ℤ B) +ℤ t) step₂)
  (trans
   step₃
   refl))
```

Chapter 31

Measurement Symmetries

Every measurement act $m : S\ d \to S$ Two defines a two-valued observable. Two symmetries act on such measurements without introducing new structure: swapping the output (post-composing with swapTwo) and swapping the input (pre-composing with the forced dual automorphism Distinction-dual). Each symmetry acts on the K_4Map classification by a forced permutation, and that permutation is determined by evaluation at the two constructors.

Output and Input Swap

The output swap post-composes with swapTwo, exchanging the two possible measurement outcomes. The input swap pre-composes with Distinction-dual, exchanging the two halves of the domain.

```
-- § output swap: post-compose with swapTwo
swapOut : {d : Distinction} → Measurement d → Measurement d
swapOut m x = swapTwo (m x)

-- § input swap: pre-compose with the forced dual
swapIn : (d : Distinction) → Measurement d → Measurement d
swapIn d m x = m (Distinction-dual d x)

-- § swapOut respects pointwise equality
swapOut-cong :
 {d : Distinction} {m n : Measurement d} →
 _≐_ {A = S d} {B = S Two-distinction} m n →
 _≐_ {A = S d} {B = S Two-distinction} (swapOut {d = d} m) (swapOut {d = d} n)
swapOut-cong p x = cong swapTwo (p x)

-- § swapIn respects pointwise equality
swapIn-cong :
 (d : Distinction) {m n : Measurement d} →
 _≐_ {A = S d} {B = S Two-distinction} m n →
 _≐_ {A = S d} {B = S Two-distinction} (swapIn d m) (swapIn d n)
swapIn-cong d p x = p (Distinction-dual d x)
```

Induced Permutations on EndoCase

The four-element classification EndoCase transforms under each symmetry by a forced permutation. Output swap exchanges constant-left with constant-right and identity with dual. Input swap fixes the constants and exchanges identity with dual.

```
-- § output swap acts on EndoCase
permOut : EndoCase → EndoCase
permOut case-constL = case-constR
permOut case-constR = case-constL
permOut case-id     = case-dual
permOut case-dual = case-id

-- § input swap acts on EndoCase
permIn : EndoCase → EndoCase
permIn case-constL = case-constL
permIn case-constR = case-constR
permIn case-id     = case-dual
permIn case-dual = case-id
```

Interpretation Compatibility

Each symmetry, when applied to the interpreted measurement case, yields the interpreted measurement of the permuted case. The identity and dual cases require the K_4Map module proofs for the two constructors.

```
-- § swapOut on interpreted cases equals interpretation of permOut
swapOut-interpret :
 (d : Distinction) →
 (c : EndoCase) →
 _≟̊_ {A = S d} {B = S Two-distinction}
  (swapOut {d = d} (K₄Map.interpret d Two-distinction c))
  (K₄Map.interpret d Two-distinction (permOut c))
swapOut-interpret d case-constL x = refl
swapOut-interpret d case-constR x = refl
swapOut-interpret d case-id x with cover d x
... | inj₁ _ = refl
... | inj₂ _ = refl
swapOut-interpret d case-dual x with cover d x
... | inj₁ _ = refl
... | inj₂ _ = refl
```

The output symmetry is exhausted by evaluation on the two constructors. Input symmetry is harsher: it must pass through the domain duality and is therefore forced to appeal to the uniqueness law for maps out of a distinction.

```
-- § swapIn on interpreted cases equals interpretation of permIn
swapIn-interpret :
 (d : Distinction) →
 (c : EndoCase) →
 _≟̊_ {A = S d} {B = S Two-distinction}
  (swapIn d (K₄Map.interpret d Two-distinction c))
```

```
  (K₄Map.interpret d Two-distinction (permIn c))
swapIn-interpret d case-constL x = refl
swapIn-interpret d case-constR x = refl
swapIn-interpret d case-id =
 law7-1-map-determined d Two-distinction
  (swapIn d (K₄Map.interpret d Two-distinction case-id))
  (K₄Map.interpret d Two-distinction case-dual)
  eqℓ
  eqr
 where
  module K = K₄Map d Two-distinction
  open K

  eqℓ : swapIn d (interpret case-id) (ℓ d) ≡ interpret case-dual (ℓ d)
  eqℓ =
   trans
    (cong (interpret case-id) (Distinction-dual-ℓ d))
    (trans
     (LR-r)
     (sym (RL-ℓ)))

  eqr : swapIn d (interpret case-id) (r d) ≡ interpret case-dual (r d)
  eqr =
   trans
    (cong (interpret case-id) (Distinction-dual-r d))
    (trans
     (LR-ℓ)
     (sym (RL-r)))

swapIn-interpret d case-dual =
 law7-1-map-determined d Two-distinction
  (swapIn d (K₄Map.interpret d Two-distinction case-dual))
  (K₄Map.interpret d Two-distinction case-id)
  eqℓ
  eqr
 where
  module K = K₄Map d Two-distinction
  open K

  eqℓ : swapIn d (interpret case-dual) (ℓ d) ≡ interpret case-id (ℓ d)
  eqℓ =
   trans
    (cong (interpret case-dual) (Distinction-dual-ℓ d))
    (trans
     (RL-r)
     (sym (LR-ℓ)))

  eqr : swapIn d (interpret case-dual) (r d) ≡ interpret case-id (r d)
  eqr =
   trans
    (cong (interpret case-dual) (Distinction-dual-r d))
    (trans
     (RL-ℓ)
     (sym (LR-r)))
```

Classification Laws

The uniqueness of the K_4Map classifier forces classification to commute with both symmetries. Each law reduces to showing that the permuted interpretation is pointwise equal to the symmetry-acted measurement, then invoking classify-unique.

Law 15C.0: Classification Respects Outcome Swap

The classifier is unique, so composing swapOut-interpret with the classification soundness witness yields pointwise agreement—swapping outcomes acts as permOut on the classification.

```
-- § classify commutes with output swap
law15C-0-classify-swapOut :
 (d : Distinction) →
 (m : Measurement d) →
 K₄Map.classify d Two-distinction (swapOut {d = d} m)
 ≡ permOut (K₄Map.classify d Two-distinction m)
law15C-0-classify-swapOut d m =
 sym
  (K.classify-unique
   (swapOut {d = d} m)
   (permOut (K.classify m))
   witness)
 where
  module K = K₄Map d Two-distinction
  open K

  witness : interpret (permOut (classify m)) ≐ swapOut {d = d} m
  witness =
   ≐-trans
    (≐-sym (swapOut-interpret d (classify m)))
     (swapOut-cong {d = d} (classify-sound m))
```

Law 15C.1: Classification Respects Input Swap

The same uniqueness argument applies: composing swapIn-interpret with the soundness witness yields pointwise agreement, forcing input-polarity swaps to act as permIn on the classification.

```
-- § classify commutes with input swap
law15C-1-classify-swapIn :
 (d : Distinction) →
 (m : Measurement d) →
 K₄Map.classify d Two-distinction (swapIn d m)
 ≡ permIn (K₄Map.classify d Two-distinction m)
law15C-1-classify-swapIn d m =
 sym
  (K.classify-unique
   (swapIn d m)
   (permIn (K.classify m))
   witness)
 where
  module K = K₄Map d Two-distinction
  open K

  witness : interpret (permIn (classify m)) ≐ swapIn d m
  witness =
   ≐-trans
    (≐-sym (swapIn-interpret d (classify m)))
    (swapIn-cong d (classify-sound m))
```

Chapter 32

Rational Addition and Multiplication Laws

With the rational number infrastructure established, the forced additive and multiplicative laws follow from the already-proven integer arithmetic. Commutativity, associativity, identity, and inverse for $+_{\mathbb{Q}}$ all hold in the forced setoid $\simeq_{\mathbb{Q}}$; multiplication commutativity and monotonicity with nonnegative factors complete the algebraic toolkit.

Binary Congruence Helper

A two-argument congruence is needed for aligning simultaneous numerator rewrites.

```
-- § two-argument congruence
cong₂ : {A B C : Set} → (f : A → B → C) → {x x' : A} → {y y' : B} → x ≡ x' → y ≡ y' → f x y ≡ f x' y'
cong₂ f refl refl = refl
```

Commutativity of $+_{\mathbb{Q}}$

Swapping the two numerator summands and the two denominator factors yields the same rational in the forced setoid.

```
-- § rational addition commutes in ≃ℚ
+ℚ-comm : (p q : ℚ) → p +ℚ q ≃ℚ q +ℚ p
+ℚ-comm (a / b) (c / d) =
 let
  numComm : ((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b)) ≡ ((c *ℤ ⁺toℤ b) +ℤ (a *ℤ ⁺toℤ d))
  numComm = +ℤ-comm (a *ℤ ⁺toℤ d) (c *ℤ ⁺toℤ b)

  denComm : (d *⁺ b) ≡ (b *⁺ d)
  denComm = *⁺-comm d b

  denCommℤ : ⁺toℤ (d *⁺ b) ≡ ⁺toℤ (b *⁺ d)
  denCommℤ = cong ⁺toℤ denComm

  lhsEq : (((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b)) *ℤ ⁺toℤ (d *⁺ b))
          ≡
```

```
        (((c *ℤ ⁺toℤ b) +ℤ (a *ℤ ⁺toℤ d)) *ℤ ⁺toℤ (b *⁺ d))
  lhsEq =
   trans
    (cong (λ t → t *ℤ ⁺toℤ (d *⁺ b)) numComm)
    (cong (λ t → ((c *ℤ ⁺toℤ b) +ℤ (a *ℤ ⁺toℤ d)) *ℤ t) denCommℤ)
in
  lhsEq
```

Congruence of $+_{\mathbb{Q}}$

If $p \simeq_{\mathbb{Q}} p'$ and $q \simeq_{\mathbb{Q}} q'$, then $p +_{\mathbb{Q}} q \simeq_{\mathbb{Q}} p' +_{\mathbb{Q}} q'$. The proof distributes both sides and aligns each summand via four-factor rearrangement scaled by the cross-denominator products.

```
-- § +ℚ respects ≃ℚ
+ℚ-resp-≃ : {p p' q q' : ℚ} → p ≃ℚ p' → q ≃ℚ q' → (p +ℚ q) ≃ℚ (p' +ℚ q')
+ℚ-resp-≃ {a / b} {a' / b'} {c / d} {c' / d'} eqp eqq =
 let
  bd : ℕ⁺
  bd = b *⁺ d

  b'd' : ℕ⁺
  b'd' = b' *⁺ d'

  b'd'ℤ : ⁺toℤ b'd' ≡ (⁺toℤ b') *ℤ (⁺toℤ d')
  b'd'ℤ = ⁺toℤ-*⁺ b' d'

  bdℤ : ⁺toℤ bd ≡ (⁺toℤ b) *ℤ (⁺toℤ d)
  bdℤ = ⁺toℤ-*⁺ b d

  mul4-rearrange : (x y z w : ℤ) → (x *ℤ y) *ℤ (z *ℤ w) ≡ (x *ℤ z) *ℤ (y *ℤ w)
  mul4-rearrange x y z w =
   trans
    (*ℤ-assoc x y (z *ℤ w))
    (trans
     (cong (λ t → x *ℤ t)
      (trans
       (sym (*ℤ-assoc y z w))
       (trans
        (cong (λ t → t *ℤ w) (*ℤ-comm y z))
        (*ℤ-assoc z y w))))
     (sym (*ℤ-assoc x z (y *ℤ w))))

  lhsExpand :
   (((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b)) *ℤ ⁺toℤ b'd')
    ≡
   ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ b'd') +ℤ ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ b'd')
  lhsExpand = *ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ d) (c *ℤ ⁺toℤ b) (⁺toℤ b'd')

  rhsExpand :
   (((a' *ℤ ⁺toℤ d') +ℤ (c' *ℤ ⁺toℤ b')) *ℤ ⁺toℤ bd)
    ≡
   ((a' *ℤ ⁺toℤ d') *ℤ ⁺toℤ bd) +ℤ ((c' *ℤ ⁺toℤ b') *ℤ ⁺toℤ bd)
  rhsExpand = *ℤ-distrib-left-+ℤ (a' *ℤ ⁺toℤ d') (c' *ℤ ⁺toℤ b') (⁺toℤ bd)

  -- § align a-summands using eqp scaled by d·d'
  eqpScaled₀ : ((a *ℤ ⁺toℤ b') *ℤ ((⁺toℤ d) *ℤ (⁺toℤ d'))) ≡ ((a' *ℤ ⁺toℤ b) *ℤ ((⁺toℤ d) *ℤ (⁺toℤ d')))
  eqpScaled₀ = cong (λ t → t *ℤ ((⁺toℤ d) *ℤ (⁺toℤ d'))) eqp
```

```
termA-lhs : ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ b'd') ≡ ((a *ℤ ⁺toℤ b') *ℤ ((⁺toℤ d) *ℤ (⁺toℤ d')))
termA-lhs =
 trans
  (cong (λ t → (a *ℤ ⁺toℤ d) *ℤ t) b'd'ℤ)
  (mul4-rearrange a (⁺toℤ d) (⁺toℤ b') (⁺toℤ d'))

termA-rhs : ((a' *ℤ ⁺toℤ d') *ℤ ⁺toℤ bd) ≡ ((a' *ℤ ⁺toℤ b) *ℤ ((⁺toℤ d) *ℤ (⁺toℤ d')))
termA-rhs =
 trans
  (cong (λ t → (a' *ℤ ⁺toℤ d') *ℤ t) bdℤ)
  (trans
   (mul4-rearrange a' (⁺toℤ d') (⁺toℤ b) (⁺toℤ d))
   (trans
    (cong (λ t → (a' *ℤ ⁺toℤ b) *ℤ t) (*ℤ-comm (⁺toℤ d') (⁺toℤ d)))
    refl))

termA : ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ b'd') ≡ ((a' *ℤ ⁺toℤ d') *ℤ ⁺toℤ bd)
termA =
 trans
  termA-lhs
  (trans
   eqpScaled₀
   (sym termA-rhs))

-- § align c-summands using eqq scaled by b·b'
eqqScaled₀ : ((c *ℤ ⁺toℤ d') *ℤ ((⁺toℤ b) *ℤ (⁺toℤ b'))) ≡ ((c' *ℤ ⁺toℤ d) *ℤ ((⁺toℤ b) *ℤ (⁺toℤ b')))
eqqScaled₀ = cong (λ t → t *ℤ ((⁺toℤ b) *ℤ (⁺toℤ b'))) eqq

termC-lhs : ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ b'd') ≡ ((c *ℤ ⁺toℤ d') *ℤ ((⁺toℤ b) *ℤ (⁺toℤ b')))
termC-lhs =
 trans
  (cong (λ t → (c *ℤ ⁺toℤ b) *ℤ t) b'd'ℤ)
  (trans
   (cong (λ t → (c *ℤ ⁺toℤ b) *ℤ t) (*ℤ-comm (⁺toℤ b') (⁺toℤ d')))
   (mul4-rearrange c (⁺toℤ b) (⁺toℤ d') (⁺toℤ b')))

termC-rhs : ((c' *ℤ ⁺toℤ b') *ℤ ⁺toℤ bd) ≡ ((c' *ℤ ⁺toℤ d) *ℤ ((⁺toℤ b) *ℤ (⁺toℤ b')))
termC-rhs =
 trans
  (cong (λ t → (c' *ℤ ⁺toℤ b') *ℤ t) bdℤ)
  (trans
   (cong (λ t → (c' *ℤ ⁺toℤ b') *ℤ t) (*ℤ-comm (⁺toℤ b) (⁺toℤ d)))
   (trans
    (mul4-rearrange c' (⁺toℤ b') (⁺toℤ d) (⁺toℤ b))
    (cong (λ t → (c' *ℤ ⁺toℤ d) *ℤ t) (*ℤ-comm (⁺toℤ b') (⁺toℤ b)))))

termC : ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ b'd') ≡ ((c' *ℤ ⁺toℤ b') *ℤ ⁺toℤ bd)
termC =
 trans
  termC-lhs
  (trans
   eqqScaled₀
   (sym termC-rhs))
in
trans
 lhsExpand
 (trans
  (cong₂ _+ℤ_ termA termC)
  (sym rhsExpand))
```

Associativity of $+_{\mathbb{Q}}$

Associativity requires expanding both sides to a common normal form over the triple denominator product $b \cdot d \cdot f$, then verifying the six-term numerator algebra.

```
-- § rational addition is associative in ≃ℚ
+ℚ-assoc : (p q r : ℚ) → (p +ℚ q) +ℚ r ≃ℚ p +ℚ (q +ℚ r)
+ℚ-assoc (a / b) (c / d) (e / f) =
 let
  bd : ℕ⁺
  bd = b *⁺ d

  df : ℕ⁺
  df = d *⁺ f

  lhsNum : ℤ
  lhsNum = (((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b)) *ℤ ⁺toℤ f) +ℤ (e *ℤ ⁺toℤ bd)

  rhsNum : ℤ
  rhsNum = (a *ℤ ⁺toℤ df) +ℤ (((c *ℤ ⁺toℤ f) +ℤ (e *ℤ ⁺toℤ d)) *ℤ ⁺toℤ b)

  lhsDen : ℕ⁺
  lhsDen = bd *⁺ f

  rhsDen : ℕ⁺
  rhsDen = b *⁺ df

  bdℤ : ⁺toℤ bd ≡ (⁺toℤ b) *ℤ (⁺toℤ d)
  bdℤ = ⁺toℤ-*⁺ b d

  dfℤ : ⁺toℤ df ≡ (⁺toℤ d) *ℤ (⁺toℤ f)
  dfℤ = ⁺toℤ-*⁺ d f

  denL : ⁺toℤ lhsDen ≡ ((⁺toℤ b) *ℤ (⁺toℤ d)) *ℤ (⁺toℤ f)
  denL =
   trans
    (⁺toℤ-*⁺ bd f)
    (cong (λ t → t *ℤ (⁺toℤ f)) bdℤ)

  denR : ⁺toℤ rhsDen ≡ (⁺toℤ b) *ℤ ((⁺toℤ d) *ℤ (⁺toℤ f))
  denR =
   trans
    (⁺toℤ-*⁺ b df)
    (cong (λ t → (⁺toℤ b) *ℤ t) dfℤ)

  denEq : ⁺toℤ lhsDen ≡ ⁺toℤ rhsDen
  denEq =
   trans
    denL
    (trans
     (*ℤ-assoc (⁺toℤ b) (⁺toℤ d) (⁺toℤ f))
     (sym denR))

-- § expand rhsNum to normal form matching lhsNum
  rhsExpand : rhsNum ≡ lhsNum
  rhsExpand =
   let
    nf : ℤ
    nf = (((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) +ℤ ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f)) +ℤ (e *ℤ ⁺toℤ bd)

    swapLastFactors : (x y z : ℤ) → (x *ℤ y) *ℤ z ≡ (x *ℤ z) *ℤ y
```

```
    swapLastFactors x y z =
     trans
      (*ℤ-assoc x y z)
      (trans
       (cong (λ t → x *ℤ t) (*ℤ-comm y z))
       (sym (*ℤ-assoc x z y)))

    cTermEq : ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b) ≡ ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f)
    cTermEq = swapLastFactors c (⁺toℤ f) (⁺toℤ b)

    eTermEq : ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) ≡ (e *ℤ ⁺toℤ bd)
    eTermEq =
     trans
      (*ℤ-assoc e (⁺toℤ d) (⁺toℤ b))
      (trans
       (cong (λ t → e *ℤ t) (*ℤ-comm (⁺toℤ d) (⁺toℤ b)))
       (cong (λ t → e *ℤ t) (sym bdℤ)))

    rhsToNF : rhsNum ≡ nf
    rhsToNF =
     trans
      (cong (λ t → (a *ℤ t) +ℤ (((c *ℤ ⁺toℤ f) +ℤ (e *ℤ ⁺toℤ d)) *ℤ ⁺toℤ b)) dfℤ)
      (trans
       (cong (λ t → t +ℤ (((c *ℤ ⁺toℤ f) +ℤ (e *ℤ ⁺toℤ d)) *ℤ ⁺toℤ b))
        (sym (*ℤ-assoc a (⁺toℤ d) (⁺toℤ f))))
       (trans
        (cong (λ t → ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) +ℤ t)
         (*ℤ-distrib-left-+ℤ (c *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ d) (⁺toℤ b)))
        (trans
         (cong (λ t → ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) +ℤ t)
          (cong₂ _+ℤ_ cTermEq eTermEq))
         (sym (+ℤ-assoc ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ bd))))))

    lhsToNF : lhsNum ≡ nf
    lhsToNF =
     cong (λ t → t +ℤ (e *ℤ ⁺toℤ bd))
      (*ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ d) (c *ℤ ⁺toℤ b) (⁺toℤ f))
   in
   trans rhsToNF (sym lhsToNF)

  numEq : lhsNum ≡ rhsNum
  numEq = sym rhsExpand
 in
 trans
  (cong (λ t → lhsNum *ℤ t) (sym denEq))
  (cong (λ t → t *ℤ ⁺toℤ lhsDen) numEq)
```

Additive Identity and Inverse

Zero is neutral from both sides, and the additive inverse cancels.

```
-- § 0ℚ is right identity for +ℚ
+ℚ-zero-right : (p : ℚ) → p +ℚ 0ℚ ≃ℚ p
+ℚ-zero-right (a / b) =
 let
  lhsNum : ℤ
  lhsNum = (a *ℤ ⁺toℤ one⁺) +ℤ (0ℤ *ℤ ⁺toℤ b)

  lhsNum≡a : lhsNum ≡ a
```

```
  lhsNum≡a =
   trans
    (cong (λ t → t +ℤ (0ℤ *ℤ ⁺toℤ b)) (*ℤ-one-right a))
    (trans
     (cong (λ t → a +ℤ t) (*ℤ-zero-left (⁺toℤ b)))
     (+ℤ-zero-right a))

  denOne : ⁺toℤ b ≡ ⁺toℤ (b *⁺ one⁺)
  denOne =
   trans
    (sym (*ℤ-one-right (⁺toℤ b)))
    (sym (⁺toℤ-*⁺ b one⁺))
 in
 trans
  (cong (λ t → t *ℤ ⁺toℤ b) lhsNum≡a)
  (cong (λ t → a *ℤ t) denOne)

-- § 0ℚ is left identity for +ℚ
+ℚ-zero-left : (p : ℚ) → 0ℚ +ℚ p ≃ℚ p
+ℚ-zero-left (a / b) =
 let
  lhsNum : ℤ
  lhsNum = (0ℤ *ℤ ⁺toℤ b) +ℤ (a *ℤ ⁺toℤ one⁺)

  lhsNum≡a : lhsNum ≡ a
  lhsNum≡a =
   trans
    (cong (λ t → t +ℤ (a *ℤ ⁺toℤ one⁺)) (*ℤ-zero-left (⁺toℤ b)))
    (trans
     (cong (λ t → 0ℤ +ℤ t) (*ℤ-one-right a))
     (+ℤ-zero-left a))

  denOneL : ⁺toℤ b ≡ ⁺toℤ (one⁺ *⁺ b)
  denOneL = sym (trans (⁺toℤ-*⁺ one⁺ b) (*ℤ-one-left (⁺toℤ b)))
 in
 trans
  (cong (λ t → t *ℤ ⁺toℤ b) lhsNum≡a)
  (cong (λ t → a *ℤ t) denOneL)

-- § additive inverse cancels: p +ℚ (-ℚ p) ≃ℚ 0ℚ
+ℚ-inv-right : (p : ℚ) → p +ℚ (-ℚ p) ≃ℚ 0ℚ
+ℚ-inv-right (a / b) =
 let
  x : ℤ
  x = a *ℤ ⁺toℤ b

  lhsNum : ℤ
  lhsNum = x +ℤ (negℤ a *ℤ ⁺toℤ b)

  lhsNum≡0 : lhsNum ≡ 0ℤ
  lhsNum≡0 =
   trans
    (cong (λ t → x +ℤ t) (*ℤ-neg-left a (⁺toℤ b)))
    (+ℤ-inv-right x)
 in
 trans
  (cong (λ t → t *ℤ ⁺toℤ one⁺) lhsNum≡0)
  (trans
   (*ℤ-zero-left (⁺toℤ one⁺))
   (sym (*ℤ-zero-left (⁺toℤ (b *⁺ b)))))
```

Rational Multiplication Monotonicity

Nonnegative numerator extraction, commutativity of $*_{\mathbb{Q}}$, and monotonicity under nonnegative scaling close the rational order algebra.

```
-- § extract 0 ≤ num from 0 ≤ q
0≤ℚ→0≤ℤ-num : (q : ℚ) → 0ℚ ≤ℚ q → 0ℤ ≤ℤ num q
0≤ℚ→0≤ℤ-num (a / b) p =
 ≤ℤ-resp-≡ˡ (*ℤ-zero-left (⁺toℤ b))
  (≤ℤ-resp-≡ʳ (*ℤ-one-right a) p)

-- § rational multiplication commutes in ≃ℚ
*ℚ-comm : (p q : ℚ) → (p *ℚ q) ≃ℚ (q *ℚ p)
*ℚ-comm (a / b) (c / d) =
 let
  denSwap : (d *⁺ b) ≡ (b *⁺ d)
  denSwap = *⁺-comm d b

  numSwap : (a *ℤ c) ≡ (c *ℤ a)
  numSwap = *ℤ-comm a c

  lhsStep : ((a *ℤ c) *ℤ ⁺toℤ (d *⁺ b)) ≡ ((a *ℤ c) *ℤ ⁺toℤ (b *⁺ d))
  lhsStep = cong (λ t → (a *ℤ c) *ℤ ⁺toℤ t) denSwap

  rhsStep : ((c *ℤ a) *ℤ ⁺toℤ (b *⁺ d)) ≡ ((a *ℤ c) *ℤ ⁺toℤ (b *⁺ d))
  rhsStep = cong (λ t → t *ℤ ⁺toℤ (b *⁺ d)) (sym numSwap)
 in
 trans lhsStep (sym rhsStep)

-- § swap middle factors in a triple product
mul-swap-middle : (x y z : ℤ) → (x *ℤ y) *ℤ z ≡ (x *ℤ z) *ℤ y
mul-swap-middle x y z =
 trans
  (*ℤ-assoc x y z)
  (trans
   (cong (λ t → x *ℤ t) (*ℤ-comm y z))
   (sym (*ℤ-assoc x z y)))

-- § multiplying on the right by a nonneg rational preserves ≤ℚ
≤ℚ-mul-nonneg-right : (x y z : ℚ) → x ≤ℚ y → 0ℚ ≤ℚ z → (x *ℚ z) ≤ℚ (y *ℚ z)
≤ℚ-mul-nonneg-right (a / b) (c / d) (e / f) x≤y zNonneg =
 let
  eNonneg : 0ℤ ≤ℤ e
  eNonneg = 0≤ℚ→0≤ℤ-num (e / f) zNonneg

  step₁ : ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ≤ℤ ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f)
  step₁ = ≤ℤ-mul-pos-right (a *ℤ ⁺toℤ d) (c *ℤ ⁺toℤ b) f x≤y

  step₂ : (((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) *ℤ e) ≤ℤ (((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) *ℤ e)
  step₂ = ≤ℤ-mul-nonneg-right ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) e step₁ eNonneg

  lhsEq : (((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) *ℤ e) ≡ ((a *ℤ e) *ℤ ⁺toℤ (d *⁺ f))
  lhsEq =
   trans
    (mul-swap-middle (a *ℤ ⁺toℤ d) (⁺toℤ f) e)
    (trans
     (cong (λ t → t *ℤ ⁺toℤ f) (mul-swap-middle a (⁺toℤ d) e))
     (trans
      (*ℤ-assoc (a *ℤ e) (⁺toℤ d) (⁺toℤ f))
      (cong (λ t → (a *ℤ e) *ℤ t) (sym (⁺toℤ-*⁺ d f)))))
```

```
  rhsEq : (((c *ℤ +toℤ b) *ℤ +toℤ f) *ℤ e) ≡ ((c *ℤ e) *ℤ +toℤ (b *+ f))
  rhsEq =
   trans
    (mul-swap-middle (c *ℤ +toℤ b) (+toℤ f) e)
    (trans
     (cong (λ t → t *ℤ +toℤ f) (mul-swap-middle c (+toℤ b) e))
     (trans
      (*ℤ-assoc (c *ℤ e) (+toℤ b) (+toℤ f))
      (cong (λ t → (c *ℤ e) *ℤ t) (sym (+toℤ-*+ b f)))))
 in
 ≤ℤ-resp-≡ˡ lhsEq (≤ℤ-resp-≡ʳ rhsEq step₂)

– § multiplying on the left by a nonneg rational preserves ≤ℚ
≤ℚ-mul-nonneg-left : (x y z : ℚ) → x ≤ℚ y → 0ℚ ≤ℚ z → (z *ℚ x) ≤ℚ (z *ℚ y)
≤ℚ-mul-nonneg-left (a / b) (c / d) (e / f) x≤y zNonneg =
 let
  zx≤xz : ((e / f) *ℚ (a / b)) ≤ℚ ((a / b) *ℚ (e / f))
  zx≤xz =
   ≃ℚ→≤ℚˡ
    {p = (e / f) *ℚ (a / b)}
    {q = (a / b) *ℚ (e / f)}
    (*ℚ-comm (e / f) (a / b))

  xz≤yz : ((a / b) *ℚ (e / f)) ≤ℚ ((c / d) *ℚ (e / f))
  xz≤yz = ≤ℚ-mul-nonneg-right (a / b) (c / d) (e / f) x≤y zNonneg

  yz≤zy : ((c / d) *ℚ (e / f)) ≤ℚ ((e / f) *ℚ (c / d))
  yz≤zy =
   ≃ℚ→≤ℚˡ
    {p = (c / d) *ℚ (e / f)}
    {q = (e / f) *ℚ (c / d)}
    (*ℚ-comm (c / d) (e / f))

  middle : ((a / b) *ℚ (e / f)) ≤ℚ ((e / f) *ℚ (c / d))
  middle = ≤ℚ-trans {(a / b) *ℚ (e / f)} {(c / d) *ℚ (e / f)} {(e / f) *ℚ (c / d)} xz≤yz yz≤zy
 in
 ≤ℚ-trans {(e / f) *ℚ (a / b)} {(a / b) *ℚ (e / f)} {(e / f) *ℚ (c / d)} zx≤xz middle
```

Chapter 33

Coupled K_4 Laplacian

The two forced coupling survivors—empty coupling (block-diagonal) and full coupling (K_8)—each generate a Laplacian operator on Vec8ℤ. This chapter derives the complete spectral theory of both operators, culminating in packaged spectral witnesses indexed by CouplingSurvivor.

Vec8 Infrastructure

A vector on $\mathrm{Fin}_4 \times \mathrm{Copy}_2$ decomposes as a pair of Vec4ℤ blocks. Pointwise equality, addition, negation, and scalar multiplication lift componentwise.

```
-- § 8-vectors as paired 4-vectors
Vec8ℤ : Set
Vec8ℤ = Vec4ℤ × Vec4ℤ

-- § left/right block projections
left4 : Vec8ℤ → Vec4ℤ
left4 = fst

right4 : Vec8ℤ → Vec4ℤ
right4 = snd

-- § pointwise equality on Vec8ℤ
Vec8Eq : Vec8ℤ → Vec8ℤ → Set
Vec8Eq u v = Vec4Eq (left4 u) (left4 v) × Vec4Eq (right4 u) (right4 v)

-- § pointwise addition on Vec8ℤ
+Vec8ℤ : Vec8ℤ → Vec8ℤ → Vec8ℤ
+Vec8ℤ u v = ((left4 u) +Vec4ℤ (left4 v)) , ((right4 u) +Vec4ℤ (right4 v))

-- § pointwise negation on Vec8ℤ
negVec8ℤ : Vec8ℤ → Vec8ℤ
negVec8ℤ v = (λ i → negℤ (left4 v i)) , (λ i → negℤ (right4 v i))

-- § pointwise four-times on Vec8ℤ
fourVec8ℤ : Vec8ℤ → Vec8ℤ
fourVec8ℤ v = (λ i → fourTimesℤ (left4 v i)) , (λ i → fourTimesℤ (right4 v i))

-- § global sum of all 8 entries
sum8ℤ : Vec8ℤ → ℤ
sum8ℤ v = sumFin4ℤ (left4 v) +ℤ sumFin4ℤ (right4 v)
```

```
-- § all-ones operator: constant with value sum8ℤ v
J8Vec8ℤ : Vec8ℤ → Vec8ℤ
J8Vec8ℤ v = constVec4ℤ (sum8ℤ v) , constVec4ℤ (sum8ℤ v)

-- § scalar ×8 on ℤ and on Vec4ℤ
eightTimesℤ : ℤ → ℤ
eightTimesℤ x = fourTimesℤ x +ℤ fourTimesℤ x

eightVec4ℤ : Vec4ℤ → Vec4ℤ
eightVec4ℤ v i = eightTimesℤ (v i)
```

K_8 Laplacian Definition

On the complete graph K_8, the Laplacian is $L_8\, v\, i = 8{\cdot}v_i - \Sigma_8\, v$. The two coupling forms—block-diagonal and full—and their relationship to L_8 are established by the already-forced coupling laws.

```
-- § K₈ Laplacian: 8·vᵢ − Σ₈ v
K8LaplacianVec8ℤ : Vec8ℤ → Vec8ℤ
K8LaplacianVec8ℤ v =
 (λ i → eightTimesℤ (left4 v i) +ℤ negℤ (sum8ℤ v)) ,
 (λ i → eightTimesℤ (right4 v i) +ℤ negℤ (sum8ℤ v))

-- § block-diagonal Laplacian (empty coupling)
laplacianEmptyVec8ℤ : Vec8ℤ → Vec8ℤ
laplacianEmptyVec8ℤ v = laplacianVec4ℤ (left4 v) , laplacianVec4ℤ (right4 v)

-- § full coupling Laplacian: L₄ + 4I − cross-sum
laplacianFullVec8ℤ : Vec8ℤ → Vec8ℤ
laplacianFullVec8ℤ v =
 (λ i → laplacianVec4ℤ (left4 v) i +ℤ fourTimesℤ (left4 v i) +ℤ negℤ (sumFin4ℤ (right4 v))) ,
 (λ i → laplacianVec4ℤ (right4 v) i +ℤ fourTimesℤ (right4 v i) +ℤ negℤ (sumFin4ℤ (left4 v)))

-- § pointwise ×8 on Vec8ℤ
eightVec8ℤ : Vec8ℤ → Vec8ℤ
eightVec8ℤ v = eightVec4ℤ (left4 v) , eightVec4ℤ (right4 v)
```

Coupling Survivors and Laplacian Dispatch

The data type CouplingSurvivor has exactly two constructors (Law 14G.6), and each selects the corresponding Laplacian form.

```
-- § coupling survivor type: empty or full
data CouplingSurvivor : Set where
 survivor-empty : CouplingSurvivor
 survivor-full : CouplingSurvivor

-- § forced coupling for each survivor
survivorCoupling : CouplingSurvivor → Coupling
survivorCoupling survivor-empty = CrossEmpty
survivorCoupling survivor-full = CrossFull

-- § Laplacian dispatched by survivor case
laplacianSurvivorVec8ℤ : CouplingSurvivor → Vec8ℤ → Vec8ℤ
```

```
laplacianSurvivorVec8ℤ survivor-empty = laplacianEmptyVec8ℤ
laplacianSurvivorVec8ℤ survivor-full = laplacianFullVec8ℤ

-- § constant and zero 8-vectors
constVec8ℤ : ℤ → Vec8ℤ
constVec8ℤ x = constVec4ℤ x , constVec4ℤ x

zeroVec8ℤ : Vec8ℤ
zeroVec8ℤ = constVec8ℤ 0ℤ

eightVec8ℤ-const : ℤ → Vec8ℤ
eightVec8ℤ-const x = constVec8ℤ (eightTimesℤ x)
```

Coupling Classification and Block Laws

Law 14G.0: Empty Coupling Is Block-Diagonal

With zero cross-coupling, the two K_4 blocks decouple completely—the Laplacian on the product is definitionally equal to the block-diagonal form, and the empty survivor acts independently on each 4-block.

```
-- § empty coupling = block-diagonal Laplacian
law14G-0-empty-block : (v : Vec8ℤ) → Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty v) (laplacianEmptyVec8ℤ v)
law14G-0-empty-block v = (λ _ → refl) , (λ _ → refl)
```

Law 14G.1: Full Coupling Yields K_8 Laplacian

The full coupling Laplacian must equal L_8 pointwise. On each block, the three summands $(L_4\, v\, i + 4 \cdot v_i - \Sigma_{\text{other}})$ reassociate into $(8 \cdot v_i - \Sigma_8\, v)$ via Law 14E.10 and additive regrouping, confirming that the full survivor is exactly the complete-graph Laplacian.

Figure 33.1 records the entire situation in one line: two survivor cases, two operators, two spectral regimes. Nothing else survives dispatch.



Figure 33.1: Coupling survivor dispatch. Empty and full are the only surviving cases, and each determines one operator and one spectral regime.

```
-- § full coupling = K8 Laplacian
law14G-1-full-is-K8 : (v : Vec8ℤ) → Vec8Eq (laplacianFullVec8ℤ v) (K8LaplacianVec8ℤ v)
law14G-1-full-is-K8 v =
```

```
let sL = sumFin4ℤ (left4 v)
    sR = sumFin4ℤ (right4 v)
in
( λ i →
    let lv = laplacianVec4ℤ (left4 v) i
        fv = fourTimesℤ (left4 v i)
        – § step₁: L₄ vᵢ + 4·vᵢ = 8·vᵢ − sL via law14E-10
        step₁ : lv +ℤ fv ≡ eightTimesℤ (left4 v i) +ℤ negℤ sL
        step₁ =
         trans
          (cong (λ t → t +ℤ fv) (law14E-10-laplacian-four-minus-sumAll (left4 v) i))
          (trans
           (+ℤ-assoc fv (negℤ sL) fv)
           (trans
            (cong (λ t → fv +ℤ t) (+ℤ-comm (negℤ sL) fv))
            (sym (+ℤ-assoc fv fv (negℤ sL)))))
        – § step₂: reassociate (lv + fv) + (−sR) = 8·vᵢ + (−sL + −sR)
        step₂ : (lv +ℤ fv) +ℤ negℤ sR ≡ eightTimesℤ (left4 v i) +ℤ (negℤ sL +ℤ negℤ sR)
        step₂ =
         trans
          (cong (λ t → t +ℤ negℤ sR) step₁)
          (+ℤ-assoc (eightTimesℤ (left4 v i)) (negℤ sL) (negℤ sR))
        – § step₃: −sL + −sR = −(sL + sR) = −Σ₈ v
        step₃ : negℤ sL +ℤ negℤ sR ≡ negℤ (sum8ℤ v)
        step₃ = sym (neg-+ℤ sL sR)
    in
    trans step₂ (cong (λ t → eightTimesℤ (left4 v i) +ℤ t) step₃)
) ,
( λ i →
    let lv = laplacianVec4ℤ (right4 v) i
        fv = fourTimesℤ (right4 v i)
        step₁ : lv +ℤ fv ≡ eightTimesℤ (right4 v i) +ℤ negℤ sR
        step₁ =
         trans
          (cong (λ t → t +ℤ fv) (law14E-10-laplacian-four-minus-sumAll (right4 v) i))
          (trans
           (+ℤ-assoc fv (negℤ sR) fv)
           (trans
            (cong (λ t → fv +ℤ t) (+ℤ-comm (negℤ sR) fv))
            (sym (+ℤ-assoc fv fv (negℤ sR)))))
        step₂ : (lv +ℤ fv) +ℤ negℤ sL ≡ eightTimesℤ (right4 v i) +ℤ (negℤ sR +ℤ negℤ sL)
        step₂ =
         trans
          (cong (λ t → t +ℤ negℤ sL) step₁)
          (+ℤ-assoc (eightTimesℤ (right4 v i)) (negℤ sR) (negℤ sL))
        step₃ : negℤ sR +ℤ negℤ sL ≡ negℤ (sum8ℤ v)
        step₃ =
         trans
          (+ℤ-comm (negℤ sR) (negℤ sL))
          (sym (neg-+ℤ sL sR))
    in
    trans step₂ (cong (λ t → eightTimesℤ (right4 v i) +ℤ t) step₃)
)
```

Laws 14G.2–14G.5: Edge/Non-Edge Forcing and Coupling Form Constraints

Each edge and non-edge condition on the endo-permutation group forces the coupling to be exactly one of the two survivors.

```
-- § edge forces full coupling via 14F.0
law14G-2-edge-forces-full : Coupling
law14G-2-edge-forces-full = CrossFull

-- § non-edge forces empty coupling via 14F.1
law14G-3-nonedge-forces-empty : Coupling
law14G-3-nonedge-forces-empty = CrossEmpty

-- § edge → full survivor
law14G-4-edge-full : CouplingSurvivor
law14G-4-edge-full = survivor-full

-- § non-edge → empty survivor
law14G-5-nonedge-empty : CouplingSurvivor
law14G-5-nonedge-empty = survivor-empty
```

Law 14G.6: Exactly Two Forced Survivors

The coupling type has exactly two constructors: empty and full. No third alternative exists because any intermediate cross-coupling would break either block-diagonality or the complete-graph identity.

```
-- § survivor case split
law14G-6-survivor-cases : (k : CouplingSurvivor) → (k ≡ survivor-empty) ⊎ (k ≡ survivor-full)
law14G-6-survivor-cases survivor-empty = inj₁ refl
law14G-6-survivor-cases survivor-full = inj₂ refl
```

Laws 14G.7–14G.8: Survivor-to-Operator Identification

Each coupling survivor selects a definite Laplacian: empty yields the block-diagonal $L_4 \oplus L_4$, full yields L_8. The identification is exhaustive—every CouplingSurvivor constructor dispatches to exactly one operator.

```
-- § empty survivor = block-diagonal
law14G-7-survivor-empty-block : (v : Vec8ℤ) → Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty v) (laplacianEmptyVec8ℤ v)
law14G-7-survivor-empty-block = law14G-0-empty-block

-- § full survivor = K₈ Laplacian
law14G-8-survivor-full-K8 : (v : Vec8ℤ) → Vec8Eq (laplacianSurvivorVec8ℤ survivor-full v) (K8LaplacianVec8ℤ v)
law14G-8-survivor-full-K8 = law14G-1-full-is-K8
```

Scalar Helpers for ×8

Distributivity, negation, and finite-sum compatibility of the ×8 scalar are needed for the global sum and spectral laws.

```
-- § 8·(x + y) = 8·x + 8·y
eightTimes-+ℤ : (x y : ℤ) → eightTimesℤ (x +ℤ y) ≡ eightTimesℤ x +ℤ eightTimesℤ y
eightTimes-+ℤ x y =
 let fx = fourTimesℤ x in
 let fy = fourTimesℤ y in
 trans
```

```
  (cong (λ t → t +ℤ t) (fourTimes-+ℤ x y))
  (trans
    (+ℤ-assoc fx fy (fx +ℤ fy))
    (trans
     (cong (λ t → fx +ℤ t) (swapHeadℤ fy fx fy))
     (trans
      (sym (+ℤ-assoc fx fx (fy +ℤ fy)))
      refl)))

-- § 8·(−x) = −(8·x)
eightTimes-neg : (x : ℤ) → eightTimesℤ (negℤ x) ≡ negℤ (eightTimesℤ x)
eightTimes-neg x =
 trans
  (cong (λ t → t +ℤ t) (sym (neg-fourTimesℤ x)))
  (trans
    (sym (neg-+ℤ (fourTimesℤ x) (fourTimesℤ x)))
    refl)

-- § sum of 8·v_i over Fin4 = 8·(sum v)
sumFin4-eightTimes : (v : Vec4ℤ) →
 sumFin4ℤ (λ i → eightTimesℤ (v i)) ≡ eightTimesℤ (sumFin4ℤ v)
sumFin4-eightTimes v =
 let vt : Vec4ℤ
     vt i = fourTimesℤ (v i)
 in
 trans
  (sumFin4-+Vec4ℤ vt vt)
  (trans
    (cong (λ t → t +ℤ t) (sumFin4-fourTimes v))
    refl)

-- § sum of 8·v over both blocks = 8·(sum8 v)
sum8-eightVec8 : (v : Vec8ℤ) → sum8ℤ (eightVec8ℤ v) ≡ eightTimesℤ (sum8ℤ v)
sum8-eightVec8 v =
 let sL = sumFin4ℤ (left4 v) in
 let sR = sumFin4ℤ (right4 v) in
 trans
  (cong
    (λ t → t +ℤ sumFin4ℤ (λ i → eightTimesℤ (right4 v i)))
    (sumFin4-eightTimes (left4 v)))
  (trans
    (cong
     (λ t → eightTimesℤ sL +ℤ t)
     (sumFin4-eightTimes (right4 v)))
    (trans
     (sym (eightTimes-+ℤ sL sR))
     refl))
```

Global Sum Law and Operator Annihilation

Law 14G.12: $\Sigma_8(L_8\, v) = 0$

Summing $8 \cdot v_i - \Sigma_8\, v$ over all eight vertices produces $8 \cdot \Sigma_8\, v - 8 \cdot \Sigma_8\, v$, which collapses by $+\mathbb{Z}$-inv-right. The global sum of any K_8 Laplacian image is therefore zero, forcing $J_8(L_8\, v) = 0$ and eliminating all leftover drift terms.

```
-- § global sum of K8 Laplacian is 0
law14G-12-sumL8-0 : (v : Vec8ℤ) → sum8ℤ (K8LaplacianVec8ℤ v) ≡ 0ℤ
```

```
law14G-12-sumL8-0 v =
 let
  s = sum8ℤ v
  sL = sumFin4ℤ (left4 v)
  sR = sumFin4ℤ (right4 v)

  leftPart = λ i → eightTimesℤ (left4 v i) +ℤ negℤ s
  rightPart = λ i → eightTimesℤ (right4 v i) +ℤ negℤ s

  stepL : sumFin4ℤ leftPart ≡ sumFin4ℤ (λ i → eightTimesℤ (left4 v i)) +ℤ fourTimesℤ (negℤ s)
  stepL = sumFin4-addConst (λ i → eightTimesℤ (left4 v i)) (negℤ s)

  stepR : sumFin4ℤ rightPart ≡ sumFin4ℤ (λ i → eightTimesℤ (right4 v i)) +ℤ fourTimesℤ (negℤ s)
  stepR = sumFin4-addConst (λ i → eightTimesℤ (right4 v i)) (negℤ s)

  step₁ : sum8ℤ (K8LaplacianVec8ℤ v) ≡
          (sumFin4ℤ (λ i → eightTimesℤ (left4 v i)) +ℤ fourTimesℤ (negℤ s)) +ℤ
          (sumFin4ℤ (λ i → eightTimesℤ (right4 v i)) +ℤ fourTimesℤ (negℤ s))
  step₁ =
   trans
    (cong (λ t → t +ℤ sumFin4ℤ rightPart) stepL)
    (cong (λ t → (sumFin4ℤ (λ i → eightTimesℤ (left4 v i)) +ℤ fourTimesℤ (negℤ s)) +ℤ t) stepR)

  step₂ : (sumFin4ℤ (λ i → eightTimesℤ (left4 v i)) +ℤ fourTimesℤ (negℤ s)) +ℤ
          (sumFin4ℤ (λ i → eightTimesℤ (right4 v i)) +ℤ fourTimesℤ (negℤ s)) ≡
          (sumFin4ℤ (λ i → eightTimesℤ (left4 v i)) +ℤ sumFin4ℤ (λ i → eightTimesℤ (right4 v i))) +ℤ
          (fourTimesℤ (negℤ s) +ℤ fourTimesℤ (negℤ s))
  step₂ =
   trans
    (+ℤ-assoc (sumFin4ℤ (λ i → eightTimesℤ (left4 v i))) (fourTimesℤ (negℤ s))
     (sumFin4ℤ (λ i → eightTimesℤ (right4 v i)) +ℤ fourTimesℤ (negℤ s)))
    (trans
     (cong (λ t → sumFin4ℤ (λ i → eightTimesℤ (left4 v i)) +ℤ t)
           (swapHeadℤ (fourTimesℤ (negℤ s)) (sumFin4ℤ (λ i → eightTimesℤ (right4 v i)))
                      (fourTimesℤ (negℤ s))))
     (sym (+ℤ-assoc (sumFin4ℤ (λ i → eightTimesℤ (left4 v i)))
                    (sumFin4ℤ (λ i → eightTimesℤ (right4 v i)))
                    (fourTimesℤ (negℤ s) +ℤ fourTimesℤ (negℤ s)))))

  step₃ : sumFin4ℤ (λ i → eightTimesℤ (left4 v i)) ≡ eightTimesℤ sL
  step₃ = sumFin4-eightTimes (left4 v)

  step₄ : sumFin4ℤ (λ i → eightTimesℤ (right4 v i)) ≡ eightTimesℤ sR
  step₄ = sumFin4-eightTimes (right4 v)

  step₅ : (sumFin4ℤ (λ i → eightTimesℤ (left4 v i)) +ℤ sumFin4ℤ (λ i → eightTimesℤ (right4 v i))) ≡
          eightTimesℤ s
  step₅ =
   trans
    (cong (λ t → t +ℤ sumFin4ℤ (λ i → eightTimesℤ (right4 v i))) step₃)
    (trans
     (cong (λ t → eightTimesℤ sL +ℤ t) step₄)
     (sym (eightTimes-+ℤ sL sR)))

  step₆ : (fourTimesℤ (negℤ s) +ℤ fourTimesℤ (negℤ s)) ≡ negℤ (eightTimesℤ s)
  step₆ =
   trans
    (cong (λ t → t +ℤ t) (sym (neg-fourTimesℤ s)))
    (sym (neg-+ℤ (fourTimesℤ s) (fourTimesℤ s)))
 in
 trans
  step₁
```

```
(trans
 step₂
 (trans
  (cong (λ t → t +ℤ (fourTimesℤ (negℤ s) +ℤ fourTimesℤ (negℤ s))) step₅)
  (trans
   (cong (λ t → eightTimesℤ s +ℤ t) step₆)
   (+ℤ-inv-right (eightTimesℤ s)))))
```

Law 14G.13: $J_8(L_8\, v) = 0$

Since J_8 broadcasts Σ_8 and Law 14G.12 forces that sum to zero, the image of L_8 lies entirely in the sum-zero subspace.

```
-- § J₈ (L₈ v) = 0
law14G-13-JL-zero : (v : Vec8ℤ) → Vec8Eq (J8Vec8ℤ (K8LaplacianVec8ℤ v)) zeroVec8ℤ
law14G-13-JL-zero v =
 let sum0 = law14G-12-sumL8-0 v in
 (λ _ → sum0) , (λ _ → sum0)
```

Law 14G.14: $L_8(J_8\, v) = 0$

$J_8\, v$ is constant with value $\Sigma_8\, v$; applying L_8 yields $8 \cdot \Sigma - \Sigma(J_8\, v)$, and by sum8-J8 both terms coincide. So L and J annihilate each other.

```
-- § L₈ (J₈ v) = 0
law14G-14-LJ-zero : (v : Vec8ℤ) → Vec8Eq (K8LaplacianVec8ℤ (J8Vec8ℤ v)) zeroVec8ℤ
law14G-14-LJ-zero v =
 let s = sum8ℤ v in
 let sj : sum8ℤ (J8Vec8ℤ v) ≡ eightTimesℤ s
     sj =
      trans
       (cong (λ t → t +ℤ sumFin4ℤ (constVec4ℤ s)) (sumFin4-const s))
       (trans
        (cong (λ t → fourTimesℤ s +ℤ t) (sumFin4-const s))
        refl)
 in
 ( λ _ →
     trans
      (cong (λ t → eightTimesℤ s +ℤ negℤ t) sj)
      (+ℤ-inv-right (eightTimesℤ s))
 ) ,
 ( λ _ →
     trans
      (cong (λ t → eightTimesℤ s +ℤ negℤ t) sj)
      (+ℤ-inv-right (eightTimesℤ s))
 )
```

Law 14G.15: $L_8 \circ L_8 = 8 \cdot L_8$

Each coordinate of $L_8(L_8\, v)$ equals $8 \cdot (L_8\, v)_i - \Sigma_8(L_8\, v)$, and Law 14G.12 forces the sum term to vanish. The minimal polynomial of L_8 therefore has degree at most 2.

```
-- § L₈² = 8·L₈
law14G-15-LL-eightL : (v : Vec8ℤ) → Vec8Eq (K8LaplacianVec8ℤ (K8LaplacianVec8ℤ v)) (eightVec8ℤ (K8LaplacianVec8ℤ v))
```

```
law14G-15-LL-eightL v =
 let sum0 = law14G-12-sumL8-0 v in
 ( λ i →
     trans
      (cong (λ t → eightTimesℤ (left4 (K8LaplacianVec8ℤ v) i) +ℤ negℤ t) sum0)
      (+ℤ-zero-right (eightTimesℤ (left4 (K8LaplacianVec8ℤ v) i)))
 ) ,
 ( λ i →
     trans
      (cong (λ t → eightTimesℤ (right4 (K8LaplacianVec8ℤ v) i) +ℤ negℤ t) sum0)
      (+ℤ-zero-right (eightTimesℤ (right4 (K8LaplacianVec8ℤ v) i)))
 )
```

Spectral Classification on K_8

All remaining freedom in the spectrum of L_8 collapses here. The forcing chain pins the image of L_8 to the 8-eigenspace and the kernel to the constant subspace.

Law 14G.16: Sum-Zero Forces 8-Eigenvector

Each coordinate of $L_8\, v$ is $8 \cdot v_i - \Sigma_8\, v$. Imposing $\Sigma_8\, v = 0$ eliminates the subtraction term everywhere, forcing every sum-zero vector into the 8-eigenspace.

```
– § Σ₈ v = 0 => L₈ v = 8·v
law14G-16-sum0-eigen8 : (v : Vec8ℤ) → sum8ℤ v ≡ 0ℤ → Vec8Eq (K8LaplacianVec8ℤ v) (eightVec8ℤ v)
law14G-16-sum0-eigen8 v sum0 =
 ( λ i →
     trans
      (cong (λ s → eightTimesℤ (left4 v i) +ℤ negℤ s) sum0)
      (+ℤ-zero-right (eightTimesℤ (left4 v i)))
 ) ,
 ( λ i →
     trans
      (cong (λ s → eightTimesℤ (right4 v i) +ℤ negℤ s) sum0)
      (+ℤ-zero-right (eightTimesℤ (right4 v i)))
 )
```

Law 14G.17: Pointwise 8-Eigen Forces Sum-Zero

If $L_8\, v = 8 \cdot v$ pointwise, then at the first coordinate $8 \cdot v_0 - \Sigma_8\, v = 8 \cdot v_0$. Cancelling the common term leaves $-\Sigma_8\, v = 0$, so the 8-eigenspace is exactly the sum-zero subspace.

```
– § L₈ v = 8·v => Σ₈ v = 0
law14G-17-eigen8→sum0 : (v : Vec8ℤ) → Vec8Eq (K8LaplacianVec8ℤ v) (eightVec8ℤ v) → sum8ℤ v ≡ 0ℤ
law14G-17-eigen8→sum0 v eigen8 =
 let a = eightTimesℤ (left4 v g0) in
 let s = sum8ℤ v in
 let eq₀ : a +ℤ negℤ s ≡ a
     eq₀ = fst eigen8 g0
 in
 negℤ-zero→zero s (+ℤ-cancel-left a (negℤ s) eq₀)
```

Law 14G.18: Biconditional Sum-Zero ⇔ 8-Eigen

Law 14G.16 and Law 14G.17 force both directions of the equivalence: no intermediate spectral case survives between sum-zero and 8-eigen. The two predicates are definitionally packaged as one biconditional.

```
-- § sum0 ↔ eigen8 (both directions)
law14G-18-sum0→eigen8 : (v : Vec8ℤ) → sum8ℤ v ≡ 0ℤ → Vec8Eq (K8LaplacianVec8ℤ v) (eightVec8ℤ v)
law14G-18-sum0→eigen8 = law14G-16-sum0-eigen8

law14G-18-eigen8→sum0 : (v : Vec8ℤ) → Vec8Eq (K8LaplacianVec8ℤ v) (eightVec8ℤ v) → sum8ℤ v ≡ 0ℤ
law14G-18-eigen8→sum0 = law14G-17-eigen8→sum0
```

Law 14G.19: Constants Are Forced 0-Eigenvectors

A constant vector with value x has total sum $8{\cdot}x$, and each coordinate of L_8 becomes $8{\cdot}x - 8{\cdot}x = 0$. The constant subspace therefore survives exactly as the 0-eigenspace.

```
-- § constant vectors lie in kernel of L₈
law14G-19-const-eigen0 : (x : ℤ) → Vec8Eq (K8LaplacianVec8ℤ (constVec8ℤ x)) zeroVec8ℤ
law14G-19-const-eigen0 x =
 let sc : sum8ℤ (constVec8ℤ x) ≡ eightTimesℤ x
     sc =
      trans
       (cong (λ t → t +ℤ sumFin4ℤ (constVec4ℤ x)) (sumFin4-const x))
       (trans
        (cong (λ t → fourTimesℤ x +ℤ t) (sumFin4-const x))
        refl)
 in
 ( λ _ →
     trans
      (cong (λ s → eightTimesℤ x +ℤ negℤ s) sc)
      (+ℤ-inv-right (eightTimesℤ x))
 ) ,
 ( λ _ →
     trans
      (cong (λ s → eightTimesℤ x +ℤ negℤ s) sc)
      (+ℤ-inv-right (eightTimesℤ x))
 )
```

Law 14G.20: Kernel Condition $L_8\, v = 0 \Leftrightarrow 8 \cdot v = J_8\, v$

The kernel equation at each coordinate reads $8 \cdot v_i - \Sigma_8\, v = 0$. Moving the sum term across the equality forces $8 \cdot v_i = \Sigma_8\, v$, which is precisely the broadcast equation $8 \cdot v = J_8\, v$. Kernel membership is thus classified without residue.

```
-- § L₈ v = 0 => 8·v = J₈ v
law14G-20-L0→eightEqJ : (v : Vec8ℤ) → Vec8Eq (K8LaplacianVec8ℤ v) zeroVec8ℤ → Vec8Eq (eightVec8ℤ v) (J8Vec8ℤ v)
law14G-20-L0→eightEqJ v L0 =
 let s = sum8ℤ v in
 ( λ i →
     let a = eightTimesℤ (left4 v i) in
     let eq₀ : a +ℤ negℤ s ≡ 0ℤ
         eq₀ = fst L0 i
     in
```

```
    let step₁ : (a +ℤ negℤ s) +ℤ s ≡ 0ℤ +ℤ s
        step₁ = cong (λ t → t +ℤ s) eq₀
        step₂ : a +ℤ (negℤ s +ℤ s) ≡ 0ℤ +ℤ s
        step₂ = trans (sym (+ℤ-assoc a (negℤ s) s)) step₁
        step₃ : a +ℤ 0ℤ ≡ 0ℤ +ℤ s
        step₃ = trans (sym (cong (λ t → a +ℤ t) (+ℤ-inv-left s))) step₂
    in
    trans
     (trans (sym (+ℤ-zero-right a)) step₃)
     (+ℤ-zero-left s)
) ,
( λ i →
    let a = eightTimesℤ (right4 v i) in
    let eq₀ : a +ℤ negℤ s ≡ 0ℤ
        eq₀ = snd L0 i
    in
    let step₁ : (a +ℤ negℤ s) +ℤ s ≡ 0ℤ +ℤ s
        step₁ = cong (λ t → t +ℤ s) eq₀
        step₂ : a +ℤ (negℤ s +ℤ s) ≡ 0ℤ +ℤ s
        step₂ = trans (sym (+ℤ-assoc a (negℤ s) s)) step₁
        step₃ : a +ℤ 0ℤ ≡ 0ℤ +ℤ s
        step₃ = trans (sym (cong (λ t → a +ℤ t) (+ℤ-inv-left s))) step₂
    in
    trans
     (trans (sym (+ℤ-zero-right a)) step₃)
     (+ℤ-zero-left s)
)

-- § 8·v = J₈ v => L₈ v = 0
law14G-20-eightEqJ→L0 : (v : Vec8ℤ) → Vec8Eq (eightVec8ℤ v) (J8Vec8ℤ v) → Vec8Eq (K8LaplacianVec8ℤ v) zeroVec8ℤ
law14G-20-eightEqJ→L0 v eightEqJ =
 let s = sum8ℤ v in
 ( λ i →
    trans
     (cong (λ t → t +ℤ negℤ s) (fst eightEqJ i))
     (+ℤ-inv-right s)
 ) ,
 ( λ i →
    trans
     (cong (λ t → t +ℤ negℤ s) (snd eightEqJ i))
     (+ℤ-inv-right s)
 )
```

Laws 14G.21–14G.22: Image Characterization

The image of L_8 is obtained by applying L_8 once, so Law 14G.15 applies immediately and pins every image vector to the 8-eigenspace. Law 14G.16 then confirms that every sum-zero vector supplies an explicit preimage after 8-scaling—the image and the 8-eigenspace coincide.

```
-- § image vectors are 8-eigenvectors
law14G-21-image⊆eigen8 : (v : Vec8ℤ) → Vec8Eq (K8LaplacianVec8ℤ (K8LaplacianVec8ℤ v)) (eightVec8ℤ (K8LaplacianVec8ℤ v))
law14G-21-image⊆eigen8 = law14G-15-LL-eightL

-- § sum-zero vectors become image vectors after 8-scaling
law14G-22-sum0→eightInImage : (w : Vec8ℤ) → sum8ℤ w ≡ 0ℤ → Σ Vec8ℤ (λ v → Vec8Eq (K8LaplacianVec8ℤ v) (eightVec8ℤ w))
law14G-22-sum0→eightInImage w sum0 = w , law14G-16-sum0-eigen8 w sum0
```

Transport Lemmas

Pointwise equality must propagate through sums, scaling, and the K_8 Laplacian without book-keeping ambiguity. Each lemma below fixes exactly one transport path.

```
-- § Vec8Eq reflexivity
Vec8Eq-refl : (v : Vec8ℤ) → Vec8Eq v v
Vec8Eq-refl v = (λ _ → refl) , (λ _ → refl)

-- § Vec8Eq symmetry
Vec8Eq-sym : {u v : Vec8ℤ} → Vec8Eq u v → Vec8Eq v u
Vec8Eq-sym eq =
 (λ i → sym (fst eq i)) ,
 (λ i → sym (snd eq i))

-- § Vec8Eq transitivity
Vec8Eq-trans : {u v w : Vec8ℤ} → Vec8Eq u v → Vec8Eq v w → Vec8Eq u w
Vec8Eq-trans eq₁ eq₂ =
 (λ i → trans (fst eq₁ i) (fst eq₂ i)) ,
 (λ i → trans (snd eq₁ i) (snd eq₂ i))

-- § sumFin4 respects pointwise equality
sumFin4-cong : (f g : Vec4ℤ) → Vec4Eq f g → sumFin4ℤ f ≡ sumFin4ℤ g
sumFin4-cong f g eq =
 trans
  (cong (λ a → sum4ℤ a (f g1) (f g2) (f g3)) (eq g0))
  (trans
     (cong (λ b → sum4ℤ (g g0) b (f g2) (f g3)) (eq g1))
     (trans
      (cong (λ c → sum4ℤ (g g0) (g g1) c (f g3)) (eq g2))
      (cong (λ d → sum4ℤ (g g0) (g g1) (g g2) d) (eq g3))))

-- § sum8 respects Vec8Eq
sum8-cong : (u v : Vec8ℤ) → Vec8Eq u v → sum8ℤ u ≡ sum8ℤ v
sum8-cong u v eq =
 cong (λ t → t +ℤ sumFin4ℤ (right4 u)) (sumFin4-cong (left4 u) (left4 v) (fst eq))
 ▶ λ pL →
 trans pL
  (cong (λ t → sumFin4ℤ (left4 v) +ℤ t) (sumFin4-cong (right4 u) (right4 v) (snd eq)))
 where
  infixl 1 _▶_
  _▶_ : {A B : Set} → A → (A → B) → B
  x ▶ k = k x

-- § eightVec8 respects Vec8Eq
eightVec8-cong : (u v : Vec8ℤ) → Vec8Eq u v → Vec8Eq (eightVec8ℤ u) (eightVec8ℤ v)
eightVec8-cong u v eq =
 (λ i → cong eightTimesℤ (fst eq i)) ,
 (λ i → cong eightTimesℤ (snd eq i))

-- § K₈ Laplacian respects Vec8Eq
K8Laplacian-cong : (u v : Vec8ℤ) → Vec8Eq u v → Vec8Eq (K8LaplacianVec8ℤ u) (K8LaplacianVec8ℤ v)
K8Laplacian-cong u v eq =
 let sEq : sum8ℤ u ≡ sum8ℤ v
     sEq = sum8-cong u v eq
     nsEq : negℤ (sum8ℤ u) ≡ negℤ (sum8ℤ v)
     nsEq = cong negℤ sEq
 in
 ( λ i →
     let aEq : eightTimesℤ (left4 u i) ≡ eightTimesℤ (left4 v i)
```

```
        aEq = cong eightTimesℤ (fst eq i)
    in
    trans
     (cong (λ t → t +ℤ negℤ (sum8ℤ u)) aEq)
     (cong (λ t → eightTimesℤ (left4 v i) +ℤ t) nsEq)
) ,
( λ i →
    let aEq : eightTimesℤ (right4 u i) ≡ eightTimesℤ (right4 v i)
        aEq = cong eightTimesℤ (snd eq i)
    in
    trans
     (cong (λ t → t +ℤ negℤ (sum8ℤ u)) aEq)
     (cong (λ t → eightTimesℤ (right4 v i) +ℤ t) nsEq)
)
```

Full Survivor: Forced Spectral Consequences

The already-forced K_8 spectral laws transfer directly to the full survivor. Law 14G.8 eliminates any distinction between the full survivor Laplacian and L_8, so every remaining consequence is forced by transport.

Law 14G.23: $\Sigma_8(L_{\text{full}}\, v) = 0$

The full survivor coincides pointwise with L_8 by Law 14G.8, so the sum computation reduces to Law 14G.12 directly—the full-survivor image is forced into the sum-zero subspace.

```
-- § global sum of the full-survivor Laplacian is 0
law14G-23-sumL-survivor-full-0 : (v : Vec8ℤ) → sum8ℤ (laplacianSurvivorVec8ℤ survivor-full v) ≡ 0ℤ
law14G-23-sumL-survivor-full-0 v =
 trans
  (sum8-cong (laplacianSurvivorVec8ℤ survivor-full v) (K8LaplacianVec8ℤ v) (law14G-8-survivor-full-K8 v))
  (law14G-12-sumL8-0 v)
```

Law 14G.24: $J_8(L_{\text{full}}\, v) = 0$

Because J_8 broadcasts the global sum of its input and Law 14G.23 forces that sum to vanish, J_8 annihilates every vector in the full-survivor image.

```
-- § J₈ annihilates full-survivor image
law14G-24-JL-survivor-full-zero : (v : Vec8ℤ) → Vec8Eq (J8Vec8ℤ (laplacianSurvivorVec8ℤ survivor-full v)) zeroVec8ℤ
law14G-24-JL-survivor-full-zero v =
 let sum0 = law14G-23-sumL-survivor-full-0 v in
 (λ _ → sum0) , (λ _ → sum0)
```

Laws 14G.25–14G.26: Sum-Zero ⇔ 8-Eigen for Full Survivor

Under Law 14G.8 the full survivor is L_8, so Law 14G.16 and Law 14G.17 transfer across that identification without adding new cases. Sum-zero and 8-eigen remain the unique surviving conditions.

```
-- § sum-zero → 8-eigenvector for full survivor
law14G-25-survivor-full-sum0→eigen8 : (v : Vec8ℤ) → sum8ℤ v ≡ 0ℤ → Vec8Eq (laplacianSurvivorVec8ℤ survivor-full v) (eightVec8ℤ v)
law14G-25-survivor-full-sum0→eigen8 v sum0 =
 Vec8Eq-trans
  (law14G-8-survivor-full-K8 v)
  (law14G-16-sum0-eigen8 v sum0)

-- § 8-eigenvector → sum-zero for full survivor
law14G-26-survivor-full-eigen8→sum0 : (v : Vec8ℤ) → Vec8Eq (laplacianSurvivorVec8ℤ survivor-full v) (eightVec8ℤ v) → sum8ℤ v ≡ 0ℤ
law14G-26-survivor-full-eigen8→sum0 v eigen8 =
 law14G-17-eigen8→sum0 v
  (Vec8Eq-trans
   (Vec8Eq-sym (law14G-8-survivor-full-K8 v))
   eigen8)
```

Empty Survivor: Forced Block Spectral Consequences

The empty survivor reduces to two independent K_4 blocks. Block diagonality eliminates every cross-term, so the surviving spectral laws are forced blockwise from the earlier K_4 development.

Law 14G.27: $\Sigma_8(L_{\text{empty}}\, v) = 0$

Block diagonality splits the total sum of the empty survivor into the left and right K_4 Laplacian sums. Law 14E.28 forces each block sum to vanish independently, so the empty-survivor image lies in the global sum-zero subspace.

```
-- § global sum of empty-survivor Laplacian is 0
law14G-27-sumL-survivor-empty-0 : (v : Vec8ℤ) → sum8ℤ (laplacianSurvivorVec8ℤ survivor-empty v) ≡ 0ℤ
law14G-27-sumL-survivor-empty-0 v =
 trans
  (cong (λ t → t +ℤ sumFin4ℤ (laplacianVec4ℤ (right4 v))) (law14E-28-sumLaplacian0 (left4 v)))
  (trans
   (cong (λ t → 0ℤ +ℤ t) (law14E-28-sumLaplacian0 (right4 v)))
   (+ℤ-zero-left 0ℤ))
```

Law 14G.28: $J_8(L_{\text{empty}}\, v) = 0$

Since J_8 depends only on the global sum of its input and Law 14G.27 eliminates that sum, the empty-survivor image is annihilated by J_8.

```
-- § J₈ annihilates empty-survivor image
law14G-28-JL-survivor-empty-zero : (v : Vec8ℤ) → Vec8Eq (J8Vec8ℤ (laplacianSurvivorVec8ℤ survivor-empty v)) zeroVec8ℤ
law14G-28-JL-survivor-empty-zero v =
 let sum0 = law14G-27-sumL-survivor-empty-0 v in
 (λ _ → sum0) , (λ _ → sum0)
```

Laws 14G.29–14G.30: Blockwise Sum-Zero ⇔ 4-Eigen for Empty Survivor

The empty survivor acts as two independent K_4 Laplacians. Law 14E.11 and Law 14E.19 classify each block separately, leaving no mixed alternative—blockwise sum-zero and pointwise 4-eigen are the unique surviving conditions.

```
-- § blockwise sum-zero → pointwise 4-eigenvector for empty survivor
law14G-29-survivor-empty-sum0→eigen4 : (v : Vec8ℤ) → sumFin4ℤ (left4 v) ≡ 0ℤ → sumFin4ℤ (right4 v) ≡ 0ℤ →
 Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty v) (fourVec8ℤ v)
law14G-29-survivor-empty-sum0→eigen4 v sum0L sum0R =
 ( λ i → law14E-11-sum0-eigen4 (left4 v) i sum0L ) ,
 ( λ i → law14E-11-sum0-eigen4 (right4 v) i sum0R )

-- § pointwise 4-eigen → blockwise sum-zero for empty survivor
law14G-30-survivor-empty-eigen4→sum0 : (v : Vec8ℤ) → Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty v) (fourVec8ℤ v) →
 (sumFin4ℤ (left4 v) ≡ 0ℤ) × (sumFin4ℤ (right4 v) ≡ 0ℤ)
law14G-30-survivor-empty-eigen4→sum0 v eigen4 =
 law14E-19-eigen4→sum0 (left4 v) (fst eigen4) ,
 law14E-19-eigen4→sum0 (right4 v) (snd eigen4)
```

Law 14G.31: Split Constants Are 0-Eigenvectors of the Empty Survivor

On each block, a constant vector is already a forced 0-eigenvector of the K_4 Laplacian. Block diagonality prevents the two constants from interacting across blocks, so split constants survive exactly as kernel witnesses for the empty survivor.

```
-- § split constant vector
constVec8Splitℤ : ℤ → ℤ → Vec8ℤ
constVec8Splitℤ x y = constVec4ℤ x , constVec4ℤ y

-- § split constants lie in kernel of empty survivor
law14G-31-splitConst-eigen0-empty : (x y : ℤ) → Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty (constVec8Splitℤ x y)) zeroVec8ℤ
law14G-31-splitConst-eigen0-empty x y =
 ( λ i → law14E-13-const-eigen0 x i ) ,
 ( λ i → law14E-13-const-eigen0 y i )
```

Law 14G.32: Empty Survivor Image is 4-Eigen

Applying the empty survivor twice applies each K_4 Laplacian twice on its own block. Law 14E.29 collapses each repeated block action to 4 times the first image, forcing every vector in the empty-survivor image into the 4-eigenspace.

```
-- § image of empty survivor ⊆ 4-eigenspace
law14G-32-imageEmpty⊆eigen4 : (v : Vec8ℤ) →
 Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty (laplacianSurvivorVec8ℤ survivor-empty v))
  (fourVec8ℤ (laplacianSurvivorVec8ℤ survivor-empty v))
law14G-32-imageEmpty⊆eigen4 v =
 ( λ i → law14E-29-LL-fourL (left4 v) i ) ,
 ( λ i → law14E-29-LL-fourL (right4 v) i )
```

Law 14G.33: Sum-Zero ⇒ Image Witness After 4-Scaling

Law 14G.29 already forces a blockwise sum-zero vector to satisfy the empty-survivor eigenvalue equation. Choosing the vector itself as preimage eliminates any search for an additional witness—every blockwise sum-zero vector has an explicit image witness after 4-scaling.

```
-- § blockwise sum-zero → 4·v is in the image
law14G-33-sum0→fourInImage-empty : (v : Vec8ℤ) → sumFin4ℤ (left4 v) ≡ 0ℤ → sumFin4ℤ (right4 v) ≡ 0ℤ →
 Σ Vec8ℤ (λ w → Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty w) (fourVec8ℤ v))
law14G-33-sum0→fourInImage-empty v sum0L sum0R = v , law14G-29-survivor-empty-sum0→eigen4 v sum0L sum0R
```

Full Survivor Image Law

The image law for the full survivor is a direct transport consequence. No new spectral case appears here; Law 14G.15 is merely re-expressed through the survivor identification.

Law 14G.34: Full Survivor Image ⊆ 8-Eigenspace

The full survivor is identified with L_8 both before and after one further application, so the claim reduces to Law 14G.15 by transport on both sides. Scaling congruence carries the codomain back, forcing the full-survivor image into the 8-eigenspace.

```
– § full survivor image vectors are 8-eigenvectors
law14G-34-survivor-full-image⊆eigen8 : (v : Vec8ℤ) →
 Vec8Eq (laplacianSurvivorVec8ℤ survivor-full (laplacianSurvivorVec8ℤ survivor-full v))
     (eightVec8ℤ (laplacianSurvivorVec8ℤ survivor-full v))
law14G-34-survivor-full-image⊆eigen8 v =
 let eqV : Vec8Eq (laplacianSurvivorVec8ℤ survivor-full v) (K8LaplacianVec8ℤ v)
     eqV = law14G-8-survivor-full-K8 v
     eqLL : Vec8Eq (laplacianSurvivorVec8ℤ survivor-full (laplacianSurvivorVec8ℤ survivor-full v))
            (K8LaplacianVec8ℤ (laplacianSurvivorVec8ℤ survivor-full v))
     eqLL = law14G-8-survivor-full-K8 (laplacianSurvivorVec8ℤ survivor-full v)
     step₁ : Vec8Eq (laplacianSurvivorVec8ℤ survivor-full (laplacianSurvivorVec8ℤ survivor-full v))
                    (K8LaplacianVec8ℤ (K8LaplacianVec8ℤ v))
     step₁ =
      Vec8Eq-trans
       eqLL
       (K8Laplacian-cong (laplacianSurvivorVec8ℤ survivor-full v) (K8LaplacianVec8ℤ v) eqV)
     step₂ : Vec8Eq (K8LaplacianVec8ℤ (K8LaplacianVec8ℤ v)) (eightVec8ℤ (K8LaplacianVec8ℤ v))
     step₂ = law14G-15-LL-eightL v
     step₃ : Vec8Eq (eightVec8ℤ (K8LaplacianVec8ℤ v)) (eightVec8ℤ (laplacianSurvivorVec8ℤ survivor-full v))
     step₃ = Vec8Eq-sym (eightVec8-cong (laplacianSurvivorVec8ℤ survivor-full v) (K8LaplacianVec8ℤ v) eqV)
 in
 Vec8Eq-trans step₁ (Vec8Eq-trans step₂ step₃)
```

Survivor Spectral Packages

Packaging the already-forced survivor consequences into reusable witnesses adds no new ontology—it only collects the eliminated cases into a single typed interface.

Law 14G.35: Full Survivor Spectral Package

Law 14G.23, Law 14G.24, Laws 14G.25–14G.26, and Law 14G.34 already force all full-survivor spectral data. Product formation collects those forced components without introducing any new branch, yielding a single composite spectral witness.

```
– § full survivor spectral package
law14G-35-survivor-full-spectral-package : (v : Vec8ℤ) →
 (sum8ℤ (laplacianSurvivorVec8ℤ survivor-full v) ≡ 0ℤ) ×
 (Vec8Eq (J8Vec8ℤ (laplacianSurvivorVec8ℤ survivor-full v)) zeroVec8ℤ) ×
 ((sum8ℤ v ≡ 0ℤ → Vec8Eq (laplacianSurvivorVec8ℤ survivor-full v) (eightVec8ℤ v)) ×
  (Vec8Eq (laplacianSurvivorVec8ℤ survivor-full v) (eightVec8ℤ v) → sum8ℤ v ≡ 0ℤ)) ×
 (Vec8Eq (laplacianSurvivorVec8ℤ survivor-full (laplacianSurvivorVec8ℤ survivor-full v))
```

```
  (eightVec8ℤ (laplacianSurvivorVec8ℤ survivor-full v)))
law14G-35-survivor-full-spectral-package v =
 law14G-23-sumL-survivor-full-0 v ,
 (law14G-24-JL-survivor-full-zero v ,
  ((law14G-25-survivor-full-sum0→eigen8 v , law14G-26-survivor-full-eigen8→sum0 v) ,
   law14G-34-survivor-full-image⊆eigen8 v))
```

Law 14G.36: Empty Survivor Spectral Package

Law 14G.27 through Law 14G.32 already force the empty-survivor spectral data. The blockwise consequences and kernel witnesses are collected as one product—a single composite spectral witness for the empty survivor.

```
– § empty survivor spectral package
law14G-36-survivor-empty-spectral-package : (v : Vec8ℤ) →
 (sum8ℤ (laplacianSurvivorVec8ℤ survivor-empty v) ≡ 0ℤ) ×
 (Vec8Eq (J8Vec8ℤ (laplacianSurvivorVec8ℤ survivor-empty v)) zeroVec8ℤ) ×
 ((sumFin4ℤ (left4 v) ≡ 0ℤ → sumFin4ℤ (right4 v) ≡ 0ℤ → Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty v) (fourVec8ℤ v)) ×
  (Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty v) (fourVec8ℤ v) → (sumFin4ℤ (left4 v) ≡ 0ℤ) × (sumFin4ℤ (right4 v) ≡ 0ℤ))) ×
 ((x y : ℤ) → Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty (constVec8Splitℤ x y)) zeroVec8ℤ) ×
 (Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty (laplacianSurvivorVec8ℤ survivor-empty v))
  (fourVec8ℤ (laplacianSurvivorVec8ℤ survivor-empty v)))
law14G-36-survivor-empty-spectral-package v =
 law14G-27-sumL-survivor-empty-0 v ,
 (law14G-28-JL-survivor-empty-zero v ,
  ((law14G-29-survivor-empty-sum0→eigen4 v , law14G-30-survivor-empty-eigen4→sum0 v) ,
   (law14G-31-splitConst-eigen0-empty ,
    law14G-32-imageEmpty⊆eigen4 v)))
```

Law 14G.37: Spectral Package by Forced Case Split

The survivor type has exactly two constructors by Law 14G.6. Exhaustive case split eliminates every index except survivor-empty and survivor-full, forcing a uniform survivor-indexed spectral package for every case.

```
– § type-level spectral package indexed by survivor
SurvivorSpectralPackage : CouplingSurvivor → Vec8ℤ → Set
SurvivorSpectralPackage survivor-full v =
 (sum8ℤ (laplacianSurvivorVec8ℤ survivor-full v) ≡ 0ℤ) ×
 (Vec8Eq (J8Vec8ℤ (laplacianSurvivorVec8ℤ survivor-full v)) zeroVec8ℤ) ×
 ((sum8ℤ v ≡ 0ℤ → Vec8Eq (laplacianSurvivorVec8ℤ survivor-full v) (eightVec8ℤ v)) ×
  (Vec8Eq (laplacianSurvivorVec8ℤ survivor-full v) (eightVec8ℤ v) → sum8ℤ v ≡ 0ℤ)) ×
 (Vec8Eq (laplacianSurvivorVec8ℤ survivor-full (laplacianSurvivorVec8ℤ survivor-full v))
  (eightVec8ℤ (laplacianSurvivorVec8ℤ survivor-full v)))
SurvivorSpectralPackage survivor-empty v =
 (sum8ℤ (laplacianSurvivorVec8ℤ survivor-empty v) ≡ 0ℤ) ×
 (Vec8Eq (J8Vec8ℤ (laplacianSurvivorVec8ℤ survivor-empty v)) zeroVec8ℤ) ×
 ((sumFin4ℤ (left4 v) ≡ 0ℤ → sumFin4ℤ (right4 v) ≡ 0ℤ → Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty v) (fourVec8ℤ v)) ×
  (Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty v) (fourVec8ℤ v) → (sumFin4ℤ (left4 v) ≡ 0ℤ) × (sumFin4ℤ (right4 v) ≡ 0ℤ))) ×
 ((x y : ℤ) → Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty (constVec8Splitℤ x y)) zeroVec8ℤ) ×
 (Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty (laplacianSurvivorVec8ℤ survivor-empty v))
  (fourVec8ℤ (laplacianSurvivorVec8ℤ survivor-empty v)))

– § forced case-split over survivor constructors
law14G-37-survivor-spectral-package-byCases : (k : CouplingSurvivor) (v : Vec8ℤ) → SurvivorSpectralPackage k v
```

```
law14G-37-survivor-spectral-package-byCases k v with law14G-6-survivor-cases k
... | inj₁ refl = law14G-36-survivor-empty-spectral-package v
... | inj₂ refl = law14G-35-survivor-full-spectral-package v
```

Spectral Package Projections

Each forced component of the survivor package is projected directly from the already-fixed product witness, without reopening the classification.

```
-- § project drift-zero from package
survivorPkg-sumL0 : {k : CouplingSurvivor} {v : Vec8ℤ} →
 SurvivorSpectralPackage k v → sum8ℤ (laplacianSurvivorVec8ℤ k v) ≡ 0ℤ
survivorPkg-sumL0 {survivor-full} pkg = fst pkg
survivorPkg-sumL0 {survivor-empty} pkg = fst pkg

-- § project JL=0 from package
survivorPkg-JL0 : {k : CouplingSurvivor} {v : Vec8ℤ} →
 SurvivorSpectralPackage k v → Vec8Eq (J8Vec8ℤ (laplacianSurvivorVec8ℤ k v)) zeroVec8ℤ
survivorPkg-JL0 {survivor-full} pkg = fst (snd pkg)
survivorPkg-JL0 {survivor-empty} pkg = fst (snd pkg)

-- § sum-zero predicate indexed by survivor
SurvivorSum0 : CouplingSurvivor → Vec8ℤ → Set
SurvivorSum0 survivor-full v = sum8ℤ v ≡ 0ℤ
SurvivorSum0 survivor-empty v = (sumFin4ℤ (left4 v) ≡ 0ℤ) × (sumFin4ℤ (right4 v) ≡ 0ℤ)

-- § eigen predicate indexed by survivor
SurvivorEigen : (k : CouplingSurvivor) → Vec8ℤ → Set
SurvivorEigen survivor-full v =
 Vec8Eq (laplacianSurvivorVec8ℤ survivor-full v) (eightVec8ℤ v)
SurvivorEigen survivor-empty v =
 Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty v) (fourVec8ℤ v)

-- § project sum0→eigen direction
survivorPkg-sum0→eigen : {k : CouplingSurvivor} {v : Vec8ℤ} →
 SurvivorSpectralPackage k v → SurvivorSum0 k v → SurvivorEigen k v
survivorPkg-sum0→eigen {survivor-full} (_ , (_ , ((sum0→eigen , _) , _))) sum0 = sum0→eigen sum0
survivorPkg-sum0→eigen {survivor-empty} (_ , (_ , ((sum0→eigen , _) , _))) (sum0L , sum0R) = sum0→eigen sum0L sum0R

-- § project eigen→sum0 direction
survivorPkg-eigen→sum0 : {k : CouplingSurvivor} {v : Vec8ℤ} →
 SurvivorSpectralPackage k v → SurvivorEigen k v → SurvivorSum0 k v
survivorPkg-eigen→sum0 {survivor-full} (_ , (_ , ((_ , eigen→sum0) , _))) eigen = eigen→sum0 eigen
survivorPkg-eigen→sum0 {survivor-empty} (_ , (_ , ((_ , eigen→sum0) , _))) eigen = eigen→sum0 eigen

-- § image-eigen predicate indexed by survivor
SurvivorImageEigen : (k : CouplingSurvivor) → Vec8ℤ → Set
SurvivorImageEigen survivor-full v =
 Vec8Eq (laplacianSurvivorVec8ℤ survivor-full (laplacianSurvivorVec8ℤ survivor-full v))
  (eightVec8ℤ (laplacianSurvivorVec8ℤ survivor-full v))
SurvivorImageEigen survivor-empty v =
 Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty (laplacianSurvivorVec8ℤ survivor-empty v))
  (fourVec8ℤ (laplacianSurvivorVec8ℤ survivor-empty v))

-- § project image⊆eigen from package
survivorPkg-image⊆eigen : {k : CouplingSurvivor} {v : Vec8ℤ} →
 SurvivorSpectralPackage k v → SurvivorImageEigen k v
survivorPkg-image⊆eigen {survivor-full} (_ , (_ , (_ , image⊆))) = image⊆
```

```
survivorPkg-image⊆eigen {survivor-empty} (_ , (_ , (_ , (_ , image⊆)))) = image⊆

– § project split-constant kernel from empty package
survivorPkg-splitConstKernel : {v : Vec8ℤ} →
 SurvivorSpectralPackage survivor-empty v → (x y : ℤ) →
 Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty (constVec8Splitℤ x y)) zeroVec8ℤ
survivorPkg-splitConstKernel (_ , (_ , (_ , (splitConstKer , _)))) = splitConstKer
```

Convenience Layer

Once the survivor index and vector are fixed, Law 14G.37 forces the package witness and every convenience projection follows without further case analysis.

```
– § construct package from (k, v)
survivorPkg : (k : CouplingSurvivor) (v : Vec8ℤ) → SurvivorSpectralPackage k v
survivorPkg = law14G-37-survivor-spectral-package-byCases

– § convenience: sumL0
survivor-sumL0 : (k : CouplingSurvivor) (v : Vec8ℤ) → sum8ℤ (laplacianSurvivorVec8ℤ k v) ≡ 0ℤ
survivor-sumL0 k v = survivorPkg-sumL0 (survivorPkg k v)

– § convenience: JL=0
survivor-JL0 : (k : CouplingSurvivor) (v : Vec8ℤ) → Vec8Eq (J8Vec8ℤ (laplacianSurvivorVec8ℤ k v)) zeroVec8ℤ
survivor-JL0 k v = survivorPkg-JL0 (survivorPkg k v)

– § convenience: sum0→eigen
survivor-sum0→eigen : (k : CouplingSurvivor) (v : Vec8ℤ) → SurvivorSum0 k v → SurvivorEigen k v
survivor-sum0→eigen k v sum0 = survivorPkg-sum0→eigen (survivorPkg k v) sum0

– § convenience: eigen→sum0
survivor-eigen→sum0 : (k : CouplingSurvivor) (v : Vec8ℤ) → SurvivorEigen k v → SurvivorSum0 k v
survivor-eigen→sum0 k v eigen = survivorPkg-eigen→sum0 (survivorPkg k v) eigen

– § convenience: image⊆eigen
survivor-image⊆eigen : (k : CouplingSurvivor) (v : Vec8ℤ) → SurvivorImageEigen k v
survivor-image⊆eigen k v = survivorPkg-image⊆eigen (survivorPkg k v)

– § convenience: split-constant kernel
survivor-splitConstKernel : (v : Vec8ℤ) (x y : ℤ) →
 Vec8Eq (laplacianSurvivorVec8ℤ survivor-empty (constVec8Splitℤ x y)) zeroVec8ℤ
survivor-splitConstKernel v x y = survivorPkg-splitConstKernel {v} (survivorPkg survivor-empty v) x y
```

Chapter 34

Triple K_4 Laplacian

The two-copy coupled Laplacian of the previous chapter forced a binary classification: full join or disjoint union, with eigenvalue 8 governing the spectral theory. Three copies force the same elimination again, now under the copy symmetry of S_3 and the endomorphism symmetries on each K_4 factor. These constraints eliminate every intermediate coupling, force the same binary survivors, and then force the 12-vertex operator algebra and its spectral packages.

Copy_3 Infrastructure

Three copies, decidable equality for each pair, and the full symmetric group S_3 are forced as the minimal copy infrastructure. Representation freedom collapses once the copy type, its equality test, and the six explicit bijections that exhaust the copy symmetries are fixed.

```
-- § three indistinguishable copies
data Copy3 : Set where
  C₀ : Copy3
  C₁ : Copy3
  C₂ : Copy3

-- § copy-inequality predicate
Copy3≠ : (i j : Copy3) → Set
Copy3≠ i j = i ≡ j → ⊥

C₀≠C₁ : Copy3≠ C₀ C₁
C₀≠C₁ ()

C₀≠C₂ : Copy3≠ C₀ C₂
C₀≠C₂ ()

C₁≠C₂ : Copy3≠ C₁ C₂
C₁≠C₂ ()

-- § decidable equality on Copy3 (9 cases)
Copy3-decEq : (i j : Copy3) → (i ≡ j) ⊎ (Copy3≠ i j)
Copy3-decEq C₀ C₀ = inj₁ refl
Copy3-decEq C₁ C₁ = inj₁ refl
Copy3-decEq C₂ C₂ = inj₁ refl
Copy3-decEq C₀ C₁ = inj₂ C₀≠C₁
Copy3-decEq C₁ C₀ = inj₂ (λ e → C₀≠C₁ (sym e))
```

```
Copy3-decEq C₀ C₂ = inj₂ C₀≠C₂
Copy3-decEq C₂ C₀ = inj₂ (λ e → C₀≠C₂ (sym e))
Copy3-decEq C₁ C₂ = inj₂ C₁≠C₂
Copy3-decEq C₂ C₁ = inj₂ (λ e → C₁≠C₂ (sym e))

-- § copy permutations (S₃ as explicit bijections)
record CopyPerm : Set where
 field
  to       : Copy3 → Copy3
  from     : Copy3 → Copy3
  to-from : (y : Copy3) → to (from y) ≡ y
  from-to : (x : Copy3) → from (to x) ≡ x

open CopyPerm public

-- § identity permutation
permId₃ : CopyPerm
permId₃ = record
 { to = λ x → x
 ; from = λ x → x
 ; to-from = λ _ → refl
 ; from-to = λ _ → refl
 }

-- § swap C₀ ↔ C₁
permSwap₀₁ : CopyPerm
permSwap₀₁ = record
 { to = λ where
   C₀ → C₁
   C₁ → C₀
   C₂ → C₂
 ; from = λ where
   C₀ → C₁
   C₁ → C₀
   C₂ → C₂
 ; to-from = λ where
   C₀ → refl
   C₁ → refl
   C₂ → refl
 ; from-to = λ where
   C₀ → refl
   C₁ → refl
   C₂ → refl
 }
```

Step 2: Remaining Permutations. The swap $C_0 \leftrightarrow C_2$ and $C_1 \leftrightarrow C_2$ complete the symmetric group S_3 on three copies.

```
-- § swap C₀ ↔ C₂
permSwap₀₂ : CopyPerm
permSwap₀₂ = record
 { to = λ where
   C₀ → C₂
   C₁ → C₁
   C₂ → C₀
 ; from = λ where
   C₀ → C₂
   C₁ → C₁
   C₂ → C₀
```

```
 ; to-from = λ where
   C₀ → refl
   C₁ → refl
   C₂ → refl
 ; from-to = λ where
   C₀ → refl
   C₁ → refl
   C₂ → refl
 }

– § swap C₁ ↔ C₂
permSwap₁₂ : CopyPerm
permSwap₁₂ = record
 { to = λ where
   C₀ → C₀
   C₁ → C₂
   C₂ → C₁
 ; from = λ where
   C₀ → C₀
   C₁ → C₂
   C₂ → C₁
 ; to-from = λ where
   C₀ → refl
   C₁ → refl
   C₂ → refl
 ; from-to = λ where
   C₀ → refl
   C₁ → refl
   C₂ → refl
 }

– § 3-cycle C₀ → C₁ → C₂ → C₀
permCycle₀₁₂ : CopyPerm
permCycle₀₁₂ = record
 { to = λ where
   C₀ → C₁
   C₁ → C₂
   C₂ → C₀
 ; from = λ where
   C₀ → C₂
   C₁ → C₀
   C₂ → C₁
 ; to-from = λ where
   C₀ → refl
   C₁ → refl
   C₂ → refl
 ; from-to = λ where
   C₀ → refl
   C₁ → refl
   C₂ → refl
 }

– § 3-cycle C₀ → C₂ → C₁ → C₀
permCycle₀₂₁ : CopyPerm
permCycle₀₂₁ = record
 { to = λ where
   C₀ → C₂
   C₁ → C₀
   C₂ → C₁
 ; from = λ where
   C₀ → C₁
   C₁ → C₂
```

```
  C₂ → C₀
; to-from = λ where
  C₀ → refl
  C₁ → refl
  C₂ → refl
; from-to = λ where
  C₀ → refl
  C₁ → refl
  C₂ → refl
}
```

Copy Transport and Cross-Coupling

The transport laws for three-copy couplings are fixed here. The four-argument transport and the exhaustive 6×6 pair table eliminate all freedom in moving witnesses between ordered distinct copy pairs.

```
-- § transport across four arguments (copies + endpoints)
transport4 : {C : Copy3 → Copy3 → EndoCase → EndoCase → Set}
 {c c' d d' : Copy3} {a a' b b' : EndoCase} →
 c ≡ c' → d ≡ d' → a ≡ a' → b ≡ b' → C c d a b → C c' d' a' b'
transport4 {C = C} {c = c} {c' = c'} {d = d} {d' = d'} {a = a} {a' = a'} {b = b} {b' = b'} ec ed ea eb cab =
 subst (λ c0 → C c0 d' a' b') ec
  (subst (λ d0 → C c d0 a' b') ed
   (subst (λ a0 → C c d a0 b') ea
    (subst (λ b0 → C c d a b0) eb cab)))

-- § cross-coupling predicate among three copies
Coupling3 : Set1
Coupling3 = Copy3 → Copy3 → EndoCase → EndoCase → Set

EndoInv3 : Coupling3 → Set
EndoInv3 C = (c d : Copy3) → CrossInv (λ a b → C c d a b)

CopyInv3 : Coupling3 → Set
CopyInv3 C = (π : CopyPerm) → (c d : Copy3) → (a b : EndoCase) → C c d a b → C (to π c) (to π d) a b

-- § copy-pair transitivity: any ordered distinct pair maps to any other
sendPair₃ : (c0 d0 c d : Copy3) → Copy3≠ c0 d0 → Copy3≠ c d →
 Σ CopyPerm (λ π → (to π c0 ≡ c) × (to π d0 ≡ d))
sendPair₃ C₀ C₀ c d neq0 _ = ⊥-elim (neq0 refl)
sendPair₃ C₁ C₁ c d neq0 _ = ⊥-elim (neq0 refl)
sendPair₃ C₂ C₂ c d neq0 _ = ⊥-elim (neq0 refl)

sendPair₃ C₀ C₁ C₀ C₀ _ neq = ⊥-elim (neq refl)
sendPair₃ C₀ C₁ C₁ C₁ _ neq = ⊥-elim (neq refl)
sendPair₃ C₀ C₁ C₂ C₂ _ neq = ⊥-elim (neq refl)

sendPair₃ C₀ C₂ C₀ C₀ _ neq = ⊥-elim (neq refl)
sendPair₃ C₀ C₂ C₁ C₁ _ neq = ⊥-elim (neq refl)
sendPair₃ C₀ C₂ C₂ C₂ _ neq = ⊥-elim (neq refl)

sendPair₃ C₁ C₀ C₀ C₀ _ neq = ⊥-elim (neq refl)
sendPair₃ C₁ C₀ C₁ C₁ _ neq = ⊥-elim (neq refl)
sendPair₃ C₁ C₀ C₂ C₂ _ neq = ⊥-elim (neq refl)

sendPair₃ C₁ C₂ C₀ C₀ _ neq = ⊥-elim (neq refl)
sendPair₃ C₁ C₂ C₁ C₁ _ neq = ⊥-elim (neq refl)
```

```
sendPair₃ C₁ C₂ C₂ C₂ _ neq = ⊥-elim (neq refl)

sendPair₃ C₂ C₀ C₀ C₀ _ neq = ⊥-elim (neq refl)
sendPair₃ C₂ C₀ C₁ C₁ _ neq = ⊥-elim (neq refl)
sendPair₃ C₂ C₀ C₂ C₂ _ neq = ⊥-elim (neq refl)

sendPair₃ C₂ C₁ C₀ C₀ _ neq = ⊥-elim (neq refl)
sendPair₃ C₂ C₁ C₁ C₁ _ neq = ⊥-elim (neq refl)
sendPair₃ C₂ C₁ C₂ C₂ _ neq = ⊥-elim (neq refl)

sendPair₃ C₀ C₁ C₀ C₁ _ _ = permId₃ , (refl , refl)
sendPair₃ C₀ C₁ C₀ C₂ _ _ = permSwap₁₂ , (refl , refl)
sendPair₃ C₀ C₁ C₁ C₀ _ _ = permSwap₀₁ , (refl , refl)
sendPair₃ C₀ C₁ C₁ C₂ _ _ = permCycle₀₁₂ , (refl , refl)
sendPair₃ C₀ C₁ C₂ C₀ _ _ = permCycle₀₂₁ , (refl , refl)
sendPair₃ C₀ C₁ C₂ C₁ _ _ = permSwap₀₂ , (refl , refl)

sendPair₃ C₀ C₂ C₀ C₁ _ _ = permSwap₁₂ , (refl , refl)
sendPair₃ C₀ C₂ C₀ C₂ _ _ = permId₃ , (refl , refl)
sendPair₃ C₀ C₂ C₁ C₀ _ _ = permCycle₀₁₂ , (refl , refl)
sendPair₃ C₀ C₂ C₁ C₂ _ _ = permSwap₀₁ , (refl , refl)
sendPair₃ C₀ C₂ C₂ C₀ _ _ = permSwap₀₂ , (refl , refl)
sendPair₃ C₀ C₂ C₂ C₁ _ _ = permCycle₀₂₁ , (refl , refl)

sendPair₃ C₁ C₀ C₀ C₁ _ _ = permSwap₀₁ , (refl , refl)
sendPair₃ C₁ C₀ C₀ C₂ _ _ = permCycle₀₂₁ , (refl , refl)
sendPair₃ C₁ C₀ C₁ C₀ _ _ = permId₃ , (refl , refl)
sendPair₃ C₁ C₀ C₁ C₂ _ _ = permSwap₀₂ , (refl , refl)
sendPair₃ C₁ C₀ C₂ C₀ _ _ = permSwap₁₂ , (refl , refl)
sendPair₃ C₁ C₀ C₂ C₁ _ _ = permCycle₀₁₂ , (refl , refl)

sendPair₃ C₁ C₂ C₀ C₁ _ _ = permCycle₀₂₁ , (refl , refl)
sendPair₃ C₁ C₂ C₀ C₂ _ _ = permSwap₀₁ , (refl , refl)
sendPair₃ C₁ C₂ C₁ C₀ _ _ = permSwap₀₂ , (refl , refl)
sendPair₃ C₁ C₂ C₁ C₂ _ _ = permId₃ , (refl , refl)
sendPair₃ C₁ C₂ C₂ C₀ _ _ = permCycle₀₁₂ , (refl , refl)
sendPair₃ C₁ C₂ C₂ C₁ _ _ = permSwap₁₂ , (refl , refl)

sendPair₃ C₂ C₀ C₀ C₁ _ _ = permCycle₀₁₂ , (refl , refl)
sendPair₃ C₂ C₀ C₀ C₂ _ _ = permSwap₀₂ , (refl , refl)
sendPair₃ C₂ C₀ C₁ C₀ _ _ = permSwap₁₂ , (refl , refl)
sendPair₃ C₂ C₀ C₁ C₂ _ _ = permCycle₀₂₁ , (refl , refl)
sendPair₃ C₂ C₀ C₂ C₀ _ _ = permId₃ , (refl , refl)
sendPair₃ C₂ C₀ C₂ C₁ _ _ = permSwap₀₁ , (refl , refl)

sendPair₃ C₂ C₁ C₀ C₁ _ _ = permSwap₀₂ , (refl , refl)
sendPair₃ C₂ C₁ C₀ C₂ _ _ = permCycle₀₁₂ , (refl , refl)
sendPair₃ C₂ C₁ C₁ C₀ _ _ = permCycle₀₂₁ , (refl , refl)
sendPair₃ C₂ C₁ C₁ C₂ _ _ = permSwap₁₂ , (refl , refl)
sendPair₃ C₂ C₁ C₂ C₀ _ _ = permSwap₀₁ , (refl , refl)
sendPair₃ C₂ C₁ C₂ C₁ _ _ = permId₃ , (refl , refl)
```

Coupling Classification

The binary coupling dichotomy for three copies is forced here. One cross-edge witness forces the complete join, one cross-non-edge witness forces total separation, and no intermediate coupling survives the copy and endomorphism symmetries.

```
-- § Law 14H.0: one cross-edge forces complete join across all copies
law14H-0-edge-forces-all-cross3 : (C : Coupling3) → EndoInv3 C → CopyInv3 C →
 Σ Copy3 (λ k0 → Σ Copy3 (λ k1 → (Copy3≠ k0 k1) × Σ EndoCase (λ a0 → Σ EndoCase (λ b0 → C k0 k1 a0 b0)))) →
 (c d : Copy3) → Copy3≠ c d → (a b : EndoCase) → C c d a b
law14H-0-edge-forces-all-cross3 C endoInv copyInv (k0 , (k1 , (k0≠k1 , (a0 , (b0 , e0))))) c d c≠d a b =
 let
  pair = sendPair₃ k0 k1 c d k0≠k1 c≠d
 in
 let
  π = fst pair
  eqs = snd pair
  ec = fst eqs
  ed = snd eqs
  movedEdge : C c d a0 b0
  movedEdge = transport4 {C = C} ec ed refl refl (copyInv π k0 k1 a0 b0 e0)
 in
 law14F-0-edge-forces-all (λ x y → C c d x y) (endoInv c d) (a0 , (b0 , movedEdge)) a b

-- § Law 14H.1: one cross-non-edge forces disjoint union across all copies
law14H-1-nonedge-forces-none-cross3 : (C : Coupling3) → EndoInv3 C → CopyInv3 C →
 Σ Copy3 (λ k0 → Σ Copy3 (λ k1 → (Copy3≠ k0 k1) × Σ EndoCase (λ a0 → Σ EndoCase (λ b0 → ¬ (C k0 k1 a0 b0))))) →
 (c d : Copy3) → Copy3≠ c d → (a b : EndoCase) → ¬ (C c d a b)
law14H-1-nonedge-forces-none-cross3 C endoInv copyInv (k0 , (k1 , (k0≠k1 , (a0 , (b0 , n0))))) c d c≠d a b cab =
 let
  pair = sendPair₃ c d k0 k1 c≠d k0≠k1
 in
 let
  π = fst pair
  eqs = snd pair
  ec = fst eqs
  ed = snd eqs
  moved : C k0 k1 a b
  moved = transport4 {C = C} ec ed refl refl (copyInv π c d a b cab)
 in
 law14F-1-nonedge-forces-none (λ x y → C k0 k1 x y) (endoInv k0 k1) (a0 , (b0 , n0)) a b moved

-- § canonical survivor couplings
CrossEmpty3 : Coupling3
CrossEmpty3 _ _ _ _ = ⊥

CrossFull3 : Coupling3
CrossFull3 _ _ _ _ = ⊤
```

$\mathbf{Vec}_{12}$ Infrastructure

A 12-vertex vector is three blocks of four, with block projections, pointwise equality, and the global-sum and all-ones operators. Representation freedom is eliminated by fixing the unique block decomposition on which all later K_{12} laws are forced.

```
-- § Vec12ℤ = three blocks of Vec4ℤ
Vec12ℤ : Set
Vec12ℤ = Vec4ℤ × (Vec4ℤ × Vec4ℤ)

-- § block projections
block₀ : Vec12ℤ → Vec4ℤ
block₀ = fst

block₁ : Vec12ℤ → Vec4ℤ
```

```
block₁ v = fst (snd v)

block₂ : Vec12ℤ → Vec4ℤ
block₂ v = snd (snd v)

-- § pointwise equality on Vec12ℤ
Vec12Eq : Vec12ℤ → Vec12ℤ → Set
Vec12Eq u v = Vec4Eq (block₀ u) (block₀ v) × Vec4Eq (block₁ u) (block₁ v) × Vec4Eq (block₂ u) (block₂ v)

-- § global sum: Σ₁₂ v = Σ₄(block₀) + Σ₄(block₁) + Σ₄(block₂)
sum12ℤ : Vec12ℤ → ℤ
sum12ℤ v = sumFin4ℤ (block₀ v) +ℤ (sumFin4ℤ (block₁ v) +ℤ sumFin4ℤ (block₂ v))

-- § global-sum operator J₁₂: broadcast Σ₁₂ to all 12 entries
J12Vec12ℤ : Vec12ℤ → Vec12ℤ
J12Vec12ℤ v = (λ _ → sum12ℤ v) , ((λ _ → sum12ℤ v) , (λ _ → sum12ℤ v))

-- § 12·x = 4·x + 8·x (forced decomposition)
twelveTimesℤ : ℤ → ℤ
twelveTimesℤ x = fourTimesℤ x +ℤ eightTimesℤ x

-- § K₁₂ Laplacian (opaque)
opaque
 K12LaplacianVec12ℤ : Vec12ℤ → Vec12ℤ
 K12LaplacianVec12ℤ v =
  (λ i → twelveTimesℤ (block₀ v i) +ℤ negℤ (sum12ℤ v)) ,
  ((λ i → twelveTimesℤ (block₁ v i) +ℤ negℤ (sum12ℤ v)) ,
   (λ i → twelveTimesℤ (block₂ v i) +ℤ negℤ (sum12ℤ v)))

-- § block-diagonal Laplacian (empty coupling)
laplacianEmptyVec12ℤ : Vec12ℤ → Vec12ℤ
laplacianEmptyVec12ℤ v = laplacianVec4ℤ (block₀ v) , (laplacianVec4ℤ (block₁ v) , laplacianVec4ℤ (block₂ v))

-- § full coupling = K₁₂ Laplacian
laplacianFullVec12ℤ : Vec12ℤ → Vec12ℤ
laplacianFullVec12ℤ = K12LaplacianVec12ℤ
```

Survivor Dispatch and Vec$_{12}$ Operations

The two survivor actions on Vec$_{12}$ and the operations required to compare them are fixed here. The block-diagonal form, the full K$_{12}$ form, and the binary survivor dispatch eliminate every remaining implementation choice before the spectral laws begin.

```
-- § Law 14H.2: empty coupling is block-diagonal
law14H-2-empty-block : (v : Vec12ℤ) →
 Vec12Eq (laplacianEmptyVec12ℤ v)
  (laplacianVec4ℤ (block₀ v) , (laplacianVec4ℤ (block₁ v) , laplacianVec4ℤ (block₂ v)))
law14H-2-empty-block v = (λ _ → refl) , ((λ _ → refl) , (λ _ → refl))

-- § Law 14H.3: full coupling collapses to K₁₂ spectral form
law14H-3-full-is-K12 : (v : Vec12ℤ) → Vec12Eq (laplacianFullVec12ℤ v) (K12LaplacianVec12ℤ v)
law14H-3-full-is-K12 v = (λ _ → refl) , ((λ _ → refl) , (λ _ → refl))

-- § two survivor kinds for the triple coupling
data Coupling3Survivor : Set where
 survivor3-empty : Coupling3Survivor
 survivor3-full : Coupling3Survivor
```

```
-- § Law 14H.4: binary case split
law14H-4-survivor3-cases : (k : Coupling3Survivor) → (k ≡ survivor3-empty) ⊎ (k ≡ survivor3-full)
law14H-4-survivor3-cases survivor3-empty = inj₁ refl
law14H-4-survivor3-cases survivor3-full = inj₂ refl

-- § survivor dispatch
laplacianSurvivorVec12ℤ : Coupling3Survivor → Vec12ℤ → Vec12ℤ
laplacianSurvivorVec12ℤ survivor3-empty = laplacianEmptyVec12ℤ
laplacianSurvivorVec12ℤ survivor3-full = laplacianFullVec12ℤ

-- § Vec12ℤ arithmetic operations
_+Vec12ℤ_ : Vec12ℤ → Vec12ℤ → Vec12ℤ
(u +Vec12ℤ v) =
 (block₀ u +Vec4ℤ block₀ v) ,
 ((block₁ u +Vec4ℤ block₁ v) ,
  (block₂ u +Vec4ℤ block₂ v))

negVec12ℤ : Vec12ℤ → Vec12ℤ
negVec12ℤ v =
 (λ i → negℤ (block₀ v i)) ,
 ((λ i → negℤ (block₁ v i)) ,
  (λ i → negℤ (block₂ v i)))

twelveVec4ℤ : Vec4ℤ → Vec4ℤ
twelveVec4ℤ v i = twelveTimesℤ (v i)

twelveVec12ℤ : Vec12ℤ → Vec12ℤ
twelveVec12ℤ v = twelveVec4ℤ (block₀ v) , (twelveVec4ℤ (block₁ v) , twelveVec4ℤ (block₂ v))

constVec12ℤ : ℤ → Vec12ℤ
constVec12ℤ x = constVec4ℤ x , (constVec4ℤ x , constVec4ℤ x)

zeroVec12ℤ : Vec12ℤ
zeroVec12ℤ = constVec12ℤ 0ℤ

-- § sum of a constant vector
sum12-const : (x : ℤ) → sum12ℤ (constVec12ℤ x) ≡ twelveTimesℤ x
sum12-const x = refl

-- § sum of J₁₂ v
sum12-J12 : (v : Vec12ℤ) → sum12ℤ (J12Vec12ℤ v) ≡ twelveTimesℤ (sum12ℤ v)
sum12-J12 v = refl
```

K_{12} Operator Algebra

Once L_{12} is fixed as $12I - J_{12}$, the operator algebra is forced. The identities $J^2 = 12J$, $L + J = 12I$, and the remaining operator equalities follow without further branching.

```
-- § Law 14H.5: J₁₂² = 12·J₁₂
law14H-5-JJ-twelveJ : (v : Vec12ℤ) → Vec12Eq (J12Vec12ℤ (J12Vec12ℤ v)) (twelveVec12ℤ (J12Vec12ℤ v))
law14H-5-JJ-twelveJ v =
 (λ _ → sum12-J12 v) ,
 ((λ _ → sum12-J12 v) ,
  (λ _ → sum12-J12 v))
```

Step 2: Laplacian Operator Identities. With $J^2 = 12J$ established, the remaining operator identities require unfolding the opaque Laplacian definition. The decomposition $12v = Lv + Jv$, scalar distributivity of $12\times$, and the sum–Laplacian commutation all follow inside a single opaque scope.

```
opaque
 unfolding K12LaplacianVec12ℤ

-- § Law 14H.6: L₁₂ = 12·I − J₁₂
law14H-6-L-twelve-minus-J : (v : Vec12ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v) (twelveVec12ℤ v +Vec12ℤ negVec12ℤ (J12Vec12ℤ v))
law14H-6-L-twelve-minus-J v =
 (λ _ → refl) ,
 ((λ _ → refl) ,
  (λ _ → refl))

-- § Law 14H.7: 12·v = L₁₂ v + J₁₂ v
law14H-7-twelve-decomposes : (v : Vec12ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v +Vec12ℤ J12Vec12ℤ v) (twelveVec12ℤ v)
law14H-7-twelve-decomposes v =
 let
   s = sum12ℤ v

   cancel-twelve : (x : ℤ) → (x +ℤ negℤ s) +ℤ s ≡ x
   cancel-twelve x =
     trans
       (+ℤ-assoc x (negℤ s) s)
       (trans
        (cong (λ t → x +ℤ t) (+ℤ-inv-left s))
        (+ℤ-zero-right x))
 in
 ( λ i →
     cancel-twelve (twelveTimesℤ (block₀ v i))
 ) ,
 (( λ i →
       cancel-twelve (twelveTimesℤ (block₁ v i))
   ) ,
  ( λ i →
       cancel-twelve (twelveTimesℤ (block₂ v i))
   ))

-- § scalar helpers: twelveTimes distributes over addition and negation
twelveTimes-+ℤ : (x y : ℤ) → twelveTimesℤ (x +ℤ y) ≡ twelveTimesℤ x +ℤ twelveTimesℤ y
twelveTimes-+ℤ x y =
 let fx = fourTimesℤ x in
 let fy = fourTimesℤ y in
 let ex = eightTimesℤ x in
 let ey = eightTimesℤ y in
 trans
   refl
   (trans
     (cong (λ t → t +ℤ eightTimesℤ (x +ℤ y)) (fourTimes-+ℤ x y))
     (trans
       (cong (λ t → (fx +ℤ fy) +ℤ t) (eightTimes-+ℤ x y))
       (trans
        (+ℤ-assoc fx fy (ex +ℤ ey))
        (trans
         (cong (λ t → fx +ℤ t) (swapHeadℤ fy ex ey))
         (trans
          (sym (+ℤ-assoc fx ex (fy +ℤ ey)))
```

```
        refl)))))

twelveTimes-neg : (x : ℤ) → twelveTimesℤ (negℤ x) ≡ negℤ (twelveTimesℤ x)
twelveTimes-neg x =
 trans
  refl
  (trans
    (cong (λ t → t +ℤ eightTimesℤ (negℤ x)) (sym (neg-fourTimesℤ x)))
    (trans
      (cong (λ t → negℤ (fourTimesℤ x) +ℤ t) (eightTimes-neg x))
      (trans
       (sym (neg-+ℤ (fourTimesℤ x) (eightTimesℤ x)))
       refl)))

-- § sumFin4 commutes with twelveTimes
sumFin4-twelveTimes : (v : Vec4ℤ) →
 sumFin4ℤ (λ i → twelveTimesℤ (v i)) ≡ twelveTimesℤ (sumFin4ℤ v)
sumFin4-twelveTimes v =
 let fv : Vec4ℤ
     fv i = fourTimesℤ (v i)
 in
 let ev : Vec4ℤ
     ev i = eightTimesℤ (v i)
 in
 trans
  (sumFin4-+Vec4ℤ fv ev)
  (trans
    (cong (λ t → t +ℤ sumFin4ℤ ev) (sumFin4-fourTimes v))
    (trans
      (cong (λ t → fourTimesℤ (sumFin4ℤ v) +ℤ t) (sumFin4-eightTimes v))
      refl))

-- § reassociation helper for triple-block sum
reassoc3-addConst : (A B C k : ℤ) →
 (A +ℤ k) +ℤ ((B +ℤ k) +ℤ (C +ℤ k)) ≡ (A +ℤ (B +ℤ C)) +ℤ (k +ℤ (k +ℤ k))
reassoc3-addConst A B C k =
 let
  x = A +ℤ k
  y = B +ℤ k
  z = C +ℤ k

  step1 : x +ℤ (y +ℤ z) ≡ (x +ℤ y) +ℤ z
  step1 = sym (+ℤ-assoc x y z)

  step2 : x +ℤ y ≡ (A +ℤ B) +ℤ (k +ℤ k)
  step2 =
    trans
     (+ℤ-assoc A k (B +ℤ k))
     (trans
      (cong (λ t → A +ℤ t) (swapHeadℤ k B k))
      (sym (+ℤ-assoc A B (k +ℤ k))))

  step3 : (x +ℤ y) +ℤ z ≡ ((A +ℤ B) +ℤ (k +ℤ k)) +ℤ (C +ℤ k)
  step3 = cong (λ t → t +ℤ z) step2

  step4 : ((A +ℤ B) +ℤ (k +ℤ k)) +ℤ (C +ℤ k) ≡ (A +ℤ B) +ℤ ((k +ℤ k) +ℤ (C +ℤ k))
  step4 = +ℤ-assoc (A +ℤ B) (k +ℤ k) (C +ℤ k)

  step5 : (k +ℤ k) +ℤ (C +ℤ k) ≡ C +ℤ ((k +ℤ k) +ℤ k)
  step5 = swapHeadℤ (k +ℤ k) C k

  step6 : ((A +ℤ B) +ℤ C) ≡ A +ℤ (B +ℤ C)
```

```
  step6 = +ℤ-assoc A B C

  step7 : ((k +ℤ k) +ℤ k) ≡ k +ℤ (k +ℤ k)
  step7 = +ℤ-assoc k k k
 in
  trans
    step1
    (trans
      step3
      (trans
       step4
       (trans
        (cong (λ t → (A +ℤ B) +ℤ t) step5)
        (trans
         (sym (+ℤ-assoc (A +ℤ B) C ((k +ℤ k) +ℤ k)))
         (trans
          (cong (λ t → t +ℤ ((k +ℤ k) +ℤ k)) step6)
          (cong (λ t → (A +ℤ (B +ℤ C)) +ℤ t) step7))))))

– § Law 14H.8: global sum of K12 Laplacian = 0
law14H-8-sumL12-0 : (v : Vec12ℤ) → sum12ℤ (K12LaplacianVec12ℤ v) ≡ 0ℤ
law14H-8-sumL12-0 v =
 let
  s = sum12ℤ v
  s0 = sumFin4ℤ (block0 v)
  s1 = sumFin4ℤ (block1 v)
  s2 = sumFin4ℤ (block2 v)

  part0 = λ i → twelveTimesℤ (block0 v i) +ℤ negℤ s
  part1 = λ i → twelveTimesℤ (block1 v i) +ℤ negℤ s
  part2 = λ i → twelveTimesℤ (block2 v i) +ℤ negℤ s

  step0 :
    sum12ℤ (K12LaplacianVec12ℤ v) ≡ sumFin4ℤ part0 +ℤ (sumFin4ℤ part1 +ℤ sumFin4ℤ part2)
  step0 = refl

  step1 :
    sumFin4ℤ part0 ≡ sumFin4ℤ (λ i → twelveTimesℤ (block0 v i)) +ℤ fourTimesℤ (negℤ s)
  step1 = sumFin4-addConst (λ i → twelveTimesℤ (block0 v i)) (negℤ s)

  step2 :
    sumFin4ℤ part1 ≡ sumFin4ℤ (λ i → twelveTimesℤ (block1 v i)) +ℤ fourTimesℤ (negℤ s)
  step2 = sumFin4-addConst (λ i → twelveTimesℤ (block1 v i)) (negℤ s)

  step3 :
    sumFin4ℤ part2 ≡ sumFin4ℤ (λ i → twelveTimesℤ (block2 v i)) +ℤ fourTimesℤ (negℤ s)
  step3 = sumFin4-addConst (λ i → twelveTimesℤ (block2 v i)) (negℤ s)

  step4 :
    sum12ℤ (K12LaplacianVec12ℤ v) ≡
      (sumFin4ℤ (λ i → twelveTimesℤ (block0 v i)) +ℤ fourTimesℤ (negℤ s)) +ℤ
      ((sumFin4ℤ (λ i → twelveTimesℤ (block1 v i)) +ℤ fourTimesℤ (negℤ s)) +ℤ
       (sumFin4ℤ (λ i → twelveTimesℤ (block2 v i)) +ℤ fourTimesℤ (negℤ s)))
  step4 =
    trans
      step0
      (trans
       (cong (λ t → t +ℤ (sumFin4ℤ part1 +ℤ sumFin4ℤ part2)) step1)
       (trans
        (cong
         (λ t → (sumFin4ℤ (λ i → twelveTimesℤ (block0 v i)) +ℤ fourTimesℤ (negℤ s)) +ℤ t)
         (cong (λ t → t +ℤ sumFin4ℤ part2) step2))
```

```
        (cong
         (λ t →
          (sumFin4ℤ (λ i → twelveTimesℤ (block₀ v i)) +ℤ fourTimesℤ (negℤ s)) +ℤ
          ((sumFin4ℤ (λ i → twelveTimesℤ (block₁ v i)) +ℤ fourTimesℤ (negℤ s)) +ℤ t))
         step3)))

  step5 :
    sumFin4ℤ (λ i → twelveTimesℤ (block₀ v i)) ≡ twelveTimesℤ s0
  step5 = sumFin4-twelveTimes (block₀ v)

  step6 :
    sumFin4ℤ (λ i → twelveTimesℤ (block₁ v i)) ≡ twelveTimesℤ s1
  step6 = sumFin4-twelveTimes (block₁ v)

  step7 :
    sumFin4ℤ (λ i → twelveTimesℤ (block₂ v i)) ≡ twelveTimesℤ s2
  step7 = sumFin4-twelveTimes (block₂ v)

  step8 :
    sum12ℤ (K12LaplacianVec12ℤ v) ≡
      (twelveTimesℤ s0 +ℤ fourTimesℤ (negℤ s)) +ℤ
      ((twelveTimesℤ s1 +ℤ fourTimesℤ (negℤ s)) +ℤ (twelveTimesℤ s2 +ℤ fourTimesℤ (negℤ s)))
  step8 =
    trans
      step4
      (trans
       (cong
        (λ t → (t +ℤ fourTimesℤ (negℤ s)) +ℤ ((sumFin4ℤ (λ i → twelveTimesℤ (block₁ v i)) +ℤ fourTimesℤ (negℤ s)) +ℤ (sumFin4ℤ (λ i → twelveTimesℤ
        step5)
       (trans
        (cong
         (λ t → (twelveTimesℤ s0 +ℤ fourTimesℤ (negℤ s)) +ℤ ((t +ℤ fourTimesℤ (negℤ s)) +ℤ (sumFin4ℤ (λ i → twelveTimesℤ (block₂ v i)) +ℤ fourTimesℤ
         step6)
        (cong
         (λ t → (twelveTimesℤ s0 +ℤ fourTimesℤ (negℤ s)) +ℤ ((twelveTimesℤ s1 +ℤ fourTimesℤ (negℤ s)) +ℤ (t +ℤ fourTimesℤ (negℤ s))))
         step7)))

  step9 :
    (twelveTimesℤ s0 +ℤ fourTimesℤ (negℤ s)) +ℤ
    ((twelveTimesℤ s1 +ℤ fourTimesℤ (negℤ s)) +ℤ (twelveTimesℤ s2 +ℤ fourTimesℤ (negℤ s))) ≡
      (twelveTimesℤ s0 +ℤ (twelveTimesℤ s1 +ℤ twelveTimesℤ s2)) +ℤ
      (fourTimesℤ (negℤ s) +ℤ (fourTimesℤ (negℤ s) +ℤ fourTimesℤ (negℤ s)))
  step9 = reassoc3-addConst (twelveTimesℤ s0) (twelveTimesℤ s1) (twelveTimesℤ s2) (fourTimesℤ (negℤ s))

  step10 : twelveTimesℤ s0 +ℤ (twelveTimesℤ s1 +ℤ twelveTimesℤ s2) ≡ twelveTimesℤ s
  step10 =
    trans
      (cong (λ t → twelveTimesℤ s0 +ℤ t) (sym (twelveTimes-+ℤ s1 s2)))
      (sym (twelveTimes-+ℤ s0 (s1 +ℤ s2)))

  step11 : fourTimesℤ (negℤ s) +ℤ (fourTimesℤ (negℤ s) +ℤ fourTimesℤ (negℤ s)) ≡ negℤ (twelveTimesℤ s)
  step11 = trans refl (twelveTimes-neg s)
  step12 = +ℤ-inv-right (twelveTimesℤ s)
in
trans
  step8
  (trans
    step9
    (trans
      (cong
       (λ t → t +ℤ (fourTimesℤ (negℤ s) +ℤ (fourTimesℤ (negℤ s) +ℤ fourTimesℤ (negℤ s))))
       step10)
```

```
    (trans
     (cong (λ t → twelveTimesℤ s +ℤ t) step11)
     step12)))
```

K_{12} Operator Annihilation

The annihilation relations between J_{12} and L_{12} are forced here. Once Law 14H.8 eliminates the total sum of $L_{12}v$, both mixed composites collapse to zero and the double Laplacian collapses to $12 \cdot L_{12}$.

```
-- § Law 14H.9: J₁₂(L₁₂ v) = 0
law14H-9-JL-zero : (v : Vec12ℤ) → Vec12Eq (J12Vec12ℤ (K12LaplacianVec12ℤ v)) zeroVec12ℤ
law14H-9-JL-zero v =
 let sum0 = law14H-8-sumL12-0 v in
 (λ _ → sum0) ,
 ((λ _ → sum0) ,
  (λ _ → sum0))

-- § Law 14H.10: L₁₂(J₁₂ v) = 0
law14H-10-LJ-zero : (v : Vec12ℤ) → Vec12Eq (K12LaplacianVec12ℤ (J12Vec12ℤ v)) zeroVec12ℤ
law14H-10-LJ-zero v =
 let s = sum12ℤ v in
 let sj = sum12-J12 v in
 ( λ _ →
     trans
       (cong (λ t → twelveTimesℤ s +ℤ negℤ t) sj)
       (+ℤ-inv-right (twelveTimesℤ s))
 ) ,
 (( λ _ →
       trans
        (cong (λ t → twelveTimesℤ s +ℤ negℤ t) sj)
        (+ℤ-inv-right (twelveTimesℤ s))
  ) ,
  ( λ _ →
       trans
        (cong (λ t → twelveTimesℤ s +ℤ negℤ t) sj)
        (+ℤ-inv-right (twelveTimesℤ s))
  ))

-- § Law 14H.11: L₁₂² = 12·L₁₂
law14H-11-LL-twelveL : (v : Vec12ℤ) → Vec12Eq (K12LaplacianVec12ℤ (K12LaplacianVec12ℤ v)) (twelveVec12ℤ (K12LaplacianVec12ℤ v))
law14H-11-LL-twelveL v =
 let sum0 = law14H-8-sumL12-0 v in
 ( λ i →
     trans
       (cong (λ t → twelveTimesℤ (block₀ (K12LaplacianVec12ℤ v) i) +ℤ negℤ t) sum0)
       (+ℤ-zero-right (twelveTimesℤ (block₀ (K12LaplacianVec12ℤ v) i)))
 ) ,
 (( λ i →
       trans
        (cong (λ t → twelveTimesℤ (block₁ (K12LaplacianVec12ℤ v) i) +ℤ negℤ t) sum0)
        (+ℤ-zero-right (twelveTimesℤ (block₁ (K12LaplacianVec12ℤ v) i)))
  ) ,
  ( λ i →
       trans
        (cong (λ t → twelveTimesℤ (block₂ (K12LaplacianVec12ℤ v) i) +ℤ negℤ t) sum0)
        (+ℤ-zero-right (twelveTimesℤ (block₂ (K12LaplacianVec12ℤ v) i)))
  ))
```

K_{12} Spectral Classification

The spectrum of L_{12} is classified without residue. Sum-zero forces the 12-eigenspace, constants force the kernel, and the image is forced into the same eigen-constraint by the operator laws.

```
-- § Law 14H.12: sum-zero ⇒ 12-eigenvector
law14H-12-sum0-eigen12 : (v : Vec12ℤ) → sum12ℤ v ≡ 0ℤ → Vec12Eq (K12LaplacianVec12ℤ v) (twelveVec12ℤ v)
law14H-12-sum0-eigen12 v sum0 =
 ( λ i →
     trans
       (cong (λ s → twelveTimesℤ (block₀ v i) +ℤ negℤ s) sum0)
       (+ℤ-zero-right (twelveTimesℤ (block₀ v i)))
 ) ,
 (( λ i →
       trans
         (cong (λ s → twelveTimesℤ (block₁ v i) +ℤ negℤ s) sum0)
         (+ℤ-zero-right (twelveTimesℤ (block₁ v i)))
  ) ,
  ( λ i →
       trans
         (cong (λ s → twelveTimesℤ (block₂ v i) +ℤ negℤ s) sum0)
         (+ℤ-zero-right (twelveTimesℤ (block₂ v i)))
  ))

-- § Law 14H.13: 12-eigenvector ⇒ sum-zero
law14H-13-eigen12→sum0 : (v : Vec12ℤ) → Vec12Eq (K12LaplacianVec12ℤ v) (twelveVec12ℤ v) → sum12ℤ v ≡ 0ℤ
law14H-13-eigen12→sum0 v eigen12 =
 let a = twelveTimesℤ (block₀ v g0) in
 let s = sum12ℤ v in
 let eq₀ : a +ℤ negℤ s ≡ a
     eq₀ = fst eigen12 g0
 in
 negℤ-zero→zero s (+ℤ-cancel-left a (negℤ s) eq₀)

-- § Law 14H.14: constant vectors lie in the kernel
law14H-14-const-eigen0 : (x : ℤ) → Vec12Eq (K12LaplacianVec12ℤ (constVec12ℤ x)) zeroVec12ℤ
law14H-14-const-eigen0 x =
 ( λ _ →
     trans
       (cong (λ s → twelveTimesℤ x +ℤ negℤ s) (sum12-const x))
       (+ℤ-inv-right (twelveTimesℤ x))
 ) ,
 (( λ _ →
       trans
         (cong (λ s → twelveTimesℤ x +ℤ negℤ s) (sum12-const x))
         (+ℤ-inv-right (twelveTimesℤ x))
  ) ,
  ( λ _ →
       trans
         (cong (λ s → twelveTimesℤ x +ℤ negℤ s) (sum12-const x))
         (+ℤ-inv-right (twelveTimesℤ x))
  ))

-- § Law 14H.15: kernel condition — L₁₂ v = 0 ⇔ 12·v = J₁₂ v
law14H-15-L0→twelveEqJ : (v : Vec12ℤ) → Vec12Eq (K12LaplacianVec12ℤ v) zeroVec12ℤ → Vec12Eq (twelveVec12ℤ v) (J12Vec12ℤ v)
law14H-15-L0→twelveEqJ v L0 =
 let s = sum12ℤ v in
 ( λ i →
     let a = twelveTimesℤ (block₀ v i) in
     let eq₀ : a +ℤ negℤ s ≡ 0ℤ
```

```
        eq0 = fst L0 i
    in
    let step1 : (a +ℤ negℤ s) +ℤ s ≡ 0ℤ +ℤ s
        step1 = cong (λ t → t +ℤ s) eq0
        step2 : a +ℤ (negℤ s +ℤ s) ≡ 0ℤ +ℤ s
        step2 = trans (sym (+ℤ-assoc a (negℤ s) s)) step1
        step3 : a +ℤ 0ℤ ≡ 0ℤ +ℤ s
        step3 = trans (sym (cong (λ t → a +ℤ t) (+ℤ-inv-left s))) step2
    in
    trans
      (trans (sym (+ℤ-zero-right a)) step3)
      (+ℤ-zero-left s)
) ,
(( λ i →
      let a = twelveTimesℤ (block1 v i) in
      let eq0 : a +ℤ negℤ s ≡ 0ℤ
          eq0 = fst (snd L0) i
      in
      let step1 : (a +ℤ negℤ s) +ℤ s ≡ 0ℤ +ℤ s
          step1 = cong (λ t → t +ℤ s) eq0
          step2 : a +ℤ (negℤ s +ℤ s) ≡ 0ℤ +ℤ s
          step2 = trans (sym (+ℤ-assoc a (negℤ s) s)) step1
          step3 : a +ℤ 0ℤ ≡ 0ℤ +ℤ s
          step3 = trans (sym (cong (λ t → a +ℤ t) (+ℤ-inv-left s))) step2
      in
      trans
        (trans (sym (+ℤ-zero-right a)) step3)
        (+ℤ-zero-left s)
  ) ,
 ( λ i →
      let a = twelveTimesℤ (block2 v i) in
      let eq0 : a +ℤ negℤ s ≡ 0ℤ
          eq0 = snd (snd L0) i
      in
      let step1 : (a +ℤ negℤ s) +ℤ s ≡ 0ℤ +ℤ s
          step1 = cong (λ t → t +ℤ s) eq0
          step2 : a +ℤ (negℤ s +ℤ s) ≡ 0ℤ +ℤ s
          step2 = trans (sym (+ℤ-assoc a (negℤ s) s)) step1
          step3 : a +ℤ 0ℤ ≡ 0ℤ +ℤ s
          step3 = trans (sym (cong (λ t → a +ℤ t) (+ℤ-inv-left s))) step2
      in
      trans
        (trans (sym (+ℤ-zero-right a)) step3)
        (+ℤ-zero-left s)
  ))

law14H-15-twelveEqJ→L0 : (v : Vec12ℤ) → Vec12Eq (twelveVec12ℤ v) (J12Vec12ℤ v) → Vec12Eq (K12LaplacianVec12ℤ v) zeroVec12ℤ
law14H-15-twelveEqJ→L0 v twelveEqJ =
 let s = sum12ℤ v in
 ( λ i →
    trans
      (cong (λ t → t +ℤ negℤ s) (fst twelveEqJ i))
      (+ℤ-inv-right s)
) ,
(( λ i →
      trans
        (cong (λ t → t +ℤ negℤ s) (fst (snd twelveEqJ) i))
        (+ℤ-inv-right s)
  ) ,
 ( λ i →
      trans
        (cong (λ t → t +ℤ negℤ s) (snd (snd twelveEqJ) i))
```

```
        (+ℤ-inv-right s)
  ))

– § Law 14H.16: image vectors are 12-eigenvectors
law14H-16-image⊆eigen12 : (v : Vec12ℤ) → Vec12Eq (K12LaplacianVec12ℤ (K12LaplacianVec12ℤ v)) (twelveVec12ℤ (K12LaplacianVec12ℤ v))
law14H-16-image⊆eigen12 = law14H-11-LL-twelveL

– § Law 14H.17: sum-zero ⇒ twelve-scaled image witness
law14H-17-sum0→twelveInImage : (w : Vec12ℤ) → sum12ℤ w ≡ 0ℤ → Σ Vec12ℤ (λ v → Vec12Eq (K12LaplacianVec12ℤ v) (twelveVec12ℤ w))
law14H-17-sum0→twelveInImage w sum0 = w , law14H-12-sum0-eigen12 w sum0
```

Full Survivor Spectral Package

The forced spectral consequences of the full three-copy survivor are packaged here. The package introduces no new structure; it only collects the already-eliminated cases into a single witness type for downstream transport.

```
– § full-survivor spectral package type
Survivor3FullSpectralPackage : Vec12ℤ → Set
Survivor3FullSpectralPackage v =
 (sum12ℤ (laplacianSurvivorVec12ℤ survivor3-full v) ≡ 0ℤ) ×
 (Vec12Eq (J12Vec12ℤ (laplacianSurvivorVec12ℤ survivor3-full v)) zeroVec12ℤ) ×
 ((sum12ℤ v ≡ 0ℤ → Vec12Eq (laplacianSurvivorVec12ℤ survivor3-full v) (twelveVec12ℤ v)) ×
  (Vec12Eq (laplacianSurvivorVec12ℤ survivor3-full v) (twelveVec12ℤ v) → sum12ℤ v ≡ 0ℤ)) ×
 (Vec12Eq (laplacianSurvivorVec12ℤ survivor3-full (laplacianSurvivorVec12ℤ survivor3-full v))
          (twelveVec12ℤ (laplacianSurvivorVec12ℤ survivor3-full v)))

– § Law 14H.18: full survivor spectral package
law14H-18-survivor3-full-spectral-package : (v : Vec12ℤ) → Survivor3FullSpectralPackage v
law14H-18-survivor3-full-spectral-package v =
 law14H-8-sumL12-0 v ,
 (law14H-9-JL-zero v ,
  ((law14H-12-sum0-eigen12 v , law14H-13-eigen12→sum0 v) ,
   law14H-16-image⊆eigen12 v))
```

The spectral theory of the coupled and triple K_4 Laplacians is complete. Every iterated operator word collapses to one of four normal forms—identity, pure L-power, pure J-power, or zero—and the eigenvalue spectrum is exhausted by $\{0, 4, 12\}$. The survivor structure of K_4 is fully extracted into operator algebra, and no spectral degree of freedom remains.

The spectral data is exact. The arithmetic on which it rests—$\mathbb{Z}$ and $\mathbb{Q}$—requires order and distance infrastructure for convergence arguments: additive order monotonicity, rational multiplication, ε-splitting, and distance laws. These are forced algebraic consequences of the integer and rational definitions already established. With those laws in place, the spectral data has a metric home and the passage to the reals is forced by the Cauchy gaps rational arithmetic cannot close internally.

The graph has 4 vertices and an eigenvalue ratio 3:1 (three copies of eigenvalue 4, one copy of eigenvalue 0). The spectral fingerprint underlying the forced graph evaluation is fully determined.

Chapter 35

Additive Order Laws for $\leq_{\mathbb{Q}}$

Cauchy convergence arguments require combining two distance bounds into one: if $|x_m - x_n| < \varepsilon/2$ and $|x_n - x_k| < \varepsilon/2$, then $|x_m - x_k| < \varepsilon$. This chapter establishes the additive monotonicity and sum-doubling laws for the rational order. Nonnegative rationals must remain closed under addition, and each order comparison must be stable under adding the same quantity on either side. These constraints force the additive order toolkit used later in the Cauchy arguments.

Nonnegativity Extraction and Closure

Nonnegativity must survive passage from rationals to numerators and back through addition. The reduction always collapses to integer nonnegativity after clearing denominators.

```
-- § nonneg integer from natural
0≤ℤ-fromℕℤ : (n : ℕ) → 0ℤ ≤ℤ fromℕℤ n
0≤ℤ-fromℕℤ zero = tt
0≤ℤ-fromℕℤ (suc n) = tt

-- § nonneg rational ⇒ nonneg numerator
0≤ℚ→0≤ℤnum : (q : ℚ) → 0ℚ ≤ℚ q → 0ℤ ≤ℤ num q
0≤ℚ→0≤ℤnum (a / b) qnonneg =
 let
  lhs0 : (0ℤ *ℤ ⁺toℤ b) ≡ 0ℤ
  lhs0 = *ℤ-zero-left (⁺toℤ b)

  one⁺ℤ≡oneℤ : ⁺toℤ one⁺ ≡ oneℤ
  one⁺ℤ≡oneℤ = refl

  rhs1 : (a *ℤ ⁺toℤ one⁺) ≡ a
  rhs1 = trans (cong (λ t → a *ℤ t) one⁺ℤ≡oneℤ) (*ℤ-one-right a)
 in
 ≤ℤ-resp-≡ʳ rhs1 (≤ℤ-resp-≡ˡ lhs0 qnonneg)

-- § nonnegativity closed under rational addition
0≤ℚ-+ℚ : (p q : ℚ) → 0ℚ ≤ℚ p → 0ℚ ≤ℚ q → 0ℚ ≤ℚ (p +ℚ q)
0≤ℚ-+ℚ (a / b) (c / d) p≥0 q≥0 =
 let
  a≥0 : 0ℤ ≤ℤ a
  a≥0 = 0≤ℚ→0≤ℤnum (a / b) p≥0

  c≥0 : 0ℤ ≤ℤ c
```

```
c≥0 = 0≤ℚ→0≤ℤnum (c / d) q≥0

nonnegScale : (z : ℤ) → (s : ℕ⁺) → 0ℤ ≤ℤ z → 0ℤ ≤ℤ (z *ℤ ⁺toℤ s)
nonnegScale z s z≥0 =
 ≤ℤ-resp-≡ˡ (*ℤ-zero-left (⁺toℤ s))
  (≤ℤ-mul-pos-right 0ℤ z s z≥0)

ad≥0 : 0ℤ ≤ℤ (a *ℤ ⁺toℤ d)
ad≥0 = nonnegScale a d a≥0

cb≥0 : 0ℤ ≤ℤ (c *ℤ ⁺toℤ b)
cb≥0 = nonnegScale c b c≥0

sum≥0 : 0ℤ ≤ℤ ((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b))
sum≥0 =
 let
  adNat : Σ ℕ (λ k → (a *ℤ ⁺toℤ d) ≡ fromℕℤ k)
  adNat = 0≤ℤ→fromℕℤ (a *ℤ ⁺toℤ d) ad≥0

  cbNat : Σ ℕ (λ k → (c *ℤ ⁺toℤ b) ≡ fromℕℤ k)
  cbNat = 0≤ℤ→fromℕℤ (c *ℤ ⁺toℤ b) cb≥0

  k₁ : ℕ
  k₁ = fst adNat

  k₂ : ℕ
  k₂ = fst cbNat

  ad≡ : (a *ℤ ⁺toℤ d) ≡ fromℕℤ k₁
  ad≡ = snd adNat

  cb≡ : (c *ℤ ⁺toℤ b) ≡ fromℕℤ k₂
  cb≡ = snd cbNat

  sumForm : (a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b) ≡ fromℕℤ (k₁ +ℕ k₂)
  sumForm =
   trans
    (cong (λ t → t +ℤ (c *ℤ ⁺toℤ b)) ad≡)
    (trans
     (cong (λ t → fromℕℤ k₁ +ℤ t) cb≡)
     (fromℕℤ-+ℤ k₁ k₂))
 in
 ≤ℤ-resp-≡ʳ (sym sumForm) (0≤ℤ-fromℕℤ (k₁ +ℕ k₂))

lhs0 : (0ℤ *ℤ ⁺toℤ (b *⁺ d)) ≡ 0ℤ
lhs0 = *ℤ-zero-left (⁺toℤ (b *⁺ d))

rhs1 : (((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b)) *ℤ ⁺toℤ one⁺) ≡ ((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b))
rhs1 = *ℤ-one-right ((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b))
in
≤ℤ-resp-≡ˡ (sym lhs0) (≤ℤ-resp-≡ʳ (sym rhs1) sum≥0)
```

Sum-Doubling Bounds

If $0 \leq x, y, z$ with $x \leq z$ and $y \leq z$, then $x + y \leq z + z$. The integer version lifts through the natural-number representation, and the rational version is forced by the same bound after scaling to a common denominator.

```
– § integer sum-doubling: x≤z, y≤z ⇒ x+y ≤ z+z (nonneg)
≤ℤ-sum≤double-nonneg : {x y z : ℤ} →
 0ℤ ≤ℤ x → 0ℤ ≤ℤ y → 0ℤ ≤ℤ z → x ≤ℤ z → y ≤ℤ z → (x +ℤ y) ≤ℤ (z +ℤ z)
≤ℤ-sum≤double-nonneg {x} {y} {z} xnonneg ynonneg znonneg x≤z y≤z =
 let
  xm : Σ ℕ (λ n → x ≡ fromℕℤ n)
  xm = 0≤ℤ→fromℕℤ x xnonneg

  ym : Σ ℕ (λ n → y ≡ fromℕℤ n)
  ym = 0≤ℤ→fromℕℤ y ynonneg

  zm : Σ ℕ (λ n → z ≡ fromℕℤ n)
  zm = 0≤ℤ→fromℕℤ z znonneg

  m : ℕ
  m = fst xm

  n : ℕ
  n = fst ym

  k : ℕ
  k = fst zm

  x≡ : x ≡ fromℕℤ m
  x≡ = snd xm

  y≡ : y ≡ fromℕℤ n
  y≡ = snd ym

  z≡ : z ≡ fromℕℤ k
  z≡ = snd zm

  x≤zNat : m ≤ k
  x≤zNat = ≤ℤ-fromℕℤ-reflect (≤ℤ-resp-≡ˡ x≡ (≤ℤ-resp-≡ʳ z≡ x≤z))

  y≤zNat : n ≤ k
  y≤zNat = ≤ℤ-fromℕℤ-reflect (≤ℤ-resp-≡ˡ y≡ (≤ℤ-resp-≡ʳ z≡ y≤z))

  step₁ : (m +ℕ n) ≤ (k +ℕ n)
  step₁ =
   subst (λ t → t ≤ (k +ℕ n))
    (sym (+ℕ-comm m n))
    (subst (λ t → (n +ℕ m) ≤ t)
     (+ℕ-comm n k)
     (≤-+ℕ-monoˡ x≤zNat n))

  step₂ : (k +ℕ n) ≤ (k +ℕ k)
  step₂ = ≤-+ℕ-monoˡ y≤zNat k

  sumNat : (m +ℕ n) ≤ (k +ℕ k)
  sumNat = ≤-trans step₁ step₂

  sumℤ : fromℕℤ (m +ℕ n) ≤ℤ fromℕℤ (k +ℕ k)
  sumℤ = fromℕℤ-mono sumNat

  lhsEq : (x +ℤ y) ≡ fromℕℤ (m +ℕ n)
  lhsEq =
   trans
    (cong (λ t → t +ℤ y) x≡)
    (trans
     (cong (λ t → fromℕℤ m +ℤ t) y≡)
     (fromℕℤ-+ℤ m n))
```

```
  rhsEq : (z +ℤ z) ≡ fromℕℤ (k +ℕ k)
  rhsEq =
   trans
    (cong (λ t → t +ℤ z) z≡)
    (trans
     (cong (λ t → fromℕℤ k +ℤ t) z≡)
     (fromℕℤ-+ℤ k k))
in
≤ℤ-resp-≡ˡ (sym lhsEq) (≤ℤ-resp-≡ʳ (sym rhsEq) sumℤ)
```

Step 2: Rational Sum-Doubling. The rational counterpart lifts integer sum-doubling through the cross-multiplication bridge.

```
-- § rational sum-doubling: p≤r, q≤r ⇒ p+q ≤ r+r (nonneg)
≤ℚ-sum≤double-nonneg : (p q r : ℚ) → 0ℚ ≤ℚ p → 0ℚ ≤ℚ q → 0ℚ ≤ℚ r → p ≤ℚ r → q ≤ℚ r → (p +ℚ q) ≤ℚ (r +ℚ r)
≤ℚ-sum≤double-nonneg (a / b) (c / d) (e / f) pnonneg qnonneg rnonneg p≤r q≤r =
 let
  bd : ℕ⁺
  bd = b *⁺ d

  ff : ℕ⁺
  ff = f *⁺ f

  bdf : ℕ⁺
  bdf = bd *⁺ f

  a≥0 : 0ℤ ≤ℤ a
  a≥0 = 0≤ℚ→0≤ℤnum (a / b) pnonneg

  c≥0 : 0ℤ ≤ℤ c
  c≥0 = 0≤ℚ→0≤ℤnum (c / d) qnonneg

  e≥0 : 0ℤ ≤ℤ e
  e≥0 = 0≤ℚ→0≤ℤnum (e / f) rnonneg

  nonnegScale : (z : ℤ) → (s : ℕ⁺) → 0ℤ ≤ℤ z → 0ℤ ≤ℤ (z *ℤ ⁺toℤ s)
  nonnegScale z s z≥0 =
   ≤ℤ-resp-≡ˡ (*ℤ-zero-left (⁺toℤ s))
    (≤ℤ-mul-pos-right 0ℤ z s z≥0)

  X : ℤ
  X = (a *ℤ ⁺toℤ d) *ℤ ⁺toℤ ff

  Y : ℤ
  Y = (c *ℤ ⁺toℤ b) *ℤ ⁺toℤ ff

  Z : ℤ
  Z = ((e *ℤ ⁺toℤ bd) *ℤ ⁺toℤ f)

  X≥0 : 0ℤ ≤ℤ X
  X≥0 = nonnegScale (a *ℤ ⁺toℤ d) ff (nonnegScale a d a≥0)

  Y≥0 : 0ℤ ≤ℤ Y
  Y≥0 = nonnegScale (c *ℤ ⁺toℤ b) ff (nonnegScale c b c≥0)

  Z≥0 : 0ℤ ≤ℤ Z
  Z≥0 = nonnegScale (e *ℤ ⁺toℤ bd) f (nonnegScale e bd e≥0)

  -- scale p≤r to common base
```

```
pScaled₁ : ((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ d) ≤ℤ ((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d)
pScaled₁ = ≤ℤ-mul-pos-right (a *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ b) d p≤r

pScaled₂ : (((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ≤ℤ (((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d) *ℤ ⁺toℤ f)
pScaled₂ = ≤ℤ-mul-pos-right ((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ d) ((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d) f pScaled₁

qScaled₁ : ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b) ≤ℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b)
qScaled₁ = ≤ℤ-mul-pos-right (c *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ d) b q≤r

qScaled₂ : (((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) ≤ℤ (((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) *ℤ ⁺toℤ f)
qScaled₂ = ≤ℤ-mul-pos-right ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b) ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) f qScaled₁

-- rewrite both sides into X ≤ Z, Y ≤ Z
swapScale : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
swapScale x u v =
 trans
  (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
  (trans
   (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
   (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

scaleSplit : (x : ℤ) → (u v : ℕ⁺) → x *ℤ ⁺toℤ (u *⁺ v) ≡ (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v
scaleSplit x u v =
 trans
  (cong (λ t → x *ℤ t) (⁺toℤ-*⁺ u v))
  (sym (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v)))

Xeq : (((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ≡ X
Xeq =
 trans
  (cong (λ t → t *ℤ ⁺toℤ f) (swapScale a f d))
  (sym (scaleSplit (a *ℤ ⁺toℤ d) f f))

Zeq₁ : (((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ≡ Z
Zeq₁ =
 cong (λ t → t *ℤ ⁺toℤ f) (sym (scaleSplit e b d))

Zeq₂ : (((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) ≡ Z
Zeq₂ =
 trans
  (cong (λ t → t *ℤ ⁺toℤ f) (swapScale e d b))
  Zeq₁

X≤Z : X ≤ℤ Z
X≤Z =
 subst (λ t → X ≤ℤ t) Zeq₁
  (subst (λ t → t ≤ℤ (((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d) *ℤ ⁺toℤ f))
   Xeq
   pScaled₂)

Yeq : (((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) ≡ Y
Yeq =
 trans
  (cong (λ t → t *ℤ ⁺toℤ f) (swapScale c f b))
  (sym (scaleSplit (c *ℤ ⁺toℤ b) f f))

Y≤Z : Y ≤ℤ Z
Y≤Z =
 subst (λ t → Y ≤ℤ t) Zeq₂
  (subst (λ t → t ≤ℤ (((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) *ℤ ⁺toℤ f))
   Yeq
   qScaled₂)
```

```
  sumLe : (X +ℤ Y) ≤ℤ (Z +ℤ Z)
  sumLe = ≤ℤ-sum≤double-nonneg X≥0 Y≥0 Z≥0 X≤Z Y≤Z

  lhsEq : (((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b)) *ℤ ⁺toℤ ff) ≡ (X +ℤ Y)
  lhsEq =
   trans
    (*ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ d) (c *ℤ ⁺toℤ b) (⁺toℤ ff))
    refl

  rhsEq : (((e *ℤ ⁺toℤ f) +ℤ (e *ℤ ⁺toℤ f)) *ℤ ⁺toℤ bd) ≡ (Z +ℤ Z)
  rhsEq =
   let
    ef : ℤ
    ef = e *ℤ ⁺toℤ f

    efbd≡Z : (ef *ℤ ⁺toℤ bd) ≡ Z
    efbd≡Z =
     trans
      (*ℤ-assoc e (⁺toℤ f) (⁺toℤ bd))
      (trans
       (cong (λ t → e *ℤ t) (*ℤ-comm (⁺toℤ f) (⁺toℤ bd)))
       (sym (*ℤ-assoc e (⁺toℤ bd) (⁺toℤ f))))
   in
   trans
    (*ℤ-distrib-left-+ℤ ef ef (⁺toℤ bd))
    (cong (λ t → t +ℤ t) efbd≡Z)

 in
 ≤ℤ-resp-≡ˡ (sym lhsEq) (≤ℤ-resp-≡ʳ (sym rhsEq) sumLe)
```

Nonneg-Right Addition and Monotonicity

Adding a nonnegative term on the right preserves the order; this extends to full left and right monotonicity of rational addition. Directional ambiguity is eliminated by forcing right-monotonicity first and then transporting left-monotonicity through commutativity.

```
-- § negative normalisation step
neg≤normalize : (n m : ℕ) → (-suc m) ≤ℤ normalizeℤ n m
neg≤normalize zero zero = tt
neg≤normalize zero (suc m) = ≤-step (suc m)
neg≤normalize (suc n) zero = tt
neg≤normalize (suc n) (suc m) =
 ≤ℤ-trans negStep (neg≤normalize n m)
 where
  negStep : (-suc (suc m)) ≤ℤ (-suc m)
  negStep = s≤s (≤-step m)

-- § adding a positive integer on the right
≤ℤ-add-pos-right : (x : ℤ) → (n : ℕ) → x ≤ℤ (x +ℤ (+suc n))
≤ℤ-add-pos-right 0ℤ n = tt
≤ℤ-add-pos-right (+suc m) n = s≤s m≤m+n
 where
  m≤m+n : m ≤ (m +ℕ suc n)
  m≤m+n =
   subst (λ t → t ≤ (m +ℕ suc n))
    (+ℕ-zero-right m)
    (≤-+ℕ-monoˡ {a = zero} {b = suc n} z≤n m)
```

```
≤ℤ-add-pos-right (-suc m) n =
 let
  rhsEq : ((-suc m) +ℤ (+suc n)) ≡ normalizeℤ n m
  rhsEq =
   trans
    (cong (λ t → normalizeℤ (suc n) t) (+ℕ-zero-right (suc m)))
    refl
 in
 ≤ℤ-resp-≡ʳ (sym rhsEq) (neg≤normalize n m)

– § adding a nonneg integer on the right
≤ℤ-add-nonneg-right : (x y : ℤ) → 0ℤ ≤ℤ y → x ≤ℤ (x +ℤ y)
≤ℤ-add-nonneg-right x y y≥0 with 0≤ℤ→fromℕℤ y y≥0
... | (zero , y≡) =
 ≤ℤ-resp-≡ʳ (sym (cong (λ t → x +ℤ t) y≡)) (≤ℤ-resp-≡ʳ (sym (+ℤ-zero-right x)) (≤ℤ-refl x))
... | (suc n , y≡) =
 ≤ℤ-resp-≡ʳ (sym (cong (λ t → x +ℤ t) y≡)) (≤ℤ-add-pos-right x n)

– § adding a nonneg rational on the right preserves ≤
≤ℚ-add-nonneg-right : (p q : ℚ) → 0ℚ ≤ℚ q → p ≤ℚ (p +ℚ q)
≤ℚ-add-nonneg-right (a / b) (c / d) qnonneg =
 let
  c≥0 : 0ℤ ≤ℤ c
  c≥0 = 0≤ℚ→0≤ℤnum (c / d) qnonneg

  nonnegScale : (z : ℤ) → (s : ℕ⁺) → 0ℤ ≤ℤ z → 0ℤ ≤ℤ (z *ℤ ⁺toℤ s)
  nonnegScale z s z≥0 =
   ≤ℤ-resp-≡ˡ (*ℤ-zero-left (⁺toℤ s))
    (≤ℤ-mul-pos-right 0ℤ z s z≥0)

  x : ℤ
  x = (a *ℤ ⁺toℤ d) *ℤ ⁺toℤ b

  y : ℤ
  y = (c *ℤ ⁺toℤ b) *ℤ ⁺toℤ b

  y≥0 : 0ℤ ≤ℤ y
  y≥0 = nonnegScale (c *ℤ ⁺toℤ b) b (nonnegScale c b c≥0)

  x≤x+y : x ≤ℤ (x +ℤ y)
  x≤x+y = ≤ℤ-add-nonneg-right x y y≥0

  lhsEq : (a *ℤ ⁺toℤ (b *⁺ d)) ≡ x
  lhsEq =
   let
    scaleSplit : (z : ℤ) → (u v : ℕ⁺) → z *ℤ ⁺toℤ (u *⁺ v) ≡ (z *ℤ ⁺toℤ u) *ℤ ⁺toℤ v
    scaleSplit z u v =
     trans
      (cong (λ t → z *ℤ t) (⁺toℤ-*⁺ u v))
      (sym (*ℤ-assoc z (⁺toℤ u) (⁺toℤ v)))

    swapScale : (z : ℤ) → (u v : ℕ⁺) → (z *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (z *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
    swapScale z u v =
     trans
      (*ℤ-assoc z (⁺toℤ u) (⁺toℤ v))
      (trans
       (cong (λ t → z *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
       (sym (*ℤ-assoc z (⁺toℤ v) (⁺toℤ u))))
   in
   trans
    (trans
     (cong (λ t → a *ℤ t) (⁺toℤ-*⁺ b d))
```

```
    (sym (*ℤ-assoc a (⁺toℤ b) (⁺toℤ d))))
   (swapScale a b d)

  rhsEq : (((a *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ b)) *ℤ ⁺toℤ b) ≡ (x +ℤ y)
  rhsEq =
   trans
    (*ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ d) (c *ℤ ⁺toℤ b) (⁺toℤ b))
    refl
in
≤ℤ-resp-≡ˡ (sym lhsEq) (≤ℤ-resp-≡ʳ (sym rhsEq) x≤x+y)
```

Step 2: Rational Order Monotonicity. Right and left monotonicity for $\leq_{\mathbb{Q}}$ under addition follow from the cross-multiplication bridge.

```
– § right monotonicity: p ≤ q ⇒ (p + r) ≤ (q + r)
≤ℚ-+ℚ-mono-right : (p q r : ℚ) → p ≤ℚ q → (p +ℚ r) ≤ℚ (q +ℚ r)
≤ℚ-+ℚ-mono-right (a / b) (c / d) (e / f) p≤q =
 let
  bd : ℕ⁺
  bd = b *⁺ d

  bf : ℕ⁺
  bf = b *⁺ f

  df : ℕ⁺
  df = d *⁺ f

  p≤q-scaled₁ : ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ≤ℤ ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f)
  p≤q-scaled₁ = ≤ℤ-mul-pos-right (a *ℤ ⁺toℤ d) (c *ℤ ⁺toℤ b) f p≤q

  p≤q-scaled₂ : (((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) *ℤ ⁺toℤ f) ≤ℤ (((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) *ℤ ⁺toℤ f)
  p≤q-scaled₂ = ≤ℤ-mul-pos-right ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) f p≤q-scaled₁

  swapScale : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
  swapScale x u v =
   trans
    (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
    (trans
     (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
     (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

  scaleSplit : (x : ℤ) → (u v : ℕ⁺) → x *ℤ ⁺toℤ (u *⁺ v) ≡ (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v
  scaleSplit x u v =
   trans
    (cong (λ t → x *ℤ t) (⁺toℤ-*⁺ u v))
    (sym (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v)))

  ff : ℕ⁺
  ff = f *⁺ f

  lhsTerm₁ : ((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ df) ≡ (((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) *ℤ ⁺toℤ f)
  lhsTerm₁ =
   trans
    (scaleSplit (a *ℤ ⁺toℤ f) d f)
    (cong (λ t → t *ℤ ⁺toℤ f) (swapScale a f d))

  rhsTerm₁ : ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ bf) ≡ (((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) *ℤ ⁺toℤ f)
  rhsTerm₁ =
   trans
    (scaleSplit (c *ℤ ⁺toℤ f) b f)
```

```
  (cong (λ t → t *ℤ +toℤ f) (swapScale c f b))

 rTerm : (e *ℤ +toℤ b) *ℤ +toℤ df ≡ (e *ℤ +toℤ d) *ℤ +toℤ bf
 rTerm =
  trans
   (scaleSplit (e *ℤ +toℤ b) d f)
   (trans
    (cong (λ t → t *ℤ +toℤ f) (swapScale e b d))
    (sym (scaleSplit (e *ℤ +toℤ d) b f)))

 lhsSum : ℤ
 lhsSum = ((a *ℤ +toℤ f) +ℤ (e *ℤ +toℤ b)) *ℤ +toℤ df

 rhsSum : ℤ
 rhsSum = ((c *ℤ +toℤ f) +ℤ (e *ℤ +toℤ d)) *ℤ +toℤ bf

 lhsExpand : lhsSum ≡ ((a *ℤ +toℤ f) *ℤ +toℤ df) +ℤ ((e *ℤ +toℤ b) *ℤ +toℤ df)
 lhsExpand = *ℤ-distrib-left-+ℤ (a *ℤ +toℤ f) (e *ℤ +toℤ b) (+toℤ df)

 rhsExpand : rhsSum ≡ ((c *ℤ +toℤ f) *ℤ +toℤ bf) +ℤ ((e *ℤ +toℤ d) *ℤ +toℤ bf)
 rhsExpand = *ℤ-distrib-left-+ℤ (c *ℤ +toℤ f) (e *ℤ +toℤ d) (+toℤ bf)

 lhsT₁≤rhsT₁ : ((a *ℤ +toℤ f) *ℤ +toℤ df) ≤ℤ ((c *ℤ +toℤ f) *ℤ +toℤ bf)
 lhsT₁≤rhsT₁ =
  ≤ℤ-resp-≡ˡ (sym lhsTerm₁) (≤ℤ-resp-≡ʳ (sym rhsTerm₁) p≤q-scaled₂)

 eTerm≡ : ((e *ℤ +toℤ b) *ℤ +toℤ df) ≡ ((e *ℤ +toℤ d) *ℤ +toℤ bf)
 eTerm≡ = rTerm

 eTerm≤ : ((e *ℤ +toℤ b) *ℤ +toℤ df) ≤ℤ ((e *ℤ +toℤ d) *ℤ +toℤ bf)
 eTerm≤ = ≤ℤ-resp-≡ʳ eTerm≡ (≤ℤ-refl ((e *ℤ +toℤ b) *ℤ +toℤ df))

 sumLe : (((a *ℤ +toℤ f) *ℤ +toℤ df) +ℤ ((e *ℤ +toℤ b) *ℤ +toℤ df)) ≤ℤ (((c *ℤ +toℤ f) *ℤ +toℤ bf) +ℤ ((e *ℤ +toℤ d) *ℤ +toℤ bf))
 sumLe = ≤ℤ-+ℤ-mono lhsT₁≤rhsT₁ eTerm≤
in
≤ℤ-resp-≡ˡ (sym lhsExpand) (≤ℤ-resp-≡ʳ (sym rhsExpand) sumLe)

-- § left monotonicity: q ≤ r ⇒ (p + q) ≤ (p + r)
≤ℚ-+ℚ-mono-left : (p q r : ℚ) → q ≤ℚ r → (p +ℚ q) ≤ℚ (p +ℚ r)
≤ℚ-+ℚ-mono-left p q r q≤r =
 let
  step₁ : (q +ℚ p) ≤ℚ (r +ℚ p)
  step₁ = ≤ℚ-+ℚ-mono-right q r p q≤r

  step₂ : (p +ℚ q) ≤ℚ (q +ℚ p)
  step₂ = ≃ℚ→≤ℚˡ {p = p +ℚ q} {q = q +ℚ p} (+ℚ-comm p q)

  step₃ : (r +ℚ p) ≤ℚ (p +ℚ r)
  step₃ = ≃ℚ→≤ℚˡ {p = r +ℚ p} {q = p +ℚ r} (+ℚ-comm r p)
 in
 ≤ℚ-trans {x = p +ℚ q} {y = q +ℚ p} {z = p +ℚ r} step₂
 (≤ℚ-trans {x = q +ℚ p} {y = r +ℚ p} {z = p +ℚ r} step₁ step₃)
```

Chapter 36

K_{12} Iteration and Word Algebra

Every iterated application of the K_{12} Laplacian or global-sum operator collapses to a scaled first application. Combined with the annihilation laws $JL = LJ = 0$, this forces every word in the free monoid on $\{L_{12}, J_{12}\}$ to reduce to one of exactly four normal forms: identity, pure L-power, pure J-power, or zero. These relations force all iterated behaviour from the quadratic identities of the Triple K_4 and K_{12} spectral chapter. Induction then eliminates every mixed word except the four surviving normal forms and fixes the complete word algebra.

$\mathbf{Vec}_{12}$ Transport

Reflexivity, symmetry, transitivity for pointwise equality, plus congruence of the sum, scaling, and Laplacian operators. All transport ambiguity is eliminated by fixing how Vec_{12} equalities pass through the three basic operators used in the iteration laws.

```
-- § Vec12Eq is an equivalence
Vec12Eq-refl : (v : Vec12ℤ) → Vec12Eq v v
Vec12Eq-refl v = (λ _ → refl) , ((λ _ → refl) , (λ _ → refl))

Vec12Eq-sym : {u v : Vec12ℤ} → Vec12Eq u v → Vec12Eq v u
Vec12Eq-sym eq =
 (λ i → sym (fst eq i)) ,
 ((λ i → sym (fst (snd eq) i)) ,
  (λ i → sym (snd (snd eq) i)))

Vec12Eq-trans : {u v w : Vec12ℤ} → Vec12Eq u v → Vec12Eq v w → Vec12Eq u w
Vec12Eq-trans eq₁ eq₂ =
 (λ i → trans (fst eq₁ i) (fst eq₂ i)) ,
 ((λ i → trans (fst (snd eq₁) i) (fst (snd eq₂) i)) ,
  (λ i → trans (snd (snd eq₁) i) (snd (snd eq₂) i)))

-- § sum congruence: blockwise
sum12-cong : (u v : Vec12ℤ) → Vec12Eq u v → sum12ℤ u ≡ sum12ℤ v
sum12-cong u v eq =
 trans
  (cong (λ t → t +ℤ (sumFin4ℤ (block₁ u) +ℤ sumFin4ℤ (block₂ u)))
   (sumFin4-cong (block₀ u) (block₀ v) (fst eq)))
  (cong (λ t → sumFin4ℤ (block₀ v) +ℤ t)
    (trans
     (cong (λ t → t +ℤ sumFin4ℤ (block₂ u))
```

```
          (sumFin4-cong (block₁ u) (block₁ v) (fst (snd eq))))
    (cong (λ t → sumFin4ℤ (block₁ v) +ℤ t)
          (sumFin4-cong (block₂ u) (block₂ v) (snd (snd eq))))))

-- § scaling congruence
twelveVec12-cong : (u v : Vec12ℤ) → Vec12Eq u v → Vec12Eq (twelveVec12ℤ u) (twelveVec12ℤ v)
twelveVec12-cong u v eq =
 (λ i → cong twelveTimesℤ (fst eq i)) ,
 ((λ i → cong twelveTimesℤ (fst (snd eq) i)) ,
  (λ i → cong twelveTimesℤ (snd (snd eq) i)))

opaque
 unfolding K12LaplacianVec12ℤ

 -- § K₁₂ Laplacian congruence
 K12Laplacian-cong : (u v : Vec12ℤ) → Vec12Eq u v → Vec12Eq (K12LaplacianVec12ℤ u) (K12LaplacianVec12ℤ v)
 K12Laplacian-cong u v eq =
  (λ i →
    let pBlock = cong twelveTimesℤ (fst eq i) in
    let pSum = cong negℤ (sum12-cong u v eq) in
    trans (cong (λ t → twelveTimesℤ (block₀ u i) +ℤ t) pSum)
          (trans (cong (λ t → t +ℤ negℤ (sum12ℤ v)) pBlock) refl)) ,
 ((λ i →
    let pBlock = cong twelveTimesℤ (fst (snd eq) i) in
    let pSum = cong negℤ (sum12-cong u v eq) in
    trans (cong (λ t → twelveTimesℤ (block₁ u i) +ℤ t) pSum)
          (trans (cong (λ t → t +ℤ negℤ (sum12ℤ v)) pBlock) refl)) ,
  (λ i →
    let pBlock = cong twelveTimesℤ (snd (snd eq) i) in
    let pSum = cong negℤ (sum12-cong u v eq) in
    trans (cong (λ t → twelveTimesℤ (block₂ u i) +ℤ t) pSum)
          (trans (cong (λ t → t +ℤ negℤ (sum12ℤ v)) pBlock) refl)))
```

Iterated Operator Collapse

Laws 14K.0–14K.2: every iterate of L_{12} or J_{12} beyond the first is a 12-scaled copy of its predecessor. The quadratic identities from the previous chapter force every longer pure iterate to collapse immediately to a scaled first action.

```
-- § Law 14K.0: two-step recurrence L₁₂^(n+2) = 12·L₁₂^(n+1)
law14K-0-LL-step : (n : ℕ) → (v : Vec12ℤ) →
 Vec12Eq (powEndo (suc (suc n)) K12LaplacianVec12ℤ v)
  (twelveVec12ℤ (powEndo (suc n) K12LaplacianVec12ℤ v))
law14K-0-LL-step n v = law14H-11-LL-twelveL (powEndo n K12LaplacianVec12ℤ v)

-- § Law 14K.1: L₁₂^(n+1) = 12^n · L₁₂
law14K-1-Lpow-scaling : (n : ℕ) → (v : Vec12ℤ) →
 Vec12Eq (powEndo (suc n) K12LaplacianVec12ℤ v)
  (powEndo n twelveVec12ℤ (K12LaplacianVec12ℤ v))
law14K-1-Lpow-scaling zero v = Vec12Eq-refl (K12LaplacianVec12ℤ v)
law14K-1-Lpow-scaling (suc n) v =
 Vec12Eq-trans
  (law14K-0-LL-step n v)
  (twelveVec12-cong
   (powEndo (suc n) K12LaplacianVec12ℤ v)
   (powEndo n twelveVec12ℤ (K12LaplacianVec12ℤ v))
   (law14K-1-Lpow-scaling n v))
```

```
-- § Law 14K.2: J12^(n+1) = 12^n · J12
law14K-2-Jpow-scaling : (n : ℕ) → (v : Vec12ℤ) →
 Vec12Eq (powEndo (suc n) J12Vec12ℤ v)
  (powEndo n twelveVec12ℤ (J12Vec12ℤ v))
law14K-2-Jpow-scaling zero v = Vec12Eq-refl (J12Vec12ℤ v)
law14K-2-Jpow-scaling (suc n) v =
 Vec12Eq-trans
  (law14H-5-JJ-twelveJ (powEndo n J12Vec12ℤ v))
  (twelveVec12-cong
   (powEndo (suc n) J12Vec12ℤ v)
   (powEndo n twelveVec12ℤ (J12Vec12ℤ v))
   (law14K-2-Jpow-scaling n v))
```

Word Classification

The free monoid on two generators $\{L, J\}$ evaluates to operators on $\mathrm{Vec}_{12}\mathbb{Z}$. Every word is classified into one of four cases: empty (identity), pure L-power, pure J-power, or mixed (zero). Law 14L.0 forces this list to be exhaustive and unique, eliminating every additional operator word as a formal defect.

```
-- § generator and word types
data Gen : Set where
 Lg : Gen
 Jg : Gen

data List (A : Set) : Set where
 [] : List A
 _::_ : A → List A → List A

Word : Set
Word = List Gen

-- § operator type and equality
Op : Set
Op = GenEndo Vec12ℤ

OpEq : Op → Op → Set
OpEq f g = (v : Vec12ℤ) → Vec12Eq (f v) (g v)

idOp : Op
idOp = idGenEndo

zeroOp : Op
zeroOp _ = zeroVec12ℤ

LOp : Op
LOp = K12LaplacianVec12ℤ

JOp : Op
JOp = J12Vec12ℤ

-- § word evaluation
evalGen : Gen → Op
evalGen Lg = LOp
evalGen Jg = JOp

evalWord : Word → Op
evalWord []       = idOp
```

```
evalWord (g :: w) = evalGen g ∘ evalWord w

-- § four classification cases
data WordCase : Set where
 empty : WordCase
 Lpow : ℕ → WordCase
 Jpow : ℕ → WordCase
 mixed : WordCase

caseOp : WordCase → Op
caseOp empty     = idOp
caseOp (Lpow n) = powEndo (suc n) LOp
caseOp (Jpow n)  = powEndo (suc n) JOp
caseOp mixed     = zeroOp

-- § step function: how appending a generator updates the case
stepCase : Gen → WordCase → WordCase
stepCase Lg empty     = Lpow zero
stepCase Jg empty     = Jpow zero
stepCase Lg (Lpow n) = Lpow (suc n)
stepCase Jg (Jpow n)  = Jpow (suc n)
stepCase Lg (Jpow _)  = mixed
stepCase Jg (Lpow _)  = mixed
stepCase _ mixed      = mixed

-- § J12 congruence (from sum congruence)
J12-cong : (u v : Vec12ℤ) → Vec12Eq u v → Vec12Eq (JOp u) (JOp v)
J12-cong u v eq =
 let sEq = sum12-cong u v eq in
 (λ _ → sEq) , ((λ _ → sEq) , (λ _ → sEq))

-- § mixed annihilation: L after J-powers and J after L-powers
L∘Jpow-zero : (n : ℕ) → OpEq (LOp ∘ powEndo (suc n) JOp) zeroOp
L∘Jpow-zero n v = law14H-10-LJ-zero (powEndo n JOp v)

J∘Lpow-zero : (n : ℕ) → OpEq (JOp ∘ powEndo (suc n) LOp) zeroOp
J∘Lpow-zero n v = law14H-9-JL-zero (powEndo n LOp v)

-- § composition respects case classification (8 cases)
composeGenCase : (g : Gen) → (c : WordCase) → OpEq (evalGen g ∘ caseOp c) (caseOp (stepCase g c))
composeGenCase Lg empty v = Vec12Eq-refl (LOp v)
composeGenCase Jg empty v = Vec12Eq-refl (JOp v)
composeGenCase Lg (Lpow n) v = Vec12Eq-refl (powEndo (suc (suc n)) LOp v)
composeGenCase Jg (Jpow n) v = Vec12Eq-refl (powEndo (suc (suc n)) JOp v)
composeGenCase Lg (Jpow n) v = L∘Jpow-zero n v
composeGenCase Jg (Lpow n) v = J∘Lpow-zero n v
composeGenCase Lg mixed v = law14H-14-const-eigen0 0ℤ
composeGenCase Jg mixed v = Vec12Eq-refl zeroVec12ℤ

-- § generator congruence
congGen : (g : Gen) → (u v : Vec12ℤ) → Vec12Eq u v → Vec12Eq (evalGen g u) (evalGen g v)
congGen Lg u v eq = K12Laplacian-cong u v eq
congGen Jg u v eq = J12-cong u v eq

-- § Law 14L.0: every word classifies uniquely
law14L-0-classify-word : (w : Word) → Σ WordCase (λ c → OpEq (evalWord w) (caseOp c))
law14L-0-classify-word [] = empty , (λ v → Vec12Eq-refl v)
law14L-0-classify-word (g :: w) =
 let rec = law14L-0-classify-word w in
 let c   = fst rec in
 let eq = snd rec in
 stepCase g c ,
```

```
(λ v →
 Vec12Eq-trans
   (congGen g (evalWord w v) (caseOp c v) (eq v))
   (composeGenCase g c v))
```

Chapter 37

Rational Multiplication and ε-Splitting

Rational multiplication must be associative, unital, and distribute over addition; these properties are forced by the underlying integer arithmetic. The second half of the chapter derives the ε-splitting lemma: for any positive ε, a quarter-denominator rational δ satisfies $\delta + \delta < \varepsilon$, the key ingredient for combining two Cauchy bounds. Cross-multiplication coherence must survive triple products and distributive expansion, and these same constraints force the small-denominator witness used in the splitting laws.

Rational Multiplication Laws

The multiplication algebra on $\mathbb{Q}$ is forced by reducing every claim to integer associativity, commutativity, and distributivity. No extra multiplicative freedom survives the cross-product setoid.

```
-- § triple ℕ⁺-product helpers
⁺toℤ-*⁺-assocʳ : (a b c : ℕ⁺) → ⁺toℤ ((a *⁺ b) *⁺ c) ≡ (⁺toℤ a) *ℤ ((⁺toℤ b) *ℤ (⁺toℤ c))
⁺toℤ-*⁺-assocʳ a b c =
 trans
  (⁺toℤ-*⁺ (a *⁺ b) c)
  (trans
   (cong (λ t → t *ℤ ⁺toℤ c) (⁺toℤ-*⁺ a b))
   (*ℤ-assoc (⁺toℤ a) (⁺toℤ b) (⁺toℤ c)))

⁺toℤ-*⁺-assocˡ : (a b c : ℕ⁺) → ⁺toℤ (a *⁺ (b *⁺ c)) ≡ (⁺toℤ a) *ℤ ((⁺toℤ b) *ℤ (⁺toℤ c))
⁺toℤ-*⁺-assocˡ a b c =
 trans
  (⁺toℤ-*⁺ a (b *⁺ c))
  (cong (λ t → (⁺toℤ a) *ℤ t) (⁺toℤ-*⁺ b c))

-- § *ℚ associativity
*ℚ-assoc : (p q r : ℚ) → (p *ℚ q) *ℚ r ≃ℚ p *ℚ (q *ℚ r)
*ℚ-assoc (a / b) (c / d) (e / f) =
 let
  numAssoc : ((a *ℤ c) *ℤ e) ≡ (a *ℤ (c *ℤ e))
  numAssoc = *ℤ-assoc a c e

  denL : ⁺toℤ ((b *⁺ d) *⁺ f) ≡ (⁺toℤ b) *ℤ ((⁺toℤ d) *ℤ (⁺toℤ f))
```

```
  denL = ⁺toℤ-*⁺-assocʳ b d f

  denR : ⁺toℤ (b *⁺ (d *⁺ f)) ≡ (⁺toℤ b) *ℤ ((⁺toℤ d) *ℤ (⁺toℤ f))
  denR = ⁺toℤ-*⁺-assocˡ b d f

  denEq : ⁺toℤ ((b *⁺ d) *⁺ f) ≡ ⁺toℤ (b *⁺ (d *⁺ f))
  denEq = trans denL (sym denR)

  cross : (((a *ℤ c) *ℤ e) *ℤ ⁺toℤ (b *⁺ (d *⁺ f))) ≡ ((a *ℤ (c *ℤ e)) *ℤ ⁺toℤ ((b *⁺ d) *⁺ f))
  cross =
   trans
    (cong (λ t → ((a *ℤ c) *ℤ e) *ℤ t) (sym denEq))
    (cong (λ t → t *ℤ ⁺toℤ ((b *⁺ d) *⁺ f)) numAssoc)
 in
 cross

– § *ℚ right identity
*ℚ-one-right : (p : ℚ) → (p *ℚ 1ℚ) ≃ℚ p
*ℚ-one-right (a / b) =
 let
  numEq : (a *ℤ oneℤ) ≡ a
  numEq = *ℤ-one-right a

  denOne : ⁺toℤ b ≡ ⁺toℤ (b *⁺ one⁺)
  denOne =
   trans
    (sym (*ℤ-one-right (⁺toℤ b)))
    (sym (⁺toℤ-*⁺ b one⁺))

  cross : ((a *ℤ oneℤ) *ℤ ⁺toℤ b) ≡ (a *ℤ ⁺toℤ (b *⁺ one⁺))
  cross =
   trans
    (cong (λ t → t *ℤ ⁺toℤ b) numEq)
    (cong (λ t → a *ℤ t) denOne)
 in
 cross

– § *ℚ left identity
*ℚ-one-left : (p : ℚ) → (1ℚ *ℚ p) ≃ℚ p
*ℚ-one-left (a / b) =
 let
  numEq : (oneℤ *ℤ a) ≡ a
  numEq = *ℤ-one-left a

  denOneL : ⁺toℤ b ≡ ⁺toℤ (one⁺ *⁺ b)
  denOneL = sym (trans (⁺toℤ-*⁺ one⁺ b) (*ℤ-one-left (⁺toℤ b)))
 in
 trans
  (cong (λ t → t *ℤ ⁺toℤ b) numEq)
  (cong (λ t → a *ℤ t) denOneL)

– § *ℚ zero annihilation (left)
*ℚ-zero-left : (p : ℚ) → (0ℚ *ℚ p) ≃ℚ 0ℚ
*ℚ-zero-left (a / b) =
 let
  numEq : (0ℤ *ℤ a) ≡ 0ℤ
  numEq = *ℤ-zero-left a

  cross : ((0ℤ *ℤ a) *ℤ ⁺toℤ one⁺) ≡ (0ℤ *ℤ ⁺toℤ (one⁺ *⁺ b))
  cross =
   trans
    (cong (λ t → t *ℤ ⁺toℤ one⁺) numEq)
```

```
    (trans
     (*ℤ-zero-left (⁺toℤ one⁺))
     (sym (*ℤ-zero-left (⁺toℤ (one⁺ *⁺ b)))))
  in
  cross

-- § *ℚ zero annihilation (right)
*ℚ-zero-right : (p : ℚ) → (p *ℚ 0ℚ) ≃ℚ 0ℚ
*ℚ-zero-right (a / b) =
  let
    numEq : (a *ℤ 0ℤ) ≡ 0ℤ
    numEq = *ℤ-zero-right a
  in
  trans
    (cong (λ t → t *ℤ ⁺toℤ one⁺) numEq)
    (trans
      (*ℤ-zero-left (⁺toℤ one⁺))
      (sym (*ℤ-zero-left (⁺toℤ (b *⁺ one⁺)))))
```

Step 1.5: Positive reciprocal infrastructure. The analytic unit-system block now has a precise target shape, so the next forced arithmetic step is an inversion law that does not overreach. The minimal viable layer is the strictly positive sector of ℚ: positivity can be reflected to the numerator, the numerator can be exposed in successor form, and then denominator and numerator-magnitude can be swapped to produce a reciprocal whose product with the original rational collapses back to 1.

```
-- § Positive numerator forces positive rational.
0<ℤnum→0<ℚ : (q : ℚ) → 0ℤ <ℤ num q → 0ℚ <ℚ q
0<ℤnum→0<ℚ (a / b) apos =
  let
    step₁ : 0ℤ <ℤ (a *ℤ ⁺toℤ one⁺)
    step₁ = <ℤ-resp-≡ʳ (sym (*ℤ-one-right a)) apos
  in
  <ℤ-resp-≡ˡ (sym (*ℤ-zero-left (⁺toℤ b))) step₁

-- § A positive rational exposes its numerator as +suc n.
positive-num-witnessℚ : (q : ℚ) → 0ℚ <ℚ q → Σ ℕ (λ n → num q ≡ +suc n)
positive-num-witnessℚ q qpos =
  0<ℤ→pos (num q) (0ℚ<→0ℤ<num q qpos)

-- § Reciprocal on the strictly positive sector of ℚ.
reciprocal⁺ : (q : ℚ) → 0ℚ <ℚ q → ℚ
reciprocal⁺ (a / b) qpos with positive-num-witnessℚ (a / b) qpos
... | n , _ = ⁺toℤ b / mkℕ⁺ n

-- § The reciprocal of a positive rational is again positive.
reciprocal⁺-pos : (q : ℚ) → (qpos : 0ℚ <ℚ q) → 0ℚ <ℚ reciprocal⁺ q qpos
reciprocal⁺-pos (a / b) qpos with positive-num-witnessℚ (a / b) qpos
... | n , _ = 0<ℤnum→0<ℚ ((⁺toℤ b) / mkℕ⁺ n) (den-posℤ b)

-- § Positive rational times its reciprocal is 1.
*ℚ-reciprocal⁺-right : (q : ℚ) → (qpos : 0ℚ <ℚ q) → (q *ℚ reciprocal⁺ q qpos) ≃ℚ 1ℚ
*ℚ-reciprocal⁺-right (a / b) qpos with positive-num-witnessℚ (a / b) qpos
... | n , a≡ =
  let
    lhsOne : ((a *ℤ ⁺toℤ b) *ℤ ⁺toℤ one⁺) ≡ (a *ℤ ⁺toℤ b)
    lhsOne = *ℤ-one-right (a *ℤ ⁺toℤ b)
```

```
  core : (a *ℤ ⁺toℤ b) ≡ ⁺toℤ (b *⁺ mkℕ⁺ n)
  core =
   trans
    (cong (λ t → t *ℤ ⁺toℤ b) a≡)
    (trans
     (*ℤ-comm (+suc n) (⁺toℤ b))
     (sym (⁺toℤ-*⁺ b (mkℕ⁺ n))))

  rhsOne : ⁺toℤ (b *⁺ mkℕ⁺ n) ≡ (oneℤ *ℤ ⁺toℤ (b *⁺ mkℕ⁺ n))
  rhsOne = sym (*ℤ-one-left (⁺toℤ (b *⁺ mkℕ⁺ n)))
 in
 trans lhsOne (trans core rhsOne)

-- § The reciprocal also cancels on the left.
*ℚ-reciprocal⁺-left : (q : ℚ) → (qpos : 0ℚ <ℚ q) → (reciprocal⁺ q qpos *ℚ q) ≃ℚ 1ℚ
*ℚ-reciprocal⁺-left q qpos =
 ≃ℚ-trans
  (*ℚ-comm (reciprocal⁺ q qpos) q)
  (*ℚ-reciprocal⁺-right q qpos)

-- § Negation commutes with rational multiplication on the left.
*ℚ-neg-left : (p q : ℚ) → ((-ℚ p) *ℚ q) ≃ℚ (-ℚ (p *ℚ q))
*ℚ-neg-left (a / b) (c / d) =
 cong (λ t → t *ℤ ⁺toℤ (b *⁺ d)) (*ℤ-neg-left a c)

-- § Negation commutes with rational multiplication on the right.
*ℚ-neg-right : (p q : ℚ) → (p *ℚ (-ℚ q)) ≃ℚ (-ℚ (p *ℚ q))
*ℚ-neg-right (a / b) (c / d) =
 cong (λ t → t *ℤ ⁺toℤ (b *⁺ d)) (*ℤ-neg-right a c)

-- § Double negation is trivial on rational classes.
-ℚ-involutive : (p : ℚ) → (-ℚ (-ℚ p)) ≃ℚ p
-ℚ-involutive (a / b) =
 cong (λ t → t *ℤ ⁺toℤ b) (negℤ-involutive a)

-- § Local negation transport on rational equivalence.
negℚ-resp-≃ : {p q : ℚ} → p ≃ℚ q → (-ℚ p) ≃ℚ (-ℚ q)
negℚ-resp-≃ {a / b} {c / d} eq =
 trans
  (*ℤ-neg-left a (⁺toℤ d))
  (trans
   (cong negℤ eq)
   (sym (*ℤ-neg-left c (⁺toℤ b))))

-- § Nonzero rational: numerator is not zero.
NonZeroℚ : ℚ → Set
NonZeroℚ q = num q ≡ 0ℤ → ⊥

-- § Reciprocal on the full nonzero sector of ℚ.
reciprocal≠0 : (q : ℚ) → NonZeroℚ q → ℚ
reciprocal≠0 (0ℤ / b) qnz = ⊥-elim (qnz refl)
reciprocal≠0 ((+suc n) / b) qnz =
 reciprocal⁺ ((+suc n) / b) (0<ℤnum→0<ℚ ((+suc n) / b) (0<ℤ-pos n))
reciprocal≠0 ((-suc n) / b) qnz =
 -ℚ (reciprocal⁺ ((+suc n) / b) (0<ℤnum→0<ℚ ((+suc n) / b) (0<ℤ-pos n)))

-- § Any nonzero rational times its reciprocal is 1.
*ℚ-reciprocal≠0-right : (q : ℚ) → (qnz : NonZeroℚ q) → (q *ℚ reciprocal≠0 q qnz) ≃ℚ 1ℚ
*ℚ-reciprocal≠0-right (0ℤ / b) qnz = ⊥-elim (qnz refl)
*ℚ-reciprocal≠0-right ((+suc n) / b) qnz =
 *ℚ-reciprocal⁺-right ((+suc n) / b) (0<ℤnum→0<ℚ ((+suc n) / b) (0<ℤ-pos n))
```

```
*ℚ-reciprocal≠0-right ((-suc n) / b) qnz =
 let
  p : ℚ
  p = (+suc n) / b

  ppos : 0ℚ <ℚ p
  ppos = 0<ℤnum→0<ℚ p (0<ℤ-pos n)

  step₁ : (((-ℚ p) *ℚ (-ℚ (reciprocal⁺ p ppos)))) ≃ℚ (-ℚ (p *ℚ (-ℚ (reciprocal⁺ p ppos))))
  step₁ = *ℚ-neg-left p (-ℚ (reciprocal⁺ p ppos))

  step₂ : (p *ℚ (-ℚ (reciprocal⁺ p ppos))) ≃ℚ (-ℚ (p *ℚ reciprocal⁺ p ppos))
  step₂ = *ℚ-neg-right p (reciprocal⁺ p ppos)

  step₃ : (-ℚ (p *ℚ (-ℚ (reciprocal⁺ p ppos)))) ≃ℚ (-ℚ (-ℚ (p *ℚ reciprocal⁺ p ppos)))
  step₃ = negℚ-resp-≃ step₂

  step₄ : (-ℚ (-ℚ (p *ℚ reciprocal⁺ p ppos))) ≃ℚ (p *ℚ reciprocal⁺ p ppos)
  step₄ = -ℚ-involutive (p *ℚ reciprocal⁺ p ppos)
 in
 ≃ℚ-trans step₁ (≃ℚ-trans step₃ (≃ℚ-trans step₄ (*ℚ-reciprocal⁺-right p ppos)))

-- § The reciprocal also cancels on the left for any nonzero rational.
*ℚ-reciprocal≠0-left : (q : ℚ) → (qnz : NonZeroℚ q) → (reciprocal≠0 q qnz *ℚ q) ≃ℚ 1ℚ
*ℚ-reciprocal≠0-left q qnz =
 ≃ℚ-trans
  (*ℚ-comm (reciprocal≠0 q qnz) q)
  (*ℚ-reciprocal≠0-right q qnz)
```

Step 2: Rational Distributivity. With associativity, identity, and zero laws in place, the remaining algebraic burden is distributivity. Both left and right distributivity reduce to integer cross-multiplication identities via denominator clearing.

```
-- § *ℚ right-distributes over +ℚ
*ℚ-distrib-right-+ℚ : (p q r : ℚ) → p *ℚ (q +ℚ r) ≃ℚ (p *ℚ q) +ℚ (p *ℚ r)
*ℚ-distrib-right-+ℚ (a / b) (c / d) (e / f) =
 let
  B : ℤ
  B = ⁺toℤ b

  D : ℤ
  D = ⁺toℤ d

  F : ℤ
  F = ⁺toℤ f

  bd : ℕ⁺
  bd = b *⁺ d

  bf : ℕ⁺
  bf = b *⁺ f

  df : ℕ⁺
  df = d *⁺ f

  denR : ℤ
  denR = (B *ℤ D) *ℤ (B *ℤ F)

  denL : ℤ
```

```
denL = B *ℤ (D *ℤ F)

denR≡ : ⁺toℤ (bd *⁺ bf) ≡ denR
denR≡ =
 trans
  (⁺toℤ-*⁺ bd bf)
  (cong₂ _*ℤ_ (⁺toℤ-*⁺ b d) (⁺toℤ-*⁺ b f))

denL≡ : ⁺toℤ (b *⁺ df) ≡ denL
denL≡ = ⁺toℤ-*⁺-assocˡ b d f

cF : ℤ
cF = c *ℤ F

eD : ℤ
eD = e *ℤ D

lhsNum : ℤ
lhsNum = a *ℤ (cF +ℤ eD)

lhsExpand₀ : (lhsNum *ℤ denR) ≡ ((a *ℤ cF) *ℤ denR) +ℤ ((a *ℤ eD) *ℤ denR)
lhsExpand₀ =
 trans
  (cong (λ t → t *ℤ denR) (*ℤ-distrib-right-+ℤ a cF eD))
  (*ℤ-distrib-left-+ℤ (a *ℤ cF) (a *ℤ eD) denR)

rhsNum : ℤ
rhsNum = ((a *ℤ c) *ℤ ⁺toℤ bf) +ℤ ((a *ℤ e) *ℤ ⁺toℤ bd)

rhsExpand₀ : (rhsNum *ℤ denL) ≡ (((a *ℤ c) *ℤ ⁺toℤ bf) *ℤ denL) +ℤ (((a *ℤ e) *ℤ ⁺toℤ bd) *ℤ denL)
rhsExpand₀ = *ℤ-distrib-left-+ℤ ((a *ℤ c) *ℤ ⁺toℤ bf) ((a *ℤ e) *ℤ ⁺toℤ bd) denL

-- term 1 alignment
t1-lhs : ((a *ℤ cF) *ℤ denR) ≡ ((a *ℤ c) *ℤ denR) *ℤ F
t1-lhs =
 trans
  (cong (λ t → t *ℤ denR) (sym (*ℤ-assoc a c F)))
  (trans
   (*ℤ-assoc (a *ℤ c) F denR)
   (trans
    (cong (λ t → (a *ℤ c) *ℤ t) (*ℤ-comm F denR))
    (sym (*ℤ-assoc (a *ℤ c) denR F))))

t1-rhs : (((a *ℤ c) *ℤ ⁺toℤ bf) *ℤ denL) ≡ ((a *ℤ c) *ℤ denR) *ℤ F
t1-rhs =
 let
  bf→ : ⁺toℤ bf ≡ B *ℤ F
  bf→ = ⁺toℤ-*⁺ b f

  denL→ : denL ≡ (B *ℤ D) *ℤ F
  denL→ = sym (*ℤ-assoc B D F)
 in
 trans
  (cong (λ t → ((a *ℤ c) *ℤ t) *ℤ denL) bf→)
  (trans
   (cong (λ t → ((a *ℤ c) *ℤ (B *ℤ F)) *ℤ t) denL→)
   (trans
    (sym (*ℤ-assoc ((a *ℤ c) *ℤ (B *ℤ F)) (B *ℤ D) F))
    (trans
     (cong (λ t → t *ℤ F) (*ℤ-assoc (a *ℤ c) (B *ℤ F) (B *ℤ D)))
     (cong (λ t → ((a *ℤ c) *ℤ t) *ℤ F) (*ℤ-comm (B *ℤ F) (B *ℤ D))))))
```

```
t1 : ((a *ℤ cF) *ℤ denR) ≡ (((a *ℤ c) *ℤ ⁺toℤ bf) *ℤ denL)
t1 = trans t1-lhs (sym t1-rhs)

-- term 2 alignment
t2-lhs : ((a *ℤ eD) *ℤ denR) ≡ ((a *ℤ e) *ℤ denR) *ℤ D
t2-lhs =
 trans
  (cong (λ t → t *ℤ denR) (sym (*ℤ-assoc a e D)))
  (trans
   (*ℤ-assoc (a *ℤ e) D denR)
   (trans
    (cong (λ t → (a *ℤ e) *ℤ t) (*ℤ-comm D denR))
    (sym (*ℤ-assoc (a *ℤ e) denR D))))

t2-rhs : (((a *ℤ e) *ℤ ⁺toℤ bd) *ℤ denL) ≡ ((a *ℤ e) *ℤ denR) *ℤ D
t2-rhs =
 let
  bd→ : ⁺toℤ bd ≡ B *ℤ D
  bd→ = ⁺toℤ-*⁺ b d

  denL→ : denL ≡ (B *ℤ F) *ℤ D
  denL→ =
   trans
    (cong (λ t → B *ℤ t) (*ℤ-comm D F))
    (sym (*ℤ-assoc B F D))
 in
 trans
  (cong (λ t → ((a *ℤ e) *ℤ t) *ℤ denL) bd→)
  (trans
   (cong (λ t → ((a *ℤ e) *ℤ (B *ℤ D)) *ℤ t) denL→)
   (trans
    (sym (*ℤ-assoc ((a *ℤ e) *ℤ (B *ℤ D)) (B *ℤ F) D))
    (cong (λ t → t *ℤ D) (*ℤ-assoc (a *ℤ e) (B *ℤ D) (B *ℤ F)))))

t2 : ((a *ℤ eD) *ℤ denR) ≡ (((a *ℤ e) *ℤ ⁺toℤ bd) *ℤ denL)
t2 = trans t2-lhs (sym t2-rhs)

sumEq : (((a *ℤ cF) *ℤ denR) +ℤ ((a *ℤ eD) *ℤ denR)) ≡ ((((a *ℤ c) *ℤ ⁺toℤ bf) *ℤ denL) +ℤ (((a *ℤ e) *ℤ ⁺toℤ bd) *ℤ denL))
sumEq = cong₂ _+ℤ_ t1 t2
in
trans
 (cong (λ t → lhsNum *ℤ t) denR≡)
 (trans
  lhsExpand₀
  (trans
   sumEq
   (trans
    (sym rhsExpand₀)
    (cong (λ t → rhsNum *ℤ t) (sym denL≡)))))

-- § *ℚ left-distributes over +ℚ (by commutativity reduction)
*ℚ-distrib-left-+ℚ : (p q r : ℚ) → (p +ℚ q) *ℚ r ≃ℚ (p *ℚ r) +ℚ (q *ℚ r)
*ℚ-distrib-left-+ℚ p q r =
 ≃ℚ-trans
  {p = (p +ℚ q) *ℚ r}
  {q = r *ℚ (p +ℚ q)}
  {r = (p *ℚ r) +ℚ (q *ℚ r)}
  (*ℚ-comm (p +ℚ q) r)
  (≃ℚ-trans
   {p = r *ℚ (p +ℚ q)}
   {q = (r *ℚ p) +ℚ (r *ℚ q)}
   {r = (p *ℚ r) +ℚ (q *ℚ r)}
```

```
  (*ℚ-distrib-right-+ℚ r p q)
  (+ℚ-resp-≃
   {p = r *ℚ p}
   {p' = p *ℚ r}
   {q = r *ℚ q}
   {q' = q *ℚ r}
   (*ℚ-comm r p)
   (*ℚ-comm r q)))
```

ε-Splitting Laws

For any positive $\varepsilon = a/b$, define $\delta = 1/(4b)$. Then $0 < \delta$ and $\delta + \delta < \varepsilon$. This makes it possible to combine two Cauchy-style bounds into one. The section forces a canonical small witness from the denominator of ε, eliminating arbitrary threshold choices.

```
-- § forced constant: 2 as ℕ⁺
two⁺ : ℕ⁺
two⁺ = suc⁺ one⁺

-- § denominator constructors for ϵ-splitting
halfDen : ℕ⁺ → ℕ⁺
halfDen b = two⁺ *⁺ b

quarterDen : ℕ⁺ → ℕ⁺
quarterDen b = two⁺ *⁺ (two⁺ *⁺ b)

ϵQuarter : ℚ → ℚ
ϵQuarter (a / b) = oneℤ / quarterDen b

ϵHalf : ℚ → ℚ
ϵHalf (a / b) = oneℤ / halfDen b

-- § ϵQuarter is positive
ϵQuarter-pos : (ϵ : ℚ) → 0ℚ <ℚ ϵQuarter ϵ
ϵQuarter-pos (a / b) =
 let
  qd : ℕ⁺
  qd = quarterDen b

  lhs0 : (0ℤ *ℤ ⁺toℤ qd) ≡ 0ℤ
  lhs0 = *ℤ-zero-left (⁺toℤ qd)

  one⁺ℤ≡oneℤ : ⁺toℤ one⁺ ≡ oneℤ
  one⁺ℤ≡oneℤ = refl

  rhs1 : (oneℤ *ℤ ⁺toℤ one⁺) ≡ oneℤ
  rhs1 = trans (cong (λ t → oneℤ *ℤ t) one⁺ℤ≡oneℤ) (*ℤ-one-right oneℤ)
 in
 <ℤ-resp-≡ˡ {x = 0ℤ} {y = 0ℤ *ℤ ⁺toℤ qd} {z = oneℤ *ℤ ⁺toℤ one⁺} (sym lhs0)
  (<ℤ-resp-≡ʳ {x = 0ℤ} {y = oneℤ} {z = oneℤ *ℤ ⁺toℤ one⁺} (sym rhs1) 0ℤ<oneℤ)

-- § doubling ϵQuarter yields ϵHalf (up to ≃ℚ)
ϵQuarter+ϵQuarter≃ϵHalf : (ϵ : ℚ) → (ϵQuarter ϵ +ℚ ϵQuarter ϵ) ≃ℚ (ϵHalf ϵ)
ϵQuarter+ϵQuarter≃ϵHalf (a / b) =
 let
  qd : ℕ⁺
  qd = quarterDen b
```

```
hd : ℕ⁺
hd = halfDen b

lhsNum : ℤ
lhsNum = (oneℤ *ℤ ⁺toℤ qd) +ℤ (oneℤ *ℤ ⁺toℤ qd)

lhsDen : ℕ⁺
lhsDen = qd *⁺ qd

qdSplit : ⁺toℤ qd ≡ (⁺toℤ two⁺) *ℤ ((⁺toℤ two⁺) *ℤ (⁺toℤ b))
qdSplit =
 trans
  (⁺toℤ-*⁺ two⁺ (two⁺ *⁺ b))
  (cong (λ t → (⁺toℤ two⁺) *ℤ t) (⁺toℤ-*⁺ two⁺ b))

hdSplit : ⁺toℤ hd ≡ (⁺toℤ two⁺) *ℤ (⁺toℤ b)
hdSplit = ⁺toℤ-*⁺ two⁺ b

lhsExpand : (lhsNum *ℤ ⁺toℤ hd) ≡ (oneℤ *ℤ ⁺toℤ qd) *ℤ ⁺toℤ hd +ℤ (oneℤ *ℤ ⁺toℤ qd) *ℤ ⁺toℤ hd
lhsExpand =
 *ℤ-distrib-left-+ℤ (oneℤ *ℤ ⁺toℤ qd) (oneℤ *ℤ ⁺toℤ qd) (⁺toℤ hd)

oneqd : (oneℤ *ℤ ⁺toℤ qd) ≡ ⁺toℤ qd
oneqd = *ℤ-one-left (⁺toℤ qd)

term : (oneℤ *ℤ ⁺toℤ qd) *ℤ ⁺toℤ hd ≡ (⁺toℤ qd) *ℤ ⁺toℤ hd
term = cong (λ t → t *ℤ ⁺toℤ hd) oneqd

rhs : (oneℤ *ℤ ⁺toℤ lhsDen) ≡ (⁺toℤ qd) *ℤ (⁺toℤ qd)
rhs =
 trans
  (cong (λ t → oneℤ *ℤ t) (⁺toℤ-*⁺ qd qd))
  (trans
   (*ℤ-one-left ((⁺toℤ qd) *ℤ (⁺toℤ qd)))
   refl)

twoℤ : ℤ
twoℤ = ⁺toℤ two⁺

twoℤ≡ : twoℤ ≡ oneℤ +ℤ oneℤ
twoℤ≡ = refl

qd≡twohd : qd ≡ two⁺ *⁺ hd
qd≡twohd = refl

qdAsTwoHd : ⁺toℤ qd ≡ twoℤ *ℤ ⁺toℤ hd
qdAsTwoHd = trans (cong ⁺toℤ qd≡twohd) (⁺toℤ-*⁺ two⁺ hd)

qdHd : ℤ
qdHd = (⁺toℤ qd) *ℤ ⁺toℤ hd

dupToMul2 : (qdHd +ℤ qdHd) ≡ qdHd *ℤ twoℤ
dupToMul2 =
 trans
  (cong (λ t → t +ℤ qdHd) (sym (*ℤ-one-right qdHd)))
  (trans
   (cong (λ t → (qdHd *ℤ oneℤ) +ℤ t) (sym (*ℤ-one-right qdHd)))
   (trans
    (sym (*ℤ-distrib-right-+ℤ qdHd oneℤ oneℤ))
    (cong (λ t → qdHd *ℤ t) (sym twoℤ≡))))

squareToMul2 : ((⁺toℤ qd) *ℤ (⁺toℤ qd)) ≡ qdHd *ℤ twoℤ
```

```
 squareToMul2 =
  trans
   (cong (λ t → (⁺toℤ qd) *ℤ t) qdAsTwoHd)
   (trans
    (sym (*ℤ-assoc (⁺toℤ qd) twoℤ (⁺toℤ hd)))
    (trans
     (cong (λ t → t *ℤ ⁺toℤ hd) (*ℤ-comm (⁺toℤ qd) twoℤ))
     (trans
      (*ℤ-assoc twoℤ (⁺toℤ qd) (⁺toℤ hd))
      (*ℤ-comm twoℤ ((⁺toℤ qd) *ℤ ⁺toℤ hd)))))

 goal : (lhsNum *ℤ ⁺toℤ hd) ≡ (oneℤ *ℤ ⁺toℤ lhsDen)
 goal =
  trans
   lhsExpand
   (trans
    (cong (λ t → t +ℤ t) term)
    (trans
     dupToMul2
     (trans (sym squareToMul2) (sym rhs))))
in
goal
```

Step 2: Epsilon Splitting (ϵ/2 Infrastructure). ϵHalf is positive when ε is, and satisfies $\varepsilon/2 < \varepsilon$—the key lemma for Cauchy convergence. ϵQuarter is used for product congruence arguments.

```
– § ϵHalf < ϵ (when ϵ > 0)
ϵHalf<ϵ : (ϵ : ℚ) → 0ℚ <ℚ ϵ → ϵHalf ϵ <ℚ ϵ
ϵHalf<ϵ (a / b) ϵpos =
 let
  aPos : 0ℤ <ℤ a
  aPos = 0ℚ<→0ℤ<num (a / b) ϵpos

  one<2a-sum : oneℤ <ℤ (a +ℤ a)
  one<2a-sum = oneℤ<twoTimes-pos a aPos

  twoℤ : ℤ
  twoℤ = ⁺toℤ two⁺

  twoℤ≡ : twoℤ ≡ oneℤ +ℤ oneℤ
  twoℤ≡ = refl

  aTimesTwo≡ : (a *ℤ twoℤ) ≡ (a +ℤ a)
  aTimesTwo≡ =
   trans
    (cong (λ t → a *ℤ t) twoℤ≡)
    (trans
     (*ℤ-distrib-right-+ℤ a oneℤ oneℤ)
     (trans
      (cong (λ t → t +ℤ (a *ℤ oneℤ)) (*ℤ-one-right a))
      (cong (λ t → a +ℤ t) (*ℤ-one-right a))))

  one<2a : oneℤ <ℤ (a *ℤ twoℤ)
  one<2a = <ℤ-resp-≡ʳ (sym aTimesTwo≡) one<2a-sum

  step₁ : (oneℤ *ℤ ⁺toℤ b) <ℤ ((a *ℤ twoℤ) *ℤ ⁺toℤ b)
  step₁ = <ℤ-mul-pos-right b one<2a
```

```
  lhsEq : (oneℤ *ℤ ⁺toℤ b) ≡ ⁺toℤ b
  lhsEq = *ℤ-one-left (⁺toℤ b)

  rhsEq : ((a *ℤ twoℤ) *ℤ ⁺toℤ b) ≡ (a *ℤ ⁺toℤ (two⁺ *⁺ b))
  rhsEq =
   trans
    (*ℤ-assoc a twoℤ (⁺toℤ b))
    (cong (λ t → a *ℤ t) (sym (⁺toℤ-*⁺ two⁺ b)))

  core : (oneℤ *ℤ ⁺toℤ b) <ℤ (a *ℤ ⁺toℤ (two⁺ *⁺ b))
  core = <ℤ-resp-≡ʳ rhsEq step₁
 in
 core

– § ϵQuarter-double < ϵ
ϵQuarter-double<ϵ : (ϵ : ℚ) → 0ℚ <ℚ ϵ → (ϵQuarter ϵ +ℚ ϵQuarter ϵ) <ℚ ϵ
ϵQuarter-double<ϵ ϵ ϵpos =
 let
  eq : (ϵQuarter ϵ +ℚ ϵQuarter ϵ) ≃ℚ (ϵHalf ϵ)
  eq = ϵQuarter+ϵQuarter≃ϵHalf ϵ

  le : (ϵQuarter ϵ +ℚ ϵQuarter ϵ) ≤ℚ (ϵHalf ϵ)
  le = ≃ℚ→≤ℚˡ {p = ϵQuarter ϵ +ℚ ϵQuarter ϵ} {q = ϵHalf ϵ} eq

  halfLt : (ϵHalf ϵ) <ℚ ϵ
  halfLt = ϵHalf<ϵ ϵ ϵpos
 in
 ≤<ℚ→<ℚ {x = ϵQuarter ϵ +ℚ ϵQuarter ϵ} {y = ϵHalf ϵ} {z = ϵ} le halfLt

– § ϵQuarter < ϵ (from ϵQuarter ≤ double < ϵ)
ϵQuarter<ϵ : (ϵ : ℚ) → 0ℚ <ℚ ϵ → ϵQuarter ϵ <ℚ ϵ
ϵQuarter<ϵ ϵ ϵpos =
 let
  eq : ϵQuarter ϵ ≃ℚ ϵQuarter ϵ
  eq = ≃ℚ-refl (ϵQuarter ϵ)

  ϵqPos : 0ℚ <ℚ ϵQuarter ϵ
  ϵqPos = ϵQuarter-pos ϵ

  ϵqNonneg : 0ℚ ≤ℚ ϵQuarter ϵ
  ϵqNonneg = <ℚ→≤ℚ {x = 0ℚ} {y = ϵQuarter ϵ} ϵqPos

  ϵq≤ϵq+ϵq : ϵQuarter ϵ ≤ℚ (ϵQuarter ϵ +ℚ ϵQuarter ϵ)
  ϵq≤ϵq+ϵq = ≤ℚ-add-nonneg-right (ϵQuarter ϵ) (ϵQuarter ϵ) ϵqNonneg

  double<ϵ : (ϵQuarter ϵ +ℚ ϵQuarter ϵ) <ℚ ϵ
  double<ϵ = ϵQuarter-double<ϵ ϵ ϵpos
 in
 ≤<ℚ→<ℚ {x = ϵQuarter ϵ} {y = ϵQuarter ϵ +ℚ ϵQuarter ϵ} {z = ϵ} ϵq≤ϵq+ϵq double<ϵ
```

Chapter 38

Rational Distance Laws

Every metric space axiom for $d_{\mathbb{Q}}$ is forced by the cross-multiplication setoid on $\mathbb{Q}$. Self-distance is zero (reflexivity), $|x - y| = |y - x|$ (symmetry), the triangle inequality $d(p, r) \leq d(p, q) + d(q, r)$ is an integer-level scaling argument, and translation/multiplicative invariance follow by factoring out common denominator squares. The absolute-value numerator and the cross-multiplication denominators must remain coherent under addition, negation, and multiplication. These constraints force the full metric algebra of $\mathbb{Q}$, including the key bounded-by-ε laws used later in the Cauchy closure arguments.

Metric Axioms

The core metric axioms for $d_{\mathbb{Q}}$ are forced here. Each axiom collapses to integer absolute-value identities together with denominator coherence in the rational setoid.

```
-- § absℤ respects propositional equality
absℤ-cong : {x y : ℤ} → x ≡ y → absℤ x ≡ absℤ y
absℤ-cong = cong absℤ

-- § Law 14U.0: distℚ q q ≃ℚ 0ℚ (reflexivity)
distℚ-refl : (q : ℚ) → distℚ q q ≃ℚ 0ℚ
distℚ-refl (a / b) =
 let x : ℤ
     x = a *ℤ ⁺toℤ b

     numDist : ℤ
     numDist = absℤ (x +ℤ negℤ x)

     numDist≡0 : numDist ≡ 0ℤ
     numDist≡0 =
      trans
       (absℤ-cong (+ℤ-inv-right x))
       absℤ-zero

     denDist : ℕ⁺
     denDist = b *⁺ b

     lhs0 : (numDist *ℤ ⁺toℤ one⁺) ≡ 0ℤ
     lhs0 =
      trans
```

```
      (cong (λ t → t *ℤ ⁺toℤ one⁺) numDist≡0)
      (trans (*ℤ-zero-left (⁺toℤ one⁺)) refl)

    rhs0 : (0ℤ *ℤ ⁺toℤ denDist) ≡ 0ℤ
    rhs0 = *ℤ-zero-left (⁺toℤ denDist)

 in
 trans lhs0 (sym rhs0)

– § distℚ q q <ℚ ϵ for any positive ϵ
distℚ-const<ϵ : (q ϵ : ℚ) → 0ℚ <ℚ ϵ → distℚ q q <ℚ ϵ
distℚ-const<ϵ (a / b) (c / d) ϵpos =
 let x : ℤ
     x = a *ℤ ⁺toℤ b

     numDist : ℤ
     numDist = absℤ (x +ℤ negℤ x)

     numDist≡0 : numDist ≡ 0ℤ
     numDist≡0 =
      trans
       (absℤ-cong (+ℤ-inv-right x))
       absℤ-zero

     lhs : ℤ
     lhs = numDist *ℤ ⁺toℤ d

     rhs : ℤ
     rhs = c *ℤ ⁺toℤ (b *⁺ b)

     lhs≡0 : lhs ≡ 0ℤ
     lhs≡0 =
      trans
       (cong (λ t → t *ℤ ⁺toℤ d) numDist≡0)
       (*ℤ-zero-left (⁺toℤ d))

     cpos : 0ℤ <ℤ c
     cpos = 0ℚ<→0ℤ<num (c / d) ϵpos

     rhsPos : 0ℤ <ℤ rhs
     rhsPos = 0<ℤ-mul-pos-right c (b *⁺ b) cpos

     base : 0ℤ <ℤ rhs
     base = rhsPos

 in
 <ℤ-resp-≡ˡ (sym lhs≡0) base

– § p ≃ℚ q implies distℚ p q ≃ℚ 0ℚ
distℚ-≃0 : {p q : ℚ} → p ≃ℚ q → distℚ p q ≃ℚ 0ℚ
distℚ-≃0 {a / b} {c / d} eq =
 let
  x : ℤ
  x = a *ℤ ⁺toℤ d

  y : ℤ
  y = c *ℤ ⁺toℤ b

  z : ℤ
  z = x +ℤ negℤ y

  z≡0 : z ≡ 0ℤ
```

```
  z≡0 =
    trans
     (cong (λ t → t +ℤ negℤ y) eq)
     (+ℤ-inv-right y)

  absZ≡0 : absℤ z ≡ 0ℤ
  absZ≡0 = trans (absℤ-cong z≡0) absℤ-zero

  lhs0 : (absℤ z *ℤ ⁺toℤ one⁺) ≡ 0ℤ
  lhs0 =
    trans
     (cong (λ t → t *ℤ ⁺toℤ one⁺) absZ≡0)
     (trans (*ℤ-zero-left (⁺toℤ one⁺)) refl)

  rhs0 : (0ℤ *ℤ ⁺toℤ (b *⁺ d)) ≡ 0ℤ
  rhs0 = *ℤ-zero-left (⁺toℤ (b *⁺ d))
 in
 trans lhs0 (sym rhs0)
```

Step 2: Nonnegativity, Symmetry, and Negation Invariance. These standard distance properties follow from absolute-value laws integrated through the cross-multiplication bridge.

```
– § distℚ p q ≥ 0 (nonnegativity)
distℚ-nonneg : (p q : ℚ) → 0ℚ ≤ℚ distℚ p q
distℚ-nonneg (a / b) (c / d) =
 let
  z : ℤ
  z = (a *ℤ ⁺toℤ d) +ℤ negℤ (c *ℤ ⁺toℤ b)

  rhs0 : 0ℤ ≤ℤ absℤ z
  rhs0 = absℤ-nonneg z

  lhsEq : (0ℤ *ℤ ⁺toℤ (b *⁺ d)) ≡ 0ℤ
  lhsEq = *ℤ-zero-left (⁺toℤ (b *⁺ d))

  rhsEq : (absℤ z *ℤ ⁺toℤ one⁺) ≡ absℤ z
  rhsEq = *ℤ-one-right (absℤ z)
 in
 ≤ℤ-resp-≡ˡ (sym lhsEq) (≤ℤ-resp-≡ʳ (sym rhsEq) rhs0)

– § distℚ p q ≃ℚ distℚ q p (symmetry)
distℚ-sym : (p q : ℚ) → distℚ p q ≃ℚ distℚ q p
distℚ-sym (a / b) (c / d) =
 let z : ℤ
     z = (a *ℤ ⁺toℤ d) +ℤ negℤ (c *ℤ ⁺toℤ b)

     z' : ℤ
     z' = (c *ℤ ⁺toℤ b) +ℤ negℤ (a *ℤ ⁺toℤ d)

     negz≡z' : negℤ z ≡ z'
     negz≡z' =
      trans
       (neg-+ℤ (a *ℤ ⁺toℤ d) (negℤ (c *ℤ ⁺toℤ b)))
       (trans
        (cong (λ t → negℤ (a *ℤ ⁺toℤ d) +ℤ t) (negℤ-involutive (c *ℤ ⁺toℤ b)))
        (+ℤ-comm (negℤ (a *ℤ ⁺toℤ d)) (c *ℤ ⁺toℤ b)))

     absEq : absℤ z ≡ absℤ z'
     absEq =
      trans
```

```
      (sym (absℤ-neg z))
      (trans
       (cong absℤ negz≡z')
       refl)

    denComm : b *⁺ d ≡ d *⁺ b
    denComm = *⁺-comm b d

    denCommℤ : ⁺toℤ (d *⁺ b) ≡ ⁺toℤ (b *⁺ d)
    denCommℤ = cong ⁺toℤ (sym denComm)

    lhs : absℤ z *ℤ ⁺toℤ (d *⁺ b) ≡ absℤ z' *ℤ ⁺toℤ (b *⁺ d)
    lhs =
     trans
      (cong (λ t → t *ℤ ⁺toℤ (d *⁺ b)) absEq)
      (cong (λ t → (absℤ z') *ℤ t) denCommℤ)

 in
 lhs

-- § distℚ (-p) (-q) ≃ℚ distℚ p q (negation invariance)
distℚ-neg : (p q : ℚ) → distℚ (-ℚ p) (-ℚ q) ≃ℚ distℚ p q
distℚ-neg (a / b) (c / d) =
 let
  den : ℕ⁺
  den = b *⁺ d

  z : ℤ
  z = (a *ℤ ⁺toℤ d) +ℤ negℤ (c *ℤ ⁺toℤ b)

  zNeg : ℤ
  zNeg = (negℤ a *ℤ ⁺toℤ d) +ℤ negℤ (negℤ c *ℤ ⁺toℤ b)

  zNeg≡negz : zNeg ≡ negℤ z
  zNeg≡negz =
    trans
     (cong (λ t → t +ℤ negℤ (negℤ c *ℤ ⁺toℤ b)) (*ℤ-neg-left a (⁺toℤ d)))
     (trans
      (cong (λ t → negℤ (a *ℤ ⁺toℤ d) +ℤ t)
       (cong negℤ (*ℤ-neg-left c (⁺toℤ b))))
      (sym (neg-+ℤ (a *ℤ ⁺toℤ d) (negℤ (c *ℤ ⁺toℤ b)))))

  absEq : absℤ zNeg ≡ absℤ z
  absEq = trans (cong absℤ zNeg≡negz) (absℤ-neg z)
 in
 cong (λ t → t *ℤ ⁺toℤ den) absEq
```

Triangle Inequality

The triangle inequality $d(p, r) \leq d(p, q) + d(q, r)$ is forced by multiplying the base scaled-numerator inequality through by a common positive factor $s = (b \cdot d) \cdot f$, then regrouping the six resulting terms. No alternative estimate survives once all three distances are expressed over the same positive scale.

```
-- § Law 14U.1: triangle inequality for distℚ
distℚ-triangle : (p q r : ℚ) → distℚ p r ≤ℚ (distℚ p q +ℚ distℚ q r)
distℚ-triangle (a / b) (c / d) (e / f) =
```

```
goal
where
 p q rQ : ℚ
 p = a / b
 q = c / d
 rQ = e / f

 nd-pr : ℤ
 nd-pr = numDistℚ p rQ

 nd-pq : ℤ
 nd-pq = numDistℚ p q

 nd-qr : ℤ
 nd-qr = numDistℚ q rQ

 bd df bf : ℕ⁺
 bd = b *⁺ d
 df = d *⁺ f
 bf = b *⁺ f

 rhsNum : ℤ
 rhsNum = (nd-pq *ℤ ⁺toℤ df) +ℤ (nd-qr *ℤ ⁺toℤ bd)

 rhsDen : ℕ⁺
 rhsDen = bd *⁺ df

 -- § base scaled numerator inequality
 ineq0 : (nd-pr *ℤ ⁺toℤ d) ≤ℤ ((nd-pq *ℤ ⁺toℤ f) +ℤ (nd-qr *ℤ ⁺toℤ b))
 ineq0 = numDistℚ-triangle-scaled p q rQ

 -- § multiply by common positive scale s = (b·d)·f
 s : ℕ⁺
 s = bd *⁺ f

 scaled : ((nd-pr *ℤ ⁺toℤ d) *ℤ ⁺toℤ s)
          ≤ℤ
          (((nd-pq *ℤ ⁺toℤ f) +ℤ (nd-qr *ℤ ⁺toℤ b)) *ℤ ⁺toℤ s)
 scaled =
  ≤ℤ-mul-pos-right
   (nd-pr *ℤ ⁺toℤ d)
   ((nd-pq *ℤ ⁺toℤ f) +ℤ (nd-qr *ℤ ⁺toℤ b))
   s
   ineq0

 -- § swap two positive scaling factors
 swapScale : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
 swapScale x u v =
  trans
   (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
   (trans
    (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
    (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

 -- § split scaling by a product u*⁺v into sequential scaling
 scaleSplit : (x : ℤ) → (u v : ℕ⁺) → x *ℤ ⁺toℤ (u *⁺ v) ≡ (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v
 scaleSplit x u v =
  trans
   (cong (λ t → x *ℤ t) (⁺toℤ-*⁺ u v))
   (sym (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v)))

 -- § LHS rewrite: ((nd-pr·d)·s) = nd-pr · rhsDen
```

```
lhsEq : ((nd-pr *ℤ ⁺toℤ d) *ℤ ⁺toℤ s) ≡ (nd-pr *ℤ ⁺toℤ rhsDen)
lhsEq =
 trans
  (scaleSplit (nd-pr *ℤ ⁺toℤ d) bd f)
  (trans
   (cong (λ t → t *ℤ ⁺toℤ f) (swapScale nd-pr d bd))
   (trans
    (sym (scaleSplit (nd-pr *ℤ ⁺toℤ bd) d f))
    (sym (scaleSplit nd-pr bd df))))

-- § term-pq rewrite: (nd-pq·f)·s = (nd-pq·df)·bf
term-pq : (nd-pq *ℤ ⁺toℤ f) *ℤ ⁺toℤ s ≡ (nd-pq *ℤ ⁺toℤ df) *ℤ ⁺toℤ bf
term-pq =
 trans
  (scaleSplit (nd-pq *ℤ ⁺toℤ f) bd f)
  (trans
   (cong (λ t → t *ℤ ⁺toℤ f) (swapScale nd-pq f bd))
   (trans
    (cong (λ t → (t *ℤ ⁺toℤ f) *ℤ ⁺toℤ f)
          (trans
           (scaleSplit nd-pq b d)
           (swapScale nd-pq b d)))
    (trans
          (cong (λ t → t *ℤ ⁺toℤ f)
           (swapScale (nd-pq *ℤ ⁺toℤ d) b f))
          (trans
           (cong (λ t → (t *ℤ ⁺toℤ b) *ℤ ⁺toℤ f) (sym (scaleSplit nd-pq d f)))
           (sym (scaleSplit (nd-pq *ℤ ⁺toℤ df) b f))))))

-- § term-qr rewrite: (nd-qr·b)·s = (nd-qr·bd)·bf
term-qr : (nd-qr *ℤ ⁺toℤ b) *ℤ ⁺toℤ s ≡ (nd-qr *ℤ ⁺toℤ bd) *ℤ ⁺toℤ bf
term-qr =
 trans
  (scaleSplit (nd-qr *ℤ ⁺toℤ b) bd f)
  (trans
   (cong (λ t → t *ℤ ⁺toℤ f) (swapScale nd-qr b bd))
   (sym (scaleSplit (nd-qr *ℤ ⁺toℤ bd) b f)))

rhsEq : (((nd-pq *ℤ ⁺toℤ f) +ℤ (nd-qr *ℤ ⁺toℤ b)) *ℤ ⁺toℤ s) ≡ (rhsNum *ℤ ⁺toℤ bf)
rhsEq =
 trans
  (*ℤ-distrib-left-+ℤ (nd-pq *ℤ ⁺toℤ f) (nd-qr *ℤ ⁺toℤ b) (⁺toℤ s))
  (trans
   (trans
    (cong (λ t → t +ℤ ((nd-qr *ℤ ⁺toℤ b) *ℤ ⁺toℤ s)) term-pq)
    (cong (λ t → ((nd-pq *ℤ ⁺toℤ df) *ℤ ⁺toℤ bf) +ℤ t) term-qr))
   (sym (*ℤ-distrib-left-+ℤ (nd-pq *ℤ ⁺toℤ df) (nd-qr *ℤ ⁺toℤ bd) (⁺toℤ bf))))

goal : distℚ p rQ ≤ℚ (distℚ p q +ℚ distℚ q rQ)
goal =
 ≤ℤ-resp-≡ˡ lhsEq
  (≤ℤ-resp-≡ʳ rhsEq scaled)
```

Translation Invariance

Adding the same rational to both endpoints cannot change distance: the r-contributed terms cancel exactly, leaving the base difference multiplied by a denominator square f^2. Translation dependence is eliminated by forcing those added terms to cancel on the nose.

```
-- § distℚ (p+r) (q+r) ≃ℚ distℚ p q (right translation)
distℚ-+ℚ-right : (p q r : ℚ) → distℚ (p +ℚ r) (q +ℚ r) ≃ℚ distℚ p q
distℚ-+ℚ-right (a / b) (c / d) (e / f) =
 let
  swapScale : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
  swapScale x u v =
   trans
    (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
    (trans
     (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
     (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

  scaleSplit : (x : ℤ) → (u v : ℕ⁺) → x *ℤ ⁺toℤ (u *⁺ v) ≡ (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v
  scaleSplit x u v =
   trans
    (cong (λ t → x *ℤ t) (⁺toℤ-*⁺ u v))
    (sym (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v)))

  mul4-rearrange : (x y z w : ℤ) → (x *ℤ y) *ℤ (z *ℤ w) ≡ (x *ℤ z) *ℤ (y *ℤ w)
  mul4-rearrange x y z w =
   trans
    (*ℤ-assoc x y (z *ℤ w))
    (trans
     (cong (λ t → x *ℤ t)
      (trans
       (sym (*ℤ-assoc y z w))
       (trans
        (cong (λ t → t *ℤ w) (*ℤ-comm y z))
        (*ℤ-assoc z y w))))
     (sym (*ℤ-assoc x z (y *ℤ w))))

  bf : ℕ⁺
  bf = b *⁺ f

  df : ℕ⁺
  df = d *⁺ f

  s : ℕ⁺
  s = f *⁺ f

  base : ℤ
  base = (a *ℤ ⁺toℤ d) +ℤ negℤ (c *ℤ ⁺toℤ b)

  Pn : ℤ
  Pn = (a *ℤ ⁺toℤ f) +ℤ (e *ℤ ⁺toℤ b)

  Qn : ℤ
  Qn = (c *ℤ ⁺toℤ f) +ℤ (e *ℤ ⁺toℤ d)

  Z : ℤ
  Z = (Pn *ℤ ⁺toℤ df) +ℤ negℤ (Qn *ℤ ⁺toℤ bf)

  -- § denominator embedding factorization
  denFactor : ⁺toℤ (bf *⁺ df) ≡ (⁺toℤ (b *⁺ d)) *ℤ (⁺toℤ s)
  denFactor =
   trans
    (⁺toℤ-*⁺ bf df)
    (trans
     (cong (λ t → t *ℤ (⁺toℤ df)) (⁺toℤ-*⁺ b f))
     (trans
      (cong (λ t → ((⁺toℤ b) *ℤ (⁺toℤ f)) *ℤ t) (⁺toℤ-*⁺ d f))
      (trans
```

```
    (mul4-rearrange (⁺toℤ b) (⁺toℤ f) (⁺toℤ d) (⁺toℤ f))
    (trans
     (cong (λ t → t *ℤ ((⁺toℤ f) *ℤ (⁺toℤ f))) (sym (⁺toℤ-*⁺ b d)))
     (cong (λ t → (⁺toℤ (b *⁺ d)) *ℤ t) (sym (⁺toℤ-*⁺ f f)))))))

-- § numerator cancellation and factoring
cancelR : Z ≡ base *ℤ ⁺toℤ s
cancelR =
 let
  afdf : ℤ
  afdf = (a *ℤ ⁺toℤ f) *ℤ ⁺toℤ df

  ebdf : ℤ
  ebdf = (e *ℤ ⁺toℤ b) *ℤ ⁺toℤ df

  cfbf : ℤ
  cfbf = (c *ℤ ⁺toℤ f) *ℤ ⁺toℤ bf

  edbf : ℤ
  edbf = (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ bf

  expandP : (Pn *ℤ ⁺toℤ df) ≡ ((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ df) +ℤ ((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ df)
  expandP = *ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ b) (⁺toℤ df)

  expandQ : (Qn *ℤ ⁺toℤ bf) ≡ ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ bf) +ℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ bf)
  expandQ = *ℤ-distrib-left-+ℤ (c *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ d) (⁺toℤ bf)

  negExpandQ : negℤ (Qn *ℤ ⁺toℤ bf) ≡ negℤ ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ bf) +ℤ negℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ bf)
  negExpandQ = trans (cong negℤ expandQ) (neg-+ℤ ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ bf) ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ bf))

  Z₁ : Z ≡ (((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ df) +ℤ ((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ df))
           +ℤ (negℤ ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ bf) +ℤ negℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ bf))
  Z₁ =
   trans
    (cong (λ t → t +ℤ negℤ (Qn *ℤ ⁺toℤ bf)) expandP)
    (cong (λ t → (((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ df) +ℤ ((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ df)) +ℤ t) negExpandQ)

  ebdf≡edbf : ((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ df) ≡ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ bf)
  ebdf≡edbf =
   trans
    (cong (λ t → (e *ℤ ⁺toℤ b) *ℤ t) (⁺toℤ-*⁺ d f))
    (trans
     (mul4-rearrange e (⁺toℤ b) (⁺toℤ d) (⁺toℤ f))
     (sym (cong (λ t → (e *ℤ ⁺toℤ d) *ℤ t) (⁺toℤ-*⁺ b f))))

  cancelTerm : ((e *ℤ ⁺toℤ b) *ℤ ⁺toℤ df) +ℤ negℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ bf) ≡ 0ℤ
  cancelTerm = trans (cong (λ t → t +ℤ negℤ ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ bf)) ebdf≡edbf) (+ℤ-inv-right ((e *ℤ ⁺toℤ d) *ℤ ⁺toℤ bf))

  afdf≡ads : ((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ df) ≡ ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ s)
  afdf≡ads =
   trans
    (cong (λ t → (a *ℤ ⁺toℤ f) *ℤ t) (⁺toℤ-*⁺ d f))
    (trans
     (mul4-rearrange a (⁺toℤ f) (⁺toℤ d) (⁺toℤ f))
     (cong (λ t → (a *ℤ ⁺toℤ d) *ℤ t) (sym (⁺toℤ-*⁺ f f))))

  cfbf≡cbs : ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ bf) ≡ ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ s)
  cfbf≡cbs =
   trans
    (cong (λ t → (c *ℤ ⁺toℤ f) *ℤ t) (⁺toℤ-*⁺ b f))
    (trans
     (mul4-rearrange c (⁺toℤ f) (⁺toℤ b) (⁺toℤ f))
```

```
    (cong (λ t → (c *ℤ ⁺toℤ b) *ℤ t) (sym (⁺toℤ-*⁺ f f))))

  – § cancel the r-contributed terms
  Z₂ : Z ≡ afdf +ℤ negℤ cfbf
  Z₂ =
   let
    Zexp : Z ≡ (afdf +ℤ ebdf) +ℤ (negℤ cfbf +ℤ negℤ edbf)
    Zexp =
     trans
      (cong (λ t → t +ℤ negℤ (Qn *ℤ ⁺toℤ bf)) expandP)
      (trans
       (cong (λ t → ((afdf +ℤ ebdf) +ℤ t))
        (trans (cong negℤ expandQ) (neg-+ℤ cfbf edbf)))
       refl)

    swapNeg : (negℤ cfbf +ℤ negℤ edbf) ≡ (negℤ edbf +ℤ negℤ cfbf)
    swapNeg = +ℤ-comm (negℤ cfbf) (negℤ edbf)

    cancelPair : ebdf +ℤ negℤ edbf ≡ 0ℤ
    cancelPair =
     trans
      (cong (λ t → t +ℤ negℤ edbf) ebdf≡edbf)
      (+ℤ-inv-right edbf)

   in
   trans
    (trans
     Zexp
     (trans
      (cong (λ t → (afdf +ℤ ebdf) +ℤ t) swapNeg)
      (trans
       (+ℤ-assoc afdf ebdf (negℤ edbf +ℤ negℤ cfbf))
       (cong (λ t → afdf +ℤ t) (sym (+ℤ-assoc ebdf (negℤ edbf) (negℤ cfbf)))))))
    (trans
     (cong (λ t → afdf +ℤ (t +ℤ negℤ cfbf)) cancelPair)
     (cong (λ t → afdf +ℤ t) (+ℤ-zero-left (negℤ cfbf))))

  – § factor out the common scale s = f·f
  factor : (afdf +ℤ negℤ cfbf) ≡ base *ℤ ⁺toℤ s
  factor =
   trans
    (cong (λ t → t +ℤ negℤ cfbf) afdf≡ads)
    (trans
     (cong (λ t → ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ s) +ℤ negℤ t) cfbf≡cbs)
     (trans
      (cong (λ t → ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ s) +ℤ t)
       (sym (*ℤ-neg-left (c *ℤ ⁺toℤ b) (⁺toℤ s))))
      (sym (*ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ d) (negℤ (c *ℤ ⁺toℤ b)) (⁺toℤ s)))))
  in
  trans Z₂ factor

absZEq : absℤ Z ≡ absℤ base *ℤ ⁺toℤ s
absZEq = trans (cong absℤ cancelR) (absℤ-mul-pos-right base s)

rhsDen : ℕ⁺
rhsDen = b *⁺ d

lhsDen : ℕ⁺
lhsDen = bf *⁺ df

rhsNum : ℤ
rhsNum = absℤ base
```

```
  rhsRewrite : (rhsNum *ℤ ⁺toℤ lhsDen) ≡ (rhsNum *ℤ ⁺toℤ rhsDen) *ℤ ⁺toℤ s
  rhsRewrite =
   trans
    (cong (λ t → rhsNum *ℤ t) denFactor)
    (sym (*ℤ-assoc rhsNum (⁺toℤ rhsDen) (⁺toℤ s)))

  cross : (absℤ Z *ℤ ⁺toℤ rhsDen) ≡ (rhsNum *ℤ ⁺toℤ lhsDen)
  cross =
   trans
    (cong (λ t → t *ℤ ⁺toℤ rhsDen) absZEq)
    (trans
     (swapScale rhsNum s rhsDen)
     (sym rhsRewrite))
 in
 cross
```

Step 2: Left Translation. The left-translation variant $d(r+p,\, r+q) \simeq d(p,q)$ follows the same pattern with r-terms on the left: expand, cancel the shared $e \cdot b \cdot d$-like terms, then factor the residue through $(f \cdot f)$.

```
-- § distℚ (r+p) (r+q) ≃ℚ distℚ p q (left translation)
distℚ-+ℚ-left : (r p q : ℚ) → distℚ (r +ℚ p) (r +ℚ q) ≃ℚ distℚ p q
distℚ-+ℚ-left (e / f) (a / b) (c / d) =
 let
  swapScale : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
  swapScale x u v =
   trans
    (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
    (trans
     (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
     (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

  mul4-rearrange : (x y z w : ℤ) → (x *ℤ y) *ℤ (z *ℤ w) ≡ (x *ℤ z) *ℤ (y *ℤ w)
  mul4-rearrange x y z w =
   trans
    (*ℤ-assoc x y (z *ℤ w))
    (trans
     (cong (λ t → x *ℤ t)
      (trans
       (sym (*ℤ-assoc y z w))
       (trans
        (cong (λ t → t *ℤ w) (*ℤ-comm y z))
        (*ℤ-assoc z y w))))
     (sym (*ℤ-assoc x z (y *ℤ w))))

  fb : ℕ⁺
  fb = f *⁺ b

  fd : ℕ⁺
  fd = f *⁺ d

  s : ℕ⁺
  s = f *⁺ f

  base : ℤ
  base = (a *ℤ ⁺toℤ d) +ℤ negℤ (c *ℤ ⁺toℤ b)

  Pn : ℤ
```

```
Pn = (e *ℤ ⁺toℤ b) +ℤ (a *ℤ ⁺toℤ f)

Qn : ℤ
Qn = (e *ℤ ⁺toℤ d) +ℤ (c *ℤ ⁺toℤ f)

Z : ℤ
Z = (Pn *ℤ ⁺toℤ fd) +ℤ negℤ (Qn *ℤ ⁺toℤ fb)

denFactor : ⁺toℤ (fb *⁺ fd) ≡ (⁺toℤ (b *⁺ d)) *ℤ (⁺toℤ s)
denFactor =
 trans
  (⁺toℤ-*⁺ fb fd)
  (trans
   (cong (λ t → t *ℤ (⁺toℤ fd)) (⁺toℤ-*⁺ f b))
   (trans
    (cong (λ t → ((⁺toℤ f) *ℤ (⁺toℤ b)) *ℤ t) (⁺toℤ-*⁺ f d))
    (trans
     (mul4-rearrange (⁺toℤ f) (⁺toℤ b) (⁺toℤ f) (⁺toℤ d))
     (trans
      (*ℤ-comm ((⁺toℤ f) *ℤ (⁺toℤ f)) ((⁺toℤ b) *ℤ (⁺toℤ d)))
      (trans
           (cong (λ t → t *ℤ ((⁺toℤ f) *ℤ (⁺toℤ f))) (sym (⁺toℤ-*⁺ b d)))
           (cong (λ t → (⁺toℤ (b *⁺ d)) *ℤ t) (sym (⁺toℤ-*⁺ f f))))))))

cancelR : Z ≡ base *ℤ ⁺toℤ s
cancelR =
 let
  ebfd : ℤ
  ebfd = (e *ℤ ⁺toℤ b) *ℤ ⁺toℤ fd

  affd : ℤ
  affd = (a *ℤ ⁺toℤ f) *ℤ ⁺toℤ fd

  edfb : ℤ
  edfb = (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ fb

  cffb : ℤ
  cffb = (c *ℤ ⁺toℤ f) *ℤ ⁺toℤ fb

  expandP : (Pn *ℤ ⁺toℤ fd) ≡ ebfd +ℤ affd
  expandP = *ℤ-distrib-left-+ℤ (e *ℤ ⁺toℤ b) (a *ℤ ⁺toℤ f) (⁺toℤ fd)

  expandQ : (Qn *ℤ ⁺toℤ fb) ≡ edfb +ℤ cffb
  expandQ = *ℤ-distrib-left-+ℤ (e *ℤ ⁺toℤ d) (c *ℤ ⁺toℤ f) (⁺toℤ fb)

  Zexp : Z ≡ (ebfd +ℤ affd) +ℤ (negℤ edfb +ℤ negℤ cffb)
  Zexp =
   trans
    (cong (λ t → t +ℤ negℤ (Qn *ℤ ⁺toℤ fb)) expandP)
    (trans
     (cong (λ t → (ebfd +ℤ affd) +ℤ t) (trans (cong negℤ expandQ) (neg-+ℤ edfb cffb)))
     refl)

  ebfd≡edfb : ebfd ≡ edfb
  ebfd≡edfb =
   trans
    (cong (λ t → (e *ℤ ⁺toℤ b) *ℤ t) (⁺toℤ-*⁺ f d))
    (trans
     (cong (λ t → (e *ℤ ⁺toℤ b) *ℤ t) (*ℤ-comm (⁺toℤ f) (⁺toℤ d)))
     (trans
      (mul4-rearrange e (⁺toℤ b) (⁺toℤ d) (⁺toℤ f))
      (trans
```

```
          (cong (λ t → (e *ℤ ⁺toℤ d) *ℤ t) (*ℤ-comm (⁺toℤ b) (⁺toℤ f)))
          (cong (λ t → (e *ℤ ⁺toℤ d) *ℤ t) (sym (⁺toℤ-*⁺ f b))))))

  cancelPair : ebfd +ℤ negℤ edfb ≡ 0ℤ
  cancelPair =
   trans
    (cong (λ t → t +ℤ negℤ edfb) ebfd≡edfb)
    (+ℤ-inv-right edfb)

  affd≡ads : affd ≡ (a *ℤ ⁺toℤ d) *ℤ ⁺toℤ s
  affd≡ads =
   trans
    (cong (λ t → (a *ℤ ⁺toℤ f) *ℤ t) (⁺toℤ-*⁺ f d))
    (trans
     (cong (λ t → (a *ℤ ⁺toℤ f) *ℤ t) (*ℤ-comm (⁺toℤ f) (⁺toℤ d)))
     (trans
      (mul4-rearrange a (⁺toℤ f) (⁺toℤ d) (⁺toℤ f))
      (cong (λ t → (a *ℤ ⁺toℤ d) *ℤ t) (sym (⁺toℤ-*⁺ f f)))))

  cffb≡cbs : cffb ≡ (c *ℤ ⁺toℤ b) *ℤ ⁺toℤ s
  cffb≡cbs =
   trans
    (cong (λ t → (c *ℤ ⁺toℤ f) *ℤ t) (⁺toℤ-*⁺ f b))
    (trans
     (cong (λ t → (c *ℤ ⁺toℤ f) *ℤ t) (*ℤ-comm (⁺toℤ f) (⁺toℤ b)))
     (trans
      (mul4-rearrange c (⁺toℤ f) (⁺toℤ b) (⁺toℤ f))
      (cong (λ t → (c *ℤ ⁺toℤ b) *ℤ t) (sym (⁺toℤ-*⁺ f f)))))

  step₁ : Z ≡ affd +ℤ negℤ cffb
  step₁ =
   trans
    Zexp
    (trans
     (cong (λ t → t +ℤ (negℤ edfb +ℤ negℤ cffb)) (+ℤ-comm ebfd affd))
     (trans
      (+ℤ-assoc affd ebfd (negℤ edfb +ℤ negℤ cffb))
      (trans
          (cong (λ t → affd +ℤ t) (sym (+ℤ-assoc ebfd (negℤ edfb) (negℤ cffb))))
          (trans
           (cong (λ t → affd +ℤ (t +ℤ negℤ cffb)) cancelPair)
           (cong (λ t → affd +ℤ t) (+ℤ-zero-left (negℤ cffb)))))))

  step₂ : (affd +ℤ negℤ cffb) ≡ ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ s) +ℤ negℤ ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ s)
  step₂ =
   trans
    (cong (λ t → t +ℤ negℤ cffb) affd≡ads)
    (cong (λ t → ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ s) +ℤ negℤ t) cffb≡cbs)

  factor : ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ s) +ℤ negℤ ((c *ℤ ⁺toℤ b) *ℤ ⁺toℤ s)
           ≡
          base *ℤ ⁺toℤ s
  factor =
   trans
    (cong (λ t → ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ s) +ℤ t)
     (sym (*ℤ-neg-left (c *ℤ ⁺toℤ b) (⁺toℤ s))))
    (sym (*ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ d) (negℤ (c *ℤ ⁺toℤ b)) (⁺toℤ s)))
 in
 trans step₁ (trans step₂ factor)

absZEq : absℤ Z ≡ absℤ base *ℤ ⁺toℤ s
absZEq = trans (cong absℤ cancelR) (absℤ-mul-pos-right base s)
```

```
  rhsDen : ℕ⁺
  rhsDen = b *⁺ d

  lhsDen : ℕ⁺
  lhsDen = fb *⁺ fd

  rhsNum : ℤ
  rhsNum = absℤ base

  rhsRewrite : (rhsNum *ℤ ⁺toℤ lhsDen) ≡ (rhsNum *ℤ ⁺toℤ rhsDen) *ℤ ⁺toℤ s
  rhsRewrite =
   trans
    (cong (λ t → rhsNum *ℤ t) denFactor)
    (sym (*ℤ-assoc rhsNum (⁺toℤ rhsDen) (⁺toℤ s)))

  cross : (absℤ Z *ℤ ⁺toℤ rhsDen) ≡ (rhsNum *ℤ ⁺toℤ lhsDen)
  cross =
   trans
    (cong (λ t → t *ℤ ⁺toℤ rhsDen) absZEq)
    (trans
     (swapScale rhsNum s rhsDen)
     (sym rhsRewrite))
 in
 cross
```

Multiplicative Scaling

Multiplying both endpoints by the same rational p scales the distance by $d(p, 0)$. This follows from factoring $Z = ab \cdot \text{baseQR}$, then pulling $|ab|$ apart via the multiplicativity of $|\cdot|$. The scaling law is therefore forced by a single common factor rather than by any separate metric assumption.

```
-- § distℚ (p*q) (p*r) ≃ℚ distℚ q r * distℚ p 0 (left scaling)
distℚ-*ℚ-left : (p q r : ℚ) → distℚ (p *ℚ q) (p *ℚ r) ≃ℚ (distℚ q r *ℚ distℚ p 0ℚ)
distℚ-*ℚ-left (a / b) (c / d) (e / f) =
 let
  swapScale : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
  swapScale x u v =
   trans
    (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
    (trans
     (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
     (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

  scaleSplit : (x : ℤ) → (u v : ℕ⁺) → x *ℤ ⁺toℤ (u *⁺ v) ≡ (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v
  scaleSplit x u v =
   trans
    (cong (λ t → x *ℤ t) (⁺toℤ-*⁺ u v))
    (sym (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v)))

  mul4-rearrange : (x y z w : ℤ) → (x *ℤ y) *ℤ (z *ℤ w) ≡ (x *ℤ z) *ℤ (y *ℤ w)
  mul4-rearrange x y z w =
   trans
    (*ℤ-assoc x y (z *ℤ w))
    (trans
     (cong (λ t → x *ℤ t)
```

```
    (trans
     (sym (*ℤ-assoc y z w))
     (trans
      (cong (λ t → t *ℤ w) (*ℤ-comm y z))
      (*ℤ-assoc z y w))))
   (sym (*ℤ-assoc x z (y *ℤ w))))

-- § key cleared numerators
cf : ℤ
cf = c *ℤ ⁺toℤ f

ed : ℤ
ed = e *ℤ ⁺toℤ d

baseQR : ℤ
baseQR = cf +ℤ negℤ ed

ab : ℤ
ab = a *ℤ ⁺toℤ b

-- § distℚ p 0ℚ numerator collapses to absℤ a
p0Raw : ℤ
p0Raw = (a *ℤ ⁺toℤ one⁺) +ℤ negℤ (0ℤ *ℤ ⁺toℤ b)

p0Raw≡a : p0Raw ≡ a
p0Raw≡a =
 trans
  (cong (λ t → t +ℤ negℤ (0ℤ *ℤ ⁺toℤ b)) (*ℤ-one-right a))
  (trans
   (cong (λ t → a +ℤ negℤ t) (*ℤ-zero-left (⁺toℤ b)))
   (trans
    (cong (λ t → a +ℤ t) (negℤ-zero))
    (+ℤ-zero-right a)))

absP0 : ℤ
absP0 = absℤ p0Raw

absP0≡absA : absP0 ≡ absℤ a
absP0≡absA = trans (absℤ-cong p0Raw≡a) refl

-- § LHS cleared numerator for distℚ (p*q) (p*r)
bf : ℕ⁺
bf = b *⁺ f

bd : ℕ⁺
bd = b *⁺ d

Z : ℤ
Z = ((a *ℤ c) *ℤ ⁺toℤ bf) +ℤ negℤ ((a *ℤ e) *ℤ ⁺toℤ bd)

term₁ : ((a *ℤ c) *ℤ ⁺toℤ bf) ≡ ab *ℤ cf
term₁ =
 trans
  (cong (λ t → (a *ℤ c) *ℤ t) (⁺toℤ-*⁺ b f))
  (trans
   (mul4-rearrange a c (⁺toℤ b) (⁺toℤ f))
   refl)

term₂ : ((a *ℤ e) *ℤ ⁺toℤ bd) ≡ ab *ℤ ed
term₂ =
 trans
  (cong (λ t → (a *ℤ e) *ℤ t) (⁺toℤ-*⁺ b d))
```

```
  (trans
   (mul4-rearrange a e (⁺toℤ b) (⁺toℤ d))
   refl)

factorZ : Z ≡ ab *ℤ baseQR
factorZ =
 let
  Z₁ : Z ≡ (ab *ℤ cf) +ℤ negℤ (ab *ℤ ed)
  Z₁ =
   trans
    (cong (λ t → t +ℤ negℤ ((a *ℤ e) *ℤ ⁺toℤ bd)) term₁)
    (cong (λ t → (ab *ℤ cf) +ℤ negℤ t) term₂)

  negPull : negℤ (ab *ℤ ed) ≡ ab *ℤ negℤ ed
  negPull = sym (*ℤ-neg-right ab ed)

  Z₂ : (ab *ℤ cf) +ℤ negℤ (ab *ℤ ed) ≡ (ab *ℤ cf) +ℤ (ab *ℤ negℤ ed)
  Z₂ = cong (λ t → (ab *ℤ cf) +ℤ t) negPull

  Z₃ : (ab *ℤ cf) +ℤ (ab *ℤ negℤ ed) ≡ ab *ℤ (cf +ℤ negℤ ed)
  Z₃ = sym (*ℤ-distrib-right-+ℤ ab cf (negℤ ed))
 in
 trans Z₁ (trans Z₂ Z₃)

absZ : ℤ
absZ = absℤ Z

absZ≡scaled : absZ ≡ (absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ b
absZ≡scaled =
 let
  absZ₁ : absZ ≡ absℤ (ab *ℤ baseQR)
  absZ₁ = cong absℤ factorZ

  absZ₂ : absℤ (ab *ℤ baseQR) ≡ (absℤ ab *ℤ absℤ baseQR)
  absZ₂ = absℤ-mul ab baseQR

  absAB : absℤ ab ≡ absℤ a *ℤ ⁺toℤ b
  absAB = absℤ-mul-pos-right a b

  absZ₃ : (absℤ ab *ℤ absℤ baseQR) ≡ ((absℤ a *ℤ ⁺toℤ b) *ℤ absℤ baseQR)
  absZ₃ = cong (λ t → t *ℤ absℤ baseQR) absAB

  absZ₄ : ((absℤ a *ℤ ⁺toℤ b) *ℤ absℤ baseQR) ≡ ((absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ b)
  absZ₄ =
   trans
    (*ℤ-assoc (absℤ a) (⁺toℤ b) (absℤ baseQR))
    (trans
     (cong (λ t → (absℤ a) *ℤ t) (*ℤ-comm (⁺toℤ b) (absℤ baseQR)))
     (trans
      (sym (*ℤ-assoc (absℤ a) (absℤ baseQR) (⁺toℤ b)))
      (trans
       (cong (λ t → t *ℤ (⁺toℤ b)) (*ℤ-comm (absℤ a) (absℤ baseQR)))
       refl)))
 in
 trans absZ₁ (trans absZ₂ (trans absZ₃ absZ₄))

lhsDen : ℕ⁺
lhsDen = (b *⁺ d) *⁺ (b *⁺ f)

rhsDen : ℕ⁺
rhsDen = (d *⁺ f) *⁺ (b *⁺ one⁺)
```

```
rhsNum : ℤ
rhsNum = (absℤ baseQR *ℤ absP0)

rhsNum≡ : rhsNum ≡ (absℤ baseQR *ℤ absℤ a)
rhsNum≡ = cong (λ t → (absℤ baseQR *ℤ t)) absP0≡absA

-- § denominator embedding relation
denRel : (⁺toℤ rhsDen) *ℤ (⁺toℤ b) ≡ ⁺toℤ lhsDen
denRel =
 let
  lhs₀ : ⁺toℤ lhsDen ≡ (⁺toℤ (b *⁺ d)) *ℤ (⁺toℤ (b *⁺ f))
  lhs₀ = ⁺toℤ-*⁺ (b *⁺ d) (b *⁺ f)

  rhs₀ : ⁺toℤ rhsDen ≡ (⁺toℤ (d *⁺ f)) *ℤ (⁺toℤ (b *⁺ one⁺))
  rhs₀ = ⁺toℤ-*⁺ (d *⁺ f) (b *⁺ one⁺)

  bdf : ⁺toℤ (b *⁺ d) ≡ (⁺toℤ b) *ℤ (⁺toℤ d)
  bdf = ⁺toℤ-*⁺ b d

  bff : ⁺toℤ (b *⁺ f) ≡ (⁺toℤ b) *ℤ (⁺toℤ f)
  bff = ⁺toℤ-*⁺ b f

  dff : ⁺toℤ (d *⁺ f) ≡ (⁺toℤ d) *ℤ (⁺toℤ f)
  dff = ⁺toℤ-*⁺ d f

  bone : ⁺toℤ (b *⁺ one⁺) ≡ (⁺toℤ b) *ℤ (⁺toℤ one⁺)
  bone = ⁺toℤ-*⁺ b one⁺

  stepR : (⁺toℤ rhsDen) *ℤ (⁺toℤ b) ≡ ((⁺toℤ d) *ℤ (⁺toℤ f)) *ℤ (((⁺toℤ b) *ℤ (⁺toℤ one⁺)) *ℤ (⁺toℤ b))
  stepR =
   trans
    (cong (λ t → t *ℤ (⁺toℤ b)) rhs₀)
    (trans
     (cong (λ t → ((⁺toℤ (d *⁺ f)) *ℤ t) *ℤ (⁺toℤ b)) bone)
     (trans
      (cong (λ t → (t *ℤ ((⁺toℤ b) *ℤ (⁺toℤ one⁺))) *ℤ (⁺toℤ b)) dff)
      (trans
       (*ℤ-assoc ((⁺toℤ d) *ℤ (⁺toℤ f)) ((⁺toℤ b) *ℤ (⁺toℤ one⁺)) (⁺toℤ b))
       refl)))

  stepL : ⁺toℤ lhsDen ≡ ((⁺toℤ b) *ℤ (⁺toℤ b)) *ℤ ((⁺toℤ d) *ℤ (⁺toℤ f))
  stepL =
   trans
    lhs₀
    (trans
     (cong (λ t → t *ℤ (⁺toℤ (b *⁺ f))) bdf)
     (trans
      (cong (λ t → ((⁺toℤ b) *ℤ (⁺toℤ d)) *ℤ t) bff)
      (trans
       (mul4-rearrange (⁺toℤ b) (⁺toℤ d) (⁺toℤ b) (⁺toℤ f))
       refl)))
 in
 let
  b1≡b : (⁺toℤ b) *ℤ (⁺toℤ one⁺) ≡ (⁺toℤ b)
  b1≡b = *ℤ-one-right (⁺toℤ b)

  inner : ((⁺toℤ b) *ℤ (⁺toℤ one⁺)) *ℤ (⁺toℤ b) ≡ (⁺toℤ b) *ℤ (⁺toℤ b)
  inner = cong (λ t → t *ℤ (⁺toℤ b)) b1≡b
 in
 trans
  stepR
  (trans
```

```
    (cong (λ t → ((⁺toℤ d) *ℤ (⁺toℤ f)) *ℤ t) inner)
    (trans
     (*ℤ-comm ((⁺toℤ d) *ℤ (⁺toℤ f)) ((⁺toℤ b) *ℤ (⁺toℤ b)))
     (sym stepL)))

  cross : (absZ *ℤ ⁺toℤ rhsDen) ≡ (rhsNum *ℤ ⁺toℤ lhsDen)
  cross =
   let
    lhs₁ : absZ *ℤ ⁺toℤ rhsDen ≡ ((absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ b) *ℤ ⁺toℤ rhsDen
    lhs₁ = cong (λ t → t *ℤ ⁺toℤ rhsDen) absZ≡scaled

    lhs₂ : ((absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ b) *ℤ ⁺toℤ rhsDen ≡ ((absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ rhsDen) *ℤ ⁺toℤ b
    lhs₂ = swapScale (absℤ baseQR *ℤ absℤ a) b rhsDen

    lhs₃ : ((absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ rhsDen) *ℤ ⁺toℤ b ≡ (absℤ baseQR *ℤ absℤ a) *ℤ ((⁺toℤ rhsDen) *ℤ (⁺toℤ b))
    lhs₃ =
     trans
      (*ℤ-assoc (absℤ baseQR *ℤ absℤ a) (⁺toℤ rhsDen) (⁺toℤ b))
      refl

    rhs₁ : rhsNum *ℤ ⁺toℤ lhsDen ≡ (absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ lhsDen
    rhs₁ = cong (λ t → t *ℤ ⁺toℤ lhsDen) rhsNum≡

    rhs₂ : (absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ lhsDen ≡ (absℤ baseQR *ℤ absℤ a) *ℤ (⁺toℤ lhsDen)
    rhs₂ = refl

   in
   trans
    (trans lhs₁ lhs₂)
    (trans
     lhs₃
     (trans
      (cong (λ t → (absℤ baseQR *ℤ absℤ a) *ℤ t) denRel)
      (sym (trans rhs₁ rhs₂))))
 in
 cross
```

Step 2: Right Scaling. Right scaling $d(q \cdot p,\ r \cdot p) \simeq d(q, r) \cdot d(p, 0)$ follows the same factorization. The numerator order is reversed ($c \cdot a$ vs. $a \cdot c$) but the common factor $a \cdot b$ emerges identically through commutativity.

```
-- § distℚ (q*p) (r*p) ≃ℚ distℚ q r * distℚ p 0 (right scaling)
distℚ-*ℚ-right : (p q r : ℚ) → distℚ (q *ℚ p) (r *ℚ p) ≃ℚ (distℚ q r *ℚ distℚ p 0ℚ)
distℚ-*ℚ-right (a / b) (c / d) (e / f) =
 let
  swapScale : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
  swapScale x u v =
   trans
    (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
    (trans
     (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
     (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

  mul4-rearrange : (x y z w : ℤ) → (x *ℤ y) *ℤ (z *ℤ w) ≡ (x *ℤ z) *ℤ (y *ℤ w)
  mul4-rearrange x y z w =
   trans
    (*ℤ-assoc x y (z *ℤ w))
    (trans
     (cong (λ t → x *ℤ t)
```

```
    (trans
     (sym (*ℤ-assoc y z w))
     (trans
      (cong (λ t → t *ℤ w) (*ℤ-comm y z))
      (*ℤ-assoc z y w))))
   (sym (*ℤ-assoc x z (y *ℤ w))))

cf : ℤ
cf = c *ℤ ⁺toℤ f

ed : ℤ
ed = e *ℤ ⁺toℤ d

baseQR : ℤ
baseQR = cf +ℤ negℤ ed

ab : ℤ
ab = a *ℤ ⁺toℤ b

p0Raw : ℤ
p0Raw = (a *ℤ ⁺toℤ one⁺) +ℤ negℤ (0ℤ *ℤ ⁺toℤ b)

p0Raw≡a : p0Raw ≡ a
p0Raw≡a =
 trans
  (cong (λ t → t +ℤ negℤ (0ℤ *ℤ ⁺toℤ b)) (*ℤ-one-right a))
  (trans
   (cong (λ t → a +ℤ negℤ t) (*ℤ-zero-left (⁺toℤ b)))
   (trans
    (cong (λ t → a +ℤ t) (negℤ-zero))
    (+ℤ-zero-right a)))

absP0 : ℤ
absP0 = absℤ p0Raw

absP0≡absA : absP0 ≡ absℤ a
absP0≡absA = trans (absℤ-cong p0Raw≡a) refl

fbDen : ℕ⁺
fbDen = f *⁺ b

dbDen : ℕ⁺
dbDen = d *⁺ b

-- § LHS cleared numerator for distℚ (q*p) (r*p)
Z : ℤ
Z = ((c *ℤ a) *ℤ ⁺toℤ fbDen) +ℤ negℤ ((e *ℤ a) *ℤ ⁺toℤ dbDen)

term₁ : ((c *ℤ a) *ℤ ⁺toℤ fbDen) ≡ ab *ℤ cf
term₁ =
 trans
  (cong (λ t → (c *ℤ a) *ℤ t) (⁺toℤ-*⁺ f b))
  (trans
   (mul4-rearrange c a (⁺toℤ f) (⁺toℤ b))
   (*ℤ-comm (c *ℤ ⁺toℤ f) (a *ℤ ⁺toℤ b)))

term₂ : ((e *ℤ a) *ℤ ⁺toℤ dbDen) ≡ ab *ℤ ed
term₂ =
 trans
  (cong (λ t → (e *ℤ a) *ℤ t) (⁺toℤ-*⁺ d b))
  (trans
   (mul4-rearrange e a (⁺toℤ d) (⁺toℤ b))
```

```
  (*ℤ-comm (e *ℤ ⁺toℤ d) (a *ℤ ⁺toℤ b)))

factorZ : Z ≡ ab *ℤ baseQR
factorZ =
 let
  Z₁ : Z ≡ (ab *ℤ cf) +ℤ negℤ (ab *ℤ ed)
  Z₁ =
   trans
    (cong (λ t → t +ℤ negℤ ((e *ℤ a) *ℤ ⁺toℤ dbDen)) term₁)
    (cong (λ t → (ab *ℤ cf) +ℤ negℤ t) term₂)

  negPull : negℤ (ab *ℤ ed) ≡ ab *ℤ negℤ ed
  negPull = sym (*ℤ-neg-right ab ed)

  Z₂ : (ab *ℤ cf) +ℤ negℤ (ab *ℤ ed) ≡ (ab *ℤ cf) +ℤ (ab *ℤ negℤ ed)
  Z₂ = cong (λ t → (ab *ℤ cf) +ℤ t) negPull

  Z₃ : (ab *ℤ cf) +ℤ (ab *ℤ negℤ ed) ≡ ab *ℤ (cf +ℤ negℤ ed)
  Z₃ = sym (*ℤ-distrib-right-+ℤ ab cf (negℤ ed))
 in
 trans Z₁ (trans Z₂ Z₃)

absZ : ℤ
absZ = absℤ Z

absZ≡scaled : absZ ≡ (absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ b
absZ≡scaled =
 let
  absZ₁ : absZ ≡ absℤ (ab *ℤ baseQR)
  absZ₁ = cong absℤ factorZ

  absZ₂ : absℤ (ab *ℤ baseQR) ≡ (absℤ ab *ℤ absℤ baseQR)
  absZ₂ = absℤ-mul ab baseQR

  absAB : absℤ ab ≡ absℤ a *ℤ ⁺toℤ b
  absAB = absℤ-mul-pos-right a b

  absZ₃ : (absℤ ab *ℤ absℤ baseQR) ≡ ((absℤ a *ℤ ⁺toℤ b) *ℤ absℤ baseQR)
  absZ₃ = cong (λ t → t *ℤ absℤ baseQR) absAB

  absZ₄ : ((absℤ a *ℤ ⁺toℤ b) *ℤ absℤ baseQR) ≡ ((absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ b)
  absZ₄ =
   trans
    (*ℤ-assoc (absℤ a) (⁺toℤ b) (absℤ baseQR))
    (trans
     (cong (λ t → (absℤ a) *ℤ t) (*ℤ-comm (⁺toℤ b) (absℤ baseQR)))
     (trans
      (sym (*ℤ-assoc (absℤ a) (absℤ baseQR) (⁺toℤ b)))
      (trans
       (cong (λ t → t *ℤ (⁺toℤ b)) (*ℤ-comm (absℤ a) (absℤ baseQR)))
       refl)))
 in
 trans absZ₁ (trans absZ₂ (trans absZ₃ absZ₄))

lhsDen : ℕ⁺
lhsDen = (d *⁺ b) *⁺ (f *⁺ b)

rhsDen : ℕ⁺
rhsDen = (d *⁺ f) *⁺ (b *⁺ one⁺)

rhsNum : ℤ
rhsNum = (absℤ baseQR *ℤ absP0)
```

```
rhsNum≡ : rhsNum ≡ (absℤ baseQR *ℤ absℤ a)
rhsNum≡ = cong (λ t → (absℤ baseQR *ℤ t)) absP0≡absA

denRel : (⁺toℤ rhsDen) *ℤ (⁺toℤ b) ≡ ⁺toℤ lhsDen
denRel =
 let
  lhs₀ : ⁺toℤ lhsDen ≡ (⁺toℤ (d *⁺ b)) *ℤ (⁺toℤ (f *⁺ b))
  lhs₀ = ⁺toℤ-*⁺ (d *⁺ b) (f *⁺ b)

  rhs₀ : ⁺toℤ rhsDen ≡ (⁺toℤ (d *⁺ f)) *ℤ (⁺toℤ (b *⁺ one⁺))
  rhs₀ = ⁺toℤ-*⁺ (d *⁺ f) (b *⁺ one⁺)

  db : ⁺toℤ (d *⁺ b) ≡ (⁺toℤ d) *ℤ (⁺toℤ b)
  db = ⁺toℤ-*⁺ d b

  fb' : ⁺toℤ (f *⁺ b) ≡ (⁺toℤ f) *ℤ (⁺toℤ b)
  fb' = ⁺toℤ-*⁺ f b

  dff : ⁺toℤ (d *⁺ f) ≡ (⁺toℤ d) *ℤ (⁺toℤ f)
  dff = ⁺toℤ-*⁺ d f

  bone : ⁺toℤ (b *⁺ one⁺) ≡ (⁺toℤ b) *ℤ (⁺toℤ one⁺)
  bone = ⁺toℤ-*⁺ b one⁺

  stepR : (⁺toℤ rhsDen) *ℤ (⁺toℤ b) ≡ ((⁺toℤ d) *ℤ (⁺toℤ f)) *ℤ (((⁺toℤ b) *ℤ (⁺toℤ one⁺)) *ℤ (⁺toℤ b))
  stepR =
   trans
    (cong (λ t → t *ℤ (⁺toℤ b)) rhs₀)
    (trans
     (cong (λ t → ((⁺toℤ (d *⁺ f)) *ℤ t) *ℤ (⁺toℤ b)) bone)
     (trans
      (cong (λ t → (t *ℤ ((⁺toℤ b) *ℤ (⁺toℤ one⁺))) *ℤ (⁺toℤ b)) dff)
      (trans
       (*ℤ-assoc ((⁺toℤ d) *ℤ (⁺toℤ f)) ((⁺toℤ b) *ℤ (⁺toℤ one⁺)) (⁺toℤ b))
       refl)))

  stepL : ⁺toℤ lhsDen ≡ ((⁺toℤ b) *ℤ (⁺toℤ b)) *ℤ ((⁺toℤ d) *ℤ (⁺toℤ f))
  stepL =
   trans
    lhs₀
    (trans
     (cong (λ t → t *ℤ (⁺toℤ (f *⁺ b))) db)
     (trans
      (cong (λ t → ((⁺toℤ d) *ℤ (⁺toℤ b)) *ℤ t) fb')
      (trans
       (mul4-rearrange (⁺toℤ d) (⁺toℤ b) (⁺toℤ f) (⁺toℤ b))
       (trans
        (cong (λ t → ((⁺toℤ d) *ℤ (⁺toℤ f)) *ℤ t) (*ℤ-comm (⁺toℤ b) (⁺toℤ b)))
        (trans
         (*ℤ-comm ((⁺toℤ d) *ℤ (⁺toℤ f)) ((⁺toℤ b) *ℤ (⁺toℤ b)))
         refl)))))
 in
 let
  b1≡b : (⁺toℤ b) *ℤ (⁺toℤ one⁺) ≡ (⁺toℤ b)
  b1≡b = *ℤ-one-right (⁺toℤ b)

  inner : ((⁺toℤ b) *ℤ (⁺toℤ one⁺)) *ℤ (⁺toℤ b) ≡ (⁺toℤ b) *ℤ (⁺toℤ b)
  inner = cong (λ t → t *ℤ (⁺toℤ b)) b1≡b
 in
 trans
  stepR
```

```
    (trans
     (cong (λ t → ((⁺toℤ d) *ℤ (⁺toℤ f)) *ℤ t) inner)
     (trans
      (*ℤ-comm ((⁺toℤ d) *ℤ (⁺toℤ f)) ((⁺toℤ b) *ℤ (⁺toℤ b)))
      (sym stepL)))

  cross : (absZ *ℤ ⁺toℤ rhsDen) ≡ (rhsNum *ℤ ⁺toℤ lhsDen)
  cross =
   let
    lhs₁ : absZ *ℤ ⁺toℤ rhsDen ≡ ((absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ b) *ℤ ⁺toℤ rhsDen
    lhs₁ = cong (λ t → t *ℤ ⁺toℤ rhsDen) absZ≡scaled

    lhs₂ : ((absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ b) *ℤ ⁺toℤ rhsDen ≡ ((absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ rhsDen) *ℤ ⁺toℤ b
    lhs₂ = swapScale (absℤ baseQR *ℤ absℤ a) b rhsDen

    lhs₃ : ((absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ rhsDen) *ℤ ⁺toℤ b ≡ (absℤ baseQR *ℤ absℤ a) *ℤ ((⁺toℤ rhsDen) *ℤ (⁺toℤ b))
    lhs₃ = trans (*ℤ-assoc (absℤ baseQR *ℤ absℤ a) (⁺toℤ rhsDen) (⁺toℤ b)) refl

    rhs₁ : rhsNum *ℤ ⁺toℤ lhsDen ≡ (absℤ baseQR *ℤ absℤ a) *ℤ ⁺toℤ lhsDen
    rhs₁ = cong (λ t → t *ℤ ⁺toℤ lhsDen) rhsNum≡
   in
   trans
    (trans lhs₁ lhs₂)
    (trans
     lhs₃
     (trans
      (cong (λ t → (absℤ baseQR *ℤ absℤ a) *ℤ t) denRel)
      (sym rhs₁)))
 in
 cross
```

Distance Bounds

The key bounding lemma: if $x \leq y + \varepsilon$ and $y \leq x + \varepsilon$ then $d(x, y) \leq \varepsilon$. The proof factors the cross-multiplication into $|d \cdot f| \leq e \cdot bd$ using the absolute-value within-bound lemma. The converse extractions recover one-sided order bounds from a distance certificate, closing the gap between order certificates and metric certificates.

```
-- § key bound: x ≤ y+ϵ and y ≤ x+ϵ imply distℚ x y ≤ ϵ
distℚ-bounded-by-ϵ : (x y ϵ : ℚ) → x ≤ℚ (y +ℚ ϵ) → y ≤ℚ (x +ℚ ϵ) → distℚ x y ≤ℚ ϵ
distℚ-bounded-by-ϵ (a / b) (c / d) (e / f) x≤y+ϵ y≤x+ϵ =
 let
  bd : ℕ⁺
  bd = b *⁺ d

  df : ℕ⁺
  df = d *⁺ f

  bf : ℕ⁺
  bf = b *⁺ f

  bdf : ℕ⁺
  bdf = bd *⁺ f

  diff : ℤ
  diff = (a *ℤ ⁺toℤ d) +ℤ negℤ (c *ℤ ⁺toℤ b)
```

```
y+ϵ-num : ℤ
y+ϵ-num = (c *ℤ ⁺toℤ f) +ℤ (e *ℤ ⁺toℤ d)

x+ϵ-num : ℤ
x+ϵ-num = (a *ℤ ⁺toℤ f) +ℤ (e *ℤ ⁺toℤ b)

hyp1 : (a *ℤ ⁺toℤ df) ≤ℤ (y+ϵ-num *ℤ ⁺toℤ b)
hyp1 = x≤y+ϵ

hyp2 : (c *ℤ ⁺toℤ bf) ≤ℤ (x+ϵ-num *ℤ ⁺toℤ d)
hyp2 = y≤x+ϵ

-- § expand hypotheses
adf≤cfb+edb : (a *ℤ ⁺toℤ df) ≤ℤ ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b +ℤ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b)
adf≤cfb+edb = ≤ℤ-resp-≡ʳ (*ℤ-distrib-left-+ℤ (c *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ d) (⁺toℤ b)) hyp1

cbf≤afd+ebd : (c *ℤ ⁺toℤ bf) ≤ℤ ((a *ℤ ⁺toℤ f) *ℤ ⁺toℤ d +ℤ (e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d)
cbf≤afd+ebd = ≤ℤ-resp-≡ʳ (*ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ b) (⁺toℤ d)) hyp2

-- § associativity lemmas
assoc-adf : a *ℤ ⁺toℤ df ≡ (a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f
assoc-adf = trans (cong (λ t → a *ℤ t) (⁺toℤ-*⁺ d f)) (sym (*ℤ-assoc a (⁺toℤ d) (⁺toℤ f)))

assoc-cbf : c *ℤ ⁺toℤ bf ≡ (c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f
assoc-cbf = trans (cong (λ t → c *ℤ t) (⁺toℤ-*⁺ b f)) (sym (*ℤ-assoc c (⁺toℤ b) (⁺toℤ f)))

swapScale : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
swapScale x u v =
 trans
  (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
  (trans
   (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
   (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

assoc-cfb : (c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b ≡ (c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f
assoc-cfb = swapScale c f b

assoc-afd : (a *ℤ ⁺toℤ f) *ℤ ⁺toℤ d ≡ (a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f
assoc-afd = swapScale a f d

edb≡ebd : (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b ≡ (e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d
edb≡ebd = swapScale e d b

-- § renamed for clarity
adf' : ℤ
adf' = (a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f

cbf' : ℤ
cbf' = (c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f

ebd : ℤ
ebd = (e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d

rhsEq₁ : ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b +ℤ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) ≡ (cbf' +ℤ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b)
rhsEq₁ = cong (λ t → t +ℤ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) assoc-cfb

rhsEq₂ : (cbf' +ℤ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) ≡ (cbf' +ℤ ebd)
rhsEq₂ = cong (λ t → cbf' +ℤ t) edb≡ebd

rhsEq : ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b +ℤ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) ≡ (cbf' +ℤ ebd)
rhsEq = trans rhsEq₁ rhsEq₂

-- § hyp1 gives: (a*d)*f ≤ (c*b)*f + ebd
```

```
hyp1' : adf' ≤ℤ (cbf' +ℤ ebd)
hyp1' = ≤ℤ-resp-≡ˡ assoc-adf (≤ℤ-resp-≡ʳ rhsEq adf≤cfb+edb)

-- § hyp2 gives: (c*b)*f ≤ (a*d)*f + ebd
hyp2' : cbf' ≤ℤ (adf' +ℤ ebd)
hyp2' = ≤ℤ-resp-≡ˡ assoc-cbf (≤ℤ-resp-≡ʳ (cong (λ t → t +ℤ ebd) assoc-afd) cbf≤afd+ebd)

-- § diff * f = adf' - cbf'
diff-f : ℤ
diff-f = adf' +ℤ negℤ cbf'

diff-f-eq : diff *ℤ ⁺toℤ f ≡ diff-f
diff-f-eq =
 trans
  (*ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ d) (negℤ (c *ℤ ⁺toℤ b)) (⁺toℤ f))
  (cong (λ t → ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) +ℤ t) (*ℤ-neg-left (c *ℤ ⁺toℤ b) (⁺toℤ f)))

-- § diff-f ≤ ebd from hyp1'
diff-f≤ebd : diff-f ≤ℤ ebd
diff-f≤ebd = ≤ℤ-+ℤ-cancelʳ adf' cbf' ebd (≤ℤ-resp-≡ʳ (sym (+ℤ-comm ebd cbf')) hyp1')

-- § negℤ diff-f ≤ ebd from hyp2'
neg-diff-f≤ebd : (negℤ diff-f) ≤ℤ ebd
neg-diff-f≤ebd =
 let
  step : cbf' +ℤ negℤ adf' ≤ℤ ebd
  step = ≤ℤ-+ℤ-cancelʳ cbf' adf' ebd (≤ℤ-resp-≡ʳ (sym (+ℤ-comm ebd adf')) hyp2')

  neg-eq : negℤ diff-f ≡ cbf' +ℤ negℤ adf'
  neg-eq =
   trans
    (neg-+ℤ adf' (negℤ cbf'))
    (trans
     (+ℤ-comm (negℤ adf') (negℤ (negℤ cbf')))
     (cong (λ t → t +ℤ negℤ adf') (negℤ-involutive cbf')))
 in
 ≤ℤ-resp-≡ˡ (sym neg-eq) step

-- § combine via absℤ-within-bound
neg-ebd≤diff-f : (negℤ ebd) ≤ℤ diff-f
neg-ebd≤diff-f = ≤ℤ-resp-≡ʳ (negℤ-involutive diff-f) (negℤ-antitone-≤ℤ neg-diff-f≤ebd)

abs-diff-f≤ebd : absℤ diff-f ≤ℤ ebd
abs-diff-f≤ebd = absℤ-within-bound diff-f ebd neg-ebd≤diff-f diff-f≤ebd

-- § transport to distℚ x y ≤ℚ ϵ
abs-diff-f-eq : absℤ diff-f ≡ absℤ (diff *ℤ ⁺toℤ f)
abs-diff-f-eq = cong absℤ (sym diff-f-eq)

abs-mul-eq : absℤ (diff *ℤ ⁺toℤ f) ≡ (absℤ diff *ℤ ⁺toℤ f)
abs-mul-eq = absℤ-mul-pos-right diff f

ebd-eq : ebd ≡ (e *ℤ ⁺toℤ bd)
ebd-eq =
 trans
  (*ℤ-assoc e (⁺toℤ b) (⁺toℤ d))
  (cong (λ t → e *ℤ t) (sym (⁺toℤ-*⁺ b d)))

goal : (absℤ diff *ℤ ⁺toℤ f) ≤ℤ (e *ℤ ⁺toℤ bd)
goal = ≤ℤ-resp-≡ˡ (trans abs-diff-f-eq abs-mul-eq) (≤ℤ-resp-≡ʳ ebd-eq abs-diff-f≤ebd)
in
goal
```

Step 2: Converse Extractions. The converse recovers one-sided order bounds from a distance certificate: $d(x, y) \leq \varepsilon$ implies both $x \leq y + \varepsilon$ and $y \leq x + \varepsilon$. The second follows from symmetry.

```
-- § distℚ x y ≤ ϵ implies x ≤ y + ϵ
distℚ≤ϵ→x≤y+ϵ : (x y ϵ : ℚ) → distℚ x y ≤ℚ ϵ → x ≤ℚ (y +ℚ ϵ)
distℚ≤ϵ→x≤y+ϵ (a / b) (c / d) (e / f) dist≤ =
 let
  bd : ℕ⁺
  bd = b *⁺ d

  df : ℕ⁺
  df = d *⁺ f

  diff : ℤ
  diff = (a *ℤ ⁺toℤ d) +ℤ negℤ (c *ℤ ⁺toℤ b)

  absDiff : ℤ
  absDiff = absℤ diff

  absDiff*f≤e*bd : (absDiff *ℤ ⁺toℤ f) ≤ℤ (e *ℤ ⁺toℤ bd)
  absDiff*f≤e*bd = dist≤

  diff≤absDiff : diff ≤ℤ absDiff
  diff≤absDiff = ≤ℤ-absℤ diff

  diff*f≤absDiff*f : (diff *ℤ ⁺toℤ f) ≤ℤ (absDiff *ℤ ⁺toℤ f)
  diff*f≤absDiff*f = ≤ℤ-mul-pos-right diff absDiff f diff≤absDiff

  diff*f≤e*bd : (diff *ℤ ⁺toℤ f) ≤ℤ (e *ℤ ⁺toℤ bd)
  diff*f≤e*bd = ≤ℤ-trans diff*f≤absDiff*f absDiff*f≤e*bd

  y+ϵ-num : ℤ
  y+ϵ-num = (c *ℤ ⁺toℤ f) +ℤ (e *ℤ ⁺toℤ d)

  assoc-adf : a *ℤ ⁺toℤ df ≡ (a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f
  assoc-adf = trans (cong (λ t → a *ℤ t) (⁺toℤ-*⁺ d f)) (sym (*ℤ-assoc a (⁺toℤ d) (⁺toℤ f)))

  swapScale : (x : ℤ) → (u v : ℕ⁺) → (x *ℤ ⁺toℤ u) *ℤ ⁺toℤ v ≡ (x *ℤ ⁺toℤ v) *ℤ ⁺toℤ u
  swapScale x u v =
   trans
    (*ℤ-assoc x (⁺toℤ u) (⁺toℤ v))
    (trans
     (cong (λ t → x *ℤ t) (*ℤ-comm (⁺toℤ u) (⁺toℤ v)))
     (sym (*ℤ-assoc x (⁺toℤ v) (⁺toℤ u))))

  assoc-cfb : (c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b ≡ (c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f
  assoc-cfb = swapScale c f b

  edb≡ebd : (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b ≡ (e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d
  edb≡ebd = swapScale e d b

  adf' : ℤ
  adf' = (a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f

  cbf' : ℤ
  cbf' = (c *ℤ ⁺toℤ b) *ℤ ⁺toℤ f

  ebd : ℤ
  ebd = (e *ℤ ⁺toℤ b) *ℤ ⁺toℤ d
```

```
ebd≡e*bd : ebd ≡ (e *ℤ ⁺toℤ bd)
ebd≡e*bd =
 trans
  (*ℤ-assoc e (⁺toℤ b) (⁺toℤ d))
  (cong (λ t → e *ℤ t) (sym (⁺toℤ-*⁺ b d)))

diff*f≤ebd : (diff *ℤ ⁺toℤ f) ≤ℤ ebd
diff*f≤ebd = ≤ℤ-resp-≡ʳ (sym ebd≡e*bd) diff*f≤e*bd

diff-f : ℤ
diff-f = adf' +ℤ negℤ cbf'

diff-f-eq : diff *ℤ ⁺toℤ f ≡ diff-f
diff-f-eq =
 trans
  (*ℤ-distrib-left-+ℤ (a *ℤ ⁺toℤ d) (negℤ (c *ℤ ⁺toℤ b)) (⁺toℤ f))
  (cong
   (λ t → ((a *ℤ ⁺toℤ d) *ℤ ⁺toℤ f) +ℤ t)
   (trans
    (*ℤ-neg-left (c *ℤ ⁺toℤ b) (⁺toℤ f))
    refl))

diff-f≤ebd' : diff-f ≤ℤ ebd
diff-f≤ebd' = ≤ℤ-resp-≡ˡ diff-f-eq diff*f≤ebd

-- § add cbf' to both sides
sumLe : (diff-f +ℤ cbf') ≤ℤ (ebd +ℤ cbf')
sumLe = ≤ℤ-+ℤ-mono diff-f≤ebd' (≤ℤ-refl cbf')

lhsEq : (diff-f +ℤ cbf') ≡ adf'
lhsEq =
 trans
  (+ℤ-assoc adf' (negℤ cbf') cbf')
  (trans
   (cong (λ t → adf' +ℤ t) (+ℤ-inv-left cbf'))
   (+ℤ-zero-right adf'))

rhsEq : (ebd +ℤ cbf') ≡ (cbf' +ℤ ebd)
rhsEq = +ℤ-comm ebd cbf'

hyp1' : adf' ≤ℤ (cbf' +ℤ ebd)
hyp1' = ≤ℤ-resp-≡ˡ lhsEq (≤ℤ-resp-≡ʳ rhsEq sumLe)

rhsExpand : (y+ϵ-num *ℤ ⁺toℤ b) ≡ (cbf' +ℤ ebd)
rhsExpand =
 let
  step₁ : ((c *ℤ ⁺toℤ f) *ℤ ⁺toℤ b +ℤ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) ≡ (cbf' +ℤ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b)
  step₁ = cong (λ t → t +ℤ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) assoc-cfb

  step₂ : (cbf' +ℤ (e *ℤ ⁺toℤ d) *ℤ ⁺toℤ b) ≡ (cbf' +ℤ ebd)
  step₂ = cong (λ t → cbf' +ℤ t) edb≡ebd
 in
  trans (*ℤ-distrib-left-+ℤ (c *ℤ ⁺toℤ f) (e *ℤ ⁺toℤ d) (⁺toℤ b)) (trans step₁ step₂)
in
≤ℤ-resp-≡ˡ (sym assoc-adf) (≤ℤ-resp-≡ʳ (sym rhsExpand) hyp1')

-- § converse: distℚ x y ≤ ϵ implies y ≤ x + ϵ (by symmetry)
distℚ≤ϵ→y≤x+ϵ : (x y ϵ : ℚ) → distℚ x y ≤ℚ ϵ → y ≤ℚ (x +ℚ ϵ)
distℚ≤ϵ→y≤x+ϵ x y ϵ dist≤ =
 let
  dyx≤dxy : distℚ y x ≤ℚ distℚ x y
  dyx≤dxy =
```

```
  ≃ℚ→≤ℚ^l
   {p = distℚ y x}
   {q = distℚ x y}
   (distℚ-sym y x)

 dyx≤ϵ : distℚ y x ≤ℚ ϵ
 dyx≤ϵ =
  ≤ℚ-trans
   {x = distℚ y x}
   {y = distℚ x y}
   {z = ϵ}
   dyx≤dxy
   dist≤
in
distℚ≤ϵ→x≤y+ϵ y x ϵ dyx≤ϵ
```

The rational distance function is fully operational: triangle inequality, translation invariance, multiplicative scaling, ε-splitting, and distance-order interconversion are all established. Together with the additive and multiplicative order laws from the preceding chapters, $\mathbb{Q}$ is a complete ordered field except for one property: metric completeness. Not every Cauchy sequence of rationals converges to a rational. That deficiency, once named, forces the next construction.

The Archimedean property of $\mathbb{Q}$ must be made explicit so that convergence estimates can quantify "how fast" sequences approach their limits. With Archimedean scaling in hand and the operator span of K_{12} reduced to its canonical (I, J)-basis, the spectral action of the Laplacian completes the rational infrastructure. After that, no further rational law is needed—only the passage to the reals remains.

Chapter 39

Archimedean Scaling

The Archimedean property for $\mathbb{Q}$: given any $\varepsilon > 0$ and any natural number m, there exists $\delta > 0$ such that $\delta \cdot (m+1) < \varepsilon$. This is forced by the existence of denominators that grow faster than linear factors, together with the half-epsilon infrastructure. The required denominator must be forced from the scaling count and the denominator of ε, leaving no arbitrary choice in the witness construction. The resulting witness collapses to the forced half-epsilon bound and supplies the scaling control needed in the Cauchy convergence arguments.

```
– § right identity for ℕ⁺ multiplication
*⁺-one-right : (u : ℕ⁺) → (u *⁺ one⁺) ≡ u
*⁺-one-right (mkℕ⁺ p) =
 cong mkℕ⁺
   (trans
    (+ℕ-zero-right (p *ℕ suc zero))
    (*ℕ-one-right p))

– § 0 < 1/b for any positive denominator
oneOver-pos : (b : ℕ⁺) → 0ℚ <ℚ (oneℤ / b)
oneOver-pos b =
 let
   rhsEq : oneℤ ≡ (oneℤ *ℤ ⁺toℤ one⁺)
   rhsEq = sym (*ℤ-one-right oneℤ)

   base : 0ℤ <ℤ (oneℤ *ℤ ⁺toℤ one⁺)
   base = <ℤ-resp-≡ʳ {x = 0ℤ} {y = oneℤ} {z = (oneℤ *ℤ ⁺toℤ one⁺)} rhsEq 0ℤ<oneℤ
 in
 <ℤ-resp-≡ˡ
   {x = 0ℤ}
   {y = (0ℤ *ℤ ⁺toℤ b)}
   {z = (oneℤ *ℤ ⁺toℤ one⁺)}
   (sym (*ℤ-zero-left (⁺toℤ b)))
   base

– § denominators are ≥ 1 in the integer order
one≤⁺toℤ : (d : ℕ⁺) → oneℤ ≤ℤ ⁺toℤ d
one≤⁺toℤ (mkℕ⁺ k) = s≤s z≤n

– § q ≥ 0 implies q ≤ num(q)/1
nonneg-≤numOverOne : (q : ℚ) → 0ℚ ≤ℚ q → q ≤ℚ (num q / one⁺)
nonneg-≤numOverOne (a / b) qNonneg =
 let
   aNonneg : 0ℤ ≤ℤ a
```

```
    aNonneg =
     let
      one⁺ℤ≡oneℤ : ⁺toℤ one⁺ ≡ oneℤ
      one⁺ℤ≡oneℤ = refl

      rhsEq : (a *ℤ ⁺toℤ one⁺) ≡ a
      rhsEq = trans (cong (λ t → a *ℤ t) one⁺ℤ≡oneℤ) (*ℤ-one-right a)

      step₀ : 0ℤ ≤ℤ (a *ℤ ⁺toℤ one⁺)
      step₀ = ≤ℤ-resp-≡ˡ (*ℤ-zero-left (⁺toℤ b)) qNonneg
     in
     ≤ℤ-resp-≡ʳ rhsEq step₀

    one≤b : oneℤ ≤ℤ ⁺toℤ b
    one≤b = one≤⁺toℤ b

    step : (oneℤ *ℤ a) ≤ℤ ((⁺toℤ b) *ℤ a)
    step = ≤ℤ-mul-nonneg-right oneℤ (⁺toℤ b) a one≤b aNonneg

    lhsEq : (oneℤ *ℤ a) ≡ (a *ℤ ⁺toℤ one⁺)
    lhsEq = trans (*ℤ-one-left a) (sym (*ℤ-one-right a))

    rhsEq : ((⁺toℤ b) *ℤ a) ≡ (a *ℤ ⁺toℤ b)
    rhsEq = *ℤ-comm (⁺toℤ b) a

    core : (a *ℤ ⁺toℤ one⁺) ≤ℤ (a *ℤ ⁺toℤ b)
    core = ≤ℤ-resp-≡ˡ lhsEq (≤ℤ-resp-≡ʳ rhsEq step)
  in
  core

-- § nonnegative q is bounded by suc(m)/1 for some m
nonneg-bound-sucInt : (q : ℚ) → 0ℚ ≤ℚ q → Σ ℕ (λ m → q ≤ℚ (fromℕℤ (suc m) / one⁺))
nonneg-bound-sucInt (a / b) qNonneg =
  let
    aNonneg : 0ℤ ≤ℤ a
    aNonneg =
     let
      one⁺ℤ≡oneℤ : ⁺toℤ one⁺ ≡ oneℤ
      one⁺ℤ≡oneℤ = refl

      rhsEq : (a *ℤ ⁺toℤ one⁺) ≡ a
      rhsEq = trans (cong (λ t → a *ℤ t) one⁺ℤ≡oneℤ) (*ℤ-one-right a)

      step₀ : 0ℤ ≤ℤ (a *ℤ ⁺toℤ one⁺)
      step₀ = ≤ℤ-resp-≡ˡ (*ℤ-zero-left (⁺toℤ b)) qNonneg
     in
     ≤ℤ-resp-≡ʳ rhsEq step₀

    aNatPack : Σ ℕ (λ n → a ≡ fromℕℤ n)
    aNatPack = 0≤ℤ→fromℕℤ a aNonneg

    m : ℕ
    m = fst aNatPack

    a≡ : a ≡ fromℕℤ m
    a≡ = snd aNatPack

    q≤a/1 : (a / b) ≤ℚ (a / one⁺)
    q≤a/1 = nonneg-≤numOverOne (a / b) qNonneg

    a/1≤m/1 : (a / one⁺) ≤ℚ (fromℕℤ m / one⁺)
    a/1≤m/1 =
```

```
    ≤ℤ-resp-≡ʳ
     (cong (λ t → t *ℤ ⁺toℤ one⁺) a≡)
     (≤ℤ-refl (a *ℤ ⁺toℤ one⁺))

   m≤sucm : m ≤ suc m
   m≤sucm = ≤-step m

   fm≤fs : fromℕℤ m ≤ℤ fromℕℤ (suc m)
   fm≤fs = fromℕℤ-mono m≤sucm

   m/1≤sucm/1 : (fromℕℤ m / one⁺) ≤ℚ (fromℕℤ (suc m) / one⁺)
   m/1≤sucm/1 =
    let
     one⁺ℤ≡oneℤ : ⁺toℤ one⁺ ≡ oneℤ
     one⁺ℤ≡oneℤ = refl

     rhsOneEq : (n : ℕ) → (fromℕℤ n *ℤ ⁺toℤ one⁺) ≡ fromℕℤ n
     rhsOneEq n = trans (cong (λ t → fromℕℤ n *ℤ t) one⁺ℤ≡oneℤ) (*ℤ-one-right (fromℕℤ n))

     stepR : fromℕℤ m ≤ℤ (fromℕℤ (suc m) *ℤ ⁺toℤ one⁺)
     stepR = ≤ℤ-resp-≡ʳ (sym (rhsOneEq (suc m))) fm≤fs
    in
    ≤ℤ-resp-≡ˡ (sym (rhsOneEq m)) stepR
in
m ,
   (≤ℚ-trans {a / b} {a / one⁺} {fromℕℤ (suc m) / one⁺} q≤a/1
    (≤ℚ-trans {a / one⁺} {fromℕℤ m / one⁺} {fromℕℤ (suc m) / one⁺} a/1≤m/1 m/1≤sucm/1))
```

Step 2: Archimedean Scaling. Given any positive tolerance ε and any natural bound m, the Archimedean property of the rationals forces a positive δ small enough that $\delta \cdot (m + 1) < \varepsilon$. This is the key ingredient for product–Cauchy proofs.

```
– § Archimedean scaling: there exists δ>0 with δ·(suc m) < ϵ
δ-scale-suc : (ϵ : ℚ) → 0ℚ <ℚ ϵ → (m : ℕ) → Σ ℚ (λ δ → (0ℚ <ℚ δ) × ((δ *ℚ (fromℕℤ (suc m) / one⁺)) <ℚ ϵ))
δ-scale-suc ϵ ϵpos m =
 let
  k : ℕ⁺
  k = mkℕ⁺ m

  b : ℕ⁺
  b = den ϵ

  δ : ℚ
  δ = oneℤ / halfDen (k *⁺ b)

  δpos : 0ℚ <ℚ δ
  δpos = oneOver-pos (halfDen (k *⁺ b))

  factor : ℚ
  factor = fromℕℤ (suc m) / one⁺

  prod : ℚ
  prod = δ *ℚ factor

  – § prod ≃ ϵHalf ϵ, hence prod < ϵ
  kZ : ℤ
  kZ = ⁺toℤ k

  kZ≡ : kZ ≡ fromℕℤ (suc m)
```

```
kZ≡ = refl

halfDenZ : (u : ℕ⁺) → ⁺toℤ (halfDen u) ≡ (⁺toℤ two⁺) *ℤ ⁺toℤ u
halfDenZ u = ⁺toℤ-*⁺ two⁺ u

rhsDenZ : ⁺toℤ (halfDen b) ≡ (⁺toℤ two⁺) *ℤ ⁺toℤ b
rhsDenZ = halfDenZ b

lhsDenZ : ⁺toℤ (halfDen (k *⁺ b)) ≡ (⁺toℤ two⁺) *ℤ ((⁺toℤ k) *ℤ ⁺toℤ b)
lhsDenZ =
 trans
  (halfDenZ (k *⁺ b))
  (cong (λ t → (⁺toℤ two⁺) *ℤ t) (⁺toℤ-*⁺ k b))

swap : (x y z : ℤ) → (x *ℤ (y *ℤ z)) ≡ (y *ℤ (x *ℤ z))
swap x y z =
 trans
  (sym (*ℤ-assoc x y z))
  (trans
   (cong (λ t → t *ℤ z) (*ℤ-comm x y))
   (*ℤ-assoc y x z))

denEq : (⁺toℤ (halfDen (k *⁺ b))) ≡ (fromℕℤ (suc m) *ℤ ⁺toℤ (halfDen b))
denEq =
 trans
  lhsDenZ
  (trans
   (cong (λ t → (⁺toℤ two⁺) *ℤ (t *ℤ ⁺toℤ b)) (sym kZ≡))
   (trans
    (swap (⁺toℤ two⁺) (fromℕℤ (suc m)) (⁺toℤ b))
    (cong (λ t → (fromℕℤ (suc m)) *ℤ t) (sym rhsDenZ))))

prod≃half : prod ≃ℚ (ϵHalf ϵ)
prod≃half =
 let
  lhsNum : ℤ
  lhsNum = oneℤ *ℤ fromℕℤ (suc m)

  lhsDen : ℕ⁺
  lhsDen = (halfDen (k *⁺ b)) *⁺ one⁺

  rhsNum : ℤ
  rhsNum = oneℤ

  rhsDen : ℕ⁺
  rhsDen = halfDen b

  lhsNumEq : lhsNum ≡ fromℕℤ (suc m)
  lhsNumEq = *ℤ-one-left (fromℕℤ (suc m))

  denOne : (halfDen (k *⁺ b)) *⁺ one⁺ ≡ halfDen (k *⁺ b)
  denOne = *⁺-one-right (halfDen (k *⁺ b))

  lhsDenEq : (⁺toℤ lhsDen) ≡ ⁺toℤ (halfDen (k *⁺ b))
  lhsDenEq = cong ⁺toℤ denOne

  cross : (lhsNum *ℤ ⁺toℤ rhsDen) ≡ (rhsNum *ℤ ⁺toℤ lhsDen)
  cross =
   trans
    (cong (λ t → t *ℤ ⁺toℤ rhsDen) lhsNumEq)
    (trans
     (sym denEq)
```

```
      (trans
       (sym (*ℤ-one-left (⁺toℤ (halfDen (k *⁺ b)))))
       (cong (λ t → oneℤ *ℤ t) (sym lhsDenEq))))
  in
  cross

 half<ϵ : (ϵHalf ϵ) <ℚ ϵ
 half<ϵ = ϵHalf<ϵ ϵ ϵpos

 prod<ϵ : prod <ℚ ϵ
 prod<ϵ =
  ≤<ℚ→<ℚ
   {x = prod} {y = ϵHalf ϵ} {z = ϵ}
   (≃ℚ→≤ℚ^l {p = prod} {q = ϵHalf ϵ} prod≃half)
   half<ϵ
in
δ , (δpos , prod<ϵ)
```

Chapter 40

$\mathbb{Z}$-Span of K_{12} Operators

The identity operator I and the all-ones operator J (which maps every vector to the constant vector of its sum) span a forced sub-algebra of $\mathrm{End}(\mathrm{Vec}_{12}\mathbb{Z})$. Every operator of the form $a{\cdot}I{+}b{\cdot}J$ is uniquely determined by its coefficients (a, b), and composition closes inside the span with the multiplication rule $(a, b){\cdot}(c, d) = (ac,\ ad{+}bc{+}12bd)$. The coefficients are forced by evaluating a single delta vector, which eliminates every alternative representation and fixes composition inside the same span.

Span Infrastructure

The (I, J)-span on Vec_{12} becomes usable only after the identity action, blockwise scaling, and the linear form $aI + bJ$ are pinned down without representational slack.

```
-- § identity operator on Vec12ℤ
I12 : Op
I12 v = v

-- § scale a 4-vector by integer a
scaleVec4ℤ : ℤ → Vec4ℤ → Vec4ℤ
scaleVec4ℤ a v i = a *ℤ v i

-- § scale a 12-vector blockwise
scaleVec12ℤ : ℤ → Vec12ℤ → Vec12ℤ
scaleVec12ℤ a v = scaleVec4ℤ a (block₀ v) , (scaleVec4ℤ a (block₁ v) , scaleVec4ℤ a (block₂ v))

-- § linear combination a·I + b·J
linIJ : ℤ → ℤ → Op
linIJ a b v = scaleVec12ℤ a v +Vec12ℤ scaleVec12ℤ b (J12Vec12ℤ v)

-- § block projection lemmas (all refl)
block₀-linIJ : (a b : ℤ) → (v : Vec12ℤ) → (i : Fin4) →
 block₀ (linIJ a b v) i ≡ (a *ℤ block₀ v i) +ℤ (b *ℤ sum12ℤ v)
block₀-linIJ a b v i = refl

block₁-linIJ : (a b : ℤ) → (v : Vec12ℤ) → (i : Fin4) →
 block₁ (linIJ a b v) i ≡ (a *ℤ block₁ v i) +ℤ (b *ℤ sum12ℤ v)
block₁-linIJ a b v i = refl

block₂-linIJ : (a b : ℤ) → (v : Vec12ℤ) → (i : Fin4) →
 block₂ (linIJ a b v) i ≡ (a *ℤ block₂ v i) +ℤ (b *ℤ sum12ℤ v)
block₂-linIJ a b v i = refl
```

Sum-Scaling Laws

Every later coefficient extraction depends on the sum-behaviour of the span operations collapsing through addition and scalar multiplication in exactly one way.

```
-- § six-term sum reassociation into (v-side) + (w-side)
shuffle3Pairs : (A A' B B' C C' : ℤ) →
 (A +ℤ A') +ℤ ((B +ℤ B') +ℤ (C +ℤ C')) ≡ (A +ℤ (B +ℤ C)) +ℤ (A' +ℤ (B' +ℤ C'))
shuffle3Pairs A A' B B' C C' =
 let
  X = (B +ℤ B') +ℤ (C +ℤ C')

  step₁ : (A +ℤ A') +ℤ X ≡ A +ℤ (A' +ℤ X)
  step₁ = +ℤ-assoc A A' X

  step₂ : A' +ℤ X ≡ A' +ℤ (B +ℤ (B' +ℤ (C +ℤ C')))
  step₂ = cong (λ t → A' +ℤ t) (+ℤ-assoc B B' (C +ℤ C'))

  step₃ : A' +ℤ (B +ℤ (B' +ℤ (C +ℤ C'))) ≡ B +ℤ (A' +ℤ (B' +ℤ (C +ℤ C')))
  step₃ = swapHeadℤ A' B (B' +ℤ (C +ℤ C'))

  step₄ : A' +ℤ (B' +ℤ (C +ℤ C')) ≡ C +ℤ (A' +ℤ (B' +ℤ C'))
  step₄ =
   trans
    (cong (λ t → A' +ℤ t) (swapHeadℤ B' C C'))
    (swapHeadℤ A' C (B' +ℤ C'))

  step₅ : B +ℤ (A' +ℤ (B' +ℤ (C +ℤ C'))) ≡ B +ℤ (C +ℤ (A' +ℤ (B' +ℤ C')))
  step₅ = cong (λ t → B +ℤ t) step₄

  step₆ : A +ℤ (B +ℤ (C +ℤ (A' +ℤ (B' +ℤ C')))) ≡ (A +ℤ (B +ℤ C)) +ℤ (A' +ℤ (B' +ℤ C'))
  step₆ =
   trans
    (cong (λ t → A +ℤ t) (sym (+ℤ-assoc B C (A' +ℤ (B' +ℤ C')))))
    (sym (+ℤ-assoc A (B +ℤ C) (A' +ℤ (B' +ℤ C'))))
 in
 trans
  step₁
  (trans
   (cong (λ t → A +ℤ t) (trans step₂ (trans step₃ step₅)))
   step₆)

-- § finite-sum scaling by right distributivity
sumFin4-scaleVec4ℤ : (a : ℤ) → (v : Vec4ℤ) →
 sumFin4ℤ (scaleVec4ℤ a v) ≡ a *ℤ sumFin4ℤ v
sumFin4-scaleVec4ℤ a v =
 let
  v0 = v g0
  v1 = v g1
  v2 = v g2
  v3 = v g3

  expand : a *ℤ (v0 +ℤ (v1 +ℤ (v2 +ℤ v3))) ≡ (a *ℤ v0) +ℤ ((a *ℤ v1) +ℤ ((a *ℤ v2) +ℤ (a *ℤ v3)))
  expand =
   trans
    (*ℤ-distrib-right-+ℤ a v0 (v1 +ℤ (v2 +ℤ v3)))
    (cong (λ t → (a *ℤ v0) +ℤ t)
     (trans
      (*ℤ-distrib-right-+ℤ a v1 (v2 +ℤ v3))
      (cong (λ t → (a *ℤ v1) +ℤ t)
```

```
      (*ℤ-distrib-right-+ℤ a v2 v3))))
 in
 sym expand

-- § 12-vector sum distributes over addition
sum12-+Vec12ℤ : (v w : Vec12ℤ) → sum12ℤ (v +Vec12ℤ w) ≡ sum12ℤ v +ℤ sum12ℤ w
sum12-+Vec12ℤ v w =
 let
  A = sumFin4ℤ (block₀ v)
  B = sumFin4ℤ (block₁ v)
  C = sumFin4ℤ (block₂ v)
  A' = sumFin4ℤ (block₀ w)
  B' = sumFin4ℤ (block₁ w)
  C' = sumFin4ℤ (block₂ w)
 in
 trans
  refl
  (trans
   (cong
    (λ t → t +ℤ (sumFin4ℤ (block₁ (v +Vec12ℤ w)) +ℤ sumFin4ℤ (block₂ (v +Vec12ℤ w))))
    (sumFin4-+Vec4ℤ (block₀ v) (block₀ w)))
   (trans
    (cong
     (λ t → (A +ℤ A') +ℤ (t +ℤ sumFin4ℤ (block₂ (v +Vec12ℤ w))) )
     (sumFin4-+Vec4ℤ (block₁ v) (block₁ w)))
    (trans
     (cong
      (λ t → (A +ℤ A') +ℤ ((B +ℤ B') +ℤ t))
      (sumFin4-+Vec4ℤ (block₂ v) (block₂ w)))
     (shuffle3Pairs A A' B B' C C'))))

-- § 12-vector sum distributes over scalar multiplication
sum12-scaleVec12ℤ : (a : ℤ) → (v : Vec12ℤ) → sum12ℤ (scaleVec12ℤ a v) ≡ a *ℤ sum12ℤ v
sum12-scaleVec12ℤ a v =
 let
  s0 = sumFin4ℤ (block₀ v)
  s1 = sumFin4ℤ (block₁ v)
  s2 = sumFin4ℤ (block₂ v)
 in
 let
  stepBlock : sum12ℤ (scaleVec12ℤ a v) ≡ (a *ℤ s0) +ℤ ((a *ℤ s1) +ℤ (a *ℤ s2))
  stepBlock =
   trans
    refl
    (trans
     (cong
      (λ t → t +ℤ (sumFin4ℤ (scaleVec4ℤ a (block₁ v)) +ℤ sumFin4ℤ (scaleVec4ℤ a (block₂ v))))
      (sumFin4-scaleVec4ℤ a (block₀ v)))
     (trans
      (cong
       (λ t → (a *ℤ s0) +ℤ (t +ℤ sumFin4ℤ (scaleVec4ℤ a (block₂ v))) )
       (sumFin4-scaleVec4ℤ a (block₁ v)))
      (cong
       (λ t → (a *ℤ s0) +ℤ ((a *ℤ s1) +ℤ t))
       (sumFin4-scaleVec4ℤ a (block₂ v)))))

  fold : a *ℤ (s0 +ℤ (s1 +ℤ s2)) ≡ (a *ℤ s0) +ℤ ((a *ℤ s1) +ℤ (a *ℤ s2))
  fold =
   trans
    (*ℤ-distrib-right-+ℤ a s0 (s1 +ℤ s2))
    (cong (λ t → (a *ℤ s0) +ℤ t) (*ℤ-distrib-right-+ℤ a s1 s2))
```

```
in
trans stepBlock (sym fold)
```

Twelve-Times Commutativity

Multiplication must commute with the forced twelve-times operator—otherwise the composition formula for the (I, J)-span inherits ambiguity from the scalar side.

```
-- § x * fourTimes y = fourTimes (x*y)
*ℤ-fourTimes-right : (x y : ℤ) → x *ℤ fourTimesℤ y ≡ fourTimesℤ (x *ℤ y)
*ℤ-fourTimes-right x y =
 trans
  (*ℤ-distrib-right-+ℤ x y (y +ℤ (y +ℤ y)))
  (cong (λ t → (x *ℤ y) +ℤ t)
   (trans
    (*ℤ-distrib-right-+ℤ x y (y +ℤ y))
    (cong (λ t → (x *ℤ y) +ℤ t)
     (*ℤ-distrib-right-+ℤ x y y))))

-- § fourTimes x * y = fourTimes (x*y)
*ℤ-fourTimes-left : (x y : ℤ) → fourTimesℤ x *ℤ y ≡ fourTimesℤ (x *ℤ y)
*ℤ-fourTimes-left x y =
 trans
  (*ℤ-distrib-left-+ℤ x (x +ℤ (x +ℤ x)) y)
  (cong (λ t → (x *ℤ y) +ℤ t)
   (trans
    (*ℤ-distrib-left-+ℤ x (x +ℤ x) y)
    (cong (λ t → (x *ℤ y) +ℤ t)
     (*ℤ-distrib-left-+ℤ x x y))))

-- § x * eightTimes y = eightTimes (x*y)
*ℤ-eightTimes-right : (x y : ℤ) → x *ℤ eightTimesℤ y ≡ eightTimesℤ (x *ℤ y)
*ℤ-eightTimes-right x y =
 trans
  (*ℤ-distrib-right-+ℤ x (fourTimesℤ y) (fourTimesℤ y))
  (cong (λ t → t +ℤ t) (*ℤ-fourTimes-right x y))

-- § eightTimes x * y = eightTimes (x*y)
*ℤ-eightTimes-left : (x y : ℤ) → eightTimesℤ x *ℤ y ≡ eightTimesℤ (x *ℤ y)
*ℤ-eightTimes-left x y =
 trans
  (*ℤ-distrib-left-+ℤ (fourTimesℤ x) (fourTimesℤ x) y)
  (cong (λ t → t +ℤ t) (*ℤ-fourTimes-left x y))

-- § x * twelveTimes y = twelveTimes (x*y)
*ℤ-twelveTimes-right : (x y : ℤ) → x *ℤ twelveTimesℤ y ≡ twelveTimesℤ (x *ℤ y)
*ℤ-twelveTimes-right x y =
 trans
  (*ℤ-distrib-right-+ℤ x (fourTimesℤ y) (eightTimesℤ y))
  (trans
   (cong (λ t → t +ℤ x *ℤ eightTimesℤ y) (*ℤ-fourTimes-right x y))
   (cong (λ t → fourTimesℤ (x *ℤ y) +ℤ t) (*ℤ-eightTimes-right x y)))

-- § twelveTimes x * y = twelveTimes (x*y)
*ℤ-twelveTimes-left : (x y : ℤ) → twelveTimesℤ x *ℤ y ≡ twelveTimesℤ (x *ℤ y)
*ℤ-twelveTimes-left x y =
 trans
  (*ℤ-distrib-left-+ℤ (fourTimesℤ x) (eightTimesℤ x) y)
```

```
  (trans
   (cong (λ t → t +ℤ eightTimesℤ x *ℤ y) (*ℤ-fourTimes-left x y))
   (cong (λ t → fourTimesℤ (x *ℤ y) +ℤ t) (*ℤ-eightTimes-left x y)))

– § x * twelveTimes y = twelveTimes x * y
mul-twelveShift : (x y : ℤ) → x *ℤ twelveTimesℤ y ≡ twelveTimesℤ x *ℤ y
mul-twelveShift x y = trans (*ℤ-twelveTimes-right x y) (sym (*ℤ-twelveTimes-left x y))

– § sum of an (I,J)-combination
sum12-linIJ : (a b : ℤ) → (v : Vec12ℤ) →
 sum12ℤ (linIJ a b v) ≡ (a *ℤ sum12ℤ v) +ℤ (b *ℤ twelveTimesℤ (sum12ℤ v))
sum12-linIJ a b v =
 let
  s = sum12ℤ v
  step₁ : sum12ℤ (linIJ a b v)
          ≡ sum12ℤ (scaleVec12ℤ a v) +ℤ sum12ℤ (scaleVec12ℤ b (J12Vec12ℤ v))
  step₁ = sum12-+Vec12ℤ (scaleVec12ℤ a v) (scaleVec12ℤ b (J12Vec12ℤ v))

  step₂ : sum12ℤ (scaleVec12ℤ a v) ≡ a *ℤ s
  step₂ = sum12-scaleVec12ℤ a v

  step₃ : sum12ℤ (scaleVec12ℤ b (J12Vec12ℤ v)) ≡ b *ℤ sum12ℤ (J12Vec12ℤ v)
  step₃ = sum12-scaleVec12ℤ b (J12Vec12ℤ v)

  step₄ : b *ℤ sum12ℤ (J12Vec12ℤ v) ≡ b *ℤ twelveTimesℤ s
  step₄ = cong (λ t → b *ℤ t) (sum12-J12 v)
 in
 trans
  step₁
  (trans
   (cong (λ t → t +ℤ sum12ℤ (scaleVec12ℤ b (J12Vec12ℤ v))) step₂)
   (cong (λ t → (a *ℤ s) +ℤ t) (trans step₃ step₄)))
```

Delta Vectors

Coefficient extraction requires delta witnesses whose support and total sum leave no room for choice: once the delta vector is fixed, every coefficient is read off rather than selected.

```
– § single-coordinate delta vector on Fin4 (16 pattern cases)
delta4 : Fin4 → ℤ → Vec4ℤ
delta4 g0 x g0 = x
delta4 g0 x g1 = 0ℤ
delta4 g0 x g2 = 0ℤ
delta4 g0 x g3 = 0ℤ

delta4 g1 x g0 = 0ℤ
delta4 g1 x g1 = x
delta4 g1 x g2 = 0ℤ
delta4 g1 x g3 = 0ℤ

delta4 g2 x g0 = 0ℤ
delta4 g2 x g1 = 0ℤ
delta4 g2 x g2 = x
delta4 g2 x g3 = 0ℤ

delta4 g3 x g0 = 0ℤ
delta4 g3 x g1 = 0ℤ
delta4 g3 x g2 = 0ℤ
```

```
delta4 g3 x g3 = x

-- § sumFin4 of delta is identity
sumFin4-delta4 : (i : Fin4) → (x : ℤ) → sumFin4ℤ (delta4 i x) ≡ x
sumFin4-delta4 g0 x =
 trans
  (cong (λ t → x +ℤ t)
   (trans
    (+ℤ-zero-left (0ℤ +ℤ 0ℤ))
    (+ℤ-zero-left 0ℤ)))
  (+ℤ-zero-right x)
sumFin4-delta4 g1 x =
 trans
  (+ℤ-zero-left (x +ℤ (0ℤ +ℤ 0ℤ)))
  (trans
   (cong (λ t → x +ℤ t) (+ℤ-zero-left 0ℤ))
   (+ℤ-zero-right x))
sumFin4-delta4 g2 x =
 trans
  (+ℤ-zero-left (0ℤ +ℤ (x +ℤ 0ℤ)))
  (trans
   (+ℤ-zero-left (x +ℤ 0ℤ))
   (+ℤ-zero-right x))
sumFin4-delta4 g3 x =
 trans
  (+ℤ-zero-left (0ℤ +ℤ (0ℤ +ℤ x)))
  (trans
   (+ℤ-zero-left (0ℤ +ℤ x))
   (+ℤ-zero-left x))

-- § delta vector on Vec12ℤ supported at (block₀, g0)
delta12 : ℤ → Vec12ℤ
delta12 x = delta4 g0 x , (delta4 g0 0ℤ , delta4 g0 0ℤ)

-- § sum12 of delta12 is identity
sum12-delta12 : (x : ℤ) → sum12ℤ (delta12 x) ≡ x
sum12-delta12 x =
 trans
  (cong (λ t → t +ℤ (sumFin4ℤ (delta4 g0 0ℤ) +ℤ sumFin4ℤ (delta4 g0 0ℤ)))
        (sumFin4-delta4 g0 x))
  (trans
   (cong (λ t → x +ℤ t)
         (cong (λ t → t +ℤ sumFin4ℤ (delta4 g0 0ℤ)) (sumFin4-delta4 g0 0ℤ)))
   (trans
    (cong (λ t → x +ℤ (0ℤ +ℤ t)) (sumFin4-delta4 g0 0ℤ))
    (trans
        (cong (λ t → x +ℤ t) (+ℤ-zero-left 0ℤ))
        (+ℤ-zero-right x))))

-- § J12 on delta12 is constant vector
J12-delta12-const : (x : ℤ) → Vec12Eq (J12Vec12ℤ (delta12 x)) (constVec12ℤ x)
J12-delta12-const x =
 let p = sum12-delta12 x in
 (λ _ → p) , ((λ _ → p) , (λ _ → p))
```

Forced Independence and Uniqueness

Coefficient multiplicity in the (I, J)-span collapses completely: evaluation on the canonical delta vector forces independence first, then forces uniqueness of every coefficient pair.

```
-- § Law 14N.0: (a·I + b·J) = 0 forces a = 0 and b = 0
law14N-0-IJ-independent : (a b : ℤ) → OpEq (linIJ a b) zeroOp → (a ≡ 0ℤ) × (b ≡ 0ℤ)
law14N-0-IJ-independent a b hyp = a0 , b0
 where
  v : Vec12ℤ
  v = delta12 oneℤ

  pSum : sum12ℤ v ≡ oneℤ
  pSum = sum12-delta12 oneℤ

  -- § at g1 the I-term vanishes, extracting b
  eqQraw : block₀ (linIJ a b v) g1 ≡ block₀ (zeroOp v) g1
  eqQraw = fst (hyp v) g1

  eqQ₀ : (a *ℤ 0ℤ) +ℤ (b *ℤ sum12ℤ v) ≡ 0ℤ
  eqQ₀ = trans (sym (block₀-linIJ a b v g1)) eqQraw

  eqQ₁ : (a *ℤ 0ℤ) +ℤ (b *ℤ oneℤ) ≡ 0ℤ
  eqQ₁ = trans (sym (cong (λ t → (a *ℤ 0ℤ) +ℤ (b *ℤ t)) pSum)) eqQ₀

  eqQ₂ : 0ℤ +ℤ (b *ℤ oneℤ) ≡ 0ℤ
  eqQ₂ =
   trans
    (sym (cong (λ t → t +ℤ (b *ℤ oneℤ)) (*ℤ-zero-right a)))
    eqQ₁

  bAtQ : (b *ℤ oneℤ) ≡ 0ℤ
  bAtQ = trans (sym (+ℤ-zero-left (b *ℤ oneℤ))) eqQ₂

  b0 : b ≡ 0ℤ
  b0 = trans (sym (*ℤ-one-right b)) bAtQ

  -- § at g0 the I-term gives a, extracting a
  eqPraw : block₀ (linIJ a b v) g0 ≡ block₀ (zeroOp v) g0
  eqPraw = fst (hyp v) g0

  eqP₀ : (a *ℤ oneℤ) +ℤ (b *ℤ sum12ℤ v) ≡ 0ℤ
  eqP₀ = trans (sym (block₀-linIJ a b v g0)) eqPraw

  eqP₁ : (a *ℤ oneℤ) +ℤ (b *ℤ oneℤ) ≡ 0ℤ
  eqP₁ = trans (sym (cong (λ t → (a *ℤ oneℤ) +ℤ (b *ℤ t)) pSum)) eqP₀

  eqP₂ : (a *ℤ oneℤ) +ℤ (0ℤ *ℤ oneℤ) ≡ 0ℤ
  eqP₂ =
   trans
    (sym (cong (λ t → (a *ℤ oneℤ) +ℤ (t *ℤ oneℤ)) b0))
    eqP₁

  eqP₃ : (a *ℤ oneℤ) +ℤ 0ℤ ≡ 0ℤ
  eqP₃ =
   trans
    (sym (cong (λ t → (a *ℤ oneℤ) +ℤ t) (*ℤ-zero-left oneℤ)))
    eqP₂

  aAtP : (a *ℤ oneℤ) ≡ 0ℤ
  aAtP = trans (sym (+ℤ-zero-right (a *ℤ oneℤ))) eqP₃

  a0 : a ≡ 0ℤ
  a0 = trans (sym (*ℤ-one-right a)) aAtP

-- § additive right cancellation
+ℤ-cancel-right : (a c b : ℤ) → a +ℤ b ≡ c +ℤ b → a ≡ c
```

```
+ℤ-cancel-right a c b eq =
 let eq' = cong (λ t → negℤ b +ℤ t) eq in
 trans
  (sym (reduce a))
  (trans eq' (reduce c))
 where
  reduce : (x : ℤ) → negℤ b +ℤ (x +ℤ b) ≡ x
  reduce x =
   trans
    (swapHeadℤ (negℤ b) x b)
    (trans
     (cong (λ t → x +ℤ t) (+ℤ-inv-left b))
     (+ℤ-zero-right x))
```

Step 2: Uniqueness of (I, J)-Representation. With linear independence established, the forced equality of scalar pairs follows by taking the difference operator and applying the independence result.

```
– § Law 14N.1: (a·I + b·J) = (c·I + d·J) forces a = c and b = d
law14N-1-IJ-unique : (a b c d : ℤ) → OpEq (linIJ a b) (linIJ c d) → (a ≡ c) × (b ≡ d)
law14N-1-IJ-unique a b c d hyp = aEq , bEq
 where
  v : Vec12ℤ
  v = delta12 oneℤ

  pSum : sum12ℤ v ≡ oneℤ
  pSum = sum12-delta12 oneℤ

  – § extract b = d from g1 evaluation
  eqQraw : block₀ (linIJ a b v) g1 ≡ block₀ (linIJ c d v) g1
  eqQraw = fst (hyp v) g1

  eqQ₀ : (a *ℤ 0ℤ) +ℤ (b *ℤ sum12ℤ v) ≡ (c *ℤ 0ℤ) +ℤ (d *ℤ sum12ℤ v)
  eqQ₀ =
   trans (sym (block₀-linIJ a b v g1))
    (trans eqQraw (block₀-linIJ c d v g1))

  eqQ₁a : (a *ℤ 0ℤ) +ℤ (b *ℤ sum12ℤ v) ≡ 0ℤ +ℤ (b *ℤ sum12ℤ v)
  eqQ₁a = cong (λ t → t +ℤ (b *ℤ sum12ℤ v)) (*ℤ-zero-right a)

  eqQ₁c : (c *ℤ 0ℤ) +ℤ (d *ℤ sum12ℤ v) ≡ 0ℤ +ℤ (d *ℤ sum12ℤ v)
  eqQ₁c = cong (λ t → t +ℤ (d *ℤ sum12ℤ v)) (*ℤ-zero-right c)

  eqQ₁ : 0ℤ +ℤ (b *ℤ sum12ℤ v) ≡ 0ℤ +ℤ (d *ℤ sum12ℤ v)
  eqQ₁ = trans (sym eqQ₁a) (trans eqQ₀ eqQ₁c)

  eqQ₂ : 0ℤ +ℤ (b *ℤ oneℤ) ≡ 0ℤ +ℤ (d *ℤ oneℤ)
  eqQ₂ =
   trans
    (cong (λ t → 0ℤ +ℤ (b *ℤ t)) pSum)
    (trans eqQ₁ (sym (cong (λ t → 0ℤ +ℤ (d *ℤ t)) pSum)))

  bEq' : (b *ℤ oneℤ) ≡ (d *ℤ oneℤ)
  bEq' =
   trans
    (sym (+ℤ-zero-left (b *ℤ oneℤ)))
    (trans eqQ₂ (+ℤ-zero-left (d *ℤ oneℤ)))

  bEq : b ≡ d
```

```
bEq =
 trans (sym (*ℤ-one-right b))
  (trans bEq' (*ℤ-one-right d))

-- § extract a = c from g0 evaluation with right cancellation
eqPraw : block₀ (linIJ a b v) g0 ≡ block₀ (linIJ c d v) g0
eqPraw = fst (hyp v) g0

eqP₀ : (a *ℤ oneℤ) +ℤ (b *ℤ sum12ℤ v) ≡ (c *ℤ oneℤ) +ℤ (d *ℤ sum12ℤ v)
eqP₀ =
 trans (sym (block₀-linIJ a b v g0))
  (trans eqPraw (block₀-linIJ c d v g0))

eqP₁ : (a *ℤ oneℤ) +ℤ (b *ℤ oneℤ) ≡ (c *ℤ oneℤ) +ℤ (d *ℤ oneℤ)
eqP₁ =
 trans (cong (λ t → (a *ℤ oneℤ) +ℤ (b *ℤ t)) pSum)
  (trans eqP₀ (sym (cong (λ t → (c *ℤ oneℤ) +ℤ (d *ℤ t)) pSum)))

eqP₂ : (a *ℤ oneℤ) +ℤ (b *ℤ oneℤ) ≡ (c *ℤ oneℤ) +ℤ (b *ℤ oneℤ)
eqP₂ =
 trans
  eqP₁
  (cong (λ t → (c *ℤ oneℤ) +ℤ t)
   (cong (λ z → z *ℤ oneℤ) (sym bEq)))

aEq' : (a *ℤ oneℤ) ≡ (c *ℤ oneℤ)
aEq' = +ℤ-cancel-right (a *ℤ oneℤ) (c *ℤ oneℤ) (b *ℤ oneℤ) eqP₂

aEq : a ≡ c
aEq =
 trans (sym (*ℤ-one-right a))
  (trans aEq' (*ℤ-one-right c))
```

Packaging and Composition Closure

Packaging the span coefficients and closing them under composition is forced by the sum and scaling identities already established—no alternative closure rule survives.

```
-- § the forced (I,J) normal form
SpanIJ : Set
SpanIJ = ℤ × ℤ

-- § interpretation into operators
interpIJ : SpanIJ → Op
interpIJ ab = linIJ (fst ab) (snd ab)

-- § injectivity of interpretation
interpIJ-injective : (p q : SpanIJ) → OpEq (interpIJ p) (interpIJ q) → p ≡ q
interpIJ-injective (a , b) (c , d) eq =
 let res = law14N-1-IJ-unique a b c d eq in
 pair-ext (fst res) (snd res)
 where
  pair-ext : {a b c d : ℤ} → a ≡ c → b ≡ d → (a , b) ≡ (c , d)
  pair-ext refl refl = refl

-- § Law 14N.2: image witness in span is forced unique
law14N-2-image-witness-unique :
 (f : Op) →
```

```
(w₁ w₂ : Σ SpanIJ (λ p → OpEq f (interpIJ p))) →
 fst w₁ ≡ fst w₂
law14N-2-image-witness-unique f (p₁ , eq₁) (p₂ , eq₂) =
 interpIJ-injective p₁ p₂ (λ v → Vec12Eq-trans (Vec12Eq-sym (eq₁ v)) (eq₂ v))

-- § multiplication rule for SpanIJ
mulSpanIJ : SpanIJ → SpanIJ → SpanIJ
mulSpanIJ (a , b) (c , d) = (a *ℤ c) , (((a *ℤ d) +ℤ (b *ℤ c)) +ℤ twelveTimesℤ (b *ℤ d))
```

Step 2: Composition Closure. The (I, J)-span is closed under composition: applying two span elements yields another span element, with the multiplication rule forced by the relation $J^2 = 12J$.

```
-- § Law 14N.3: (I,J)-span is closed under composition
law14N-3-IJ-compose-closed : (p q : SpanIJ) → OpEq (λ v → interpIJ p (interpIJ q v)) (interpIJ (mulSpanIJ p q))
law14N-3-IJ-compose-closed (a , b) (c , d) v = eq0 , (eq1 , eq2)
 where
  s : ℤ
  s = sum12ℤ v

  w : Vec12ℤ
  w = linIJ c d v

  sw : sum12ℤ w ≡ (c *ℤ s) +ℤ (d *ℤ twelveTimesℤ s)
  sw = sum12-linIJ c d v

  b' : ℤ
  b' = ((a *ℤ d) +ℤ (b *ℤ c)) +ℤ twelveTimesℤ (b *ℤ d)

  -- § generic block equality helper
  blkEq :
   (blk : Vec12ℤ → Vec4ℤ) →
   ((x y : ℤ) → (u : Vec12ℤ) → (i : Fin4) → blk (linIJ x y u) i ≡ (x *ℤ blk u i) +ℤ (y *ℤ sum12ℤ u)) →
   (i : Fin4) →
   blk (linIJ a b w) i ≡ blk (linIJ (a *ℤ c) b' v) i
  blkEq blk blk-lin i =
   let
    vi = blk v i

    lhsForm : blk (linIJ a b w) i ≡ (a *ℤ blk w i) +ℤ (b *ℤ sum12ℤ w)
    lhsForm = blk-lin a b w i

    blkW : blk w i ≡ (c *ℤ vi) +ℤ (d *ℤ s)
    blkW = blk-lin c d v i

    rhsForm : blk (linIJ (a *ℤ c) b' v) i ≡ ((a *ℤ c) *ℤ vi) +ℤ (b' *ℤ s)
    rhsForm = blk-lin (a *ℤ c) b' v i

    step₁ : blk (linIJ a b w) i ≡ (a *ℤ ((c *ℤ vi) +ℤ (d *ℤ s))) +ℤ (b *ℤ sum12ℤ w)
    step₁ =
     trans
      lhsForm
      (cong (λ t → (a *ℤ t) +ℤ (b *ℤ sum12ℤ w)) blkW)

    step₂ : (a *ℤ ((c *ℤ vi) +ℤ (d *ℤ s))) +ℤ (b *ℤ sum12ℤ w)
            ≡ ((a *ℤ (c *ℤ vi)) +ℤ (a *ℤ (d *ℤ s))) +ℤ (b *ℤ sum12ℤ w)
    step₂ = cong (λ t → t +ℤ (b *ℤ sum12ℤ w)) (*ℤ-distrib-right-+ℤ a (c *ℤ vi) (d *ℤ s))

    assocAC : a *ℤ (c *ℤ vi) ≡ (a *ℤ c) *ℤ vi
```

```
assocAC = sym (*ℤ-assoc a c vi)

assocAD : a *ℤ (d *ℤ s) ≡ (a *ℤ d) *ℤ s
assocAD = sym (*ℤ-assoc a d s)

step₃ : ((a *ℤ (c *ℤ vi)) +ℤ (a *ℤ (d *ℤ s))) +ℤ (b *ℤ sum12ℤ w)
        ≡ (((a *ℤ c) *ℤ vi) +ℤ ((a *ℤ d) *ℤ s)) +ℤ (b *ℤ sum12ℤ w)
step₃ =
 cong (λ t → t +ℤ (b *ℤ sum12ℤ w))
  (trans
   (cong (λ t → t +ℤ (a *ℤ (d *ℤ s))) assocAC)
   (cong (λ t → ((a *ℤ c) *ℤ vi) +ℤ t) assocAD))

step₄ : (((a *ℤ c) *ℤ vi) +ℤ ((a *ℤ d) *ℤ s)) +ℤ (b *ℤ sum12ℤ w)
        ≡ (((a *ℤ c) *ℤ vi) +ℤ ((a *ℤ d) *ℤ s)) +ℤ (b *ℤ ((c *ℤ s) +ℤ (d *ℤ twelveTimesℤ s)))
step₄ = cong (λ t → (((a *ℤ c) *ℤ vi) +ℤ ((a *ℤ d) *ℤ s)) +ℤ (b *ℤ t)) sw

step₅ : b *ℤ ((c *ℤ s) +ℤ (d *ℤ twelveTimesℤ s))
        ≡ (b *ℤ (c *ℤ s)) +ℤ (b *ℤ (d *ℤ twelveTimesℤ s))
step₅ = *ℤ-distrib-right-+ℤ b (c *ℤ s) (d *ℤ twelveTimesℤ s)

step₆ : b *ℤ (c *ℤ s) ≡ (b *ℤ c) *ℤ s
step₆ = sym (*ℤ-assoc b c s)

step₇ : b *ℤ (d *ℤ twelveTimesℤ s) ≡ (twelveTimesℤ (b *ℤ d)) *ℤ s
step₇ =
 trans
  (sym (*ℤ-assoc b d (twelveTimesℤ s)))
  (mul-twelveShift (b *ℤ d) s)

step₈ : b *ℤ ((c *ℤ s) +ℤ (d *ℤ twelveTimesℤ s))
        ≡ ((b *ℤ c) *ℤ s) +ℤ ((twelveTimesℤ (b *ℤ d)) *ℤ s)
step₈ =
 trans
  step₅
  (trans
   (cong (λ t → t +ℤ (b *ℤ (d *ℤ twelveTimesℤ s))) step₆)
   (cong (λ t → ((b *ℤ c) *ℤ s) +ℤ t) step₇))

step₉ : (((a *ℤ c) *ℤ vi) +ℤ ((a *ℤ d) *ℤ s)) +ℤ (b *ℤ ((c *ℤ s) +ℤ (d *ℤ twelveTimesℤ s)))
        ≡ (((a *ℤ c) *ℤ vi) +ℤ ((a *ℤ d) *ℤ s)) +ℤ (((b *ℤ c) *ℤ s) +ℤ ((twelveTimesℤ (b *ℤ d)) *ℤ s))
step₉ = cong (λ t → (((a *ℤ c) *ℤ vi) +ℤ ((a *ℤ d) *ℤ s)) +ℤ t) step₈

X = (a *ℤ c) *ℤ vi
Y = (a *ℤ d) *ℤ s
Z = ((b *ℤ c) *ℤ s) +ℤ ((twelveTimesℤ (b *ℤ d)) *ℤ s)

step₁₀ : (X +ℤ Y) +ℤ Z ≡ X +ℤ (Y +ℤ Z)
step₁₀ = +ℤ-assoc X Y Z

twelveTerm = (twelveTimesℤ (b *ℤ d)) *ℤ s
y2 = (b *ℤ c) *ℤ s

fold₁ : Y +ℤ y2 ≡ ((a *ℤ d) +ℤ (b *ℤ c)) *ℤ s
fold₁ = sym (*ℤ-distrib-left-+ℤ (a *ℤ d) (b *ℤ c) s)

fold₂ : (((a *ℤ d) +ℤ (b *ℤ c)) *ℤ s) +ℤ twelveTerm ≡ b' *ℤ s
fold₂ =
 trans
  (sym (*ℤ-distrib-left-+ℤ ((a *ℤ d) +ℤ (b *ℤ c)) (twelveTimesℤ (b *ℤ d)) s))
  refl
```

```
  innerFold : Y +ℤ (y2 +ℤ twelveTerm) ≡ b' *ℤ s
  innerFold =
   trans
    (sym (+ℤ-assoc Y y2 twelveTerm))
    (trans
     (cong (λ t → t +ℤ twelveTerm) fold₁)
     fold₂)
 in
 let
  pA : blk (linIJ a b w) i ≡ (X +ℤ Y) +ℤ (b *ℤ sum12ℤ w)
  pA = trans step₁ (trans step₂ step₃)

  pB : blk (linIJ a b w) i ≡ (X +ℤ Y) +ℤ (b *ℤ ((c *ℤ s) +ℤ (d *ℤ twelveTimesℤ s)))
  pB = trans pA step₄

  pC : blk (linIJ a b w) i ≡ (X +ℤ Y) +ℤ Z
  pC = trans pB (cong (λ t → (X +ℤ Y) +ℤ t) step₈)

  pD : blk (linIJ a b w) i ≡ X +ℤ (Y +ℤ Z)
  pD = trans pC (+ℤ-assoc X Y Z)

  pE : blk (linIJ a b w) i ≡ X +ℤ (b' *ℤ s)
  pE = trans pD (cong (λ t → X +ℤ t) innerFold)
 in
 trans pE (sym rhsForm)

eq0 : (i : Fin4) → block₀ (linIJ a b w) i ≡ block₀ (linIJ (a *ℤ c) b' v) i
eq0 = blkEq block₀ (λ x y u i → block₀-linIJ x y u i)

eq1 : (i : Fin4) → block₁ (linIJ a b w) i ≡ block₁ (linIJ (a *ℤ c) b' v) i
eq1 = blkEq block₁ (λ x y u i → block₁-linIJ x y u i)

eq2 : (i : Fin4) → block₂ (linIJ a b w) i ≡ block₂ (linIJ (a *ℤ c) b' v) i
eq2 = blkEq block₂ (λ x y u i → block₂-linIJ x y u i)
```

Chapter 41

Forced Spectral Action of the (I, J)-Span

The $(\mathbf{I}, \mathbf{J})$-span established in Ch. 40 provides normal-form coefficients for every endomorphism of $\mathrm{Vec}_{12}\mathbb{Z}$ belonging to that span. This chapter forces the *spectral decomposition*: every $(a \cdot \mathbf{I} + b \cdot \mathbf{J})$ is forced to act as scalar multiplication by a on sum-zero vectors and by $a + 12b$ on constant vectors, and these two predicates are forced invariant under every span element. The K_{12} Laplacian is then identified as the concrete span element $(12, -1)$, and the full eigenvalue-exhaustion theorem is established: no eigenvalue other than $\lambda = 12$ or $\lambda = 0$ is possible for a nonzero vector. The normal-form coefficients therefore force the spectral action, the Laplacian identification, and finally the exhaustive eigenvalue elimination.

Forced Predicates on $\mathrm{Vec}_{12}\mathbb{Z}$

The two predicates—sum-zero and constant—that will serve as invariant subspaces for the (I, J)-span are defined as Σ-witnesses, ensuring downstream consumers receive constructive content. Only two subspaces survive the later spectral elimination.

```
-- § Sum-zero and constant predicate witnesses on Vec12ℤ
ZeroSumVec12 : Vec12ℤ → Set
ZeroSumVec12 v = sum12ℤ v ≡ 0ℤ

ConstVec12 : Vec12ℤ → Set
ConstVec12 v = Σ ℤ (λ c → Vec12Eq v (constVec12ℤ c))
```

Congruence of linIJ and interpIJ

Before the spectral laws, we establish that the span representation respects pointwise equality—a precondition for transporting results across different witnesses of the same vector. Congruence eliminates representation drift before any spectral fact is transported.

```
-- § linIJ respects Vec12Eq
linIJ-cong : (a b : ℤ) → (u v : Vec12ℤ) → Vec12Eq u v → Vec12Eq (linIJ a b u) (linIJ a b v)
```

```
linIJ-cong a b u v eq = eq0 , (eq1 , eq2)
 where
  sEq : sum12ℤ u ≡ sum12ℤ v
  sEq = sum12-cong u v eq

  eq0 : (i : Fin4) → block₀ (linIJ a b u) i ≡ block₀ (linIJ a b v) i
  eq0 i =
   let
    pA : a *ℤ block₀ u i ≡ a *ℤ block₀ v i
    pA = cong (λ t → a *ℤ t) (fst eq i)

    pB : b *ℤ sum12ℤ u ≡ b *ℤ sum12ℤ v
    pB = cong (λ t → b *ℤ t) sEq

    step₁ : (a *ℤ block₀ u i) +ℤ (b *ℤ sum12ℤ u) ≡ (a *ℤ block₀ v i) +ℤ (b *ℤ sum12ℤ u)
    step₁ = cong (λ t → t +ℤ (b *ℤ sum12ℤ u)) pA

    step₂ : (a *ℤ block₀ v i) +ℤ (b *ℤ sum12ℤ u) ≡ (a *ℤ block₀ v i) +ℤ (b *ℤ sum12ℤ v)
    step₂ = cong (λ t → (a *ℤ block₀ v i) +ℤ t) pB
   in
   trans
    (block₀-linIJ a b u i)
    (trans (trans step₁ step₂) (sym (block₀-linIJ a b v i)))

  eq1 : (i : Fin4) → block₁ (linIJ a b u) i ≡ block₁ (linIJ a b v) i
  eq1 i =
   let
    pA : a *ℤ block₁ u i ≡ a *ℤ block₁ v i
    pA = cong (λ t → a *ℤ t) (fst (snd eq) i)

    pB : b *ℤ sum12ℤ u ≡ b *ℤ sum12ℤ v
    pB = cong (λ t → b *ℤ t) sEq

    step₁ : (a *ℤ block₁ u i) +ℤ (b *ℤ sum12ℤ u) ≡ (a *ℤ block₁ v i) +ℤ (b *ℤ sum12ℤ u)
    step₁ = cong (λ t → t +ℤ (b *ℤ sum12ℤ u)) pA

    step₂ : (a *ℤ block₁ v i) +ℤ (b *ℤ sum12ℤ u) ≡ (a *ℤ block₁ v i) +ℤ (b *ℤ sum12ℤ v)
    step₂ = cong (λ t → (a *ℤ block₁ v i) +ℤ t) pB
   in
   trans
    (block₁-linIJ a b u i)
    (trans (trans step₁ step₂) (sym (block₁-linIJ a b v i)))

  eq2 : (i : Fin4) → block₂ (linIJ a b u) i ≡ block₂ (linIJ a b v) i
  eq2 i =
   let
    pA : a *ℤ block₂ u i ≡ a *ℤ block₂ v i
    pA = cong (λ t → a *ℤ t) (snd (snd eq) i)

    pB : b *ℤ sum12ℤ u ≡ b *ℤ sum12ℤ v
    pB = cong (λ t → b *ℤ t) sEq

    step₁ : (a *ℤ block₂ u i) +ℤ (b *ℤ sum12ℤ u) ≡ (a *ℤ block₂ v i) +ℤ (b *ℤ sum12ℤ u)
    step₁ = cong (λ t → t +ℤ (b *ℤ sum12ℤ u)) pA

    step₂ : (a *ℤ block₂ v i) +ℤ (b *ℤ sum12ℤ u) ≡ (a *ℤ block₂ v i) +ℤ (b *ℤ sum12ℤ v)
    step₂ = cong (λ t → (a *ℤ block₂ v i) +ℤ t) pB
   in
   trans
    (block₂-linIJ a b u i)
    (trans (trans step₁ step₂) (sym (block₂-linIJ a b v i)))

-- § interpIJ inherits congruence from linIJ
interpIJ-cong : (p : SpanIJ) → (u v : Vec12ℤ) → Vec12Eq u v → Vec12Eq (interpIJ p u) (interpIJ p v)
interpIJ-cong p = linIJ-cong (fst p) (snd p)
```

Forced J-Action

The averaging operator **J** acts definitionally as the sum Σ_{12} broadcast to every coordinate. On sum-zero vectors it annihilates; on constant vectors it multiplies by 12. These two actions are the fixed witnesses from which the later span spectrum is forced.

```
-- § Law 14O.0: sum-zero forces J-annihilation
law14O-0-J-sum0 : (v : Vec12ℤ) → ZeroSumVec12 v → Vec12Eq (J12Vec12ℤ v) zeroVec12ℤ
law14O-0-J-sum0 v sum0 =
 (λ _ → sum0) , ((λ _ → sum0) , (λ _ → sum0))

-- § Law 14O.1: constant vectors force J-scaling by 12
law14O-1-J-const : (c : ℤ) → Vec12Eq (J12Vec12ℤ (constVec12ℤ c)) (constVec12ℤ (twelveTimesℤ c))
law14O-1-J-const c =
 (λ _ → sum12-const c) , ((λ _ → sum12-const c) , (λ _ → sum12-const c))
```

Forced Two-Eigenvalue Classification

Every element $a \cdot \mathbf{I} + b \cdot \mathbf{J}$ of the span is forced to act with eigenvalue a on sum-zero vectors (because the **J**-term collapses) and eigenvalue $a + 12b$ on constant vectors (because the sum of a constant vector is $12c$). No third spectral action survives on the forced invariant subspaces.

```
-- § Law 14O.2: sum-zero forces eigenvalue a for (a·I+b·J)
law14O-2-linIJ-sum0-eigen : (a b : ℤ) → (v : Vec12ℤ) → ZeroSumVec12 v → Vec12Eq (linIJ a b v) (scaleVec12ℤ a v)
law14O-2-linIJ-sum0-eigen a b v sum0 = eq0 , (eq1 , eq2)
 where
  kill : (x : ℤ) → x +ℤ (b *ℤ sum12ℤ v) ≡ x
  kill x =
   let
    p₀ : b *ℤ sum12ℤ v ≡ b *ℤ 0ℤ
    p₀ = cong (λ t → b *ℤ t) sum0

    p₁ : b *ℤ sum12ℤ v ≡ 0ℤ
    p₁ = trans p₀ (*ℤ-zero-right b)

    p₂ : x +ℤ (b *ℤ sum12ℤ v) ≡ x +ℤ 0ℤ
    p₂ = cong (λ t → x +ℤ t) p₁
   in
   trans p₂ (+ℤ-zero-right x)

  eq0 : (i : Fin4) → block₀ (linIJ a b v) i ≡ block₀ (scaleVec12ℤ a v) i
  eq0 i =
   trans
    (block₀-linIJ a b v i)
    (kill (a *ℤ block₀ v i))

  eq1 : (i : Fin4) → block₁ (linIJ a b v) i ≡ block₁ (scaleVec12ℤ a v) i
  eq1 i =
   trans
    (block₁-linIJ a b v i)
    (kill (a *ℤ block₁ v i))

  eq2 : (i : Fin4) → block₂ (linIJ a b v) i ≡ block₂ (scaleVec12ℤ a v) i
  eq2 i =
   trans
    (block₂-linIJ a b v i)
```

```
  (kill (a *ℤ block₂ v i))

– § Law 14O.3: constants force eigenvalue a+12b for (a·I+b·J)
law14O-3-linIJ-const-eigen : (a b c : ℤ) →
 Vec12Eq (linIJ a b (constVec12ℤ c)) (scaleVec12ℤ (a +ℤ twelveTimesℤ b) (constVec12ℤ c))
law14O-3-linIJ-const-eigen a b c = eq0 , (eq1 , eq2)
 where
  coord : (a b c : ℤ) → (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c) ≡ (a +ℤ twelveTimesℤ b) *ℤ c
  coord a b c =
   trans
    (cong (λ t → (a *ℤ c) +ℤ t) (mul-twelveShift b c))
    (sym (*ℤ-distrib-left-+ℤ a (twelveTimesℤ b) c))

  eq0 : (i : Fin4) →
   block₀ (linIJ a b (constVec12ℤ c)) i ≡ block₀ (scaleVec12ℤ (a +ℤ twelveTimesℤ b) (constVec12ℤ c)) i
  eq0 i =
   let
    s0 : sum12ℤ (constVec12ℤ c) ≡ twelveTimesℤ c
    s0 = sum12-const c

    step₀a : (a *ℤ block₀ (constVec12ℤ c) i) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
     ≡ (a *ℤ c) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
    step₀a = refl

    step₀b : (a *ℤ c) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
     ≡ (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c)
    step₀b = cong (λ t → (a *ℤ c) +ℤ (b *ℤ t)) s0

    step₀ : (a *ℤ block₀ (constVec12ℤ c) i) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
     ≡ (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c)
    step₀ = trans step₀a step₀b
   in
   trans
    (block₀-linIJ a b (constVec12ℤ c) i)
    (trans step₀ (coord a b c))

  eq1 : (i : Fin4) →
   block₁ (linIJ a b (constVec12ℤ c)) i ≡ block₁ (scaleVec12ℤ (a +ℤ twelveTimesℤ b) (constVec12ℤ c)) i
  eq1 i =
   let
    s0 : sum12ℤ (constVec12ℤ c) ≡ twelveTimesℤ c
    s0 = sum12-const c

    step₀a : (a *ℤ block₁ (constVec12ℤ c) i) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
     ≡ (a *ℤ c) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
    step₀a = refl

    step₀b : (a *ℤ c) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
     ≡ (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c)
    step₀b = cong (λ t → (a *ℤ c) +ℤ (b *ℤ t)) s0

    step₀ : (a *ℤ block₁ (constVec12ℤ c) i) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
     ≡ (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c)
    step₀ = trans step₀a step₀b
   in
   trans
    (block₁-linIJ a b (constVec12ℤ c) i)
    (trans step₀ (coord a b c))

  eq2 : (i : Fin4) →
   block₂ (linIJ a b (constVec12ℤ c)) i ≡ block₂ (scaleVec12ℤ (a +ℤ twelveTimesℤ b) (constVec12ℤ c)) i
  eq2 i =
```

```
  let
   s0 : sum12ℤ (constVec12ℤ c) ≡ twelveTimesℤ c
   s0 = sum12-const c

   step₀ a : (a *ℤ block₂ (constVec12ℤ c) i) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
    ≡ (a *ℤ c) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
   step₀ a = refl

   step₀ b : (a *ℤ c) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
    ≡ (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c)
   step₀ b = cong (λ t → (a *ℤ c) +ℤ (b *ℤ t)) s0

   step₀ : (a *ℤ block₂ (constVec12ℤ c) i) +ℤ (b *ℤ sum12ℤ (constVec12ℤ c))
    ≡ (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c)
   step₀ = trans step₀ a step₀ b
  in
  trans
   (block₂-linIJ a b (constVec12ℤ c) i)
   (trans step₀ (coord a b c))
```

Forced Predicate Invariance Under the (I, J)-Span

Both the sum-zero and constant predicates are forced to be invariant under every element of the (I, J)-span. The sum-zero invariance follows from the forced closed form of $\Sigma_{12}(\text{linIJ } a\ b\ v)$; the constant invariance follows from sum congruence and the eigenvalue structure of Law 14O.3. This eliminates any gap between algebraic normal form and the spectral predicates.

```
-- § Helper: fourTimes 0 = 0
fourTimesℤ-zero : fourTimesℤ 0ℤ ≡ 0ℤ
fourTimesℤ-zero =
 let
  step₀ : fourTimesℤ 0ℤ ≡ sum4ℤ 0ℤ 0ℤ 0ℤ 0ℤ
  step₀ = refl

  step₁ : sum4ℤ 0ℤ 0ℤ 0ℤ 0ℤ ≡ 0ℤ +ℤ (0ℤ +ℤ (0ℤ +ℤ 0ℤ))
  step₁ = refl

  step₂ : 0ℤ +ℤ (0ℤ +ℤ (0ℤ +ℤ 0ℤ)) ≡ 0ℤ +ℤ (0ℤ +ℤ 0ℤ)
  step₂ = cong (λ t → 0ℤ +ℤ (0ℤ +ℤ t)) (+ℤ-zero-left 0ℤ)

  step₃ : 0ℤ +ℤ (0ℤ +ℤ 0ℤ) ≡ 0ℤ +ℤ 0ℤ
  step₃ = cong (λ t → 0ℤ +ℤ t) (+ℤ-zero-left 0ℤ)
 in
 trans step₀ (trans step₁ (trans step₂ (trans step₃ (+ℤ-zero-left 0ℤ))))

-- § Helper: eightTimes 0 = 0
eightTimesℤ-zero : eightTimesℤ 0ℤ ≡ 0ℤ
eightTimesℤ-zero =
 let
  step₀ : eightTimesℤ 0ℤ ≡ fourTimesℤ 0ℤ +ℤ fourTimesℤ 0ℤ
  step₀ = refl

  step₁ a : fourTimesℤ 0ℤ +ℤ fourTimesℤ 0ℤ ≡ 0ℤ +ℤ fourTimesℤ 0ℤ
  step₁ a = cong (λ t → t +ℤ fourTimesℤ 0ℤ) fourTimesℤ-zero

  step₁ b : 0ℤ +ℤ fourTimesℤ 0ℤ ≡ 0ℤ +ℤ 0ℤ
  step₁ b = cong (λ t → 0ℤ +ℤ t) fourTimesℤ-zero
```

```
 in
 trans step₀ (trans step₁ a (trans step₁ b (+ℤ-zero-left 0ℤ)))

-- § Helper: twelveTimes 0 = 0
twelveTimesℤ-zero : twelveTimesℤ 0ℤ ≡ 0ℤ
twelveTimesℤ-zero =
 let
  step₀ : twelveTimesℤ 0ℤ ≡ fourTimesℤ 0ℤ +ℤ eightTimesℤ 0ℤ
  step₀ = refl

  step₁ a : fourTimesℤ 0ℤ +ℤ eightTimesℤ 0ℤ ≡ 0ℤ +ℤ eightTimesℤ 0ℤ
  step₁ a = cong (λ t → t +ℤ eightTimesℤ 0ℤ) fourTimesℤ-zero

  step₁ b : 0ℤ +ℤ eightTimesℤ 0ℤ ≡ 0ℤ +ℤ 0ℤ
  step₁ b = cong (λ t → 0ℤ +ℤ t) eightTimesℤ-zero
 in
 trans step₀ (trans step₁ a (trans step₁ b (+ℤ-zero-left 0ℤ)))

-- § Law 14O.8: sum-zero is forced invariant under every (a·I+b·J)
law14O-8-linIJ-preserves-sum0 : (a b : ℤ) → (v : Vec12ℤ) → ZeroSumVec12 v → ZeroSumVec12 (linIJ a b v)
law14O-8-linIJ-preserves-sum0 a b v sum0 =
 let
  step₀ : sum12ℤ (linIJ a b v)
   ≡ (a *ℤ sum12ℤ v) +ℤ (b *ℤ twelveTimesℤ (sum12ℤ v))
  step₀ = sum12-linIJ a b v

  a0 : a *ℤ sum12ℤ v ≡ 0ℤ
  a0 = trans (cong (λ t → a *ℤ t) sum0) (*ℤ-zero-right a)

  twelve0 : twelveTimesℤ (sum12ℤ v) ≡ 0ℤ
  twelve0 = trans (cong twelveTimesℤ sum0) twelveTimesℤ-zero

  b0 : b *ℤ twelveTimesℤ (sum12ℤ v) ≡ 0ℤ
  b0 = trans (cong (λ t → b *ℤ t) twelve0) (*ℤ-zero-right b)

  step₁ a : (a *ℤ sum12ℤ v) +ℤ (b *ℤ twelveTimesℤ (sum12ℤ v))
   ≡ 0ℤ +ℤ (b *ℤ twelveTimesℤ (sum12ℤ v))
  step₁ a = cong (λ t → t +ℤ (b *ℤ twelveTimesℤ (sum12ℤ v))) a0

  step₁ b : 0ℤ +ℤ (b *ℤ twelveTimesℤ (sum12ℤ v)) ≡ 0ℤ +ℤ 0ℤ
  step₁ b = cong (λ t → 0ℤ +ℤ t) b0
 in
 trans step₀ (trans step₁ a (trans step₁ b (+ℤ-zero-left 0ℤ)))
```

Constant-vector invariance under the span uses the characterisation of the constant eigenvalue $a + 12b$ from Law 14O.3.

```
-- § Helper: scaling a constant vector yields a constant vector
scaleVec12ℤ-const : (a c : ℤ) → Vec12Eq (scaleVec12ℤ a (constVec12ℤ c)) (constVec12ℤ (a *ℤ c))
scaleVec12ℤ-const a c = (λ _ → refl) , ((λ _ → refl) , (λ _ → refl))

-- § Law 14O.9: constant vectors are forced invariant under every (a·I+b·J)
law14O-9-linIJ-preserves-const : (a b : ℤ) → (v : Vec12ℤ) → ConstVec12 v → ConstVec12 (linIJ a b v)
law14O-9-linIJ-preserves-const a b v (c , vConst) = k , (eq0 , (eq1 , eq2))
 where
  sEq : sum12ℤ v ≡ twelveTimesℤ c
  sEq = trans (sum12-cong v (constVec12ℤ c) vConst) (sum12-const c)

  k : ℤ
  k = (a +ℤ twelveTimesℤ b) *ℤ c
```

```
coord : (a b c : ℤ) → (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c) ≡ (a +ℤ twelveTimesℤ b) *ℤ c
coord a b c =
 trans
  (cong (λ t → (a *ℤ c) +ℤ t) (mul-twelveShift b c))
  (sym (*ℤ-distrib-left-+ℤ a (twelveTimesℤ b) c))

eq0 : (i : Fin4) → block₀ (linIJ a b v) i ≡ block₀ (constVec12ℤ k) i
eq0 i =
 let
  v0 : block₀ v i ≡ c
  v0 = fst vConst i

  a0 : a *ℤ block₀ v i ≡ a *ℤ c
  a0 = cong (λ t → a *ℤ t) v0

  b0 : b *ℤ sum12ℤ v ≡ b *ℤ twelveTimesℤ c
  b0 = cong (λ t → b *ℤ t) sEq

  step₁ : (a *ℤ block₀ v i) +ℤ (b *ℤ sum12ℤ v) ≡ (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c)
  step₁ =
   trans
    (cong (λ t → t +ℤ (b *ℤ sum12ℤ v)) a0)
    (cong (λ t → (a *ℤ c) +ℤ t) b0)
 in
 trans
  (block₀-linIJ a b v i)
  (trans step₁ (trans (coord a b c) refl))

eq1 : (i : Fin4) → block₁ (linIJ a b v) i ≡ block₁ (constVec12ℤ k) i
eq1 i =
 let
  v1 : block₁ v i ≡ c
  v1 = fst (snd vConst) i

  a1 : a *ℤ block₁ v i ≡ a *ℤ c
  a1 = cong (λ t → a *ℤ t) v1

  b1 : b *ℤ sum12ℤ v ≡ b *ℤ twelveTimesℤ c
  b1 = cong (λ t → b *ℤ t) sEq

  step₁ : (a *ℤ block₁ v i) +ℤ (b *ℤ sum12ℤ v) ≡ (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c)
  step₁ =
   trans
    (cong (λ t → t +ℤ (b *ℤ sum12ℤ v)) a1)
    (cong (λ t → (a *ℤ c) +ℤ t) b1)
 in
 trans
  (block₁-linIJ a b v i)
  (trans step₁ (trans (coord a b c) refl))

eq2 : (i : Fin4) → block₂ (linIJ a b v) i ≡ block₂ (constVec12ℤ k) i
eq2 i =
 let
  v2 : block₂ v i ≡ c
  v2 = snd (snd vConst) i

  a2 : a *ℤ block₂ v i ≡ a *ℤ c
  a2 = cong (λ t → a *ℤ t) v2

  b2 : b *ℤ sum12ℤ v ≡ b *ℤ twelveTimesℤ c
  b2 = cong (λ t → b *ℤ t) sEq
```

```
  step₁ : (a *ℤ block₂ v i) +ℤ (b *ℤ sum12ℤ v) ≡ (a *ℤ c) +ℤ (b *ℤ twelveTimesℤ c)
  step₁ =
   trans
    (cong (λ t → t +ℤ (b *ℤ sum12ℤ v)) a2)
    (cong (λ t → (a *ℤ c) +ℤ t) b2)
 in
 trans
  (block₂-linIJ a b v i)
  (trans step₁ (trans (coord a b c) refl))
```

Spectral Package for linIJ

The four forced spectral facts—sum-zero invariance, constant invariance, sum-zero eigenvalue a, constant eigenvalue $a + 12b$—are bundled into a single witness type so that downstream consumers need only one import. Packaging adds no new freedom; it only collects the already-forced facts into a single interface.

```
-- § Law 14O.10: linIJ spectral package (4 components)
LinIJSpectralPackage : (a b : ℤ) → Set
LinIJSpectralPackage a b =
 (v : Vec12ℤ) →
   (ZeroSumVec12 v → ZeroSumVec12 (linIJ a b v)) ×
   (ConstVec12 v → ConstVec12 (linIJ a b v)) ×
   (ZeroSumVec12 v → Vec12Eq (linIJ a b v) (scaleVec12ℤ a v)) ×
   ((c : ℤ) → Vec12Eq (linIJ a b (constVec12ℤ c))
              (scaleVec12ℤ (a +ℤ twelveTimesℤ b) (constVec12ℤ c)))

law14O-10-linIJ-spectral-package : (a b : ℤ) → LinIJSpectralPackage a b
law14O-10-linIJ-spectral-package a b v =
 law14O-8-linIJ-preserves-sum0 a b v ,
 (law14O-9-linIJ-preserves-const a b v ,
  (law14O-2-linIJ-sum0-eigen a b v ,
   law14O-3-linIJ-const-eigen a b))

-- § Projections for LinIJSpectralPackage
LinIJPkg-sum0-inv : {a b : ℤ} → LinIJSpectralPackage a b → (v : Vec12ℤ) → ZeroSumVec12 v → ZeroSumVec12 (linIJ a b v)
LinIJPkg-sum0-inv pkg v = fst (pkg v)

LinIJPkg-const-inv : {a b : ℤ} → LinIJSpectralPackage a b → (v : Vec12ℤ) → ConstVec12 v → ConstVec12 (linIJ a b v)
LinIJPkg-const-inv pkg v = fst (snd (pkg v))

LinIJPkg-sum0-eigen : {a b : ℤ} → LinIJSpectralPackage a b → (v : Vec12ℤ) → ZeroSumVec12 v → Vec12Eq (linIJ a b v) (scaleVec12ℤ a v)
LinIJPkg-sum0-eigen pkg v = fst (snd (snd (pkg v)))

LinIJPkg-const-eigen : {a b : ℤ} → LinIJSpectralPackage a b → (v : Vec12ℤ) → (c : ℤ) →
 Vec12Eq (linIJ a b (constVec12ℤ c)) (scaleVec12ℤ (a +ℤ twelveTimesℤ b) (constVec12ℤ c))
LinIJPkg-const-eigen pkg v = snd (snd (snd (pkg v)))
```

Transport from Normal Form to Spectral Facts

Any operator f that possesses a span witness $f = a \cdot \mathbf{I} + b \cdot \mathbf{J}$ inherits all four spectral facts by composing the pointwise equality with the corresponding forced law for linIJ a b. The transport step eliminates any distinction between an abstract span witness and its normal-form representative.

```
-- § Law 14O.11: any f with witness f=(a·I+b·J) inherits the spectral facts
SpanOpSpectralFacts : (f : Op) → (a b : ℤ) → Set
SpanOpSpectralFacts f a b =
 (v : Vec12ℤ) →
   (ZeroSumVec12 v → ZeroSumVec12 (f v)) ×
   (ConstVec12 v → ConstVec12 (f v)) ×
   (ZeroSumVec12 v → Vec12Eq (f v) (scaleVec12ℤ a v)) ×
   ((c : ℤ) → Vec12Eq (f (constVec12ℤ c))
                (scaleVec12ℤ (a +ℤ twelveTimesℤ b) (constVec12ℤ c)))

law14O-11-spanIJ-transport : (f : Op) → (a b : ℤ) → OpEq f (linIJ a b) → SpanOpSpectralFacts f a b
law14O-11-spanIJ-transport f a b fEq v =
 sum0Inv ,
 (constInv ,
  (sum0Eigen ,
   constEigen))
 where
   sum0Inv : ZeroSumVec12 v → ZeroSumVec12 (f v)
   sum0Inv sum0 =
    trans
     (sum12-cong (f v) (linIJ a b v) (fEq v))
     (law14O-8-linIJ-preserves-sum0 a b v sum0)

   constInv : ConstVec12 v → ConstVec12 (f v)
   constInv (c , vConst) =
    let
     kLin : ConstVec12 (linIJ a b v)
     kLin = law14O-9-linIJ-preserves-const a b v (c , vConst)
    in
    fst kLin , Vec12Eq-trans (fEq v) (snd kLin)

   sum0Eigen : ZeroSumVec12 v → Vec12Eq (f v) (scaleVec12ℤ a v)
   sum0Eigen sum0 =
    Vec12Eq-trans
     (fEq v)
     (law14O-2-linIJ-sum0-eigen a b v sum0)

   constEigen : (c : ℤ) → Vec12Eq (f (constVec12ℤ c))
                            (scaleVec12ℤ (a +ℤ twelveTimesℤ b) (constVec12ℤ c))
   constEigen c =
    Vec12Eq-trans
     (fEq (constVec12ℤ c))
     (law14O-3-linIJ-const-eigen a b c)
```

Span Witness Packages

The coefficient pair (a, b) witnessing $f = a \cdot \mathbf{I} + b \cdot \mathbf{J}$ is forced unique by Law 14N.2. We package it together with the spectral facts so that downstream consumers receive a single, canonical witness. All remaining witness multiplicity at the package level is thereby removed.

```
-- § Law 14O.12: span-IJ coefficient witness is forced unique
SpanIJSpectralPackage : Op → Set
SpanIJSpectralPackage f = Σ SpanIJ (λ p → OpEq f (interpIJ p))

law14O-12-spanIJ-witness-unique : (f : Op) → (w₁ w₂ : SpanIJSpectralPackage f) → fst w₁ ≡ fst w₂
law14O-12-spanIJ-witness-unique f = law14N-2-image-witness-unique f

-- § Law 14O.13: spectral facts are read directly from a span witness
```

```
SpanIJPkg-coeffs : {f : Op} → SpanIJSpectralPackage f → SpanIJ
SpanIJPkg-coeffs pkg = fst pkg

SpanIJPkg-opEq : {f : Op} → (pkg : SpanIJSpectralPackage f) → OpEq f (interpIJ (SpanIJPkg-coeffs pkg))
SpanIJPkg-opEq pkg = snd pkg

SpanIJPkg-a : {f : Op} → SpanIJSpectralPackage f → ℤ
SpanIJPkg-a pkg = fst (SpanIJPkg-coeffs pkg)

SpanIJPkg-b : {f : Op} → SpanIJSpectralPackage f → ℤ
SpanIJPkg-b pkg = snd (SpanIJPkg-coeffs pkg)

SpanIJPkg-spectral : {f : Op} → (pkg : SpanIJSpectralPackage f) → SpanOpSpectralFacts f (SpanIJPkg-a pkg) (SpanIJPkg-b pkg)
SpanIJPkg-spectral {f} pkg =
 law14O-11-spanIJ-transport f (SpanIJPkg-a pkg) (SpanIJPkg-b pkg) (SpanIJPkg-opEq pkg)

law14O-13-spanIJ-package-projections : {f : Op} → (pkg : SpanIJSpectralPackage f) → SpanOpSpectralFacts f (SpanIJPkg-a pkg) (SpanIJPkg-b pkg)
law14O-13-spanIJ-package-projections pkg = SpanIJPkg-spectral pkg

-- § Consumer projections for SpanIJSpectralPackage
SpanIJPkg-sum0-inv : {f : Op} → (pkg : SpanIJSpectralPackage f) → (v : Vec12ℤ) → ZeroSumVec12 v → ZeroSumVec12 (f v)
SpanIJPkg-sum0-inv pkg v = fst (SpanIJPkg-spectral pkg v)

SpanIJPkg-const-inv : {f : Op} → (pkg : SpanIJSpectralPackage f) → (v : Vec12ℤ) → ConstVec12 v → ConstVec12 (f v)
SpanIJPkg-const-inv pkg v = fst (snd (SpanIJPkg-spectral pkg v))

SpanIJPkg-sum0-eigen : {f : Op} → (pkg : SpanIJSpectralPackage f) → (v : Vec12ℤ) → ZeroSumVec12 v → Vec12Eq (f v) (scaleVec12ℤ (SpanIJPkg-a pkg) v
SpanIJPkg-sum0-eigen pkg v = fst (snd (snd (SpanIJPkg-spectral pkg v)))

SpanIJPkg-const-eigen : {f : Op} → (pkg : SpanIJSpectralPackage f) → (c : ℤ) →
 Vec12Eq (f (constVec12ℤ c))
  (scaleVec12ℤ ((SpanIJPkg-a pkg) +ℤ twelveTimesℤ (SpanIJPkg-b pkg)) (constVec12ℤ c))
SpanIJPkg-const-eigen pkg c = snd (snd (snd (SpanIJPkg-spectral pkg (constVec12ℤ c)))) c
```

Unified Span Transport Package

The unified package collects the coefficient pair, the pointwise equality, and both the operator and the linIJ-level spectral facts into a single record. The package is forced because each component is fixed uniquely by the preceding laws.

```
-- § Law 14O.14: unified span transport package
SpanIJUnifiedPackage : Op → Set
SpanIJUnifiedPackage f =
 Σ SpanIJ (λ p →
   OpEq f (interpIJ p) ×
   SpanOpSpectralFacts f (fst p) (snd p) ×
   LinIJSpectralPackage (fst p) (snd p))

law14O-14-spanIJ-unified-package : (f : Op) → SpanIJSpectralPackage f → SpanIJUnifiedPackage f
law14O-14-spanIJ-unified-package f pkg =
 let
   p : SpanIJ
   p = SpanIJPkg-coeffs pkg

   a : ℤ
   a = fst p

   b : ℤ
```

```
    b = snd p

    eq : OpEq f (interpIJ p)
    eq = SpanIJPkg-opEq pkg

    facts : SpanOpSpectralFacts f a b
    facts = law14O-11-spanIJ-transport f a b eq

    linPkg : LinIJSpectralPackage a b
    linPkg = law14O-10-linIJ-spectral-package a b
  in
  p , (eq , (facts , linPkg))

-- § Projections for SpanIJUnifiedPackage
SpanIJUpkg-coeffs : {f : Op} → SpanIJUnifiedPackage f → SpanIJ
SpanIJUpkg-coeffs upkg = fst upkg

SpanIJUpkg-a : {f : Op} → SpanIJUnifiedPackage f → ℤ
SpanIJUpkg-a upkg = fst (SpanIJUpkg-coeffs upkg)

SpanIJUpkg-b : {f : Op} → SpanIJUnifiedPackage f → ℤ
SpanIJUpkg-b upkg = snd (SpanIJUpkg-coeffs upkg)

SpanIJUpkg-opEq : {f : Op} → (upkg : SpanIJUnifiedPackage f) → OpEq f (interpIJ (SpanIJUpkg-coeffs upkg))
SpanIJUpkg-opEq upkg = fst (snd upkg)

SpanIJUpkg-spectral : {f : Op} → (upkg : SpanIJUnifiedPackage f) → SpanOpSpectralFacts f (SpanIJUpkg-a upkg) (SpanIJUpkg-b upkg)
SpanIJUpkg-spectral upkg = fst (snd (snd upkg))

SpanIJUpkg-linIJ : {f : Op} → (upkg : SpanIJUnifiedPackage f) → LinIJSpectralPackage (SpanIJUpkg-a upkg) (SpanIJUpkg-b upkg)
SpanIJUpkg-linIJ upkg = snd (snd (snd upkg))

-- § Law 14O.15: unified span coefficients are forced unique
SpanIJUpkg-witness : {f : Op} → SpanIJUnifiedPackage f → Σ SpanIJ (λ p → OpEq f (interpIJ p))
SpanIJUpkg-witness upkg = SpanIJUpkg-coeffs upkg , SpanIJUpkg-opEq upkg

law14O-15-unified-coeffs-unique : (f : Op) → (u₁ u₂ : SpanIJUnifiedPackage f) → SpanIJUpkg-coeffs u₁ ≡ SpanIJUpkg-coeffs u₂
law14O-15-unified-coeffs-unique f u₁ u₂ =
  law14N-2-image-witness-unique f (SpanIJUpkg-witness u₁) (SpanIJUpkg-witness u₂)
```

Helper Coefficients

The integer $12 \in \mathbb{Z}$ is definitional from twelveTimes$\mathbb{Z}$ one$\mathbb{Z}$; its positivity witness reduces to a constructor equation. The following identities fix the coefficient forms needed to identify the Laplacian inside the (I, J)-span.

```
-- § Forced integer 12
twelveℤ : ℤ
twelveℤ = twelveTimesℤ oneℤ

-- § Forced positivity witness for twelveℤ
twelveℤ-pos : Σ ℕ (λ n → twelveℤ ≡ +suc n)
twelveℤ-pos = (suc (suc (suc (suc (suc (suc (suc (suc (suc (suc (suc zero))))))))))) , refl

-- § 12 on the left collapses to twelveTimes
twelveℤ-*ℤ-left : (x : ℤ) → twelveℤ *ℤ x ≡ twelveTimesℤ x
twelveℤ-*ℤ-left x =
  trans
```

```
  (*ℤ-twelveTimes-left oneℤ x)
  (cong twelveTimesℤ (*ℤ-one-left x))

-- § Multiplication by (−1) collapses to additive negation
negOne-*ℤ-left : (x : ℤ) → (negℤ oneℤ) *ℤ x ≡ negℤ x
negOne-*ℤ-left x =
 let
  neg1 = negℤ oneℤ

  dist : (neg1 +ℤ oneℤ) *ℤ x ≡ (neg1 *ℤ x) +ℤ (oneℤ *ℤ x)
  dist = *ℤ-distrib-left-+ℤ neg1 oneℤ x

  sum0 : (neg1 +ℤ oneℤ) ≡ 0ℤ
  sum0 = +ℤ-inv-left oneℤ

  zeroMul : (neg1 +ℤ oneℤ) *ℤ x ≡ 0ℤ
  zeroMul = trans (cong (λ t → t *ℤ x) sum0) (*ℤ-zero-left x)

  eq0 : (neg1 *ℤ x) +ℤ (oneℤ *ℤ x) ≡ 0ℤ
  eq0 = trans (sym dist) zeroMul

  eq1 : (neg1 *ℤ x) +ℤ x ≡ 0ℤ
  eq1 = trans (sym (cong (λ t → (neg1 *ℤ x) +ℤ t) (*ℤ-one-left x))) eq0

  eq2 : (neg1 *ℤ x) +ℤ x ≡ (negℤ x) +ℤ x
  eq2 = trans eq1 (sym (+ℤ-inv-left x))
 in
 +ℤ-cancel-right (neg1 *ℤ x) (negℤ x) x eq2
```

Laplacian as a Forced (I, J)-Span Element

The K_{12} Laplacian is identified as the concrete span element $(12, -1)$. Pointwise, $L_{12}\, v_i = 12\, v_i - \Sigma_{12}\, v$, which matches linIJ 12 (-1) v once the multiplication lemmas collapse.

```
-- § Law 14O.4: L12 is forced to equal (12·I)+(−1)·J
law14O-4-L-in-span : (v : Vec12ℤ) → Vec12Eq (K12LaplacianVec12ℤ v) (linIJ twelveℤ (negℤ oneℤ) v)
law14O-4-L-in-span v = eq0 , (eq1 , eq2)
 where
  s : ℤ
  s = sum12ℤ v

  neg1 = negℤ oneℤ

  rhs0 : (i : Fin4) →
   block0 (linIJ twelveℤ neg1 v) i ≡ twelveTimesℤ (block0 v i) +ℤ negℤ s
  rhs0 i =
   let
    pA : (twelveℤ *ℤ block0 v i) +ℤ (neg1 *ℤ s) ≡ twelveTimesℤ (block0 v i) +ℤ (neg1 *ℤ s)
    pA = cong (λ t → t +ℤ (neg1 *ℤ s)) (twelveℤ-*ℤ-left (block0 v i))

    pB : twelveTimesℤ (block0 v i) +ℤ (neg1 *ℤ s) ≡ twelveTimesℤ (block0 v i) +ℤ negℤ s
    pB = cong (λ t → twelveTimesℤ (block0 v i) +ℤ t) (negOne-*ℤ-left s)
   in
   trans
    (block0-linIJ twelveℤ neg1 v i)
    (trans pA pB)

  rhs1 : (i : Fin4) →
   block1 (linIJ twelveℤ neg1 v) i ≡ twelveTimesℤ (block1 v i) +ℤ negℤ s
```

```
rhs1 i =
 let
  pA : (twelveℤ *ℤ block₁ v i) +ℤ (neg1 *ℤ s) ≡ twelveTimesℤ (block₁ v i) +ℤ (neg1 *ℤ s)
  pA = cong (λ t → t +ℤ (neg1 *ℤ s)) (twelveℤ-*ℤ-left (block₁ v i))

  pB : twelveTimesℤ (block₁ v i) +ℤ (neg1 *ℤ s) ≡ twelveTimesℤ (block₁ v i) +ℤ negℤ s
  pB = cong (λ t → twelveTimesℤ (block₁ v i) +ℤ t) (negOne-*ℤ-left s)
 in
 trans
  (block₁-linIJ twelveℤ neg1 v i)
  (trans pA pB)

rhs2 : (i : Fin4) →
 block₂ (linIJ twelveℤ neg1 v) i ≡ twelveTimesℤ (block₂ v i) +ℤ negℤ s
rhs2 i =
 let
  pA : (twelveℤ *ℤ block₂ v i) +ℤ (neg1 *ℤ s) ≡ twelveTimesℤ (block₂ v i) +ℤ (neg1 *ℤ s)
  pA = cong (λ t → t +ℤ (neg1 *ℤ s)) (twelveℤ-*ℤ-left (block₂ v i))

  pB : twelveTimesℤ (block₂ v i) +ℤ (neg1 *ℤ s) ≡ twelveTimesℤ (block₂ v i) +ℤ negℤ s
  pB = cong (λ t → twelveTimesℤ (block₂ v i) +ℤ t) (negOne-*ℤ-left s)
 in
 trans
  (block₂-linIJ twelveℤ neg1 v i)
  (trans pA pB)

eq0 : (i : Fin4) → block₀ (K12LaplacianVec12ℤ v) i ≡ block₀ (linIJ twelveℤ neg1 v) i
eq0 i = trans (fst (law14H-6-L-twelve-minus-J v) i) (sym (rhs0 i))

eq1 : (i : Fin4) → block₁ (K12LaplacianVec12ℤ v) i ≡ block₁ (linIJ twelveℤ neg1 v) i
eq1 i = trans (fst (snd (law14H-6-L-twelve-minus-J v)) i) (sym (rhs1 i))

eq2 : (i : Fin4) → block₂ (K12LaplacianVec12ℤ v) i ≡ block₂ (linIJ twelveℤ neg1 v) i
eq2 i = trans (snd (snd (law14H-6-L-twelve-minus-J v)) i) (sym (rhs2 i))
```

Laplacian Composition Closure

The Laplacian, identified as the span element $(12, -1)$, is closed under composition with every other span element via the composition law 14N.3. Composition closure eliminates any residual doubt that the concrete Laplacian lies outside the forced span calculus.

```
-- § Law 14O.16: L₁₂ has forced span witness (12,−1)
LSpanIJ : SpanIJ
LSpanIJ = twelveℤ , (negℤ oneℤ)

law14O-16-L-span-witness : SpanIJSpectralPackage K12LaplacianVec12ℤ
law14O-16-L-span-witness = LSpanIJ , (λ v → law14O-4-L-in-span v)

-- § Law 14O.17: left composition by L₁₂ preserves span membership
law14O-17-L-compose-left-span : (f : Op) → SpanIJSpectralPackage f → SpanIJSpectralPackage (λ v → K12LaplacianVec12ℤ (f v))
law14O-17-L-compose-left-span f pkg = p' , eq'
 where
  p : SpanIJ
  p = SpanIJPkg-coeffs pkg

  p' : SpanIJ
  p' = mulSpanIJ LSpanIJ p
```

```
  fEq : OpEq f (interpIJ p)
  fEq = SpanIJPkg-opEq pkg

  eq' : OpEq (λ v → K12LaplacianVec12ℤ (f v)) (interpIJ p')
  eq' v =
   let
    step₁ : Vec12Eq (K12LaplacianVec12ℤ (f v)) (K12LaplacianVec12ℤ (interpIJ p v))
    step₁ = K12Laplacian-cong (f v) (interpIJ p v) (fEq v)

    step₂ : Vec12Eq (K12LaplacianVec12ℤ (interpIJ p v)) (interpIJ LSpanIJ (interpIJ p v))
    step₂ = law14O-4-L-in-span (interpIJ p v)

    step₃ : Vec12Eq (interpIJ LSpanIJ (interpIJ p v)) (interpIJ p' v)
    step₃ = law14N-3-IJ-compose-closed LSpanIJ p v
   in
   Vec12Eq-trans step₁ (Vec12Eq-trans step₂ step₃)

-- § Law 14O.18: right composition by L₁₂ preserves span membership
law14O-18-L-compose-right-span : (f : Op) → SpanIJSpectralPackage f → SpanIJSpectralPackage (λ v → f (K12LaplacianVec12ℤ v))
law14O-18-L-compose-right-span f pkg = p' , eq'
 where
  p : SpanIJ
  p = SpanIJPkg-coeffs pkg

  p' : SpanIJ
  p' = mulSpanIJ p LSpanIJ

  fEq : OpEq f (interpIJ p)
  fEq = SpanIJPkg-opEq pkg

  eq' : OpEq (λ v → f (K12LaplacianVec12ℤ v)) (interpIJ p')
  eq' v =
   let
    step₁ : Vec12Eq (f (K12LaplacianVec12ℤ v)) (interpIJ p (K12LaplacianVec12ℤ v))
    step₁ = fEq (K12LaplacianVec12ℤ v)

    step₂ : Vec12Eq (interpIJ p (K12LaplacianVec12ℤ v)) (interpIJ p (interpIJ LSpanIJ v))
    step₂ = interpIJ-cong p (K12LaplacianVec12ℤ v) (interpIJ LSpanIJ v) (law14O-4-L-in-span v)

    step₃ : Vec12Eq (interpIJ p (interpIJ LSpanIJ v)) (interpIJ p' v)
    step₃ = law14N-3-IJ-compose-closed p LSpanIJ v
   in
   Vec12Eq-trans step₁ (Vec12Eq-trans step₂ step₃)

-- § Law 14O.19: left composition by L₁₂ preserves unified packages
SpanIJUpkg-to-span : {f : Op} → SpanIJUnifiedPackage f → SpanIJSpectralPackage f
SpanIJUpkg-to-span upkg = SpanIJUpkg-coeffs upkg , SpanIJUpkg-opEq upkg

law14O-19-L-compose-left-unified : (f : Op) → SpanIJUnifiedPackage f → SpanIJUnifiedPackage (λ v → K12LaplacianVec12ℤ (f v))
law14O-19-L-compose-left-unified f upkg =
 law14O-14-spanIJ-unified-package
  (λ v → K12LaplacianVec12ℤ (f v))
  (law14O-17-L-compose-left-span f (SpanIJUpkg-to-span upkg))

-- § Law 14O.20: right composition by L₁₂ preserves unified packages
law14O-20-L-compose-right-unified : (f : Op) → SpanIJUnifiedPackage f → SpanIJUnifiedPackage (λ v → f (K12LaplacianVec12ℤ v))
law14O-20-L-compose-right-unified f upkg =
 law14O-14-spanIJ-unified-package
  (λ v → f (K12LaplacianVec12ℤ v))
  (law14O-18-L-compose-right-span f (SpanIJUpkg-to-span upkg))
```

Forced Laplacian Eigenvalues

The two Laplacian eigenvalues are direct consequences of the span identification $(12, -1)$: sum-zero forces eigenvalue 12, constants force eigenvalue 0. These are the only two spectral actions that survive on the forced invariant subspaces.

```
-- § Law 14O.5: sum-zero forces Laplacian eigenvalue 12
law14O-5-L-sum0-eigen12 : (v : Vec12ℤ) → ZeroSumVec12 v → Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ twelveℤ v)
law14O-5-L-sum0-eigen12 v sum0 =
 Vec12Eq-trans
  (law14O-4-L-in-span v)
  (law14O-2-linIJ-sum0-eigen twelveℤ (negℤ oneℤ) v sum0)

-- § Law 14O.6: constant vectors force Laplacian eigenvalue 0
law14O-6-L-const-eigen0 : (c : ℤ) → Vec12Eq (K12LaplacianVec12ℤ (constVec12ℤ c)) zeroVec12ℤ
law14O-6-L-const-eigen0 = law14H-14-const-eigen0
```

Laplacian Spectral Package

The complete Laplacian spectral package bundles all forced spectral behaviour into a single witness: span membership, drift (sum of image is zero), JL-annihilation, sum-zero eigenvector characterisation, image containment, and constant kernel. The package adds no new structure; it only collects the already-forced Laplacian facts.

```
-- § Law 14O.7: L12 spectral package (7 components)
L12ConstKernel : Set
L12ConstKernel = (x : ℤ) → Vec12Eq (K12LaplacianVec12ℤ (constVec12ℤ x)) zeroVec12ℤ

L12SpectralPackage : Vec12ℤ → Set
L12SpectralPackage v =
 (Vec12Eq (K12LaplacianVec12ℤ v) (linIJ twelveℤ (negℤ oneℤ) v)) ×
 (sum12ℤ (K12LaplacianVec12ℤ v) ≡ 0ℤ) ×
 (Vec12Eq (J12Vec12ℤ (K12LaplacianVec12ℤ v)) zeroVec12ℤ) ×
 ((sum12ℤ v ≡ 0ℤ → Vec12Eq (K12LaplacianVec12ℤ v) (twelveVec12ℤ v)) ×
  (Vec12Eq (K12LaplacianVec12ℤ v) (twelveVec12ℤ v) → sum12ℤ v ≡ 0ℤ)) ×
 (Vec12Eq (K12LaplacianVec12ℤ (K12LaplacianVec12ℤ v))
  (twelveVec12ℤ (K12LaplacianVec12ℤ v))) ×
 L12ConstKernel

law14O-7-L-spectral-package : (v : Vec12ℤ) → L12SpectralPackage v
law14O-7-L-spectral-package v =
 law14O-4-L-in-span v ,
 (law14H-8-sumL12-0 v ,
  (law14H-9-JL-zero v ,
   ((law14H-12-sum0-eigen12 v , law14H-13-eigen12→sum0 v) ,
    (law14H-16-image⊆eigen12 v ,
     law14O-6-L-const-eigen0))))

-- § Projections for L12SpectralPackage
L12Pkg-span : {v : Vec12ℤ} → L12SpectralPackage v → Vec12Eq (K12LaplacianVec12ℤ v) (linIJ twelveℤ (negℤ oneℤ) v)
L12Pkg-span pkg = fst pkg

L12Pkg-sumL0 : {v : Vec12ℤ} → L12SpectralPackage v → sum12ℤ (K12LaplacianVec12ℤ v) ≡ 0ℤ
L12Pkg-sumL0 pkg = fst (snd pkg)
```

```
L12Pkg-JL0 : {v : Vec12ℤ} → L12SpectralPackage v → Vec12Eq (J12Vec12ℤ (K12LaplacianVec12ℤ v)) zeroVec12ℤ
L12Pkg-JL0 pkg = fst (snd (snd pkg))

L12Pkg-sum0→eigen12 : {v : Vec12ℤ} → L12SpectralPackage v → sum12ℤ v ≡ 0ℤ → Vec12Eq (K12LaplacianVec12ℤ v) (twelveVec12ℤ v)
L12Pkg-sum0→eigen12 pkg = fst (fst (snd (snd (snd pkg))))

L12Pkg-eigen12→sum0 : {v : Vec12ℤ} → L12SpectralPackage v → Vec12Eq (K12LaplacianVec12ℤ v) (twelveVec12ℤ v) → sum12ℤ v ≡ 0ℤ
L12Pkg-eigen12→sum0 pkg = snd (fst (snd (snd (snd pkg))))

L12Pkg-image⊆eigen12 : {v : Vec12ℤ} → L12SpectralPackage v →
 Vec12Eq (K12LaplacianVec12ℤ (K12LaplacianVec12ℤ v)) (twelveVec12ℤ (K12LaplacianVec12ℤ v))
L12Pkg-image⊆eigen12 pkg = fst (snd (snd (snd (snd pkg))))

L12Pkg-constKer : {v : Vec12ℤ} → L12SpectralPackage v → L12ConstKernel
L12Pkg-constKer pkg = snd (snd (snd (snd (snd pkg))))
```

Eigen-Constraint Refinements

The "reverse direction" facts from the Triple K_4 and K_{12} spectral chapter are re-stated in the scaleVec12ℤ language of the (I, J)-span. This section removes the remaining mismatch between old operator notation and the forced span normal form.

```
-- § Law 14O.21: scale-by-12 agrees with twelveVec12ℤ
law14O-21-scale12≡twelveVec12 : (v : Vec12ℤ) → Vec12Eq (scaleVec12ℤ twelveℤ v) (twelveVec12ℤ v)
law14O-21-scale12≡twelveVec12 v =
 (λ i → twelveℤ-*ℤ-left (block₀ v i)) ,
 ((λ i → twelveℤ-*ℤ-left (block₁ v i)) ,
  (λ i → twelveℤ-*ℤ-left (block₂ v i)))

-- § Law 14O.22: scale-by-0 collapses to zeroVec12ℤ
law14O-22-scale0≡zeroVec12 : (v : Vec12ℤ) → Vec12Eq (scaleVec12ℤ 0ℤ v) zeroVec12ℤ
law14O-22-scale0≡zeroVec12 v =
 (λ i → *ℤ-zero-left (block₀ v i)) ,
 ((λ i → *ℤ-zero-left (block₁ v i)) ,
  (λ i → *ℤ-zero-left (block₂ v i)))

-- § Law 14O.23: scale-form 12-eigenvectors force sum-zero
law14O-23-eigen12Scale→sum0 : (v : Vec12ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ twelveℤ v) → ZeroSumVec12 v
law14O-23-eigen12Scale→sum0 v eigen12Scale =
 let
  pkg : L12SpectralPackage v
  pkg = law14O-7-L-spectral-package v

  eigen12 : Vec12Eq (K12LaplacianVec12ℤ v) (twelveVec12ℤ v)
  eigen12 = Vec12Eq-trans eigen12Scale (law14O-21-scale12≡twelveVec12 v)
 in
 L12Pkg-eigen12→sum0 {v = v} pkg eigen12

-- § Law 14O.24: scale-form 0-eigenvectors force 12·v = J v
law14O-24-eigen0Scale→twelveEqJ : (v : Vec12ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ 0ℤ v) → Vec12Eq (twelveVec12ℤ v) (J12Vec12ℤ v)
law14O-24-eigen0Scale→twelveEqJ v eigen0Scale =
 let
  L0 : Vec12Eq (K12LaplacianVec12ℤ v) zeroVec12ℤ
  L0 = Vec12Eq-trans eigen0Scale (law14O-22-scale0≡zeroVec12 v)
 in
 law14H-15-L0→twelveEqJ v L0
```

```
-- § Law 14O.25: eigen-equation forces constraints for λ=12 or λ=0
law14O-25-eigen-constraints : (v : Vec12ℤ) → (lam : ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ lam v) →
 ((lam ≡ twelveℤ) → ZeroSumVec12 v) ×
 ((lam ≡ 0ℤ) → Vec12Eq (twelveVec12ℤ v) (J12Vec12ℤ v))
law14O-25-eigen-constraints v lam eigen = sumPart , kernelPart
 where
  P : ℤ → Set
  P t = Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ t v)

  sumPart : (lam ≡ twelveℤ) → ZeroSumVec12 v
  sumPart eqλ = law14O-23-eigen12Scale→sum0 v (subst P eqλ eigen)

  kernelPart : (lam ≡ 0ℤ) → Vec12Eq (twelveVec12ℤ v) (J12Vec12ℤ v)
  kernelPart eqλ = law14O-24-eigen0Scale→twelveEqJ v (subst P eqλ eigen)

-- § Law 14O.26: J-images are forced constant
law14O-26-J-constVec : (v : Vec12ℤ) → ConstVec12 (J12Vec12ℤ v)
law14O-26-J-constVec v = (sum12ℤ v) , ((λ _ → refl) , ((λ _ → refl) , (λ _ → refl)))

-- § Law 14O.27: kernel constraint forces 12·v to be constant
law14O-27-twelveEqJ→twelveConst : (v : Vec12ℤ) →
 Vec12Eq (twelveVec12ℤ v) (J12Vec12ℤ v) → ConstVec12 (twelveVec12ℤ v)
law14O-27-twelveEqJ→twelveConst v twelveEqJ =
 let
  c : ℤ
  c = sum12ℤ v

  Jconst : Vec12Eq (J12Vec12ℤ v) (constVec12ℤ c)
  Jconst = snd (law14O-26-J-constVec v)
 in
 c , (Vec12Eq-trans twelveEqJ Jconst)

-- § Law 14O.28: scale-form 0-eigenvectors force 12·v constant
law14O-28-eigen0Scale→twelveConst : (v : Vec12ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ 0ℤ v) → ConstVec12 (twelveVec12ℤ v)
law14O-28-eigen0Scale→twelveConst v eigen0Scale =
 law14O-27-twelveEqJ→twelveConst v (law14O-24-eigen0Scale→twelveEqJ v eigen0Scale)

-- § Law 14O.29: eigen-equation forces sum-zero (λ=12) and 12·v constant (λ=0)
law14O-29-eigen-constraints-strong : (v : Vec12ℤ) → (lam : ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ lam v) →
 ((lam ≡ twelveℤ) → ZeroSumVec12 v) ×
 ((lam ≡ 0ℤ) → ConstVec12 (twelveVec12ℤ v))
law14O-29-eigen-constraints-strong v lam eigen = sumPart , twelveConstPart
 where
  P : ℤ → Set
  P t = Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ t v)

  sumPart : (lam ≡ twelveℤ) → ZeroSumVec12 v
  sumPart eqλ = law14O-23-eigen12Scale→sum0 v (subst P eqλ eigen)

  twelveConstPart : (lam ≡ 0ℤ) → ConstVec12 (twelveVec12ℤ v)
  twelveConstPart eqλ = law14O-28-eigen0Scale→twelveConst v (subst P eqλ eigen)
```

Torsion-Free Kernel Upgrade

The kernel constraint $12 \cdot v = \mathbf{J}\, v$ forces all coordinates to share the same 12-multiple. Once the positivity witness $12 = +\mathrm{suc}\ 11$ is supplied, torsion-freeness eliminates all remaining coordinate freedom and forces v itself to be constant. This is the step that collapses the kernel witness from scaled constancy to actual constancy.

```
-- § Law 14O.30: 0-eigenvectors are forced constant (with positivity witness)
law14O-30-eigen0Scale→const-assuming-twelvePos : (v : Vec12ℤ) →
 Σ ℕ (λ n → twelveℤ ≡ +suc n) →
 Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ 0ℤ v) →
 ConstVec12 v
law14O-30-eigen0Scale→const-assuming-twelvePos v (n , twelvePos) eigen0Scale =
 c , (eq0 , (eq1 , eq2))
 where
  c : ℤ
  c = block₀ v g0

  twelveEqJ : Vec12Eq (twelveVec12ℤ v) (J12Vec12ℤ v)
  twelveEqJ = law14O-24-eigen0Scale→twelveEqJ v eigen0Scale

  -- Convert a coordinate equation 12·x = Σ into twelveℤ*x = Σ
  toMul12 : (x s : ℤ) → twelveTimesℤ x ≡ s → twelveℤ *ℤ x ≡ s
  toMul12 x s eq = trans (twelveℤ-*ℤ-left x) eq

  -- From twelveℤ*x = twelveℤ*y, force x = y via torsion-freeness
  cancel12 : (x y : ℤ) → twelveℤ *ℤ x ≡ twelveℤ *ℤ y → x ≡ y
  cancel12 x y mulEq =
   let
    Q : ℤ → Set
    Q t = t *ℤ x ≡ t *ℤ y
    mulEq' : (+suc n) *ℤ x ≡ (+suc n) *ℤ y
    mulEq' = subst Q twelvePos mulEq

    diff : ℤ
    diff = x +ℤ negℤ y

    step₀ : (+suc n) *ℤ diff +ℤ ((+suc n) *ℤ y) ≡ ((+suc n) *ℤ y)
    step₀ =
     trans
      (cong (λ t → t +ℤ ((+suc n) *ℤ y)) (*ℤ-distrib-right-+ℤ (+suc n) x (negℤ y)))
      (trans
       (+ℤ-assoc ((+suc n) *ℤ x) ((+suc n) *ℤ (negℤ y)) ((+suc n) *ℤ y))
       (trans
        (cong (λ t → ((+suc n) *ℤ x) +ℤ t)
              (trans
               (sym (*ℤ-distrib-right-+ℤ (+suc n) (negℤ y) y))
               (trans
                (cong (λ t → (+suc n) *ℤ t) (+ℤ-inv-left y))
                (*ℤ-zero-right (+suc n)))))
        (trans
         (cong (λ t → t +ℤ 0ℤ) mulEq')
         (+ℤ-zero-right ((+suc n) *ℤ y)))))

    step₁ : ((+suc n) *ℤ y) +ℤ ((+suc n) *ℤ diff) ≡ ((+suc n) *ℤ y)
    step₁ =
     trans
      (sym (+ℤ-comm ((+suc n) *ℤ diff) ((+suc n) *ℤ y)))
      step₀

    mulDiff0 : (+suc n) *ℤ diff ≡ 0ℤ
    mulDiff0 = +ℤ-cancel-left ((+suc n) *ℤ y) ((+suc n) *ℤ diff) step₁

    diff0 : diff ≡ 0ℤ
    diff0 = *ℤ-pos-left-zero→zero n diff mulDiff0

    xy : x ≡ y
    xy =
     let
```

```
    addY : (x +ℤ negℤ y) +ℤ y ≡ 0ℤ +ℤ y
    addY = cong (λ t → t +ℤ y) diff0

    stepA : (x +ℤ negℤ y) +ℤ y ≡ x
    stepA =
     trans
      (+ℤ-assoc x (negℤ y) y)
      (trans
       (cong (λ t → x +ℤ t) (+ℤ-inv-left y))
       (+ℤ-zero-right x))

    stepB : (x +ℤ negℤ y) +ℤ y ≡ y
    stepB = trans addY (+ℤ-zero-left y)
   in
   trans (sym stepA) stepB
  in
  xy

sumVal : ℤ
sumVal = sum12ℤ v

eq0 : (i : Fin4) → block₀ v i ≡ c
eq0 i =
 let
  sx : twelveTimesℤ (block₀ v i) ≡ sumVal
  sx = fst twelveEqJ i

  sc : twelveTimesℤ c ≡ sumVal
  sc = fst twelveEqJ g0

  mulEq : twelveℤ *ℤ (block₀ v i) ≡ twelveℤ *ℤ c
  mulEq = trans (toMul12 (block₀ v i) sumVal sx) (sym (toMul12 c sumVal sc))
 in
 cancel12 (block₀ v i) c mulEq

eq1 : (i : Fin4) → block₁ v i ≡ c
eq1 i =
 let
  sx : twelveTimesℤ (block₁ v i) ≡ sumVal
  sx = fst (snd twelveEqJ) i

  sc : twelveTimesℤ c ≡ sumVal
  sc = fst twelveEqJ g0

  mulEq : twelveℤ *ℤ (block₁ v i) ≡ twelveℤ *ℤ c
  mulEq = trans (toMul12 (block₁ v i) sumVal sx) (sym (toMul12 c sumVal sc))
 in
 cancel12 (block₁ v i) c mulEq

eq2 : (i : Fin4) → block₂ v i ≡ c
eq2 i =
 let
  sx : twelveTimesℤ (block₂ v i) ≡ sumVal
  sx = snd (snd twelveEqJ) i

  sc : twelveTimesℤ c ≡ sumVal
  sc = fst twelveEqJ g0

  mulEq : twelveℤ *ℤ (block₂ v i) ≡ twelveℤ *ℤ c
  mulEq = trans (toMul12 (block₂ v i) sumVal sx) (sym (toMul12 c sumVal sc))
 in
 cancel12 (block₂ v i) c mulEq
```

Step 2: Eigenvalue Classification Without Positivity Witness. The positivity witness is discharged by direct construction, yielding the stand-alone classification: any eigenvector for eigenvalue 0 is necessarily constant.

```
-- § Law 14O.31: 0-eigenvectors are forced constant (no extra witness)
law14O-31-eigen0Scale→const : (v : Vec12ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ 0ℤ v) →
 ConstVec12 v
law14O-31-eigen0Scale→const v eigen0Scale =
 law14O-30-eigen0Scale→const-assuming-twelvePos v twelveℤ-pos eigen0Scale

-- § Law 14O.32: eigen-equation forces sum-zero (λ=12) and const (λ=0)
law14O-32-eigen-constraints-final : (v : Vec12ℤ) → (lam : ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ lam v) →
 ((lam ≡ twelveℤ) → ZeroSumVec12 v) ×
 ((lam ≡ 0ℤ) → ConstVec12 v)
law14O-32-eigen-constraints-final v lam eigen = sumPart , constPart
 where
  P : ℤ → Set
  P t = Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ t v)

  sumPart : (lam ≡ twelveℤ) → ZeroSumVec12 v
  sumPart eqλ = law14O-23-eigen12Scale→sum0 v (subst P eqλ eigen)

  constPart : (lam ≡ 0ℤ) → ConstVec12 v
  constPart eqλ = law14O-31-eigen0Scale→const v (subst P eqλ eigen)
```

Eigenvalue Exhaustion

The earlier laws force the constraints for $\lambda = 12$ and $\lambda = 0$; here we force that any eigen-equation can only occur with $\lambda = 12$, $\lambda = 0$, or with the zero vector. The key ingredient is the Laplacian's commutativity with scaling and torsion-freeness over $\mathbb{Z}$. Every further eigenvalue candidate is eliminated as incoherent.

```
-- § scaleVec12 congruence and associativity
scaleVec12-cong : (a : ℤ) → {u v : Vec12ℤ} → Vec12Eq u v → Vec12Eq (scaleVec12ℤ a u) (scaleVec12ℤ a v)
scaleVec12-cong a eq =
 (λ i → cong (λ t → a *ℤ t) (fst eq i)) ,
 ((λ i → cong (λ t → a *ℤ t) (fst (snd eq) i)) ,
  (λ i → cong (λ t → a *ℤ t) (snd (snd eq) i)))

scaleVec12-assoc : (a b : ℤ) → (v : Vec12ℤ) → Vec12Eq (scaleVec12ℤ a (scaleVec12ℤ b v)) (scaleVec12ℤ (a *ℤ b) v)
scaleVec12-assoc a b v =
 (λ i → sym (*ℤ-assoc a b (block₀ v i))) ,
 ((λ i → sym (*ℤ-assoc a b (block₁ v i))) ,
  (λ i → sym (*ℤ-assoc a b (block₂ v i)))
 )

-- § Law 14O.33: Laplacian commutes with scaleVec12ℤ
law14O-33-L-scale : (lam : ℤ) → (v : Vec12ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ (scaleVec12ℤ lam v)) (scaleVec12ℤ lam (K12LaplacianVec12ℤ v))
law14O-33-L-scale lam v = eq0 , (eq1 , eq2)
 where
  s : ℤ
  s = sum12ℤ v
```

```
sScale : sum12ℤ (scaleVec12ℤ lam v) ≡ lam *ℤ s
sScale = sum12-scaleVec12ℤ lam v

sNegScale : negℤ (sum12ℤ (scaleVec12ℤ lam v)) ≡ negℤ (lam *ℤ s)
sNegScale = cong negℤ sScale

rhsBlock : (x : ℤ) →
 lam *ℤ (twelveTimesℤ x +ℤ negℤ s) ≡ twelveTimesℤ (lam *ℤ x) +ℤ negℤ (lam *ℤ s)
rhsBlock x =
 trans
  (*ℤ-distrib-right-+ℤ lam (twelveTimesℤ x) (negℤ s))
  (trans
   (cong (λ t → t +ℤ (lam *ℤ negℤ s)) (*ℤ-twelveTimes-right lam x))
   (cong (λ t → twelveTimesℤ (lam *ℤ x) +ℤ t) (*ℤ-neg-right lam s)))

eq0 : (i : Fin4) → block₀ (K12LaplacianVec12ℤ (scaleVec12ℤ lam v)) i ≡ block₀ (scaleVec12ℤ lam (K12LaplacianVec12ℤ v)) i
eq0 i =
 let
  lhsBridge : block₀ (K12LaplacianVec12ℤ (scaleVec12ℤ lam v)) i ≡
              twelveTimesℤ (block₀ (scaleVec12ℤ lam v) i) +ℤ negℤ (sum12ℤ (scaleVec12ℤ lam v))
  lhsBridge = fst (law14H-6-L-twelve-minus-J (scaleVec12ℤ lam v)) i

  step₁ :
   twelveTimesℤ (lam *ℤ block₀ v i) +ℤ negℤ (sum12ℤ (scaleVec12ℤ lam v))
    ≡
   twelveTimesℤ (lam *ℤ block₀ v i) +ℤ negℤ (lam *ℤ s)
  step₁ = cong (λ t → twelveTimesℤ (lam *ℤ block₀ v i) +ℤ t) sNegScale

  rhsBridge : block₀ (scaleVec12ℤ lam (K12LaplacianVec12ℤ v)) i ≡
              lam *ℤ (twelveTimesℤ (block₀ v i) +ℤ negℤ s)
  rhsBridge = cong (λ z → lam *ℤ z) (fst (law14H-6-L-twelve-minus-J v) i)
 in
 trans lhsBridge (trans step₁ (trans (sym (rhsBlock (block₀ v i))) (sym rhsBridge)))

eq1 : (i : Fin4) → block₁ (K12LaplacianVec12ℤ (scaleVec12ℤ lam v)) i ≡ block₁ (scaleVec12ℤ lam (K12LaplacianVec12ℤ v)) i
eq1 i =
 let
  lhsBridge : block₁ (K12LaplacianVec12ℤ (scaleVec12ℤ lam v)) i ≡
              twelveTimesℤ (block₁ (scaleVec12ℤ lam v) i) +ℤ negℤ (sum12ℤ (scaleVec12ℤ lam v))
  lhsBridge = fst (snd (law14H-6-L-twelve-minus-J (scaleVec12ℤ lam v))) i

  step₁ :
   twelveTimesℤ (lam *ℤ block₁ v i) +ℤ negℤ (sum12ℤ (scaleVec12ℤ lam v))
    ≡
   twelveTimesℤ (lam *ℤ block₁ v i) +ℤ negℤ (lam *ℤ s)
  step₁ = cong (λ t → twelveTimesℤ (lam *ℤ block₁ v i) +ℤ t) sNegScale

  rhsBridge : block₁ (scaleVec12ℤ lam (K12LaplacianVec12ℤ v)) i ≡
              lam *ℤ (twelveTimesℤ (block₁ v i) +ℤ negℤ s)
  rhsBridge = cong (λ z → lam *ℤ z) (fst (snd (law14H-6-L-twelve-minus-J v)) i)
 in
 trans lhsBridge (trans step₁ (trans (sym (rhsBlock (block₁ v i))) (sym rhsBridge)))

eq2 : (i : Fin4) → block₂ (K12LaplacianVec12ℤ (scaleVec12ℤ lam v)) i ≡ block₂ (scaleVec12ℤ lam (K12LaplacianVec12ℤ v)) i
eq2 i =
 let
  lhsBridge : block₂ (K12LaplacianVec12ℤ (scaleVec12ℤ lam v)) i ≡
              twelveTimesℤ (block₂ (scaleVec12ℤ lam v) i) +ℤ negℤ (sum12ℤ (scaleVec12ℤ lam v))
  lhsBridge = snd (snd (law14H-6-L-twelve-minus-J (scaleVec12ℤ lam v))) i

  step₁ :
   twelveTimesℤ (lam *ℤ block₂ v i) +ℤ negℤ (sum12ℤ (scaleVec12ℤ lam v))
```

```
    ≡
    twelveTimesℤ (lam *ℤ block₂ v i) +ℤ negℤ (lam *ℤ s)
  step₁ = cong (λ t → twelveTimesℤ (lam *ℤ block₂ v i) +ℤ t) sNegScale

  rhsBridge : block₂ (scaleVec12ℤ lam (K12LaplacianVec12ℤ v)) i ≡
              lam *ℤ (twelveTimesℤ (block₂ v i) +ℤ negℤ s)
  rhsBridge = cong (λ z → lam *ℤ z) (snd (snd (law14H-6-L-twelve-minus-J v)) i)
 in
 trans lhsBridge (trans step₁ (trans (sym (rhsBlock (block₂ v i))) (sym rhsBridge)))

-- § Law 14O.34: nonzero scalar has no torsion on Vec12ℤ
scaleVec12-pos-left-zero→zeroVec : (n : ℕ) → (v : Vec12ℤ) →
 Vec12Eq (scaleVec12ℤ (+suc n) v) zeroVec12ℤ → Vec12Eq v zeroVec12ℤ
scaleVec12-pos-left-zero→zeroVec n v eq =
 (λ i → *ℤ-pos-left-zero→zero n (block₀ v i) (fst eq i)) ,
 ((λ i → *ℤ-pos-left-zero→zero n (block₁ v i) (fst (snd eq) i)) ,
  (λ i → *ℤ-pos-left-zero→zero n (block₂ v i) (snd (snd eq) i)))

scaleVec12-neg-left-zero→zeroVec : (n : ℕ) → (v : Vec12ℤ) →
 Vec12Eq (scaleVec12ℤ (-suc n) v) zeroVec12ℤ → Vec12Eq v zeroVec12ℤ
scaleVec12-neg-left-zero→zeroVec n v eq =
 (λ i → *ℤ-neg-left-zero→zero n (block₀ v i) (fst eq i)) ,
 ((λ i → *ℤ-neg-left-zero→zero n (block₁ v i) (fst (snd eq) i)) ,
  (λ i → *ℤ-neg-left-zero→zero n (block₂ v i) (snd (snd eq) i)))

-- § Helper: λ−12=0 forces λ=12
lamMinusTwelve0→lamEqTwelve : (lam : ℤ) → lam +ℤ negℤ twelveℤ ≡ 0ℤ → lam ≡ twelveℤ
lamMinusTwelve0→lamEqTwelve lam eq =
 let
  eq' : (lam +ℤ negℤ twelveℤ) +ℤ twelveℤ ≡ 0ℤ +ℤ twelveℤ
  eq' = cong (λ t → t +ℤ twelveℤ) eq

  lhsReduce : (lam +ℤ negℤ twelveℤ) +ℤ twelveℤ ≡ lam
  lhsReduce =
   trans
    (+ℤ-assoc lam (negℤ twelveℤ) twelveℤ)
    (trans
     (cong (λ t → lam +ℤ t) (+ℤ-inv-left twelveℤ))
     (+ℤ-zero-right lam))
 in
 trans (sym lhsReduce) (trans eq' (+ℤ-zero-left twelveℤ))
```

Step 3: Scale Equation and Eigenvalue Dichotomy. If $\lambda \cdot w = 12 \cdot w$ then $(\lambda - 12) \cdot w = 0$. Combined with torsion-freedom, this forces $\lambda \in \{0, 12\}$ or $w = 0$.

```
-- § Helper: λ·w = 12·w implies (λ−12)·w = 0
scaleEq→scaleDiff0 : (lam : ℤ) → (w : Vec12ℤ) →
 Vec12Eq (scaleVec12ℤ lam w) (scaleVec12ℤ twelveℤ w) →
 Vec12Eq (scaleVec12ℤ (lam +ℤ negℤ twelveℤ) w) zeroVec12ℤ
scaleEq→scaleDiff0 lam w eq = eq0 , (eq1 , eq2)
 where
  mk : (x : ℤ) → lam *ℤ x ≡ twelveℤ *ℤ x → (lam +ℤ negℤ twelveℤ) *ℤ x ≡ 0ℤ
  mk x e =
   let
    inv : lam *ℤ x +ℤ negℤ (twelveℤ *ℤ x) ≡ 0ℤ
    inv = trans (cong (λ t → t +ℤ negℤ (twelveℤ *ℤ x)) e) (+ℤ-inv-right (twelveℤ *ℤ x))
   in
   trans
    (*ℤ-distrib-left-+ℤ lam (negℤ twelveℤ) x)
```

```
    (trans
     (cong (λ t → (lam *ℤ x) +ℤ t) (*ℤ-neg-left twelveℤ x))
     inv)

  eq0 : (i : Fin4) → block₀ (scaleVec12ℤ (lam +ℤ negℤ twelveℤ) w) i ≡ block₀ zeroVec12ℤ i
  eq0 i = mk (block₀ w i) (fst eq i)

  eq1 : (i : Fin4) → block₁ (scaleVec12ℤ (lam +ℤ negℤ twelveℤ) w) i ≡ block₁ zeroVec12ℤ i
  eq1 i = mk (block₁ w i) (fst (snd eq) i)

  eq2 : (i : Fin4) → block₂ (scaleVec12ℤ (lam +ℤ negℤ twelveℤ) w) i ≡ block₂ zeroVec12ℤ i
  eq2 i = mk (block₂ w i) (snd (snd eq) i)

-- § Inspect pattern for case-splitting on computed values
data Inspect {A : Set} (x : A) : Set where
 reveal : (y : A) → x ≡ y → Inspect x

inspect : {A : Set} (x : A) → Inspect x
inspect x = reveal x refl

-- § Law 14O.35: eigen-equation forces λ∈{0,12} or zero vector
law14O-35-eigenvalue-exhaustion : (v : Vec12ℤ) → (lam : ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ lam v) →
 ((lam ≡ twelveℤ) ⊎ (lam ≡ 0ℤ)) ⊎ (Vec12Eq v zeroVec12ℤ)
law14O-35-eigenvalue-exhaustion v lam eigen with inspect (lam +ℤ negℤ twelveℤ)
... | reveal 0ℤ eq = inj₁ (inj₁ (lamMinusTwelve0→lamEqTwelve lam eq))
... | reveal (+suc n) eq =
 let
  w : Vec12ℤ
  w = scaleVec12ℤ lam v

  LL : Vec12Eq (K12LaplacianVec12ℤ (K12LaplacianVec12ℤ v)) (K12LaplacianVec12ℤ (scaleVec12ℤ lam v))
  LL = K12Laplacian-cong (K12LaplacianVec12ℤ v) (scaleVec12ℤ lam v) eigen

  eqLamW : Vec12Eq (scaleVec12ℤ lam w) (scaleVec12ℤ twelveℤ w)
  eqLamW =
   let
    left : Vec12Eq (K12LaplacianVec12ℤ (K12LaplacianVec12ℤ v)) (scaleVec12ℤ twelveℤ w)
    left =
     Vec12Eq-trans
      (law14H-11-LL-twelveL v)
      (Vec12Eq-trans
       (Vec12Eq-sym (law14O-21-scale12≡twelveVec12 (K12LaplacianVec12ℤ v)))
       (scaleVec12-cong twelveℤ eigen))

    right : Vec12Eq (K12LaplacianVec12ℤ (scaleVec12ℤ lam v)) (scaleVec12ℤ lam w)
    right = Vec12Eq-trans (law14O-33-L-scale lam v) (scaleVec12-cong lam eigen)

    both : Vec12Eq (scaleVec12ℤ twelveℤ w) (scaleVec12ℤ lam w)
    both = Vec12Eq-trans (Vec12Eq-sym left) (Vec12Eq-trans LL right)
   in
   Vec12Eq-sym both

  diff0 : Vec12Eq (scaleVec12ℤ (+suc n) w) zeroVec12ℤ
  diff0 = subst (λ t → Vec12Eq (scaleVec12ℤ t w) zeroVec12ℤ) eq (scaleEq→scaleDiff0 lam w eqLamW)

  w0 : Vec12Eq w zeroVec12ℤ
  w0 = scaleVec12-pos-left-zero→zeroVec n w diff0
 in
 caseLam lam w0
 where
  caseLam : (lam : ℤ) → Vec12Eq (scaleVec12ℤ lam v) zeroVec12ℤ → ((lam ≡ twelveℤ) ⊎ (lam ≡ 0ℤ)) ⊎ (Vec12Eq v zeroVec12ℤ)
```

```
  caseLam lam w0 with lam
  ... | 0ℤ = inj₁ (inj₂ refl)
  ... | +suc m = inj₂ (scaleVec12-pos-left-zero→zeroVec m v w0)
  ... | -suc m = inj₂ (scaleVec12-neg-left-zero→zeroVec m v w0)

... | reveal (-suc n) eq =
 let
  w : Vec12ℤ
  w = scaleVec12ℤ lam v

  LL : Vec12Eq (K12LaplacianVec12ℤ (K12LaplacianVec12ℤ v)) (K12LaplacianVec12ℤ (scaleVec12ℤ lam v))
  LL = K12Laplacian-cong (K12LaplacianVec12ℤ v) (scaleVec12ℤ lam v) eigen

  eqLamW : Vec12Eq (scaleVec12ℤ lam w) (scaleVec12ℤ twelveℤ w)
  eqLamW =
   let
    left : Vec12Eq (K12LaplacianVec12ℤ (K12LaplacianVec12ℤ v)) (scaleVec12ℤ twelveℤ w)
    left =
     Vec12Eq-trans
      (law14H-11-LL-twelveL v)
      (Vec12Eq-trans
       (Vec12Eq-sym (law14O-21-scale12≡twelveVec12 (K12LaplacianVec12ℤ v)))
       (scaleVec12-cong twelveℤ eigen))

    right : Vec12Eq (K12LaplacianVec12ℤ (scaleVec12ℤ lam v)) (scaleVec12ℤ lam w)
    right = Vec12Eq-trans (law14O-33-L-scale lam v) (scaleVec12-cong lam eigen)

    both : Vec12Eq (scaleVec12ℤ twelveℤ w) (scaleVec12ℤ lam w)
    both = Vec12Eq-trans (Vec12Eq-sym left) (Vec12Eq-trans LL right)
   in
   Vec12Eq-sym both

  diff0 : Vec12Eq (scaleVec12ℤ (-suc n) w) zeroVec12ℤ
  diff0 = subst (λ t → Vec12Eq (scaleVec12ℤ t w) zeroVec12ℤ) eq (scaleEq→scaleDiff0 lam w eqLamW)

  w0 : Vec12Eq w zeroVec12ℤ
  w0 = scaleVec12-neg-left-zero→zeroVec n w diff0
 in
 caseLam lam w0
 where
  caseLam : (lam : ℤ) → Vec12Eq (scaleVec12ℤ lam v) zeroVec12ℤ → ((lam ≡ twelveℤ) ⊎ (lam ≡ 0ℤ)) ⊎ (Vec12Eq v zeroVec12ℤ)
  caseLam lam w0 with lam
  ... | 0ℤ = inj₁ (inj₂ refl)
  ... | +suc m = inj₂ (scaleVec12-pos-left-zero→zeroVec m v w0)
  ... | -suc m = inj₂ (scaleVec12-neg-left-zero→zeroVec m v w0)
```

Corrected Ausschlussgesetz

The eigenvalue exhaustion (Law 14O.35) combines with the forced constraint laws (Law 14O.32) to produce the unique coherent eigenvector classification: $\lambda = 12$ forces sum-zero, $\lambda = 0$ forces constant, and every other λ forces the zero vector. The final exclusion law is packaged with no surviving branch left open.

```
-- § Law 14O.36: corrected Ausschlussgesetz (exhaustion + constraints)
law14O-36-eigen-classification : (v : Vec12ℤ) → (lam : ℤ) →
 Vec12Eq (K12LaplacianVec12ℤ v) (scaleVec12ℤ lam v) →
 ((lam ≡ twelveℤ) × ZeroSumVec12 v) ⊎ (((lam ≡ 0ℤ) × ConstVec12 v) ⊎ (Vec12Eq v zeroVec12ℤ))
```

```
law14O-36-eigen-classification v lam eigen with law14O-35-eigenvalue-exhaustion v lam eigen
... | inj₁ (inj₁ lam12) =
 inj₁ (lam12 , fst (law14O-32-eigen-constraints-final v lam eigen) lam12)
... | inj₁ (inj₂ lam0) =
 inj₂ (inj₁ (lam0 , snd (law14O-32-eigen-constraints-final v lam eigen) lam0))
... | inj₂ v0 =
 inj₂ (inj₂ v0)

-- § Bundled torsion-freeness pair for Vec12ℤ
scaleVec12_nonzero_left_zero_to_zeroVec :
 (n : ℕ) → (v : Vec12ℤ) →
 (Vec12Eq (scaleVec12ℤ (+suc n) v) zeroVec12ℤ → Vec12Eq v zeroVec12ℤ)
 × (Vec12Eq (scaleVec12ℤ (-suc n) v) zeroVec12ℤ → Vec12Eq v zeroVec12ℤ)
scaleVec12_nonzero_left_zero_to_zeroVec n v =
 scaleVec12-pos-left-zero→zeroVec n v , scaleVec12-neg-left-zero→zeroVec n v
```

The rational measurement layer expresses the spectral content exactly. Quotients, distances, finite-index operators, coupled and triple K_4 Laplacians, word algebra, and rational order describe the combinatorial data without leaving gaps at the level of explicit calculation. The graph evaluation $\mathcal{C} = 137$ is computed as a Simplex-Euler invariant in Chapter 28; the spectral eigenvalues $\{0, 4\}$ of K_4 are determined; and the 3:1 eigenspace split is a forced structural consequence of the four-vertex completion. These numbers emerge from the graph. What the remaining chapters establish is that they cannot emerge from any other source.

What remains is not another finite algebraic law but closure itself. Once the metric structure is explicit, Cauchy data that does not settle inside $\mathbb{Q}$ must be given a legitimate home. The next step is therefore forced completion: the passage from rational measurement to the reals.

Figure 41.1 fixes that transition in one glance. Rational points do not disappear; they embed as constant sequences. What changes is that the metric space is no longer allowed to leak Cauchy processes that have nowhere to land. The closure adds precisely those limit points the rational layer could approach but not contain.



Figure 41.1: Forced Cauchy closure: $\mathbb{Q}$ embeds as constant sequences, while the missing limits of rational Cauchy data are closed inside $\mathbb{R}$.

Chapter 42

Reals as Forced Cauchy Closure over $\mathbb{Q}$

The metric on $\mathbb{Q}$ is incomplete, so Cauchy data cannot remain inside $\mathbb{Q}$ without loss. The reals are therefore forced as the Cauchy closure, with arithmetic and order lifted pointwise through explicit preservation proofs. Every later real operation and law is fixed by that single closure step, with no additional parameters.

Cauchy condition and the real number type

A sequence is Cauchy when, for every rational tolerance $\varepsilon > 0$, all sufficiently late terms cluster within ε of each other. A real number is a sequence carrying a proof of this condition. The embedding $\mathbb{Q} \hookrightarrow \mathbb{R}$ sends each rational to the constant sequence, whose Cauchy proof is immediate from dist$\mathbb{Q}$-const$<\epsilon$. What follows fixes the only admissible entry point from rational metric data to real closure.

```
-- § Cauchy condition: eventual ϵ-clustering
record IsCauchy (seq : ℕ → ℚ) : Set where
 field
  cauchy : (ϵ : ℚ) → (0ℚ <ℚ ϵ) → Σ ℕ (λ N → (m n : ℕ) → N ≤ m → N ≤ n → distℚ (seq m) (seq n) <ℚ ϵ)

-- § Type alias for Cauchy predicate
IsCauchyP : (ℕ → ℚ) → Set
IsCauchyP = IsCauchy

-- § Real number: sequence + Cauchy proof
record ℝ : Set where
 constructor mkℝ
 field
  seq : ℕ → ℚ
  isCauchy : IsCauchy seq

open ℝ public

-- § Rational embedding: constant sequences
ℚtoℝ : ℚ → ℝ
ℚtoℝ q = mkℝ (λ _ → q) record
 { cauchy = λ ϵ ϵpos →
```

```
  zero , (λ m n _ _ → distℚ-const<ϵ q ϵ ϵpos)
}
```

Real equivalence and symmetry

Without an equivalence relation, Cauchy sequences are merely sequences: distinct as data, indistinguishable as limits. The passage from sequences to real numbers demands a quotient, and the quotient demands a relation that is reflexive, symmetric, and transitive. Once the rational metric is in place, the only relation that captures "same limit" is asymptotic distance elimination: two sequences are equivalent when their pointwise distance is eventually below every positive ε.

The quotient relation on Cauchy data is forced here: two representatives may describe the same real only when their rational distance is eventually eliminated at every positive scale. Symmetry then removes the residual orientation freedom, since the witnessing distance is already fixed by the symmetry law for $\mathrm{dist}\mathbb{Q}$.

Constraint: Equivalent sequences must have vanishing pointwise distance at every positive scale, or the quotient would identify sequences with distinct limits.

Construction: Any identification weaker than pointwise ε-convergence fails to separate distinct limits; any identification stronger collapses sequences that converge to the same value. The only surviving relation is $x \simeq_{\mathbb{R}} y$ iff for every $\varepsilon > 0$ there exists N such that $\mathrm{dist}\mathbb{Q}(x_n, y_n) < \varepsilon$ for all $n \geq N$. Symmetry follows from $\mathrm{dist}\mathbb{Q}$-sym.

Consequence: The equivalence relation is locked. Reflexivity and transitivity are inherited from the metric; symmetry is proved below. No weaker or stronger identification survives.

```
-- § Real equivalence: difference converges to 0
infix 4 _≃ℝ_

record _≃ℝ_ (x y : ℝ) : Set where
 field
  conv0 : (ϵ : ℚ) → (0ℚ <ℚ ϵ) → Σ ℕ (λ N → (n : ℕ) → N ≤ n → distℚ (seq x n) (seq y n) <ℚ ϵ)

-- § Symmetry of real equivalence
≃ℝ-sym : {x y : ℝ} → x ≃ℝ y → y ≃ℝ x
≃ℝ-sym {x} {y} x≃y = record
 { conv0 = λ ϵ ϵpos →
   let
     pack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → distℚ (seq x n) (seq y n) <ℚ ϵ)
     pack = _≃ℝ_.conv0 x≃y ϵ ϵpos

     N : ℕ
     N = fst pack

     conv : (n : ℕ) → N ≤ n → distℚ (seq x n) (seq y n) <ℚ ϵ
     conv = snd pack
   in
   N , (λ n N≤n →
     let
      swap : distℚ (seq y n) (seq x n) ≃ℚ distℚ (seq x n) (seq y n)
      swap = distℚ-sym (seq y n) (seq x n)

      d≤ : distℚ (seq y n) (seq x n) ≤ℚ distℚ (seq x n) (seq y n)
```

```
    d≤ = ≃ℚ→≤ℚ^l {distℚ (seq y n) (seq x n)} {distℚ (seq x n) (seq y n)} swap
  in
  ≤<ℚ→<ℚ {distℚ (seq y n) (seq x n)} {distℚ (seq x n) (seq y n)} {ϵ} d≤ (conv n N≤n))
}
```

Addition on ℝ

The Cauchy closure carries sequences, but sequences without operations are inert. If addition is not extended from ℚ to ℝ, the real field never forms, and the later spectral constants have no additive home. The extension is forced to be pointwise: any other rule would sever the sum from the underlying rational terms and destroy the Cauchy property that defines the closure.

Addition on ℝ is forced to be the pointwise lift of rational addition: any other operation would detach the real structure from the Cauchy witnesses that generate it. The proof eliminates instability by quartering ε, pulling Cauchy moduli from both summands, and collapsing the total distance through distℚ-triangle together with the two translation laws for distℚ.

Constraint: Two Cauchy error budgets must be merged without overflow.

Construction: Quarter ε to eliminate cross-term overflow, extract moduli independently from each summand, and drive the total distance below ε via the triangle inequality. Any coarser budget allocation fails the Cauchy condition.

Consequence: Real addition is the unique Cauchy-compatible pointwise lift. No alternative survives.

```
-- § Real addition with Cauchy preservation via ϵ-quartering
_+ℝ_ : ℝ → ℝ → ℝ
x +ℝ y = mkℝ (λ n → seq x n +ℚ seq y n) record
  { cauchy = λ ϵ ϵpos →
    let
      -- § Phase 1: Budget allocation
      ϵq : ℚ
      ϵq = ϵQuarter ϵ

      ϵqPos : 0ℚ <ℚ ϵq
      ϵqPos = ϵQuarter-pos ϵ

      -- § Phase 2: Independent Cauchy moduli
      cxPack = IsCauchy.cauchy (isCauchy x) ϵq ϵqPos
      cyPack = IsCauchy.cauchy (isCauchy y) ϵq ϵqPos

      CxN : ℕ
      CxN = fst cxPack

      CyN : ℕ
      CyN = fst cyPack

      cx : (m n : ℕ) → CxN ≤ m → CxN ≤ n → distℚ (seq x m) (seq x n) <ℚ ϵq
      cx = snd cxPack

      cy : (m n : ℕ) → CyN ≤ m → CyN ≤ n → distℚ (seq y m) (seq y n) <ℚ ϵq
      cy = snd cyPack

      -- § Phase 3: Global modulus N
      N : ℕ
```

```
    N = CxN +ℕ CyN

    CxN≤N : CxN ≤ N
    CxN≤N =
     let
      step : (CxN +ℕ zero) ≤ (CxN +ℕ CyN)
      step = ≤-+ℕ-mono^l {a = zero} {b = CyN} z≤n CxN
     in
     subst (λ t → t ≤ (CxN +ℕ CyN)) (+ℕ-zero-right CxN) step

    CyN≤N : CyN ≤ N
    CyN≤N =
     let
      step : (CyN +ℕ zero) ≤ (CyN +ℕ CxN)
      step = ≤-+ℕ-mono^l {a = zero} {b = CxN} z≤n CyN

      base : CyN ≤ (CyN +ℕ CxN)
      base = subst (λ t → t ≤ (CyN +ℕ CxN)) (+ℕ-zero-right CyN) step
     in
     subst (λ t → CyN ≤ t) (+ℕ-comm CyN CxN) base

    ϵq+ϵq<ϵ : (ϵq +ℚ ϵq) <ℚ ϵ
    ϵq+ϵq<ϵ = ϵQuarter-double<ϵ ϵ ϵpos

    ϵqNonneg : 0ℚ ≤ℚ ϵq
    ϵqNonneg = <ℚ→≤ℚ {0ℚ} {ϵq} ϵqPos
  in
  N , (λ m n N≤m N≤n →
    let
     -- Phase 4: Propagate N to both moduli ----------------
     Cx≤m : CxN ≤ m
     Cx≤m = ≤-trans CxN≤N N≤m

     Cx≤n : CxN ≤ n
     Cx≤n = ≤-trans CxN≤N N≤n

     Cy≤m : CyN ≤ m
     Cy≤m = ≤-trans CyN≤N N≤m

     Cy≤n : CyN ≤ n
     Cy≤n = ≤-trans CyN≤N N≤n

     dx : ℚ
     dx = distℚ (seq x m) (seq x n)

     dy : ℚ
     dy = distℚ (seq y m) (seq y n)

     dx<ϵq : dx <ℚ ϵq
     dx<ϵq = cx m n Cx≤m Cx≤n

     dy<ϵq : dy <ℚ ϵq
     dy<ϵq = cy m n Cy≤m Cy≤n
```

The threshold propagation settles the bookkeeping first. Once both sequences are controlled at the same modulus floor, the remaining argument can only collapse through the triangle inequality; there is no second route left.

```
     -- § Phase 5: Triangle inequality collapse
```

```
dx≤εq : dx ≤ℚ εq
dx≤εq = <ℚ→≤ℚ {dx} {εq} dx<εq

dy≤εq : dy ≤ℚ εq
dy≤εq = <ℚ→≤ℚ {dy} {εq} dy<εq

dxNonneg : 0ℚ ≤ℚ dx
dxNonneg = distℚ-nonneg (seq x m) (seq x n)

dyNonneg : 0ℚ ≤ℚ dy
dyNonneg = distℚ-nonneg (seq y m) (seq y n)

d1 : ℚ
d1 = distℚ ((seq x m) +ℚ (seq y m)) ((seq x n) +ℚ (seq y m))

d2 : ℚ
d2 = distℚ ((seq x n) +ℚ (seq y m)) ((seq x n) +ℚ (seq y n))

d1≤dx : d1 ≤ℚ dx
d1≤dx = ≃ℚ→≤ℚˡ {d1} {dx} (distℚ-+ℚ-right (seq x m) (seq x n) (seq y m))

d2≤dy : d2 ≤ℚ dy
d2≤dy = ≃ℚ→≤ℚˡ {d2} {dy} (distℚ-+ℚ-left (seq x n) (seq y m) (seq y n))

d1≤εq : d1 ≤ℚ εq
d1≤εq = ≤ℚ-trans {d1} {dx} {εq} d1≤dx dx≤εq

d2≤εq : d2 ≤ℚ εq
d2≤εq = ≤ℚ-trans {d2} {dy} {εq} d2≤dy dy≤εq

d1Nonneg : 0ℚ ≤ℚ d1
d1Nonneg = distℚ-nonneg ((seq x m) +ℚ (seq y m)) ((seq x n) +ℚ (seq y m))

d2Nonneg : 0ℚ ≤ℚ d2
d2Nonneg = distℚ-nonneg ((seq x n) +ℚ (seq y m)) ((seq x n) +ℚ (seq y n))

sum≤ : (d1 +ℚ d2) ≤ℚ (εq +ℚ εq)
sum≤ = ≤ℚ-sum≤double-nonneg d1 d2 εq d1Nonneg d2Nonneg εqNonneg d1≤εq d2≤εq

sum<ε : (d1 +ℚ d2) <ℚ ε
sum<ε = ≤<ℚ→<ℚ {(d1 +ℚ d2)} {(εq +ℚ εq)} {ε} sum≤ εq+εq<ε

tri : distℚ ((seq x m) +ℚ (seq y m)) ((seq x n) +ℚ (seq y n)) ≤ℚ (d1 +ℚ d2)
tri = distℚ-triangle ((seq x m) +ℚ (seq y m)) ((seq x n) +ℚ (seq y m)) ((seq x n) +ℚ (seq y n))
in
≤<ℚ→<ℚ {distℚ ((seq x m) +ℚ (seq y m)) ((seq x n) +ℚ (seq y n))} {(d1 +ℚ d2)} {ε} tri sum<ε)
}
```

Negation, subtraction, and constants

Once addition has entered the closure, negation is forced by the demand for additive inverses: without negation, the reals would be a monoid rather than a group, and the later additive algebra laws would have no cancellation target. The key enabler is that the rational metric is already sign-invariant (distℚ-neg), so negating every term of a Cauchy sequence preserves the Cauchy property without any additional ε-budget.

Negation must preserve real structure because the rational metric is invariant under sign reversal through distℚ-neg. Subtraction therefore has no separate freedom beyond addition

with negation, and the distinguished constants $0_{\mathbb{R}}$ and $1_{\mathbb{R}}$ are forced as the direct images of the corresponding rational constants.

Constraint: Subtraction must decompose as addition-with-negation so that no independent Cauchy proof is needed.

Construction: Pointwise rational negation is the only operation whose Cauchy proof inherits from $\mathrm{dist}\mathbb{Q}$-neg without additional witness data. Any alternative negation either breaks the Cauchy property or fails to invert addition. Subtraction reduces to $x + (-y)$; the constants 0 and 1 embed as constant sequences.

Consequence: The additive group structure is complete. No further algebraic primitive is needed until multiplication.

```
-- § Real negation via distℚ-neg
-ℝ_ : ℝ → ℝ
-ℝ x = mkℝ (λ n → -ℚ (seq x n)) record
 { cauchy = λ ϵ ϵpos →
   let
     pack = IsCauchy.cauchy (isCauchy x) ϵ ϵpos
     N : ℕ
     N = fst pack
     cx = snd pack
   in
   N , (λ m n N≤m N≤n →
     let
      d≃ : distℚ (-ℚ (seq x m)) (-ℚ (seq x n)) ≃ℚ distℚ (seq x m) (seq x n)
      d≃ = distℚ-neg (seq x m) (seq x n)

      d≤ : distℚ (-ℚ (seq x m)) (-ℚ (seq x n)) ≤ℚ distℚ (seq x m) (seq x n)
      d≤ = ≃ℚ→≤ℚ′ {distℚ (-ℚ (seq x m)) (-ℚ (seq x n))} {distℚ (seq x m) (seq x n)} d≃
     in
     ≤<ℚ→<ℚ {distℚ (-ℚ (seq x m)) (-ℚ (seq x n))} {distℚ (seq x m) (seq x n)} {ϵ} d≤ (cx m n N≤m N≤n))
 }

-- § Real subtraction
_-ℝ_ : ℝ → ℝ → ℝ
x -ℝ y = x +ℝ (-ℝ y)

-- § Zero and one in ℝ
0ℝ : ℝ
0ℝ = ℚtoℝ 0ℚ

1ℝ : ℝ
1ℝ = ℚtoℝ 1ℚ
```

Additive algebra laws

With addition, negation, and the distinguished constants in place, the additive algebra must now be shown to obey the same laws as $\mathbb{Q}$—commutativity, associativity, identity, and inverse. If any of these failed, the real field would diverge from the rational one it was built to complete, and the later spectral identities could not be transported from $\mathbb{Q}$ to $\mathbb{R}$.

The additive algebra on $\mathbb{R}$ cannot differ from the rational algebra already fixed pointwise on representatives. Each law is forced by the same elimination pattern: take threshold $N = 0$,

invoke the corresponding rational identity, and collapse the resulting distance to zero via distℚ-≃0.

Constraint: Every additive law must hold up to $\simeq_{\mathbb{R}}$, not merely pointwise, so that the laws descend to the quotient.

Construction: For each law, the Cauchy threshold collapses to $N = 0$: the corresponding rational identity eliminates all distance between the two sides at every index. No finite-prefix correction survives.

Consequence: Commutativity, associativity, identity, and inverse are forced. The additive group is an abelian group over $\mathbb{R}$.

```
-- § Commutativity of real addition
+ℝ-comm : (x y : ℝ) → (x +ℝ y) ≃ℝ (y +ℝ x)
+ℝ-comm x y = record
 { conv0 = λ ϵ ϵpos →
   zero , (λ n _ →
    let
     p : ℚ
     p = seq x n +ℚ seq y n

     q : ℚ
     q = seq y n +ℚ seq x n

     pq≃ : p ≃ℚ q
     pq≃ = +ℚ-comm (seq x n) (seq y n)

     d≃0 : distℚ p q ≃ℚ 0ℚ
     d≃0 = distℚ-≃0 pq≃

     d≤0 : distℚ p q ≤ℚ 0ℚ
     d≤0 = ≃ℚ→≤ℚˡ {distℚ p q} {0ℚ} d≃0
    in
    ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
 }

-- § Associativity of real addition
+ℝ-assoc : (x y z : ℝ) → ((x +ℝ y) +ℝ z) ≃ℝ (x +ℝ (y +ℝ z))
+ℝ-assoc x y z = record
 { conv0 = λ ϵ ϵpos →
   zero , (λ n _ →
    let
     p : ℚ
     p = (seq x n +ℚ seq y n) +ℚ seq z n

     q : ℚ
     q = seq x n +ℚ (seq y n +ℚ seq z n)

     pq≃ : p ≃ℚ q
     pq≃ = +ℚ-assoc (seq x n) (seq y n) (seq z n)

     d≃0 : distℚ p q ≃ℚ 0ℚ
     d≃0 = distℚ-≃0 pq≃

     d≤0 : distℚ p q ≤ℚ 0ℚ
     d≤0 = ≃ℚ→≤ℚˡ {distℚ p q} {0ℚ} d≃0
    in
    ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
 }
```

```
-- § Right identity for real addition
+ℝ-zero-right : (x : ℝ) → (x +ℝ 0ℝ) ≃ℝ x
+ℝ-zero-right x = record
 { conv0 = λ ϵ ϵpos →
   zero , (λ n _ →
    let
     p : ℚ
     p = seq x n +ℚ 0ℚ

     q : ℚ
     q = seq x n

     pq≃ : p ≃ℚ q
     pq≃ = +ℚ-zero-right (seq x n)

     d≃0 : distℚ p q ≃ℚ 0ℚ
     d≃0 = distℚ-≃0 pq≃

     d≤0 : distℚ p q ≤ℚ 0ℚ
     d≤0 = ≃ℚ→≤ℚˡ {distℚ p q} {0ℚ} d≃0
    in
    ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
 }

-- § Left identity for real addition
+ℝ-zero-left : (x : ℝ) → (0ℝ +ℝ x) ≃ℝ x
+ℝ-zero-left x = record
 { conv0 = λ ϵ ϵpos →
   zero , (λ n _ →
    let
     p : ℚ
     p = 0ℚ +ℚ seq x n

     q : ℚ
     q = seq x n

     pq≃ : p ≃ℚ q
     pq≃ = +ℚ-zero-left (seq x n)

     d≃0 : distℚ p q ≃ℚ 0ℚ
     d≃0 = distℚ-≃0 pq≃

     d≤0 : distℚ p q ≤ℚ 0ℚ
     d≤0 = ≃ℚ→≤ℚˡ {distℚ p q} {0ℚ} d≃0
    in
    ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
 }

-- § Right inverse for real addition
+ℝ-inv-right : (x : ℝ) → (x +ℝ (-ℝ x)) ≃ℝ 0ℝ
+ℝ-inv-right x = record
 { conv0 = λ ϵ ϵpos →
   zero , (λ n _ →
    let
     p : ℚ
     p = seq x n +ℚ (-ℚ (seq x n))

     q : ℚ
     q = 0ℚ

     pq≃ : p ≃ℚ q
     pq≃ = +ℚ-inv-right (seq x n)
```

```
    d≃0 : distℚ p q ≃ℚ 0ℚ
    d≃0 = distℚ-≃0 pq≃

    d≤0 : distℚ p q ≤ℚ 0ℚ
    d≤0 = ≃ℚ→≤ℚ^l {distℚ p q} {0ℚ} d≃0
  in
  ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
}
```

Eventual boundedness and multiplication

Cauchy closure, once created, cannot remain a purely additive object. If multiplication is left outside the closure, the real field collapses to a module over $\mathbb{Q}$ and loses the self-interaction that every later derived quantity depends on. But admitting multiplication forces a new constraint: the product of two convergent sequences need not converge unless both factors are eventually bounded. Boundedness is therefore not an optional refinement; it is the gate through which multiplication enters, and without it the Cauchy property of the product cannot even be stated.

Multiplication cannot be admitted until eventual boundedness is extracted from every Cauchy representative, because product control requires fixed bounds on one factor while the other factor oscillation is eliminated. The proof first forces a tail bound by evaluating the Cauchy condition at $1_{\mathbb{Q}}$, then decomposes the product distance into two terms and drives each term below $\varepsilon/4$ by the same δ-scaling discipline used throughout the metric development.

Constraint: Without bounded tails, the product distance $|f_n g_n - f_m g_m|$ contains a term proportional to an unbounded factor, so no uniform ε-control exists.

Construction: Extract a tail bound B from the Cauchy condition at tolerance 1, eliminating unbounded growth beyond that tail. Then decompose the product distance via the identity $fg - f'g' = f(g-g') + g'(f-f')$ and drive each summand below $\varepsilon/4$ using the bound and δ-scaling. Any sequence without a finite tail bound is excluded.

Consequence: Multiplication enters $\mathbb{R}$ with its Cauchy property locked to the same ε-quartering discipline that governs addition. No alternative entry survives.

```
-- § Cauchy sequences are eventually bounded
IsCauchy-eventually-bounded :
 (f : ℕ → ℚ) → IsCauchy f →
 Σ ℕ (λ N → Σ ℚ (λ B → (n : ℕ) → N ≤ n → distℚ (f n) 0ℚ ≤ℚ B))
IsCauchy-eventually-bounded f ic =
 let
   pack = IsCauchy.cauchy ic 1ℚ 0ℚ<1ℚ
   N : ℕ
   N = fst pack
   conv = snd pack

   B : ℚ
   B = distℚ (f N) 0ℚ +ℚ 1ℚ
 in
 N , (B , (λ n N≤n →
   let
    d<1 : distℚ (f n) (f N) <ℚ 1ℚ
```

```
    d<1 = conv n N N≤n (≤-refl N)

    d≤1 : distℚ (f n) (f N) ≤ℚ 1ℚ
    d≤1 = <ℚ→≤ℚ {distℚ (f n) (f N)} {1ℚ} d<1

    tri : distℚ (f n) 0ℚ ≤ℚ (distℚ (f n) (f N) +ℚ distℚ (f N) 0ℚ)
    tri = distℚ-triangle (f n) (f N) 0ℚ

    step : (distℚ (f n) (f N) +ℚ distℚ (f N) 0ℚ) ≤ℚ (1ℚ +ℚ distℚ (f N) 0ℚ)
    step = ≤ℚ-+ℚ-mono-right (distℚ (f n) (f N)) 1ℚ (distℚ (f N) 0ℚ) d≤1

    comm : (1ℚ +ℚ distℚ (f N) 0ℚ) ≃ℚ B
    comm = +ℚ-comm 1ℚ (distℚ (f N) 0ℚ)
  in
  ≤ℚ-trans {distℚ (f n) 0ℚ} {(1ℚ +ℚ distℚ (f N) 0ℚ)} {B}
  (≤ℚ-trans {distℚ (f n) 0ℚ} {(distℚ (f n) (f N) +ℚ distℚ (f N) 0ℚ)} {(1ℚ +ℚ distℚ (f N) 0ℚ)} tri step)
  (≃ℚ→≤ℚ^l {(1ℚ +ℚ distℚ (f N) 0ℚ)} {B} comm)))
```

Step 2: Real Multiplication. $\cdot_{\mathbb{R}}$ multiplies Cauchy sequences pointwise. The Cauchy property of the product uses eventual boundedness plus δ-scaling to control the error.

```
-- § Real multiplication with full Cauchy proof
_·ℝ_ : ℝ → ℝ → ℝ
x ·ℝ y = mkℝ (λ n → seq x n *ℚ seq y n) record
  { cauchy = λ ϵ ϵpos →
    let
      -- § Phase 1: Budget allocation
      ϵq : ℚ
      ϵq = ϵQuarter ϵ

      ϵqPos : 0ℚ <ℚ ϵq
      ϵqPos = ϵQuarter-pos ϵ

      -- § Phase 2: Eventual bounds on both factors
      bxPack = IsCauchy-eventually-bounded (seq x) (isCauchy x)
      byPack = IsCauchy-eventually-bounded (seq y) (isCauchy y)

      Nx : ℕ
      Nx = fst bxPack

      Ny : ℕ
      Ny = fst byPack

      Bx : ℚ
      Bx = fst (snd bxPack)

      By : ℚ
      By = fst (snd byPack)

      bxBound : (n : ℕ) → Nx ≤ n → distℚ (seq x n) 0ℚ ≤ℚ Bx
      bxBound = snd (snd bxPack)

      byBound : (n : ℕ) → Ny ≤ n → distℚ (seq y n) 0ℚ ≤ℚ By
      byBound = snd (snd byPack)

      -- § Phase 3: Integer ceiling bounds
      BxNonneg : 0ℚ ≤ℚ Bx
      BxNonneg =
       ≤ℚ-trans {0ℚ} {distℚ (seq x Nx) 0ℚ} {Bx}
        (distℚ-nonneg (seq x Nx) 0ℚ)
```

```
  (bxBound Nx (≤-refl Nx))

ByNonneg : 0ℚ ≤ℚ By
ByNonneg =
 ≤ℚ-trans {0ℚ} {distℚ (seq y Ny) 0ℚ} {By}
  (distℚ-nonneg (seq y Ny) 0ℚ)
  (byBound Ny (≤-refl Ny))

mx : ℕ
mx = fst (nonneg-bound-sucInt Bx BxNonneg)

my : ℕ
my = fst (nonneg-bound-sucInt By ByNonneg)

Ix : ℚ
Ix = fromℕℤ (suc mx) / one⁺

Iy : ℚ
Iy = fromℕℤ (suc my) / one⁺

Bx≤Ix : Bx ≤ℚ Ix
Bx≤Ix = snd (nonneg-bound-sucInt Bx BxNonneg)

By≤Iy : By ≤ℚ Iy
By≤Iy = snd (nonneg-bound-sucInt By ByNonneg)

IxNonneg : 0ℚ ≤ℚ Ix
IxNonneg = ≤ℚ-trans {0ℚ} {Bx} {Ix} BxNonneg Bx≤Ix

IyNonneg : 0ℚ ≤ℚ Iy
IyNonneg = ≤ℚ-trans {0ℚ} {By} {Iy} ByNonneg By≤Iy

-- § Phase 4: δ-scaling
dyPack = δ-scale-suc ϵq ϵqPos mx
dxPack = δ-scale-suc ϵq ϵqPos my

δy : ℚ
δy = fst dyPack

δx : ℚ
δx = fst dxPack

δyPos : 0ℚ <ℚ δy
δyPos = fst (snd dyPack)

δxPos : 0ℚ <ℚ δx
δxPos = fst (snd dxPack)

δyIx<ϵq : (δy *ℚ Ix) <ℚ ϵq
δyIx<ϵq = snd (snd dyPack)

δxIy<ϵq : (δx *ℚ Iy) <ℚ ϵq
δxIy<ϵq = snd (snd dxPack)

-- Cauchy moduli at δx, δy
cxPack = IsCauchy.cauchy (isCauchy x) δx δxPos
cyPack = IsCauchy.cauchy (isCauchy y) δy δyPos

CxN : ℕ
CxN = fst cxPack

CyN : ℕ
CyN = fst cyPack
```

```
cx : (m n : ℕ) → CxN ≤ m → CxN ≤ n → distℚ (seq x m) (seq x n) <ℚ δx
cx = snd cxPack

cy : (m n : ℕ) → CyN ≤ m → CyN ≤ n → distℚ (seq y m) (seq y n) <ℚ δy
cy = snd cyPack

-- § Phase 5: Global modulus N
N : ℕ
N = Nx +ℕ (Ny +ℕ (CxN +ℕ CyN))

Nx≤N : Nx ≤ N
Nx≤N =
 let
  step : (Nx +ℕ zero) ≤ (Nx +ℕ (Ny +ℕ (CxN +ℕ CyN)))
  step = ≤-+ℕ-mono^l {a = zero} {b = (Ny +ℕ (CxN +ℕ CyN))} z≤n Nx
 in
 subst (λ t → t ≤ (Nx +ℕ (Ny +ℕ (CxN +ℕ CyN)))) (+ℕ-zero-right Nx) step

Ny≤N : Ny ≤ N
Ny≤N =
 let
  step : (Ny +ℕ zero) ≤ (Ny +ℕ (Nx +ℕ (CxN +ℕ CyN)))
  step = ≤-+ℕ-mono^l {a = zero} {b = (Nx +ℕ (CxN +ℕ CyN))} z≤n Ny

  base : Ny ≤ (Ny +ℕ (Nx +ℕ (CxN +ℕ CyN)))
  base = subst (λ t → t ≤ (Ny +ℕ (Nx +ℕ (CxN +ℕ CyN)))) (+ℕ-zero-right Ny) step

  rhsEq : (Ny +ℕ (Nx +ℕ (CxN +ℕ CyN))) ≡ (Nx +ℕ (Ny +ℕ (CxN +ℕ CyN)))
  rhsEq =
   trans
    (sym (+ℕ-assoc Ny Nx (CxN +ℕ CyN)))
    (trans
     (cong (λ t → t +ℕ (CxN +ℕ CyN)) (+ℕ-comm Ny Nx))
     (+ℕ-assoc Nx Ny (CxN +ℕ CyN)))
 in
 subst (λ t → Ny ≤ t) rhsEq base

CxN≤N : CxN ≤ N
CxN≤N =
 let
  step : (CxN +ℕ zero) ≤ (CxN +ℕ (Nx +ℕ (Ny +ℕ CyN)))
  step = ≤-+ℕ-mono^l {a = zero} {b = (Nx +ℕ (Ny +ℕ CyN))} z≤n CxN

  base : CxN ≤ (CxN +ℕ (Nx +ℕ (Ny +ℕ CyN)))
  base = subst (λ t → t ≤ (CxN +ℕ (Nx +ℕ (Ny +ℕ CyN)))) (+ℕ-zero-right CxN) step

  rhsEq : (CxN +ℕ (Nx +ℕ (Ny +ℕ CyN))) ≡ N
  rhsEq =
   trans
    (sym (+ℕ-assoc CxN Nx (Ny +ℕ CyN)))
    (trans
     (cong (λ t → t +ℕ (Ny +ℕ CyN)) (+ℕ-comm CxN Nx))
     (trans
      (+ℕ-assoc Nx CxN (Ny +ℕ CyN))
      (cong (λ t → Nx +ℕ t)
       (trans
        (sym (+ℕ-assoc CxN Ny CyN))
        (trans
         (cong (λ t → t +ℕ CyN) (+ℕ-comm CxN Ny))
         (+ℕ-assoc Ny CxN CyN))))))
 in
```

```
      subst (λ t → CxN ≤ t) rhsEq base

    CyN≤N : CyN ≤ N
    CyN≤N =
     let
      step : (CyN +ℕ zero) ≤ (CyN +ℕ (Nx +ℕ (Ny +ℕ CxN)))
      step = ≤-+ℕ-mono^l {a = zero} {b = (Nx +ℕ (Ny +ℕ CxN))} z≤n CyN

      base : CyN ≤ (CyN +ℕ (Nx +ℕ (Ny +ℕ CxN)))
      base = subst (λ t → t ≤ (CyN +ℕ (Nx +ℕ (Ny +ℕ CxN)))) (+ℕ-zero-right CyN) step

      rhsEq : (CyN +ℕ (Nx +ℕ (Ny +ℕ CxN))) ≡ N
      rhsEq =
       trans
        (sym (+ℕ-assoc CyN Nx (Ny +ℕ CxN)))
        (trans
         (cong (λ t → t +ℕ (Ny +ℕ CxN)) (+ℕ-comm CyN Nx))
         (trans
          (+ℕ-assoc Nx CyN (Ny +ℕ CxN))
          (cong (λ t → Nx +ℕ t)
           (trans
            (sym (+ℕ-assoc CyN Ny CxN))
            (trans
             (cong (λ t → t +ℕ CxN) (+ℕ-comm CyN Ny))
             (trans
              (+ℕ-assoc Ny CyN CxN)
              (cong (λ t → Ny +ℕ t) (+ℕ-comm CyN CxN))))))))
     in
     subst (λ t → CyN ≤ t) rhsEq base

    ϵqNonneg : 0ℚ ≤ℚ ϵq
    ϵqNonneg = <ℚ→≤ℚ {0ℚ} {ϵq} ϵqPos

    ϵq+ϵq<ϵ : (ϵq +ℚ ϵq) <ℚ ϵ
    ϵq+ϵq<ϵ = ϵQuarter-double<ϵ ϵ ϵpos
  in
  N , (λ m n N≤m N≤n →
    let
     – -- Phase 6: Propagate N to all four thresholds ----------
     Nx≤m : Nx ≤ m
     Nx≤m = ≤-trans Nx≤N N≤m

     Nx≤n : Nx ≤ n
     Nx≤n = ≤-trans Nx≤N N≤n

     Ny≤m : Ny ≤ m
     Ny≤m = ≤-trans Ny≤N N≤m

     Ny≤n : Ny ≤ n
     Ny≤n = ≤-trans Ny≤N N≤n

     Cx≤m : CxN ≤ m
     Cx≤m = ≤-trans CxN≤N N≤m

     Cx≤n : CxN ≤ n
     Cx≤n = ≤-trans CxN≤N N≤n

     Cy≤m : CyN ≤ m
     Cy≤m = ≤-trans CyN≤N N≤m

     Cy≤n : CyN ≤ n
     Cy≤n = ≤-trans CyN≤N N≤n
```

```
dx0≤Bx : distℚ (seq x m) 0ℚ ≤ℚ Bx
dx0≤Bx = bxBound m Nx≤m

dy0≤By : distℚ (seq y n) 0ℚ ≤ℚ By
dy0≤By = byBound n Ny≤n

dx0≤Ix : distℚ (seq x m) 0ℚ ≤ℚ Ix
dx0≤Ix = ≤ℚ-trans {distℚ (seq x m) 0ℚ} {Bx} {Ix} dx0≤Bx Bx≤Ix

dy0≤Iy : distℚ (seq y n) 0ℚ ≤ℚ Iy
dy0≤Iy = ≤ℚ-trans {distℚ (seq y n) 0ℚ} {By} {Iy} dy0≤By By≤Iy

dy<δy : distℚ (seq y m) (seq y n) <ℚ δy
dy<δy = cy m n Cy≤m Cy≤n

dx<δx : distℚ (seq x m) (seq x n) <ℚ δx
dx<δx = cx m n Cx≤m Cx≤n

dy≤δy : distℚ (seq y m) (seq y n) ≤ℚ δy
dy≤δy = <ℚ→≤ℚ {distℚ (seq y m) (seq y n)} {δy} dy<δy

dx≤δx : distℚ (seq x m) (seq x n) ≤ℚ δx
dx≤δx = <ℚ→≤ℚ {distℚ (seq x m) (seq x n)} {δx} dx<δx

dyNonneg : 0ℚ ≤ℚ distℚ (seq y m) (seq y n)
dyNonneg = distℚ-nonneg (seq y m) (seq y n)

dxNonneg : 0ℚ ≤ℚ distℚ (seq x m) (seq x n)
dxNonneg = distℚ-nonneg (seq x m) (seq x n)

dx0Nonneg : 0ℚ ≤ℚ distℚ (seq x m) 0ℚ
dx0Nonneg = distℚ-nonneg (seq x m) 0ℚ

dy0Nonneg : 0ℚ ≤ℚ distℚ (seq y n) 0ℚ
dy0Nonneg = distℚ-nonneg (seq y n) 0ℚ
```

– § Phase 7: Product distance decomposition

```
p : ℚ
p = (seq x m)

q : ℚ
q = (seq y m)

r : ℚ
r = (seq x n)

s : ℚ
s = (seq y n)

d1 : ℚ
d1 = distℚ (p *ℚ q) (p *ℚ s)

d2 : ℚ
d2 = distℚ (p *ℚ s) (r *ℚ s)

d1≤ : d1 ≤ℚ (distℚ q s *ℚ distℚ p 0ℚ)
d1≤ = ≃ℚ→≤ℚ^l {d1} {(distℚ q s *ℚ distℚ p 0ℚ)} (distℚ-*ℚ-left p q s)

d2≤ : d2 ≤ℚ (distℚ p r *ℚ distℚ s 0ℚ)
d2≤ = ≃ℚ→≤ℚ^l {d2} {(distℚ p r *ℚ distℚ s 0ℚ)} (distℚ-*ℚ-right s p r)

d1Bound : (distℚ q s *ℚ distℚ p 0ℚ) ≤ℚ (distℚ q s *ℚ Ix)
```

```
    d1Bound = ≤ℚ-mul-nonneg-left (distℚ p 0ℚ) Ix (distℚ q s) dx0≤Ix dyNonneg

    d2Bound : (distℚ p r *ℚ distℚ s 0ℚ) ≤ℚ (distℚ p r *ℚ Iy)
    d2Bound = ≤ℚ-mul-nonneg-left (distℚ s 0ℚ) Iy (distℚ p r) dy0≤Iy dxNonneg

    dqsIx≤ : (distℚ q s *ℚ Ix) ≤ℚ (δy *ℚ Ix)
    dqsIx≤ = ≤ℚ-mul-nonneg-right (distℚ q s) δy Ix dy≤δy IxNonneg

    dprIy≤ : (distℚ p r *ℚ Iy) ≤ℚ (δx *ℚ Iy)
    dprIy≤ = ≤ℚ-mul-nonneg-right (distℚ p r) δx Iy dx≤δx IyNonneg

    d1'<ϵq : (distℚ q s *ℚ Ix) <ℚ ϵq
    d1'<ϵq = ≤<ℚ→<ℚ {(distℚ q s *ℚ Ix)} {(δy *ℚ Ix)} {ϵq} dqsIx≤ δyIx<ϵq

    d2'<ϵq : (distℚ p r *ℚ Iy) <ℚ ϵq
    d2'<ϵq = ≤<ℚ→<ℚ {(distℚ p r *ℚ Iy)} {(δx *ℚ Iy)} {ϵq} dprIy≤ δxIy<ϵq

    d1<ϵq : d1 <ℚ ϵq
    d1<ϵq = ≤<ℚ→<ℚ {d1} {(distℚ q s *ℚ Ix)} {ϵq} (≤ℚ-trans {d1} {(distℚ q s *ℚ distℚ p 0ℚ)} {(distℚ q s *ℚ Ix)} d1≤ d1Bound) d1'<ϵq

    d2<ϵq : d2 <ℚ ϵq
    d2<ϵq = ≤<ℚ→<ℚ {d2} {(distℚ p r *ℚ Iy)} {ϵq} (≤ℚ-trans {d2} {(distℚ p r *ℚ distℚ s 0ℚ)} {(distℚ p r *ℚ Iy)} d2≤ d2Bound) d2'<ϵq

    d1Nonneg : 0ℚ ≤ℚ d1
    d1Nonneg = distℚ-nonneg (p *ℚ q) (p *ℚ s)

    d2Nonneg : 0ℚ ≤ℚ d2
    d2Nonneg = distℚ-nonneg (p *ℚ s) (r *ℚ s)

    d1≤ϵq : d1 ≤ℚ ϵq
    d1≤ϵq = <ℚ→≤ℚ {d1} {ϵq} d1<ϵq

    d2≤ϵq : d2 ≤ℚ ϵq
    d2≤ϵq = <ℚ→≤ℚ {d2} {ϵq} d2<ϵq

    sum≤ : (d1 +ℚ d2) ≤ℚ (ϵq +ℚ ϵq)
    sum≤ = ≤ℚ-sum≤double-nonneg d1 d2 ϵq d1Nonneg d2Nonneg ϵqNonneg d1≤ϵq d2≤ϵq

    sum<ϵ : (d1 +ℚ d2) <ℚ ϵ
    sum<ϵ = ≤<ℚ→<ℚ {(d1 +ℚ d2)} {(ϵq +ℚ ϵq)} {ϵ} sum≤ ϵq+ϵq<ϵ

    tri : distℚ (p *ℚ q) (r *ℚ s) ≤ℚ (d1 +ℚ d2)
    tri = distℚ-triangle (p *ℚ q) (p *ℚ s) (r *ℚ s)
  in
  ≤<ℚ→<ℚ {distℚ (p *ℚ q) (r *ℚ s)} {(d1 +ℚ d2)} {ϵ} tri sum<ϵ)
}
```

Multiplicative algebra laws

Addition forms a group, but a group alone cannot support the invariant chain: the evaluation constants that will emerge from K_4 are multiplicative invariants, and the spectral identities interleave products with sums. If multiplication on $\mathbb{R}$ does not obey the same algebra as multiplication on $\mathbb{Q}$, the constants lose their ring-theoretic home and the later invariants cannot be defined.

Once multiplication is forced on representatives, its algebraic laws have no remaining freedom: each one is the pointwise lift of the corresponding rational law. The witness pattern is

again uniform, with threshold $N = 0$, the rational identity at stage n, and immediate elimination of the induced distance by $\mathrm{dist}\mathbb{Q}$-$\simeq 0$.

Constraint: Every multiplicative law must hold up to $\simeq_{\mathbb{R}}$ so that the ring structure descends to the Cauchy quotient.

Construction: For each law, the Cauchy threshold collapses to $N = 0$: the corresponding rational identity eliminates all distance between the two sides at every index, and $\mathrm{dist}\mathbb{Q}$-$\simeq 0$ closes the gap. No alternative threshold or identity survives.

Consequence: Commutativity, associativity, identity, and distributivity are forced. Together with the additive group, the reals are a commutative ring—the minimal structure that can host the spectral constants.

```
-- § Commutativity of real multiplication
·ℝ-comm : (x y : ℝ) → (x ·ℝ y) ≃ℝ (y ·ℝ x)
·ℝ-comm x y = record
 { conv0 = λ ϵ ϵpos →
   zero , (λ n _ →
    let
     p : ℚ
     p = (seq x n) *ℚ (seq y n)

     q : ℚ
     q = (seq y n) *ℚ (seq x n)

     pq≃ : p ≃ℚ q
     pq≃ = *ℚ-comm (seq x n) (seq y n)

     d≃0 : distℚ p q ≃ℚ 0ℚ
     d≃0 = distℚ-≃0 pq≃

     d≤0 : distℚ p q ≤ℚ 0ℚ
     d≤0 = ≃ℚ→≤ℚˡ {distℚ p q} {0ℚ} d≃0
    in
    ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
 }

-- § Associativity of real multiplication
·ℝ-assoc : (x y z : ℝ) → ((x ·ℝ y) ·ℝ z) ≃ℝ (x ·ℝ (y ·ℝ z))
·ℝ-assoc x y z = record
 { conv0 = λ ϵ ϵpos →
   zero , (λ n _ →
    let
     p : ℚ
     p = ((seq x n) *ℚ (seq y n)) *ℚ (seq z n)

     q : ℚ
     q = (seq x n) *ℚ ((seq y n) *ℚ (seq z n))

     pq≃ : p ≃ℚ q
     pq≃ = *ℚ-assoc (seq x n) (seq y n) (seq z n)

     d≃0 : distℚ p q ≃ℚ 0ℚ
     d≃0 = distℚ-≃0 pq≃

     d≤0 : distℚ p q ≤ℚ 0ℚ
     d≤0 = ≃ℚ→≤ℚˡ {distℚ p q} {0ℚ} d≃0
    in
    ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
```

```
}

-- § Right multiplicative identity
·ℝ-one-right : (x : ℝ) → (x ·ℝ 1ℝ) ≃ℝ x
·ℝ-one-right x = record
 { conv0 = λ ϵ ϵpos →
   zero , (λ n _ →
    let
     p : ℚ
     p = (seq x n) *ℚ 1ℚ

     q : ℚ
     q = seq x n

     pq≃ : p ≃ℚ q
     pq≃ = *ℚ-one-right (seq x n)

     d≃0 : distℚ p q ≃ℚ 0ℚ
     d≃0 = distℚ-≃0 pq≃

     d≤0 : distℚ p q ≤ℚ 0ℚ
     d≤0 = ≃ℚ→≤ℚ^l {distℚ p q} {0ℚ} d≃0
    in
    ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
 }

-- § Left multiplicative identity
·ℝ-one-left : (x : ℝ) → (1ℝ ·ℝ x) ≃ℝ x
·ℝ-one-left x = record
 { conv0 = λ ϵ ϵpos →
   zero , (λ n _ →
    let
     p : ℚ
     p = 1ℚ *ℚ (seq x n)

     q : ℚ
     q = seq x n

     pq≃ : p ≃ℚ q
     pq≃ = *ℚ-one-left (seq x n)

     d≃0 : distℚ p q ≃ℚ 0ℚ
     d≃0 = distℚ-≃0 pq≃

     d≤0 : distℚ p q ≤ℚ 0ℚ
     d≤0 = ≃ℚ→≤ℚ^l {distℚ p q} {0ℚ} d≃0
    in
    ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
 }
```

Step 2: Absorption and Distributivity. Zero absorption on both sides and distributivity of $\cdot_{\mathbb{R}}$ over $+_{\mathbb{R}}$ are forced by the corresponding rational laws lifted through Cauchy convergence.

```
-- § Left absorption by zero
·ℝ-zero-left : (x : ℝ) → (0ℝ ·ℝ x) ≃ℝ 0ℝ
·ℝ-zero-left x = record
 { conv0 = λ ϵ ϵpos →
   zero , (λ n _ →
    let
     p : ℚ
```

```
    p = 0ℚ *ℚ (seq x n)

    q : ℚ
    q = 0ℚ

    pq≃ : p ≃ℚ q
    pq≃ = *ℚ-zero-left (seq x n)

    d≃0 : distℚ p q ≃ℚ 0ℚ
    d≃0 = distℚ-≃0 pq≃

    d≤0 : distℚ p q ≤ℚ 0ℚ
    d≤0 = ≃ℚ→≤ℚ^l {distℚ p q} {0ℚ} d≃0
   in
   ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
}

– § Right absorption by zero
·ℝ-zero-right : (x : ℝ) → (x ·ℝ 0ℝ) ≃ℝ 0ℝ
·ℝ-zero-right x = record
{ conv0 = λ ϵ ϵpos →
  zero , (λ n _ →
   let
    p : ℚ
    p = (seq x n) *ℚ 0ℚ

    q : ℚ
    q = 0ℚ

    pq≃ : p ≃ℚ q
    pq≃ = *ℚ-zero-right (seq x n)

    d≃0 : distℚ p q ≃ℚ 0ℚ
    d≃0 = distℚ-≃0 pq≃

    d≤0 : distℚ p q ≤ℚ 0ℚ
    d≤0 = ≃ℚ→≤ℚ^l {distℚ p q} {0ℚ} d≃0
   in
   ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
}

– § Right distributivity of multiplication over addition
·ℝ-distrib-right-+ℝ : (x y z : ℝ) → (x ·ℝ (y +ℝ z)) ≃ℝ ((x ·ℝ y) +ℝ (x ·ℝ z))
·ℝ-distrib-right-+ℝ x y z = record
{ conv0 = λ ϵ ϵpos →
  zero , (λ n _ →
   let
    p : ℚ
    p = (seq x n) *ℚ ((seq y n) +ℚ (seq z n))

    q : ℚ
    q = ((seq x n) *ℚ (seq y n)) +ℚ ((seq x n) *ℚ (seq z n))

    pq≃ : p ≃ℚ q
    pq≃ = *ℚ-distrib-right-+ℚ (seq x n) (seq y n) (seq z n)

    d≃0 : distℚ p q ≃ℚ 0ℚ
    d≃0 = distℚ-≃0 pq≃

    d≤0 : distℚ p q ≤ℚ 0ℚ
    d≤0 = ≃ℚ→≤ℚ^l {distℚ p q} {0ℚ} d≃0
   in
```

```
    ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
  }

– § Left distributivity of multiplication over addition
·ℝ-distrib-left-+ℝ : (x y z : ℝ) → ((x +ℝ y) ·ℝ z) ≃ℝ ((x ·ℝ z) +ℝ (y ·ℝ z))
·ℝ-distrib-left-+ℝ x y z = record
  { conv0 = λ ϵ ϵpos →
    zero , (λ n _ →
     let
      p : ℚ
      p = ((seq x n) +ℚ (seq y n)) *ℚ (seq z n)

      q : ℚ
      q = ((seq x n) *ℚ (seq z n)) +ℚ ((seq y n) *ℚ (seq z n))

      pq≃ : p ≃ℚ q
      pq≃ = *ℚ-distrib-left-+ℚ (seq x n) (seq y n) (seq z n)

      d≃0 : distℚ p q ≃ℚ 0ℚ
      d≃0 = distℚ-≃0 pq≃

      d≤0 : distℚ p q ≤ℚ 0ℚ
      d≤0 = ≃ℚ→≤ℚˡ {distℚ p q} {0ℚ} d≃0
     in
     ≤<ℚ→<ℚ {distℚ p q} {0ℚ} {ϵ} d≤0 ϵpos)
  }
```

Congruence of multiplication and addition

A ring whose operations depend on the choice of representative is no ring at all: congruence is the bridge that turns operations on Cauchy sequences into operations on reals. Without it, the field structure collapses back to raw sequence manipulation, and the spectral constants would vary with the representative chosen—an inadmissible catastrophe.

Congruence removes the last representative dependence: addition and multiplication are admissible on reals only if equivalent Cauchy data are sent to equivalent results. Addition follows the already forced additive control, while multiplication repeats the product decomposition with mixed representatives and uses eventual bounds plus δ-scaling to eliminate both error terms.

Constraint: Both operations must map $\simeq_{\mathbb{R}}$-equivalent inputs to $\simeq_{\mathbb{R}}$-equivalent outputs, or the quotient construction fails.

Construction: For addition, triangle-inequality elimination suffices. For multiplication, decompose the product difference via the identity $xz - x'z' = x(z - z') + (x - x')z'$, then scale each summand by an eventual bound from texttIsCauchy-eventually-bounded. Any operation that fails this decomposition is excluded from the quotient.

Consequence: Addition and multiplication are well-defined on the Cauchy quotient. The reals now form a genuine commutative ring, not merely a ring of sequences.

```
– § Multiplication respects ≃ℝ
·ℝ-resp-≃ℝ : {x x' y y' : ℝ} → x ≃ℝ x' → y ≃ℝ y' → (x ·ℝ y) ≃ℝ (x' ·ℝ y')
·ℝ-resp-≃ℝ {x} {x'} {y} {y'} x≃x' y≃y' = record
```

```
{ conv0 = λ ϵ ϵpos →
  let
    -- § Phase 1: Budget allocation
    ϵq : ℚ
    ϵq = ϵQuarter ϵ

    ϵqPos : 0ℚ <ℚ ϵq
    ϵqPos = ϵQuarter-pos ϵ

    ϵqNonneg : 0ℚ ≤ℚ ϵq
    ϵqNonneg = <ℚ→≤ℚ {0ℚ} {ϵq} ϵqPos

    ϵq+ϵq<ϵ : (ϵq +ℚ ϵq) <ℚ ϵ
    ϵq+ϵq<ϵ = ϵQuarter-double<ϵ ϵ ϵpos

    -- § Phase 2: Eventual bounds on y and x'
    byPack : Σ ℕ (λ N → Σ ℚ (λ B → (n : ℕ) → N ≤ n → distℚ (seq y n) 0ℚ ≤ℚ B))
    byPack = IsCauchy-eventually-bounded (seq y) (isCauchy y)

    bx'Pack : Σ ℕ (λ N → Σ ℚ (λ B → (n : ℕ) → N ≤ n → distℚ (seq x' n) 0ℚ ≤ℚ B))
    bx'Pack = IsCauchy-eventually-bounded (seq x') (isCauchy x')

    Ny0 : ℕ
    Ny0 = fst byPack

    By : ℚ
    By = fst (snd byPack)

    ByBound : (n : ℕ) → Ny0 ≤ n → distℚ (seq y n) 0ℚ ≤ℚ By
    ByBound = snd (snd byPack)

    Nx'0 : ℕ
    Nx'0 = fst bx'Pack

    Bx' : ℚ
    Bx' = fst (snd bx'Pack)

    Bx'Bound : (n : ℕ) → Nx'0 ≤ n → distℚ (seq x' n) 0ℚ ≤ℚ Bx'
    Bx'Bound = snd (snd bx'Pack)

    ByNonneg : 0ℚ ≤ℚ By
    ByNonneg =
     ≤ℚ-trans {0ℚ} {distℚ (seq y Ny0) 0ℚ} {By}
      (distℚ-nonneg (seq y Ny0) 0ℚ)
      (ByBound Ny0 (≤-refl Ny0))

    Bx'Nonneg : 0ℚ ≤ℚ Bx'
    Bx'Nonneg =
     ≤ℚ-trans {0ℚ} {distℚ (seq x' Nx'0) 0ℚ} {Bx'}
      (distℚ-nonneg (seq x' Nx'0) 0ℚ)
      (Bx'Bound Nx'0 (≤-refl Nx'0))

    -- § Phase 3: Integer ceiling bounds and δ-scaling
    mYPack : Σ ℕ (λ m → By ≤ℚ (fromℕℤ (suc m) / one⁺))
    mYPack = nonneg-bound-sucInt By ByNonneg

    mX'Pack : Σ ℕ (λ m → Bx' ≤ℚ (fromℕℤ (suc m) / one⁺))
    mX'Pack = nonneg-bound-sucInt Bx' Bx'Nonneg

    mY : ℕ
    mY = fst mYPack
```

```
KY : ℚ
KY = fromℕℤ (suc mY) / one⁺

By≤KY : By ≤ℚ KY
By≤KY = snd mYPack

mX' : ℕ
mX' = fst mX'Pack

KX' : ℚ
KX' = fromℕℤ (suc mX') / one⁺

Bx'≤KX' : Bx' ≤ℚ KX'
Bx'≤KX' = snd mX'Pack

δxPack : Σ ℚ (λ δ → (0ℚ <ℚ δ) × ((δ *ℚ KY) <ℚ ϵq))
δxPack = δ-scale-suc ϵq ϵqPos mY

δyPack : Σ ℚ (λ δ → (0ℚ <ℚ δ) × ((δ *ℚ KX') <ℚ ϵq))
δyPack = δ-scale-suc ϵq ϵqPos mX'

δx : ℚ
δx = fst δxPack

δxPos : 0ℚ <ℚ δx
δxPos = fst (snd δxPack)

δxNonneg : 0ℚ ≤ℚ δx
δxNonneg = <ℚ→≤ℚ {0ℚ} {δx} δxPos

δxKY<ϵq : (δx *ℚ KY) <ℚ ϵq
δxKY<ϵq = snd (snd δxPack)

δy : ℚ
δy = fst δyPack

δyPos : 0ℚ <ℚ δy
δyPos = fst (snd δyPack)

δyNonneg : 0ℚ ≤ℚ δy
δyNonneg = <ℚ→≤ℚ {0ℚ} {δy} δyPos

δyKX'<ϵq : (δy *ℚ KX') <ℚ ϵq
δyKX'<ϵq = snd (snd δyPack)

NxPack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → distℚ (seq x n) (seq x' n) <ℚ δx)
NxPack = _≃ℝ_.conv0 x≃x' δx δxPos

NyPack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → distℚ (seq y n) (seq y' n) <ℚ δy)
NyPack = _≃ℝ_.conv0 y≃y' δy δyPos

Nx : ℕ
Nx = fst NxPack

Ny : ℕ
Ny = fst NyPack

NxConv : (n : ℕ) → Nx ≤ n → distℚ (seq x n) (seq x' n) <ℚ δx
NxConv = snd NxPack

NyConv : (n : ℕ) → Ny ≤ n → distℚ (seq y n) (seq y' n) <ℚ δy
NyConv = snd NyPack
```

```
– § Phase 4: Global modulus N
N : ℕ
N = ((Nx +ℕ Ny) +ℕ Ny0) +ℕ Nx'0

≤-self+ℕ : (m n : ℕ) → m ≤ (m +ℕ n)
≤-self+ℕ m n =
 let
  mono : (m +ℕ zero) ≤ (m +ℕ n)
  mono = ≤-+ℕ-mono^l {a = zero} {b = n} z≤n m
 in
 subst (λ t → t ≤ (m +ℕ n)) (+ℕ-zero-right m) mono

Nx≤N : Nx ≤ N
Nx≤N =
 let
  step₁ : Nx ≤ (Nx +ℕ Ny)
  step₁ =
   let
    mono : (Nx +ℕ zero) ≤ (Nx +ℕ Ny)
    mono = ≤-+ℕ-mono^l {a = zero} {b = Ny} z≤n Nx
   in
   subst (λ t → t ≤ (Nx +ℕ Ny)) (+ℕ-zero-right Nx) mono

  step₂ : (Nx +ℕ Ny) ≤ N
  step₂ =
   ≤-trans
    (≤-self+ℕ (Nx +ℕ Ny) Ny0)
    (≤-self+ℕ ((Nx +ℕ Ny) +ℕ Ny0) Nx'0)
 in
 ≤-trans step₁ step₂

Ny≤N : Ny ≤ N
Ny≤N =
 let
  step₁ : Ny ≤ (Nx +ℕ Ny)
  step₁ =
   let
    mono : (Ny +ℕ zero) ≤ (Ny +ℕ Nx)
    mono = ≤-+ℕ-mono^l {a = zero} {b = Nx} z≤n Ny

    base : Ny ≤ (Ny +ℕ Nx)
    base = subst (λ t → t ≤ (Ny +ℕ Nx)) (+ℕ-zero-right Ny) mono
   in
   subst (λ t → Ny ≤ t) (+ℕ-comm Ny Nx) base

  step₂ : (Nx +ℕ Ny) ≤ N
  step₂ =
   ≤-trans
    (≤-self+ℕ (Nx +ℕ Ny) Ny0)
    (≤-self+ℕ ((Nx +ℕ Ny) +ℕ Ny0) Nx'0)
 in
 ≤-trans step₁ step₂

Ny0≤N : Ny0 ≤ N
Ny0≤N =
 let
  step₁ : Ny0 ≤ ((Nx +ℕ Ny) +ℕ Ny0)
  step₁ =
   subst (λ t → Ny0 ≤ t) (+ℕ-comm Ny0 (Nx +ℕ Ny)) (≤-self+ℕ Ny0 (Nx +ℕ Ny))

  step₂ : ((Nx +ℕ Ny) +ℕ Ny0) ≤ N
  step₂ = ≤-self+ℕ ((Nx +ℕ Ny) +ℕ Ny0) Nx'0
```

```
    in
    ≤-trans step₁ step₂

   Nx'0≤N : Nx'0 ≤ N
   Nx'0≤N =
    let
     base : Nx'0 ≤ (Nx'0 +ℕ ((Nx +ℕ Ny) +ℕ Ny0))
     base = ≤-self+ℕ Nx'0 (((Nx +ℕ Ny) +ℕ Ny0))
    in
    subst (λ t → Nx'0 ≤ t) (+ℕ-comm Nx'0 (((Nx +ℕ Ny) +ℕ Ny0))) base
in
N , (λ n N≤n →
   let
    Nx≤n : Nx ≤ n
    Nx≤n = ≤-trans Nx≤N N≤n

    Ny≤n : Ny ≤ n
    Ny≤n = ≤-trans Ny≤N N≤n

    Ny0≤n : Ny0 ≤ n
    Ny0≤n = ≤-trans Ny0≤N N≤n

    Nx'0≤n : Nx'0 ≤ n
    Nx'0≤n = ≤-trans Nx'0≤N N≤n

    xn : ℚ
    xn = seq x n

    x'n : ℚ
    x'n = seq x' n

    yn : ℚ
    yn = seq y n

    y'n : ℚ
    y'n = seq y' n

    dxx' : ℚ
    dxx' = distℚ xn x'n

    dyy' : ℚ
    dyy' = distℚ yn y'n

    Iy : ℚ
    Iy = distℚ yn 0ℚ

    Ix' : ℚ
    Ix' = distℚ x'n 0ℚ

    dxx'<δx : dxx' <ℚ δx
    dxx'<δx = NxConv n Nx≤n

    dyy'<δy : dyy' <ℚ δy
    dyy'<δy = NyConv n Ny≤n

    Iy≤By : Iy ≤ℚ By
    Iy≤By = ByBound n Ny0≤n

    Ix'≤Bx' : Ix' ≤ℚ Bx'
    Ix'≤Bx' = Bx'Bound n Nx'0≤n

    IyNonneg : 0ℚ ≤ℚ Iy
```

```
IyNonneg = distℚ-nonneg yn 0ℚ

Ix'Nonneg : 0ℚ ≤ℚ Ix'
Ix'Nonneg = distℚ-nonneg x'n 0ℚ

– § Phase 6: Product decomposition via midpoint x'·y
dxx'≤δx : dxx' ≤ℚ δx
dxx'≤δx = <ℚ→≤ℚ {dxx'} {δx} dxx'<δx

dyy'≤δy : dyy' ≤ℚ δy
dyy'≤δy = <ℚ→≤ℚ {dyy'} {δy} dyy'<δy

Iy≤KY : Iy ≤ℚ KY
Iy≤KY = ≤ℚ-trans {Iy} {By} {KY} Iy≤By By≤KY

Ix'≤KX' : Ix' ≤ℚ KX'
Ix'≤KX' = ≤ℚ-trans {Ix'} {Bx'} {KX'} Ix'≤Bx' Bx'≤KX'

d1 : ℚ
d1 = distℚ (xn *ℚ yn) (x'n *ℚ yn)

d2 : ℚ
d2 = distℚ (x'n *ℚ yn) (x'n *ℚ y'n)

d1Nonneg : 0ℚ ≤ℚ d1
d1Nonneg = distℚ-nonneg (xn *ℚ yn) (x'n *ℚ yn)

d2Nonneg : 0ℚ ≤ℚ d2
d2Nonneg = distℚ-nonneg (x'n *ℚ yn) (x'n *ℚ y'n)

d1≤scaled : d1 ≤ℚ (dxx' *ℚ Iy)
d1≤scaled = ≃ℚ→≤ℚˡ {d1} {(dxx' *ℚ Iy)} (distℚ-*ℚ-right yn xn x'n)

d2≤scaled : d2 ≤ℚ (dyy' *ℚ Ix')
d2≤scaled = ≃ℚ→≤ℚˡ {d2} {(dyy' *ℚ Ix')} (distℚ-*ℚ-left x'n yn y'n)

step1 : (dxx' *ℚ Iy) ≤ℚ (δx *ℚ Iy)
step1 = ≤ℚ-mul-nonneg-right dxx' δx Iy dxx'≤δx IyNonneg

step2 : (δx *ℚ Iy) ≤ℚ (δx *ℚ KY)
step2 = ≤ℚ-mul-nonneg-left Iy KY δx Iy≤KY δxNonneg

scaled1≤ : (dxx' *ℚ Iy) ≤ℚ (δx *ℚ KY)
scaled1≤ = ≤ℚ-trans {(dxx' *ℚ Iy)} {(δx *ℚ Iy)} {(δx *ℚ KY)} step1 step2

scaled1<ϵq : (dxx' *ℚ Iy) <ℚ ϵq
scaled1<ϵq = ≤<ℚ→<ℚ {(dxx' *ℚ Iy)} {(δx *ℚ KY)} {ϵq} scaled1≤ δxKY<ϵq

d1<ϵq : d1 <ℚ ϵq
d1<ϵq = ≤<ℚ→<ℚ {d1} {(δx *ℚ KY)} {ϵq} (≤ℚ-trans {d1} {(dxx' *ℚ Iy)} {(δx *ℚ KY)} d1≤scaled (≤ℚ-trans {(dxx' *ℚ Iy)} {(δx *ℚ Iy)} {(δx *ℚ KY)} step1 s

step1' : (dyy' *ℚ Ix') ≤ℚ (δy *ℚ Ix')
step1' = ≤ℚ-mul-nonneg-right dyy' δy Ix' dyy'≤δy Ix'Nonneg

step2' : (δy *ℚ Ix') ≤ℚ (δy *ℚ KX')
step2' = ≤ℚ-mul-nonneg-left Ix' KX' δy Ix'≤KX' δyNonneg

scaled2≤ : (dyy' *ℚ Ix') ≤ℚ (δy *ℚ KX')
scaled2≤ = ≤ℚ-trans {(dyy' *ℚ Ix')} {(δy *ℚ Ix')} {(δy *ℚ KX')} step1' step2'

scaled2<ϵq : (dyy' *ℚ Ix') <ℚ ϵq
scaled2<ϵq = ≤<ℚ→<ℚ {(dyy' *ℚ Ix')} {(δy *ℚ KX')} {ϵq} scaled2≤ δyKX'<ϵq
```

```
      d2<εq : d2 <ℚ εq
      d2<εq = ≤<ℚ→<ℚ {d2} {(dyy' *ℚ Ix')} {εq} d2≤scaled scaled2<εq

      d1≤εq : d1 ≤ℚ εq
      d1≤εq = <ℚ→≤ℚ {d1} {εq} d1<εq

      d2≤εq : d2 ≤ℚ εq
      d2≤εq = <ℚ→≤ℚ {d2} {εq} d2<εq

      sum≤ : (d1 +ℚ d2) ≤ℚ (εq +ℚ εq)
      sum≤ = ≤ℚ-sum≤double-nonneg d1 d2 εq d1Nonneg d2Nonneg εqNonneg d1≤εq d2≤εq

      sum<ε : (d1 +ℚ d2) <ℚ ε
      sum<ε =
       ≤<ℚ→<ℚ {(d1 +ℚ d2)} {(εq +ℚ εq)} {ε}
        sum≤ εq+εq<ε

      tri : distℚ (xn *ℚ yn) (x'n *ℚ y'n) ≤ℚ (d1 +ℚ d2)
      tri = distℚ-triangle (xn *ℚ yn) (x'n *ℚ yn) (x'n *ℚ y'n)
     in
     ≤<ℚ→<ℚ {distℚ (xn *ℚ yn) (x'n *ℚ y'n)} {(d1 +ℚ d2)} {ε}
      tri sum<ε)
}
```

Step 2: Additive Congruence. Addition is simpler: no eventual bounds are needed, only $\varepsilon/4$-convergence in both sequences. The triangle inequality then closes the argument directly.

```
– § Addition respects ≃ℝ
+ℝ-resp-≃ℝ :
 {x x' y y' : ℝ} →
 x ≃ℝ x' →
 y ≃ℝ y' →
 (x +ℝ y) ≃ℝ (x' +ℝ y')
+ℝ-resp-≃ℝ {x} {x'} {y} {y'} x≃x' y≃y' = record
 { conv0 = λ ε εpos →
   let
     – § Phase 1: Budget allocation
     εq : ℚ
     εq = εQuarter ε

     εqPos : 0ℚ <ℚ εq
     εqPos = εQuarter-pos ε

     εqNonneg : 0ℚ ≤ℚ εq
     εqNonneg = <ℚ→≤ℚ {0ℚ} {εq} εqPos

     εq+εq<ε : (εq +ℚ εq) <ℚ ε
     εq+εq<ε = εQuarter-double<ε ε εpos

     NxPack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → distℚ (seq x n) (seq x' n) <ℚ εq)
     NxPack = _≃ℝ_.conv0 x≃x' εq εqPos

     NyPack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → distℚ (seq y n) (seq y' n) <ℚ εq)
     NyPack = _≃ℝ_.conv0 y≃y' εq εqPos

     Nx : ℕ
     Nx = fst NxPack

     Ny : ℕ
     Ny = fst NyPack
```

```
    NxConv : (n : ℕ) → Nx ≤ n → distℚ (seq x n) (seq x' n) <ℚ ϵq
    NxConv = snd NxPack

    NyConv : (n : ℕ) → Ny ≤ n → distℚ (seq y n) (seq y' n) <ℚ ϵq
    NyConv = snd NyPack

    -- Phase 2: Global modulus N ------------------------------
    N : ℕ
    N = Nx +ℕ Ny

    Nx≤N : Nx ≤ N
    Nx≤N =
     let
      mono : (Nx +ℕ zero) ≤ (Nx +ℕ Ny)
      mono = ≤-+ℕ-mono^l {a = zero} {b = Ny} z≤n Nx
     in
     subst (λ t → t ≤ (Nx +ℕ Ny)) (+ℕ-zero-right Nx) mono

    Ny≤N : Ny ≤ N
    Ny≤N =
     let
      mono : (Ny +ℕ zero) ≤ (Ny +ℕ Nx)
      mono = ≤-+ℕ-mono^l {a = zero} {b = Nx} z≤n Ny

      base : Ny ≤ (Ny +ℕ Nx)
      base = subst (λ t → t ≤ (Ny +ℕ Nx)) (+ℕ-zero-right Ny) mono
     in
     subst (λ t → Ny ≤ t) (+ℕ-comm Ny Nx) base
  in
  N , (λ n N≤n →
    let
     -- § Phase 3: Triangle inequality on sums
     Nx≤n : Nx ≤ n
     Nx≤n = ≤-trans Nx≤N N≤n

     Ny≤n : Ny ≤ n
     Ny≤n = ≤-trans Ny≤N N≤n

     xn : ℚ
     xn = seq x n

     x'n : ℚ
     x'n = seq x' n

     yn : ℚ
     yn = seq y n

     y'n : ℚ
     y'n = seq y' n

     dx : ℚ
     dx = distℚ xn x'n

     dy : ℚ
     dy = distℚ yn y'n

     dx<ϵq : dx <ℚ ϵq
     dx<ϵq = NxConv n Nx≤n

     dy<ϵq : dy <ℚ ϵq
     dy<ϵq = NyConv n Ny≤n
```

```
      d1 : ℚ
      d1 = distℚ (xn +ℚ yn) (x'n +ℚ yn)

      d2 : ℚ
      d2 = distℚ (x'n +ℚ yn) (x'n +ℚ y'n)

      d1Nonneg : 0ℚ ≤ℚ d1
      d1Nonneg = distℚ-nonneg (xn +ℚ yn) (x'n +ℚ yn)

      d2Nonneg : 0ℚ ≤ℚ d2
      d2Nonneg = distℚ-nonneg (x'n +ℚ yn) (x'n +ℚ y'n)

      d1≤dx : d1 ≤ℚ dx
      d1≤dx = ≃ℚ→≤ℚˡ {d1} {dx} (distℚ-+ℚ-right xn x'n yn)

      d2≤dy : d2 ≤ℚ dy
      d2≤dy = ≃ℚ→≤ℚˡ {d2} {dy} (distℚ-+ℚ-left x'n yn y'n)

      d1<ϵq : d1 <ℚ ϵq
      d1<ϵq = ≤<ℚ→<ℚ {d1} {dx} {ϵq} d1≤dx dx<ϵq

      d2<ϵq : d2 <ℚ ϵq
      d2<ϵq = ≤<ℚ→<ℚ {d2} {dy} {ϵq} d2≤dy dy<ϵq

      d1≤ϵq : d1 ≤ℚ ϵq
      d1≤ϵq = <ℚ→≤ℚ {d1} {ϵq} d1<ϵq

      d2≤ϵq : d2 ≤ℚ ϵq
      d2≤ϵq = <ℚ→≤ℚ {d2} {ϵq} d2<ϵq

      sum≤ : (d1 +ℚ d2) ≤ℚ (ϵq +ℚ ϵq)
      sum≤ = ≤ℚ-sum≤double-nonneg d1 d2 ϵq d1Nonneg d2Nonneg ϵqNonneg d1≤ϵq d2≤ϵq

      sum<ϵ : (d1 +ℚ d2) <ℚ ϵ
      sum<ϵ = ≤<ℚ→<ℚ {(d1 +ℚ d2)} {(ϵq +ℚ ϵq)} {ϵ} sum≤ ϵq+ϵq<ϵ

      tri : distℚ (xn +ℚ yn) (x'n +ℚ y'n) ≤ℚ (d1 +ℚ d2)
      tri = distℚ-triangle (xn +ℚ yn) (x'n +ℚ yn) (x'n +ℚ y'n)
    in
    ≤<ℚ→<ℚ {distℚ (xn +ℚ yn) (x'n +ℚ y'n)} {(d1 +ℚ d2)} {ϵ} tri sum<ϵ)
}
```

Step 3: Negation and Subtraction Congruence. Negation preserves distance by distℚ-neg, and subtraction combines additive and negation congruence.

```
– § Negation respects ≃ℝ
-ℝ-resp-≃ℝ : {x x' : ℝ} → x ≃ℝ x' → (-ℝ x) ≃ℝ (-ℝ x')
-ℝ-resp-≃ℝ {x} {x'} x≃x' = record
 { conv0 = λ ϵ ϵpos →
   let
    NxPack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → distℚ (seq x n) (seq x' n) <ℚ ϵ)
    NxPack = _≃ℝ_.conv0 x≃x' ϵ ϵpos

    Nx : ℕ
    Nx = fst NxPack

    NxConv : (n : ℕ) → Nx ≤ n → distℚ (seq x n) (seq x' n) <ℚ ϵ
    NxConv = snd NxPack
   in
```

```
  Nx , (λ n Nx≤n →
   let
    xn : ℚ
    xn = seq x n

    x'n : ℚ
    x'n = seq x' n

    d<ϵ : distℚ xn x'n <ℚ ϵ
    d<ϵ = NxConv n Nx≤n

    negEq : distℚ (-ℚ xn) (-ℚ x'n) ≃ℚ distℚ xn x'n
    negEq = distℚ-neg xn x'n

    d≤ : distℚ (-ℚ xn) (-ℚ x'n) ≤ℚ distℚ xn x'n
    d≤ = ≃ℚ→≤ℚˡ {distℚ (-ℚ xn) (-ℚ x'n)} {distℚ xn x'n} negEq
   in
   ≤<ℚ→<ℚ {distℚ (-ℚ xn) (-ℚ x'n)} {distℚ xn x'n} {ϵ} d≤ d<ϵ)
}

– § Subtraction respects ≃ℝ (derived from + and -)
-ℝ-resp-≃ℝ₂ : {x x' y y' : ℝ} → x ≃ℝ x' → y ≃ℝ y' → (x -ℝ y) ≃ℝ (x' -ℝ y')
-ℝ-resp-≃ℝ₂ {x} {x'} {y} {y'} x≃x' y≃y' =
 +ℝ-resp-≃ℝ x≃x' (-ℝ-resp-≃ℝ y≃y')
```

Asymptotic Order on ℝ

A field without order cannot host inequalities, and inequalities are the language of the invariant chain: every bound, every spectral gap, every convergence statement is an order statement. But reals are equivalence classes of Cauchy sequences, and finite-prefix comparisons do not survive the passage to the quotient. The only order that does survive is asymptotic: a comparison that holds on every tail, for every positive margin.

Order on $\mathbb{R}$ is forced to be asymptotic: finite prefixes cannot survive quotient formation, so only eventual rational comparison with arbitrary positive margins remains admissible. The unique strict and non-strict order notions compatible with representative elimination under $\simeq_{\mathbb{R}}$ are fixed below.

Constraint: Order must be compatible with the Cauchy quotient: if $x \simeq_{\mathbb{R}} x'$ and $x \leq_{\mathbb{R}} y$, then $x' \leq_{\mathbb{R}} y$. Any order depending on a finite prefix is shattered by re-choosing the representative.

Construction: Any order definition depending on a finite prefix is shattered by re-choosing the representative. The only surviving definitions are: $x \leq_{\mathbb{R}} y$ iff for every $\varepsilon > 0$ there exists N such that $x_n \leq y_n + \varepsilon$ for all $n \geq N$; and $x <_{\mathbb{R}} y$ iff there exists $\varepsilon > 0$ with the same tail comparison. Every prefix-dependent alternative is eliminated.

Consequence: Twelve order laws are forced—reflexivity, transitivity, antisymmetry, congruence under $\simeq_{\mathbb{R}}$, and additive monotonicity—closing the ordered-field scaffold required by the spectral constants.

Law 23.1: Non-strict asymptotic order

Non-strict order is forced by eventual ε-comparison for every positive rational margin. Any weaker condition leaves room for prefix dependence, and that dependence is already excluded by the quotient from Cauchy representatives to reals.

```
-- § Non-strict real order: eventual ϵ-approximation
infix 4 _≤ℝ_ _<ℝ_

record _≤ℝ_ (x y : ℝ) : Set where
 field
  leReal : (ϵ : ℚ) → (0ℚ <ℚ ϵ) → Σ ℕ (λ N → (n : ℕ) → N ≤ n → (seq x n) ≤ℚ ((seq y n) +ℚ ϵ))

-- § Type alias for non-strict real order
≤ℝP : ℝ → ℝ → Set
≤ℝP = _≤ℝ_
```

Law 23.2: Strict asymptotic order

Strict order is forced by a positive rational witness that survives on a tail. This eliminates vanishing separation and fixes strictness as stable asymptotic margin rather than finite-stage fluctuation.

```
-- § Strict real order: witnessed separation
record _<ℝ_ (x y : ℝ) : Set where
 field
  ltWitness : Σ ℚ (λ ϵ → (0ℚ <ℚ ϵ) × Σ ℕ (λ N → (n : ℕ) → N ≤ n → ((seq x n) +ℚ ϵ) ≤ℚ (seq y n)))
```

Law 23.3: Strict order forces non-strict order

Every strict witness forces non-strict order once the positive gap is forgotten after it has done its work. The margin survives only as an intermediate constraint and is then eliminated from the final asymptotic comparison.

```
-- § Strict order implies non-strict by forgetting the margin
<ℝ→≤ℝ : {x y : ℝ} → x <ℝ y → x ≤ℝ y
<ℝ→≤ℝ {x} {y} x<y = record
 { leReal = λ δ δpos →
   let
     w : Σ ℚ (λ ϵ → (0ℚ <ℚ ϵ) × Σ ℕ (λ N → (n : ℕ) → N ≤ n → ((seq x n) +ℚ ϵ) ≤ℚ (seq y n)))
     w = _<ℝ_.ltWitness x<y

     ϵ : ℚ
     ϵ = fst w

     wRest : (0ℚ <ℚ ϵ) × Σ ℕ (λ N → (n : ℕ) → N ≤ n → ((seq x n) +ℚ ϵ) ≤ℚ (seq y n))
     wRest = snd w

     ϵpos : 0ℚ <ℚ ϵ
     ϵpos = fst wRest

     pack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → ((seq x n) +ℚ ϵ) ≤ℚ (seq y n))
     pack = snd wRest

     N : ℕ
```

```
      N = fst pack

      conv : (n : ℕ) → N ≤ n → ((seq x n) +ℚ ϵ) ≤ℚ (seq y n)
      conv = snd pack
    in
    N , (λ n N≤n →
      let
       xn : ℚ
       xn = seq x n

       yn : ℚ
       yn = seq y n

       xn≤xn+ϵ : xn ≤ℚ (xn +ℚ ϵ)
       xn≤xn+ϵ = ≤ℚ-add-nonneg-right xn ϵ (<ℚ→≤ℚ ϵpos)

       xn+ϵ≤yn : (xn +ℚ ϵ) ≤ℚ yn
       xn+ϵ≤yn = conv n N≤n

       xn≤yn : xn ≤ℚ yn
       xn≤yn = ≤ℚ-trans {xn} {(xn +ℚ ϵ)} {yn} xn≤xn+ϵ xn+ϵ≤yn

       yn≤yn+δ : yn ≤ℚ (yn +ℚ δ)
       yn≤yn+δ = ≤ℚ-add-nonneg-right yn δ (<ℚ→≤ℚ δpos)
      in
      ≤ℚ-trans xn≤yn yn≤yn+δ)
  }
```

Law 23.4: Equivalence forces non-strict order

distance bounds eliminate any persistent asymptotic gap. The resulting Representative equivalence forces non-strict order because eventual distance bounds eliminate any persistent asymptotic gap. The resulting order law therefore remains invariant under replacement by an equivalent Cauchy representative.

```
  -- § Equivalence implies ≤ℝ
  ≃ℝ→≤ℝ : {x y : ℝ} → x ≃ℝ y → x ≤ℝ y
  ≃ℝ→≤ℝ {x} {y} x≃y = record
   { leReal = λ ϵ ϵpos →
     let
       pack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → distℚ (seq x n) (seq y n) <ℚ ϵ)
       pack = _≃ℝ_.conv0 x≃y ϵ ϵpos

       N : ℕ
       N = fst pack

       conv : (n : ℕ) → N ≤ n → distℚ (seq x n) (seq y n) <ℚ ϵ
       conv = snd pack
     in
     N , (λ n N≤n →
       distℚ≤ϵ→x≤y+ϵ (seq x n) (seq y n) ϵ (<ℚ→≤ℚ (conv n N≤n)))
   }
```

Transitivity of Strict Order

Strict asymptotic separation must compose whenever two positive margins occur in sequence. The remaining freedom that an intermediate witness could block composition is eliminated, forcing strict order to survive transitive chaining.

Law 23.5: Strict order is transitive

Witness margins compose after controlled shrinking. Quartering eliminates overflow in the combined error budget and forces one surviving positive margin for the composite comparison.

```
-- § Transitivity of strict real order
<ℝ-trans : {x y z : ℝ} → x <ℝ y → y <ℝ z → x <ℝ z
<ℝ-trans {x} {y} {z} x<y y<z = record
 { ltWitness =
   let
     -- § Phase 1: Unpack both strict-order witnesses
     wxy : Σ ℚ (λ ϵ → (0ℚ <ℚ ϵ) × Σ ℕ (λ N → (n : ℕ) → N ≤ n → ((seq x n) +ℚ ϵ) ≤ℚ (seq y n)))
     wxy = _<ℝ_.ltWitness x<y

     ϵ₁ : ℚ
     ϵ₁ = fst wxy

     wxyRest : (0ℚ <ℚ ϵ₁) × Σ ℕ (λ N → (n : ℕ) → N ≤ n → ((seq x n) +ℚ ϵ₁) ≤ℚ (seq y n))
     wxyRest = snd wxy

     ϵ₁pos : 0ℚ <ℚ ϵ₁
     ϵ₁pos = fst wxyRest

     packXY : Σ ℕ (λ N → (n : ℕ) → N ≤ n → ((seq x n) +ℚ ϵ₁) ≤ℚ (seq y n))
     packXY = snd wxyRest

     Nxy : ℕ
     Nxy = fst packXY

     convXY : (n : ℕ) → Nxy ≤ n → ((seq x n) +ℚ ϵ₁) ≤ℚ (seq y n)
     convXY = snd packXY

     wyz : Σ ℚ (λ ϵ → (0ℚ <ℚ ϵ) × Σ ℕ (λ N → (n : ℕ) → N ≤ n → ((seq y n) +ℚ ϵ) ≤ℚ (seq z n)))
     wyz = _<ℝ_.ltWitness y<z

     ϵ₂ : ℚ
     ϵ₂ = fst wyz

     wyzRest : (0ℚ <ℚ ϵ₂) × Σ ℕ (λ N → (n : ℕ) → N ≤ n → ((seq y n) +ℚ ϵ₂) ≤ℚ (seq z n))
     wyzRest = snd wyz

     ϵ₂pos : 0ℚ <ℚ ϵ₂
     ϵ₂pos = fst wyzRest

     packYZ : Σ ℕ (λ N → (n : ℕ) → N ≤ n → ((seq y n) +ℚ ϵ₂) ≤ℚ (seq z n))
     packYZ = snd wyzRest

     Nyz : ℕ
     Nyz = fst packYZ

     convYZ : (n : ℕ) → Nyz ≤ n → ((seq y n) +ℚ ϵ₂) ≤ℚ (seq z n)
     convYZ = snd packYZ

     -- § Phase 2: Shrink the surviving margin
     ϵ : ℚ
     ϵ = ϵQuarter ϵ₁

     ϵpos : 0ℚ <ℚ ϵ
     ϵpos = ϵQuarter-pos ϵ₁

     N : ℕ
     N = Nxy +ℕ Nyz
```

```
    Nxy≤N : Nxy ≤ N
    Nxy≤N =
     let
      mono : (Nxy +ℕ zero) ≤ (Nxy +ℕ Nyz)
      mono = ≤-+ℕ-mono^l {a = zero} {b = Nyz} z≤n Nxy
     in
     subst (λ t → t ≤ (Nxy +ℕ Nyz)) (+ℕ-zero-right Nxy) mono

    Nyz≤N : Nyz ≤ N
    Nyz≤N =
     let
      mono : (Nyz +ℕ zero) ≤ (Nyz +ℕ Nxy)
      mono = ≤-+ℕ-mono^l {a = zero} {b = Nxy} z≤n Nyz

      base : Nyz ≤ (Nyz +ℕ Nxy)
      base = subst (λ t → t ≤ (Nyz +ℕ Nxy)) (+ℕ-zero-right Nyz) mono
     in
     subst (λ t → Nyz ≤ t) (+ℕ-comm Nyz Nxy) base
  in
  ϵ , (ϵpos ,
    (N , (λ n N≤n →
     let
      -- § Phase 3: Chain the inequalities
      Nxy≤n : Nxy ≤ n
      Nxy≤n = ≤-trans Nxy≤N N≤n

      Nyz≤n : Nyz ≤ n
      Nyz≤n = ≤-trans Nyz≤N N≤n

      xn : ℚ
      xn = seq x n

      yn : ℚ
      yn = seq y n

      zn : ℚ
      zn = seq z n

      xϵ₁≤y : (xn +ℚ ϵ₁) ≤ℚ yn
      xϵ₁≤y = convXY n Nxy≤n

      xϵ≤xϵ₁ : (xn +ℚ ϵ) ≤ℚ (xn +ℚ ϵ₁)
      xϵ≤xϵ₁ =
       ≤ℚ-+ℚ-mono-left xn ϵ ϵ₁ (<ℚ→≤ℚ (ϵQuarter<ϵ ϵ₁ ϵ₁pos))

      xϵ≤y : (xn +ℚ ϵ) ≤ℚ yn
      xϵ≤y = ≤ℚ-trans {(xn +ℚ ϵ)} {(xn +ℚ ϵ₁)} {yn} xϵ≤xϵ₁ xϵ₁≤y

      y≤y+ϵ₂ : yn ≤ℚ (yn +ℚ ϵ₂)
      y≤y+ϵ₂ = ≤ℚ-add-nonneg-right yn ϵ₂ (<ℚ→≤ℚ ϵ₂pos)

      xϵ≤y+ϵ₂ : (xn +ℚ ϵ) ≤ℚ (yn +ℚ ϵ₂)
      xϵ≤y+ϵ₂ = ≤ℚ-trans {(xn +ℚ ϵ)} {yn} {(yn +ℚ ϵ₂)} xϵ≤y y≤y+ϵ₂
     in
     ≤ℚ-trans xϵ≤y+ϵ₂ (convYZ n Nyz≤n))))
}
```

Congruence of Strict Order under $\simeq_{\mathbb{R}}$

If strict order depends on which representative carries it, it is not an order on real numbers—it is merely an order on sequences. The Cauchy quotient annihilates any comparison that cannot survive a representative swap. The proof below shows that strict order does survive, by quartering the original witness gap and absorbing the equivalence corrections into the margin.

Strict order must survive elimination of representative choice, otherwise it would not descend from Cauchy data to the real quotient. That dependence is removed by transporting a strict witness across equivalence on both sides while preserving a positive asymptotic gap.

Constraint: The positive gap ε_0 that witnesses $x <_{\mathbb{R}} y$ must remain strictly positive after both sides are perturbed by representative change.

Construction: Quarter ε_0 into four budgets, spend two on transporting through $x \simeq x'$ and $y \simeq y'$, and retain a strictly positive remainder as the new witness. Any budget that fails to leave a positive remainder is eliminated; the quartering is the unique surviving allocation.

Consequence: $<_{\mathbb{R}}$ is well-defined on the Cauchy quotient. No comparison can be fabricated or destroyed by representative choice.

Law 23.6: Strict order is invariant under equivalence

The witness margin survives both equivalence corrections by repeated quartering. This eliminates representative drift while preserving a strictly positive asymptotic gap.

```
-- § Strict order respects ≃ℝ on both sides
<ℝ-resp-≃ℝ : {x x' y y' : ℝ} → x ≃ℝ x' → y ≃ℝ y' → x <ℝ y → x' <ℝ y'
<ℝ-resp-≃ℝ {x} {x'} {y} {y'} x≃x' y≃y' x<y =
 let
  -- § Phase 1: Unpack the strict-order witness
  wxy = _<ℝ_.ltWitness x<y

  ϵ₀ : ℚ
  ϵ₀ = fst wxy

  wxyRest = snd wxy

  ϵ₀pos : 0ℚ <ℚ ϵ₀
  ϵ₀pos = fst wxyRest

  packXY = snd wxyRest

  Nxy : ℕ
  Nxy = fst packXY

  convXY : (n : ℕ) → Nxy ≤ n → ((seq x n) +ℚ ϵ₀) ≤ℚ (seq y n)
  convXY = snd packXY

  -- § Phase 2: Quarter the margin twice
  ϵ : ℚ
  ϵ = ϵQuarter ϵ₀

  ϵpos : 0ℚ <ℚ ϵ
  ϵpos = ϵQuarter-pos ϵ₀
```

```
α : ℚ
α = ϵQuarter ϵ

β : ℚ
β = ϵQuarter ϵ

αpos : 0ℚ <ℚ α
αpos = ϵQuarter-pos ϵ

βpos : 0ℚ <ℚ β
βpos = ϵQuarter-pos ϵ

-- § Phase 3: Derive closeness from equivalences
x'≤x : x' ≤ℝ x
x'≤x = ≃ℝ→≤ℝ (≃ℝ-sym x≃x')

y≤y' : y ≤ℝ y'
y≤y' = ≃ℝ→≤ℝ y≃y'

packX = _≤ℝ_.leReal x'≤x α αpos
packY = _≤ℝ_.leReal y≤y' β βpos

Nx : ℕ
Nx = fst packX

Ny : ℕ
Ny = fst packY

boundX : (n : ℕ) → Nx ≤ n → (seq x' n) ≤ℚ ((seq x n) +ℚ α)
boundX = snd packX

boundY : (n : ℕ) → Ny ≤ n → (seq y n) ≤ℚ ((seq y' n) +ℚ β)
boundY = snd packY

-- § Phase 4: Global modulus N
N : ℕ
N = Nxy +ℕ (Nx +ℕ Ny)

Nxy≤N : Nxy ≤ N
Nxy≤N =
 let
   step : (Nxy +ℕ zero) ≤ (Nxy +ℕ (Nx +ℕ Ny))
   step = ≤-+ℕ-mono^l {a = zero} {b = (Nx +ℕ Ny)} z≤n Nxy
 in
 subst (λ t → t ≤ (Nxy +ℕ (Nx +ℕ Ny))) (+ℕ-zero-right Nxy) step

Nx≤N : Nx ≤ N
Nx≤N =
 let
   step : (Nx +ℕ zero) ≤ (Nx +ℕ (Nxy +ℕ Ny))
   step = ≤-+ℕ-mono^l {a = zero} {b = (Nxy +ℕ Ny)} z≤n Nx

   base : Nx ≤ (Nx +ℕ (Nxy +ℕ Ny))
   base = subst (λ t → t ≤ (Nx +ℕ (Nxy +ℕ Ny))) (+ℕ-zero-right Nx) step

   eq : (Nx +ℕ (Nxy +ℕ Ny)) ≡ (Nxy +ℕ (Nx +ℕ Ny))
   eq =
    trans
     (sym (+ℕ-assoc Nx Nxy Ny))
     (trans
      (cong (λ t → t +ℕ Ny) (+ℕ-comm Nx Nxy))
      (+ℕ-assoc Nxy Nx Ny))
```

```
  in
  subst (λ t → Nx ≤ t) eq base

 Ny≤N : Ny ≤ N
 Ny≤N =
  let
    step : (Ny +ℕ zero) ≤ (Ny +ℕ (Nxy +ℕ Nx))
    step = ≤-+ℕ-mono^l {a = zero} {b = (Nxy +ℕ Nx)} z≤n Ny

    base : Ny ≤ (Ny +ℕ (Nxy +ℕ Nx))
    base = subst (λ t → t ≤ (Ny +ℕ (Nxy +ℕ Nx))) (+ℕ-zero-right Ny) step

    eq : (Ny +ℕ (Nxy +ℕ Nx)) ≡ (Nxy +ℕ (Nx +ℕ Ny))
    eq =
     trans
      (sym (+ℕ-assoc Ny Nxy Nx))
      (trans
       (cong (λ t → t +ℕ Nx) (+ℕ-comm Ny Nxy))
       (trans
        (+ℕ-assoc Nxy Ny Nx)
        (cong (λ t → Nxy +ℕ t) (+ℕ-comm Ny Nx))))
  in
  subst (λ t → Ny ≤ t) eq base
in
record
 { ltWitness =
    ϵ ,
    ( ϵpos
    , ( N
     , (λ n N≤n →
       let
        -- § Phase 5: The chain x'_n + ϵ ≤ y'_n
        Nxy≤n : Nxy ≤ n
        Nxy≤n = ≤-trans Nxy≤N N≤n

        Nx≤n : Nx ≤ n
        Nx≤n = ≤-trans Nx≤N N≤n

        Ny≤n : Ny ≤ n
        Ny≤n = ≤-trans Ny≤N N≤n

        xn : ℚ
        xn = seq x n

        x'n : ℚ
        x'n = seq x' n

        yn : ℚ
        yn = seq y n

        y'n : ℚ
        y'n = seq y' n

        x'n≤xn+α : x'n ≤ℚ (xn +ℚ α)
        x'n≤xn+α = boundX n Nx≤n

        α+β<ϵ : (α +ℚ β) <ℚ ϵ
        α+β<ϵ = ϵQuarter-double<ϵ ϵ ϵpos

        α+β≤ϵ : (α +ℚ β) ≤ℚ ϵ
        α+β≤ϵ = <ℚ→≤ℚ {(α +ℚ β)} {ϵ} α+β<ϵ
```

```
ϵ+α+β≤ϵ+ϵ : (ϵ +ℚ (α +ℚ β)) ≤ℚ (ϵ +ℚ ϵ)
ϵ+α+β≤ϵ+ϵ = ≤ℚ-+ℚ-mono-left ϵ (α +ℚ β) ϵ α+β≤ϵ

ϵ+ϵ<ϵ₀ : (ϵ +ℚ ϵ) <ℚ ϵ₀
ϵ+ϵ<ϵ₀ = ϵQuarter-double<ϵ ϵ₀ ϵ₀pos

ϵ+ϵ≤ϵ₀ : (ϵ +ℚ ϵ) ≤ℚ ϵ₀
ϵ+ϵ≤ϵ₀ = <ℚ→≤ℚ {(ϵ +ℚ ϵ)} {ϵ₀} ϵ+ϵ<ϵ₀

ϵ+α+β≤ϵ₀ : (ϵ +ℚ (α +ℚ β)) ≤ℚ ϵ₀
ϵ+α+β≤ϵ₀ = ≤ℚ-trans {(ϵ +ℚ (α +ℚ β))} {(ϵ +ℚ ϵ)} {ϵ₀} ϵ+α+β≤ϵ+ϵ ϵ+ϵ≤ϵ₀

t : ℚ
t = α +ℚ (ϵ +ℚ β)

t≃ϵ+α+β : t ≃ℚ (ϵ +ℚ (α +ℚ β))
t≃ϵ+α+β =
 ≃ℚ-trans
  (≃ℚ-sym (+ℚ-assoc α ϵ β))
  (≃ℚ-trans
   (+ℚ-resp-≃ (+ℚ-comm α ϵ) (≃ℚ-refl β))
   (+ℚ-assoc ϵ α β))

t≤ϵ₀ : t ≤ℚ ϵ₀
t≤ϵ₀ = ≤ℚ-trans (≃ℚ→≤ℚˡ t≃ϵ+α+β) ϵ+α+β≤ϵ₀

xnt≤xnϵ₀ : (xn +ℚ t) ≤ℚ (xn +ℚ ϵ₀)
xnt≤xnϵ₀ = ≤ℚ-+ℚ-mono-left xn t ϵ₀ t≤ϵ₀

x'n+ϵ+β≤xn+t : (x'n +ℚ (ϵ +ℚ β)) ≤ℚ (xn +ℚ t)
x'n+ϵ+β≤xn+t =
 let
  step₁ : (x'n +ℚ (ϵ +ℚ β)) ≤ℚ ((xn +ℚ α) +ℚ (ϵ +ℚ β))
  step₁ = ≤ℚ-+ℚ-mono-right x'n (xn +ℚ α) (ϵ +ℚ β) x'n≤xn+α

  lhsEq : ((xn +ℚ α) +ℚ (ϵ +ℚ β)) ≃ℚ (xn +ℚ t)
  lhsEq = +ℚ-assoc xn α (ϵ +ℚ β)
 in
 ≤ℚ-trans step₁ (≃ℚ→≤ℚˡ lhsEq)

x'n+ϵ+β≤xn+ϵ₀ : (x'n +ℚ (ϵ +ℚ β)) ≤ℚ (xn +ℚ ϵ₀)
x'n+ϵ+β≤xn+ϵ₀ = ≤ℚ-trans {(x'n +ℚ (ϵ +ℚ β))} {(xn +ℚ t)} {(xn +ℚ ϵ₀)} x'n+ϵ+β≤xn+t xnt≤xnϵ₀

xn+ϵ₀≤yn : (xn +ℚ ϵ₀) ≤ℚ yn
xn+ϵ₀≤yn = convXY n Nxy≤n

x'n+ϵ+β≤yn : (x'n +ℚ (ϵ +ℚ β)) ≤ℚ yn
x'n+ϵ+β≤yn = ≤ℚ-trans {(x'n +ℚ (ϵ +ℚ β))} {(xn +ℚ ϵ₀)} {yn} x'n+ϵ+β≤xn+ϵ₀ xn+ϵ₀≤yn

x'n+ϵ≤yn-β : (x'n +ℚ ϵ) ≤ℚ (yn +ℚ (-ℚ β))
x'n+ϵ≤yn-β =
 let
  step₁ : ((x'n +ℚ (ϵ +ℚ β)) +ℚ (-ℚ β)) ≤ℚ (yn +ℚ (-ℚ β))
  step₁ = ≤ℚ-+ℚ-mono-right (x'n +ℚ (ϵ +ℚ β)) yn (-ℚ β) x'n+ϵ+β≤yn

  lhsEq₁ : ((x'n +ℚ (ϵ +ℚ β)) +ℚ (-ℚ β)) ≃ℚ (x'n +ℚ ((ϵ +ℚ β) +ℚ (-ℚ β)))
  lhsEq₁ = +ℚ-assoc x'n (ϵ +ℚ β) (-ℚ β)

  lhsEq₂ : ((ϵ +ℚ β) +ℚ (-ℚ β)) ≃ℚ ϵ
  lhsEq₂ =
   ≃ℚ-trans
    (+ℚ-assoc ϵ β (-ℚ β))
```

```
        (≃ℚ-trans
         (+ℚ-resp-≃ (≃ℚ-refl ϵ) (+ℚ-inv-right β))
         (+ℚ-zero-right ϵ))

      lhsEq : ((x'n +ℚ (ϵ +ℚ β)) +ℚ (-ℚ β)) ≃ℚ (x'n +ℚ ϵ)
      lhsEq = ≃ℚ-trans lhsEq₁ (+ℚ-resp-≃ (≃ℚ-refl x'n) lhsEq₂)
    in
    ≤ℚ-trans (≃ℚ→≤ℚʳ lhsEq) step₁

    yn≤y'n+β : yn ≤ℚ (y'n +ℚ β)
    yn≤y'n+β = boundY n Ny≤n

    yn-β≤y'n : (yn +ℚ (-ℚ β)) ≤ℚ y'n
    yn-β≤y'n =
    let
      step₁ : (yn +ℚ (-ℚ β)) ≤ℚ ((y'n +ℚ β) +ℚ (-ℚ β))
      step₁ = ≤ℚ-+ℚ-mono-right yn (y'n +ℚ β) (-ℚ β) yn≤y'n+β

      rhsEq₁ : ((y'n +ℚ β) +ℚ (-ℚ β)) ≃ℚ (y'n +ℚ (β +ℚ (-ℚ β)))
      rhsEq₁ = +ℚ-assoc y'n β (-ℚ β)

      rhsEq₂ : (β +ℚ (-ℚ β)) ≃ℚ 0ℚ
      rhsEq₂ = +ℚ-inv-right β

      rhsEq : ((y'n +ℚ β) +ℚ (-ℚ β)) ≃ℚ y'n
      rhsEq =
       ≃ℚ-trans
        rhsEq₁
        (≃ℚ-trans
         (+ℚ-resp-≃ (≃ℚ-refl y'n) rhsEq₂)
         (+ℚ-zero-right y'n))
    in
    ≤ℚ-trans step₁ (≃ℚ→≤ℚˡ rhsEq)
  in
  ≤ℚ-trans x'n+ϵ≤yn-β yn-β≤y'n
 )
)
)
}
```

Reflexivity of $\leq_{\mathbb{R}}$

Any admissible asymptotic order must retain self-comparison. The positive margin only relaxes the comparison further, so any failure of reflexivity would contradict the order structure already forced on representatives.

Law 23.7: Non-strict order is reflexive

Reflexivity is forced because every positive margin preserves the same sequence pointwise. Self-comparison must therefore hold on every tail with no residual freedom.

```
-- § Reflexivity of ≤ℝ
≤ℝ-refl : (x : ℝ) → x ≤ℝ x
≤ℝ-refl x = record
 { leReal = λ ϵ ϵpos →
   zero , (λ n _ →
    ≤ℚ-add-nonneg-right (seq x n) ϵ (<ℚ→≤ℚ ϵpos))
 }
```

Transitivity of $\leq_{\mathbb{R}}$

Eventual upper bounds are forced to compose across an intermediate real. The only remaining work is to control the accumulated margin so that the composite comparison still fits inside the requested tolerance.

Law 23.8: Non-strict order is transitive

Two eventual $\varepsilon/4$ bounds are forced into one eventual ε bound. Associativity eliminates ambiguity in how the margins accumulate along the composite comparison.

```
– § Transitivity of ≤ℝ via ϵ-splitting
≤ℝ-trans : {x y z : ℝ} → x ≤ℝ y → y ≤ℝ z → x ≤ℝ z
≤ℝ-trans {x} {y} {z} x≤y y≤z = record
 { leReal = λ ϵ ϵpos →
   let
     – § Phase 1: Budget allocation
     ϵq : ℚ
     ϵq = ϵQuarter ϵ

     ϵqPos : 0ℚ <ℚ ϵq
     ϵqPos = ϵQuarter-pos ϵ

     ϵqNonneg : 0ℚ ≤ℚ ϵq
     ϵqNonneg = <ℚ→≤ℚ {0ℚ} {ϵq} ϵqPos

     ϵq+ϵq<ϵ : (ϵq +ℚ ϵq) <ℚ ϵ
     ϵq+ϵq<ϵ = ϵQuarter-double<ϵ ϵ ϵpos

     NxyPack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → (seq x n) ≤ℚ ((seq y n) +ℚ ϵq))
     NxyPack = _≤ℝ_.leReal x≤y ϵq ϵqPos

     NyzPack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → (seq y n) ≤ℚ ((seq z n) +ℚ ϵq))
     NyzPack = _≤ℝ_.leReal y≤z ϵq ϵqPos

     Nxy : ℕ
     Nxy = fst NxyPack

     Nyz : ℕ
     Nyz = fst NyzPack

     NxyConv : (n : ℕ) → Nxy ≤ n → (seq x n) ≤ℚ ((seq y n) +ℚ ϵq)
     NxyConv = snd NxyPack

     NyzConv : (n : ℕ) → Nyz ≤ n → (seq y n) ≤ℚ ((seq z n) +ℚ ϵq)
     NyzConv = snd NyzPack

     – -- Phase 2: Global modulus N -------------------------------
     N : ℕ
     N = Nxy +ℕ Nyz

     Nxy≤N : Nxy ≤ N
     Nxy≤N =
      let
       mono : (Nxy +ℕ zero) ≤ (Nxy +ℕ Nyz)
       mono = ≤-+ℕ-mono^l {a = zero} {b = Nyz} z≤n Nxy
      in
      subst (λ t → t ≤ (Nxy +ℕ Nyz)) (+ℕ-zero-right Nxy) mono
```

```
      Nyz≤N : Nyz ≤ N
      Nyz≤N =
       let
        mono : (Nyz +ℕ zero) ≤ (Nyz +ℕ Nxy)
        mono = ≤-+ℕ-mono^l {a = zero} {b = Nxy} z≤n Nyz

        base : Nyz ≤ (Nyz +ℕ Nxy)
        base = subst (λ t → t ≤ (Nyz +ℕ Nxy)) (+ℕ-zero-right Nyz) mono
       in
       subst (λ t → Nyz ≤ t) (+ℕ-comm Nyz Nxy) base
    in
    N , (λ n N≤n →
      let
       – § Phase 3: Chain and reassociate
       Nxy≤n : Nxy ≤ n
       Nxy≤n = ≤-trans Nxy≤N N≤n

       Nyz≤n : Nyz ≤ n
       Nyz≤n = ≤-trans Nyz≤N N≤n

       xn : ℚ
       xn = seq x n

       yn : ℚ
       yn = seq y n

       zn : ℚ
       zn = seq z n

       xn≤yn+ϵq : xn ≤ℚ (yn +ℚ ϵq)
       xn≤yn+ϵq = NxyConv n Nxy≤n

       yn≤zn+ϵq : yn ≤ℚ (zn +ℚ ϵq)
       yn≤zn+ϵq = NyzConv n Nyz≤n

       step₁ : (yn +ℚ ϵq) ≤ℚ ((zn +ℚ ϵq) +ℚ ϵq)
       step₁ = ≤ℚ-+ℚ-mono-right yn (zn +ℚ ϵq) ϵq yn≤zn+ϵq

       step₂ : xn ≤ℚ ((zn +ℚ ϵq) +ℚ ϵq)
       step₂ = ≤ℚ-trans {xn} {(yn +ℚ ϵq)} {((zn +ℚ ϵq) +ℚ ϵq)} xn≤yn+ϵq step₁

       step₃ : ((zn +ℚ ϵq) +ℚ ϵq) ≤ℚ (zn +ℚ (ϵq +ℚ ϵq))
       step₃ = ≃ℚ→≤ℚ^l {((zn +ℚ ϵq) +ℚ ϵq)} {(zn +ℚ (ϵq +ℚ ϵq))} (+ℚ-assoc zn ϵq ϵq)

       step₄ : (zn +ℚ (ϵq +ℚ ϵq)) ≤ℚ (zn +ℚ ϵ)
       step₄ = ≤ℚ-+ℚ-mono-left zn (ϵq +ℚ ϵq) ϵ (<ℚ→≤ℚ ϵq+ϵq<ϵ)

       done : xn ≤ℚ (zn +ℚ ϵ)
       done = ≤ℚ-trans {xn} {((zn +ℚ ϵq) +ℚ ϵq)} {(zn +ℚ ϵ)} step₂ (≤ℚ-trans step₃ step₄)
      in
      done)
}
```

Antisymmetry of $\leq_{\mathbb{R}}$

Mutual asymptotic domination must collapse to equality of reals. If two representatives eventually bound each other at every positive margin, no residual distance can survive in the quotient.

Law 23.9: Mutual non-strict order forces equivalence

Two-sided eventual bounds force asymptotic distance below every positive margin. What survives is exactly equivalence of the underlying Cauchy representatives.

```
-- § Antisymmetry: mutual ≤ℝ yields ≃ℝ
≤ℝ-antisym : {x y : ℝ} → x ≤ℝ y → y ≤ℝ x → x ≃ℝ y
≤ℝ-antisym {x} {y} x≤y y≤x = record
 { conv0 = λ ϵ ϵpos →
   let
     ϵq : ℚ
     ϵq = ϵQuarter ϵ

     ϵqPos : 0ℚ <ℚ ϵq
     ϵqPos = ϵQuarter-pos ϵ

     NxyPack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → (seq x n) ≤ℚ ((seq y n) +ℚ ϵq))
     NxyPack = _≤ℝ_.leReal x≤y ϵq ϵqPos

     NyxPack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → (seq y n) ≤ℚ ((seq x n) +ℚ ϵq))
     NyxPack = _≤ℝ_.leReal y≤x ϵq ϵqPos

     Nxy : ℕ
     Nxy = fst NxyPack

     Nyx : ℕ
     Nyx = fst NyxPack

     NxyConv : (n : ℕ) → Nxy ≤ n → (seq x n) ≤ℚ ((seq y n) +ℚ ϵq)
     NxyConv = snd NxyPack

     NyxConv : (n : ℕ) → Nyx ≤ n → (seq y n) ≤ℚ ((seq x n) +ℚ ϵq)
     NyxConv = snd NyxPack

     N : ℕ
     N = Nxy +ℕ Nyx

     Nxy≤N : Nxy ≤ N
     Nxy≤N =
      let
       mono : (Nxy +ℕ zero) ≤ (Nxy +ℕ Nyx)
       mono = ≤-+ℕ-mono^l {a = zero} {b = Nyx} z≤n Nxy
      in
      subst (λ t → t ≤ (Nxy +ℕ Nyx)) (+ℕ-zero-right Nxy) mono

     Nyx≤N : Nyx ≤ N
     Nyx≤N =
      let
       mono : (Nyx +ℕ zero) ≤ (Nyx +ℕ Nxy)
       mono = ≤-+ℕ-mono^l {a = zero} {b = Nxy} z≤n Nyx

       base : Nyx ≤ (Nyx +ℕ Nxy)
       base = subst (λ t → t ≤ (Nyx +ℕ Nxy)) (+ℕ-zero-right Nyx) mono
      in
      subst (λ t → Nyx ≤ t) (+ℕ-comm Nyx Nxy) base
   in
   N , (λ n N≤n →
     let
      Nxy≤n : Nxy ≤ n
      Nxy≤n = ≤-trans Nxy≤N N≤n
```

```
    Nyx≤n : Nyx ≤ n
    Nyx≤n = ≤-trans Nyx≤N N≤n

    xn : ℚ
    xn = seq x n

    yn : ℚ
    yn = seq y n

    xn≤yn+ϵq : xn ≤ℚ (yn +ℚ ϵq)
    xn≤yn+ϵq = NxyConv n Nxy≤n

    yn≤xn+ϵq : yn ≤ℚ (xn +ℚ ϵq)
    yn≤xn+ϵq = NyxConv n Nyx≤n

    d≤ϵq : distℚ xn yn ≤ℚ ϵq
    d≤ϵq = distℚ-bounded-by-ϵ xn yn ϵq xn≤yn+ϵq yn≤xn+ϵq

    ϵq<ϵ : ϵq <ℚ ϵ
    ϵq<ϵ = ϵQuarter<ϵ ϵ ϵpos
  in
  ≤<ℚ→<ℚ {distℚ xn yn} {ϵq} {ϵ} d≤ϵq ϵq<ϵ)
}
```

Congruence of $\leq_{\mathbb{R}}$ under $\simeq_{\mathbb{R}}$

Strict order has been saved. But if non-strict order cannot survive the same representative swap, the ordered-field structure is only half-built: reflexivity and transitivity would apply to sequences, not to reals. The rescue is simpler than for strict order, because $\leq_{\mathbb{R}}$ can be transported by composing with the equivalence-induced bounds that already exist.

Non-strict order must also survive elimination of representative choice, otherwise order would not descend to the real quotient. The only admissible transport is composition with the equivalence-induced order bounds already forced above.

Constraint: $\leq_{\mathbb{R}}$ must be well-defined on the Cauchy quotient: if $x \simeq x'$ and $y \simeq y'$, then $x \leq y$ implies $x' \leq y'$.

Construction: Chain $x' \leq x$ (from $x \simeq x'$), $x \leq y$ (given), and $y \leq y'$ (from $y \simeq y'$) via transitivity. Any path that fails to compose through the equivalences is eliminated; the transitive chain is the only surviving route.

Consequence: $\leq_{\mathbb{R}}$ descends to the quotient. Together with $<_{\mathbb{R}}$, the full order structure is representative-independent.

Law 23.10: Non-strict order is invariant under equivalence

The congruence law is forced by composing equivalence-induced bounds on the left and right. No additional order data survives elimination.

```
– § Non-strict order respects ≃ℝ
≤ℝ-resp-≃ℝ : {x x' y y' : ℝ} → x ≃ℝ x' → y ≃ℝ y' → x ≤ℝ y → x' ≤ℝ y'
≤ℝ-resp-≃ℝ {x} {x'} {y} {y'} x≃x' y≃y' x≤y =
 let
```

```
  x'≤x : x' ≤ℝ x
  x'≤x = ≃ℝ→≤ℝ (≃ℝ-sym x≃x')

  y≤y' : y ≤ℝ y'
  y≤y' = ≃ℝ→≤ℝ y≃y'
 in
 ≤ℝ-trans (≤ℝ-trans x'≤x x≤y) y≤y'
```

Right Additive Monotonicity of $\leq_{\mathbb{R}}$

An ordered ring in which addition can reverse an inequality is useless for the invariant chain: every spectral bound, every additive transport depends on monotonicity under addition. Adding a common term to both sides of an inequality must not destroy the comparison, or the later additive transport laws for the derived constants collapse.

Right addition must preserve asymptotic order. Once addition has been forced on reals, adjoining the same summand on the right cannot create a new comparison failure.

Constraint: $x \leq y$ must imply $x + z \leq y + z$ for every real z.

Construction: Lift pointwise rational monotonicity through $+\mathbb{Q}$-mono-$\leq$-right, then use ε-margin associativity to eliminate ambiguity in the placement of the surviving margin. Any alternative placement breaks the tail bound.

Consequence: Both right and left monotonicity are forced, completing the twelve-law ordered-field scaffold.

Law 23.11: Right addition preserves non-strict order

Right monotonicity is forced by pointwise rational monotonicity. Associativity eliminates ambiguity in the placement of the surviving ε-margin.

```
-- § Right monotonicity of +ℝ under ≤ℝ
≤ℝ-+ℝ-mono-right : {x y z : ℝ} → x ≤ℝ y → (x +ℝ z) ≤ℝ (y +ℝ z)
≤ℝ-+ℝ-mono-right {x} {y} {z} x≤y = record
 { leReal = λ ϵ ϵpos →
   let
     pack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → (seq x n) ≤ℚ ((seq y n) +ℚ ϵ))
     pack = _≤ℝ_.leReal x≤y ϵ ϵpos

     N : ℕ
     N = fst pack

     conv : (n : ℕ) → N ≤ n → (seq x n) ≤ℚ ((seq y n) +ℚ ϵ)
     conv = snd pack
   in
   N , (λ n N≤n →
     let
      xn : ℚ
      xn = seq x n

      yn : ℚ
      yn = seq y n

      zn : ℚ
```

```
      zn = seq z n

      step₁ : (xn +ℚ zn) ≤ℚ (((yn +ℚ ϵ) +ℚ zn))
      step₁ = ≤ℚ-+ℚ-mono-right xn (yn +ℚ ϵ) zn (conv n N≤n)

      rhsEq : ((yn +ℚ ϵ) +ℚ zn) ≃ℚ ((yn +ℚ zn) +ℚ ϵ)
      rhsEq =
       ≃ℚ-trans
        (+ℚ-assoc yn ϵ zn)
        (≃ℚ-trans
         (+ℚ-resp-≃ (≃ℚ-refl yn) (+ℚ-comm ϵ zn))
         (≃ℚ-sym (+ℚ-assoc yn zn ϵ)))

      step₂ : (((yn +ℚ ϵ) +ℚ zn)) ≤ℚ ((yn +ℚ zn) +ℚ ϵ)
      step₂ = ≃ℚ→≤ℚˡ {(((yn +ℚ ϵ) +ℚ zn))} {((yn +ℚ zn) +ℚ ϵ)} rhsEq
    in
    ≤ℚ-trans step₁ step₂)
}
```

Left Additive Monotonicity of $\leq_{\mathbb{R}}$

Left addition must preserve the same asymptotic order. This removes any residual asymmetry between the two inputs of addition at the level of order transport.

Law 23.12: Left addition preserves non-strict order

Left monotonicity is forced by the same rational order law, now applied through the left summand. Associativity again eliminates ambiguity in the placement of the surviving margin.

```
– § Left monotonicity of +ℝ under ≤ℝ
≤ℝ-+ℝ-mono-left : {x y z : ℝ} → x ≤ℝ y → (z +ℝ x) ≤ℝ (z +ℝ y)
≤ℝ-+ℝ-mono-left {x} {y} {z} x≤y = record
 { leReal = λ ϵ ϵpos →
   let
     pack : Σ ℕ (λ N → (n : ℕ) → N ≤ n → (seq x n) ≤ℚ ((seq y n) +ℚ ϵ))
     pack = _≤ℝ_.leReal x≤y ϵ ϵpos

     N : ℕ
     N = fst pack

     conv : (n : ℕ) → N ≤ n → (seq x n) ≤ℚ ((seq y n) +ℚ ϵ)
     conv = snd pack
   in
   N , (λ n N≤n →
     let
      xn : ℚ
      xn = seq x n

      yn : ℚ
      yn = seq y n

      zn : ℚ
      zn = seq z n

      step₁ : (zn +ℚ xn) ≤ℚ (zn +ℚ (yn +ℚ ϵ))
      step₁ = ≤ℚ-+ℚ-mono-left zn xn (yn +ℚ ϵ) (conv n N≤n)
```

```
    rhsEq : (zn +ℚ (yn +ℚ ϵ)) ≃ℚ ((zn +ℚ yn) +ℚ ϵ)
    rhsEq = sym (+ℚ-assoc zn yn ϵ)

    step₂ : (zn +ℚ (yn +ℚ ϵ)) ≤ℚ ((zn +ℚ yn) +ℚ ϵ)
    step₂ = ≃ℚ→≤ℚˡ {(zn +ℚ (yn +ℚ ϵ))} {((zn +ℚ yn) +ℚ ϵ)} rhsEq
  in
  ≤ℚ-trans step₁ step₂)
}
```

The numerical machinery is in place. Natural numbers, integers, rationals, reals, order, distance, scaling, and spectral operators have all been forced from the surviving structure rather than imported from outside it. The full language required to evaluate K_4 quantitatively is established—and every law in that language is a theorem, not a postulate. This is the methodological extreme the eliminative discipline demands: the arithmetic that measures the survivor is itself a consequence of the survivor.

The final step is assembly. The invariants already derived must be gathered, their values evaluated, and the logical closure of the chain confirmed.

Part VI

Derived Constants of K_4

The arithmetic, spectral theory, and evaluation apparatus built in Part V constitute the machinery needed to extract numerical values from K_4's combinatorial invariants. This part performs that extraction—and then closes the loop.

Nothing new is assumed. The vertex count, edge count, Euler characteristic, and Laplacian eigenvalues of K_4 are assembled into a verified computation record. Each entry is a definitional equality closed by the Agda type system. The numerical values that result—including the graph evaluation $\mathcal{C} = 137$—are consequences of the structure derived in Parts I through IV, evaluated by the arithmetic derived in Part V. Not one import, not one postulate, not one adjustable parameter.

The invariant record is then proved to be a singleton: any two admissible records must agree on every field. This is the sharpest conclusion the eliminative method can deliver—not merely that K_4 exists, but that its invariant description is the only one that survives.

Two further results close the derivation. The measurement kernel establishes that any apparatus capable of binary discrimination already presupposes the distinction D_0 from which the chain began—an independent route to the same root, sharing no lemma with the eliminative chain. And the final theorem proves that every admissible invariant record already consumes a distinction, closing the loop: $D_0 \Longrightarrow K_4 \Longrightarrow \text{record} \Longrightarrow D_0$.

The reader should keep two claims sharply apart. The theorem-level claim is internal to the formal system: given the derivation already established, these equalities reduce and these numbers compute. This claim is proved here. Whether these numbers have further significance is an interpretive question that belongs outside the formal chain.

Chapter 43

Natural-Number Division Infrastructure

The combinatorial laws of K_4 require exact natural-number division, yet the safe base environment does not provide the needed machinery. This chapter therefore fixes the minimal arithmetic infrastructure that survives the safety constraints and still forces every later combinatorial count to remain mechanically decidable.

Two primitives are needed: a greatest common divisor that terminates on all inputs, and an integer division that recovers exact quotients when they exist. Both are fuel-bounded—the recursion carries an explicit natural-number counter that decreases at each step—because the safe base environment provides no other termination discipline. This is not a design choice; it is forced by the absence of well-founded recursion in the minimal base. The fuel bound is always the sum of the two inputs, which is enough because each Euclidean subtraction step reduces that sum by at least one.

Constraint: Termination of the Euclidean algorithm on arbitrary naturals requires an explicit fuel counter in the safe base.

Construction: Without structural recursion on an explicit fuel counter, no terminating implementation of the Euclidean algorithm survives the safe base. The only surviving form is a three-argument gcd-fuel recurrence that subtracts the smaller input from the larger at each step, consuming one unit of fuel, and a div-fuel recurrence that counts how many times the divisor fits.

Consequence: Both primitives are total and structurally decreasing in fuel. Every downstream combinatorial identity reduces to refl once the fuel evaluates.

```
-- § Boolean comparison on ℕ
_≤ℕ_ : ℕ → ℕ → Bool
zero ≤ℕ _       = true
suc _ ≤ℕ zero = false
suc m ≤ℕ suc n = m ≤ℕ n

-- § Fuel-bounded GCD
gcd-fuel : ℕ → ℕ → ℕ → ℕ
gcd-fuel zero m _       = m
```

```
gcd-fuel (suc _) zero n = n
gcd-fuel (suc _) m zero = m
gcd-fuel (suc f) (suc m) (suc n) with (suc m) ≤ℕ (suc n)
... | true = gcd-fuel f (suc m) (n ∸ m)
... | false = gcd-fuel f (m ∸ n) (suc n)

-- § One-step exposure of gcd-fuel on positive inputs.
gcd-fuel-step : ℕ → ℕ → ℕ → Bool → ℕ
gcd-fuel-step f m n true = gcd-fuel f m (n ∸ m)
gcd-fuel-step f m n false = gcd-fuel f (m ∸ n) n

gcd-fuel-suc-suc : (f m n : ℕ) → gcd-fuel (suc f) (suc m) (suc n) ≡ gcd-fuel-step f (suc m) (suc n) (m ≤ℕ n)
gcd-fuel-suc-suc f m n with m ≤ℕ n
... | true = refl
... | false = refl

-- § GCD with canonical fuel
gcd : ℕ → ℕ → ℕ
gcd m n = gcd-fuel (m + n) m n
```

Once the GCD engine is in place, the only remaining primitive is exact division. A rational quotient n/d must be decomposable into a whole-number part whenever d divides n; otherwise the correction fractions in the companion module would remain opaque to computation. Division is again fuel-bounded, counting how many times the divisor can be subtracted before the remainder drops below it.

```
-- § Successor coercion to ℕ⁺
sucToℕ⁺ : ℕ → ℕ⁺
sucToℕ⁺ zero = one⁺
sucToℕ⁺ (suc n) = suc⁺ (sucToℕ⁺ n)

-- § General ℕ to ℕ⁺ coercion
ℕ-to-ℕ⁺ : ℕ → ℕ⁺
ℕ-to-ℕ⁺ = mkℕ⁺

-- § Fuel-bounded integer division
div-fuel : ℕ → ℕ → ℕ⁺ → ℕ
div-fuel zero _ _ = zero
div-fuel (suc f) n d with ⁺toℕ d ≤ℕ n
... | true = suc (div-fuel f (n ∸ ⁺toℕ d) d)
... | false = zero

-- § One-step exposure of div-fuel on positive fuel.
div-fuel-step : ℕ → ℕ → ℕ⁺ → Bool → ℕ
div-fuel-step f n d true = suc (div-fuel f (n ∸ ⁺toℕ d) d)
div-fuel-step f n d false = zero

div-fuel-suc : (f n : ℕ) → (d : ℕ⁺) → div-fuel (suc f) n d ≡ div-fuel-step f n d (⁺toℕ d ≤ℕ n)
div-fuel-suc f n d with ⁺toℕ d ≤ℕ n
... | true = refl
... | false = refl

-- § Division by ℕ⁺
_div_ : ℕ → ℕ⁺ → ℕ
n div d = div-fuel n n d

-- § Division by ℕ (zero-safe)
_divℕ_ : ℕ → ℕ → ℕ
_ divℕ zero = zero
n divℕ (suc d) = n div (sucToℕ⁺ d)
```

Canonical Quotient Data and Reduced Witnesses

The quotient layer cannot remain hidden behind decimal notation or behind the raw setoid. If a rational observable entered the theory with its numerator and denominator left implicit, the same presentation-noise that earlier chapters eliminated would quietly return at the arithmetic boundary. The rational layer must therefore expose its own surviving ledger.

Part IV already forced admissible observables to collapse to canonical base content. That pressure now reaches the quotient level. Every admissible rational observable must carry pointwise quotient data visible at the base, and any reduced witness that survives must be unique. The gcd-and-division infrastructure built above now extracts a reduced witness for every quotient class—including negative and zero classes—so the canonical normal form is globally available. What follows is therefore the full quotient-presentation layer: from the raw setoid lift through the divisibility engine to the final signed reduced form that every admissible rational observable is forced to carry.

Constraint: A rational observable may not hide its quotient structure behind the equality relation. If numerator and denominator remained observationally ambiguous, admissibility would collapse back into representation choice.

Construction: Any observable structure that hides its quotient fields behind the equality relation is eliminated by the admissibility constraint. The only surviving pathway lifts rational values into Set_ω, packages their explicit quotient data, and then lifts that presentation pointwise along admissible observables. Reduced witnesses are forced as positive numerator/denominator presentations together with coprimality, and uniqueness is forced by the quotient fields themselves. The same mechanism extracts a canonical reduction candidate from the raw fields by dividing numerator and denominator by their computed gcd.

Consequence: Every rational class now admits a signed reduced normal form—proved via the canonical-reduction-form theorem that splits on sign, reduces the magnitude through the gcd engine, and lifts the result through negation compatibility. The irreducible nonnegative sector, the zero class, and the negative classes are all closed. At the observable level, quotient fields are globally visible and any reduced witness is unique whenever it exists.

Quotient presentation and field uniqueness

Before reduction can begin, the rational type must expose its quotient fields as inspectable data. If a rational $q = n/d$ entered the theory opaquely—with the constructor fields hidden behind the setoid relation—then later admissibility tests would have nothing concrete to classify. The lift into Set_ω makes rational observables composable with the drift framework, and the presentation record simply reads off the constructor fields that already exist. The uniqueness lemma then eliminates any residual doubt: these fields are not a choice of presentation but the only surviving data.

```
– § Lift rationals into Setω so admissible observables can target them.
record ℚω : Setω where
 constructor wrapℚ
```

```
 field
  lowerℚ : ℚ

open ℚω public

AdmissibleRationalObservable : Setω
AdmissibleRationalObservable = AdmissibleObservable ℚω

-- § Quotient presentation of a rational value.
record RationalPresentation (q : ℚ) : Set where
 field
  pres-num : ℤ
  pres-den : ℕ⁺
  presents-q : q ≡ pres-num / pres-den

-- § The constructor fields are already the canonical quotient data.
canonical-rational-presentation : (q : ℚ) → RationalPresentation q
canonical-rational-presentation (n / d) = record
 { pres-num = n
 ; pres-den = d
 ; presents-q = refl
 }

-- § Quotient fields are unique once a rational value is fixed.
rational-fields-unique :
 (q : ℚ) →
 (n₁ n₂ : ℤ) →
 (d₁ d₂ : ℕ⁺) →
 q ≡ (n₁ / d₁) →
 q ≡ (n₂ / d₂) →
 (n₁ ≡ n₂) × (d₁ ≡ d₂)
rational-fields-unique (n / d) n₁ n₂ d₁ d₂ refl refl = refl , refl
```

Reduced witnesses and irreducibility

Once the quotient fields are visible and unique, the next question is sharper: when is a rational already in reduced form? The answer is forced by coprimality. A quotient n/d is *irreducible* when $\gcd(|n|, d) = 1$—when the numerator magnitude and the denominator share no factor beyond one.

A *reduced rational witness* makes this concrete. It records a natural numerator, a positive denominator, a proof that the rational equals this pair (up to definitional equality), and a proof that the pair is coprime. The uniqueness of reduced witnesses follows immediately from the uniqueness of quotient fields: if two reduced witnesses both present the same rational, their numerators and denominators must agree, because the fields are read from the same constructor.

This subsection also establishes the injectivity of the natural embedding $\mathbb{N} \hookrightarrow \mathbb{Z}$, which is needed to transport the numerator equality from the integer level down to the natural level.

```
-- § The ℕ-embedding into ℤ is injective.
fromℕℤ-injective : {m n : ℕ} → fromℕℤ m ≡ fromℕℤ n → m ≡ n
fromℕℤ-injective {zero} {zero} refl = refl
fromℕℤ-injective {zero} {suc n} ()
fromℕℤ-injective {suc m} {zero} ()
fromℕℤ-injective {suc m} {suc n} refl = refl
```

```
-- § Irreducibility for rational quotients: numerator magnitude and denominator are coprime.
IrreducibleQuotient : ℚ → Set
IrreducibleQuotient q = gcd (magℤ (num q)) (⁺toℕ (den q)) ≡ 1

-- § Reduced witness for a rational quotient with nonnegative numerator.
record ReducedRationalWitness (q : ℚ) : Set where
 field
  red-num : ℕ
  red-den : ℕ⁺
  red-value : q ≡ fromℕℤ red-num / red-den
  red-coprime : gcd red-num (⁺toℕ red-den) ≡ 1

-- § Reduced witnesses are unique whenever they exist.
reduced-rational-witness-unique :
 {q : ℚ} →
 (r₁ r₂ : ReducedRationalWitness q) →
 ReducedRationalWitness.red-num r₁ ≡ ReducedRationalWitness.red-num r₂
 × ReducedRationalWitness.red-den r₁ ≡ ReducedRationalWitness.red-den r₂
reduced-rational-witness-unique {q} r₁ r₂ =
 let
  pair : fromℕℤ (ReducedRationalWitness.red-num r₁)
       ≡ fromℕℤ (ReducedRationalWitness.red-num r₂)
       × (ReducedRationalWitness.red-den r₁ ≡ ReducedRationalWitness.red-den r₂)
  pair =
   rational-fields-unique q
    (fromℕℤ (ReducedRationalWitness.red-num r₁))
    (fromℕℤ (ReducedRationalWitness.red-num r₂))
    (ReducedRationalWitness.red-den r₁)
    (ReducedRationalWitness.red-den r₂)
    (ReducedRationalWitness.red-value r₁)
    (ReducedRationalWitness.red-value r₂)
 in
 fromℕℤ-injective (fst pair) , snd pair
```

Arithmetic lemmas and exact division

The reduction pipeline requires a corridor of small arithmetic facts—about subtraction, comparison reflection, packaging, and exact division—that would otherwise interrupt the flow of the main argument if proved inline. None of these is surprising. Each is a single-step verification that the safe base arithmetic behaves as expected under successor encoding.

The culmination of this corridor is the exact-division theorem: when d divides n, the fuel-bounded division recovers the quotient exactly. The proof proceeds by induction on the quotient q, showing that each subtraction step peels off one copy of d and that the accumulated fuel suffices for the recursion. This is the bridge between the raw division recurrence and the structured divisibility theory that follows.

```
-- § Magnitude of the ℕ-embedding is the original natural number.
magℤ-fromℕℤ : (n : ℕ) → magℤ (fromℕℤ n) ≡ n
magℤ-fromℕℤ zero = refl
magℤ-fromℕℤ (suc n) = refl

-- § Subtracting zero on the right does nothing.
∸-zero-right : (n : ℕ) → n ∸ zero ≡ n
∸-zero-right zero = refl
∸-zero-right (suc n) = refl
```

```
-- § Subtracting one from a successor recovers the predecessor.
∸-one-suc : (n : ℕ) → suc n ∸ 1 ≡ n
∸-one-suc n = ∸-zero-right n

-- § A left summand cancels against subtraction from the whole sum.
+ℕ-∸-cancel-left : (m n : ℕ) → (m +ℕ n) ∸ m ≡ n
+ℕ-∸-cancel-left zero n = ∸-zero-right n
+ℕ-∸-cancel-left (suc m) n = +ℕ-∸-cancel-left m n

-- § Every natural is ≤ℕ its own right extension.
≤ℕ-self-+ℕ-right : (m n : ℕ) → m ≤ℕ (m +ℕ n) ≡ true
≤ℕ-self-+ℕ-right zero n = refl
≤ℕ-self-+ℕ-right (suc m) n = ≤ℕ-self-+ℕ-right m n

-- § Boolean ≤ℕ reflects propositional ≤.
≤ℕ-true→≤ : {m n : ℕ} → m ≤ℕ n ≡ true → m ≤ n
≤ℕ-true→≤ {zero} {n} _ = z≤n
≤ℕ-true→≤ {suc m} {zero} ()
≤ℕ-true→≤ {suc m} {suc n} eq = s≤s (≤ℕ-true→≤ eq)

-- § Boolean failure of ≤ℕ forces the reverse propositional order.
≤ℕ-false→≤ : {m n : ℕ} → m ≤ℕ n ≡ false → n ≤ m
≤ℕ-false→≤ {zero} {n} ()
≤ℕ-false→≤ {suc m} {zero} _ = z≤n
≤ℕ-false→≤ {suc m} {suc n} eq = s≤s (≤ℕ-false→≤ eq)

-- § Ordered subtraction splits the larger number into base plus remainder.
≤→+ℕ-∸-split : {m n : ℕ} → m ≤ n → m +ℕ (n ∸ m) ≡ n
≤→+ℕ-∸-split {zero} {n} z≤n = ∸-zero-right n
≤→+ℕ-∸-split {suc m} {suc n} (s≤s p) = cong suc (≤→+ℕ-∸-split p)

-- § Packing the predecessor of a positive natural recovers the same ℕ⁺.
mkℕ⁺-⁺toℕ-minus-one : (d : ℕ⁺) → mkℕ⁺ (⁺toℕ d ∸ 1) ≡ d
mkℕ⁺-⁺toℕ-minus-one (mkℕ⁺ p) = cong mkℕ⁺ (∸-zero-right p)

-- § Division by one leaves naturals unchanged.
div-one⁺ : (n : ℕ) → n div one⁺ ≡ n
div-one⁺ zero = refl
div-one⁺ (suc n) =
 cong suc
  (trans
   (cong (λ t → div-fuel n t one⁺) (∸-zero-right n))
   (div-one⁺ n))
```

At this point the corridor is narrow enough that the exact-division theorem can fire cleanly. The recurrence has no freedom left: each successful subtraction removes one copy of the divisor, and the surplus fuel merely witnesses that the recursion cannot stall too early.

```
-- § Division recovers the quotient on exact multiples, even with extra fuel.
div-fuel-exact-multiple :
 (q slack : ℕ) → (d : ℕ⁺) →
 div-fuel ((q *ℕ ⁺toℕ d) +ℕ slack) (q *ℕ ⁺toℕ d) d ≡ q
div-fuel-exact-multiple zero zero (mkℕ⁺ p) = refl
div-fuel-exact-multiple zero (suc slack) (mkℕ⁺ p) = refl
div-fuel-exact-multiple (suc q) slack (mkℕ⁺ p) =
 let
  qk : ℕ
```

```
  qk = q *ℕ suc p

  fuelShape : ((suc q *ℕ suc p) +ℕ slack) ≡ suc (p +ℕ (qk +ℕ slack))
  fuelShape = cong suc (+ℕ-assoc p qk slack)

  cmpEq : suc p ≤ℕ (suc q *ℕ suc p) ≡ true
  cmpEq = ≤ℕ-self-+ℕ-right p qk

  subEq : (suc q *ℕ suc p) ∸ suc p ≡ qk
  subEq = +ℕ-∸-cancel-left (suc p) qk

  fuelEq : p +ℕ (qk +ℕ slack) ≡ qk +ℕ (p +ℕ slack)
  fuelEq =
   trans
    (sym (+ℕ-assoc p qk slack))
    (trans
     (cong (λ t → t +ℕ slack) (+ℕ-comm p qk))
     (+ℕ-assoc qk p slack))
 in
 trans
  (cong (λ t → div-fuel t (suc q *ℕ suc p) (mkℕ⁺ p)) fuelShape)
  (trans
   (div-fuel-suc (p +ℕ (qk +ℕ slack)) (suc q *ℕ suc p) (mkℕ⁺ p))
   (trans
    (cong (div-fuel-step (p +ℕ (qk +ℕ slack)) (suc q *ℕ suc p) (mkℕ⁺ p)) cmpEq)
    (cong suc
     (trans
      (cong (λ t → div-fuel (p +ℕ (qk +ℕ slack)) t (mkℕ⁺ p)) subEq)
      (trans
       (cong (λ t → div-fuel t qk (mkℕ⁺ p)) fuelEq)
       (div-fuel-exact-multiple q (p +ℕ slack) (mkℕ⁺ p)))))))

-- § Division by a positive factor recovers the quotient on exact multiples.
div-exact-multiple : (q : ℕ) → (d : ℕ⁺) → (q *ℕ ⁺toℕ d) div d ≡ q
div-exact-multiple q d =
 trans
  (cong (λ t → div-fuel t (q *ℕ ⁺toℕ d) d) (sym (+ℕ-zero-right (q *ℕ ⁺toℕ d))))
  (div-fuel-exact-multiple q zero d)
```

Positive divisibility theory

Before the gcd can serve the reduction pipeline, a divisibility language is needed. The raw statement "d divides n" must be a constructive record carrying the explicit quotient and the factorization proof, because later proofs need to extract that quotient for exact division. This is not a library convenience; it is forced by the absence of classical existentials in the safe base.

The $\mathrm{Divides}^+$ record captures exactly this: a positive divisor d, a quotient, and a proof that $n = q \cdot d$. From this single record, the section derives closure under addition, exact quotient extraction, quotient positivity, multiplication lift, right cancellation, order reflection, and subtraction—the complete divisibility algebra that the gcd engine needs.

Constraint: The gcd proofs require divisibility witnesses that carry computational content (the quotient), not merely propositional existence.

Construction: Any divisibility witness that lacks computational content—carrying only propositional existence without an explicit quotient—is eliminated by the downstream gcd

proofs. The only surviving form is a record Divides⁺ d n with field quotient⁺ and factorization proof. Closure under +, −, multiplication, and cancellation follows.

Consequence: Every later divisibility argument reduces to record operations on Divides⁺. No ad hoc arithmetic witness is needed downstream.

```
-- § Positive divisibility packages an explicit quotient witness.
record Divides⁺ (d : ℕ⁺) (n : ℕ) : Set where
 field
  quotient⁺ : ℕ
  factor⁺ : n ≡ quotient⁺ *ℕ ⁺toℕ d

open Divides⁺ public

-- § Every exact multiple yields a positive divisibility witness.
divides⁺-multiple : (q : ℕ) → (d : ℕ⁺) → Divides⁺ d (q *ℕ ⁺toℕ d)
divides⁺-multiple q d = record
 { quotient⁺ = q
 ; factor⁺ = refl
 }

-- § The divisor divides itself.
divides⁺-self : (d : ℕ⁺) → Divides⁺ d (⁺toℕ d)
divides⁺-self d = record
 { quotient⁺ = oneNat
 ; factor⁺ = sym (*ℕ-one-left (⁺toℕ d))
 }

-- § Zero is divisible by every positive natural.
divides⁺-zero : (d : ℕ⁺) → Divides⁺ d zero
divides⁺-zero d = record
 { quotient⁺ = zero
 ; factor⁺ = refl
 }

-- § Positive divisibility is closed under addition.
divides⁺-+ℕ : {d : ℕ⁺} {m n : ℕ} → Divides⁺ d m → Divides⁺ d n → Divides⁺ d (m +ℕ n)
divides⁺-+ℕ {d} {m} {n} dm dn = record
 { quotient⁺ = quotient⁺ dm +ℕ quotient⁺ dn
 ; factor⁺ =
   trans
    (cong₂ _+ℕ_ (factor⁺ dm) (factor⁺ dn))
    (sym (*ℕ-distrib-left-+ℕ (quotient⁺ dm) (quotient⁺ dn) (⁺toℕ d)))
 }

-- § Exact division extracts the stored quotient from a positive divisibility witness.
divides⁺→div : {d : ℕ⁺} {n : ℕ} → (dvd : Divides⁺ d n) → n div d ≡ quotient⁺ dvd
divides⁺→div {d} {n} dvd =
 trans
  (cong (λ t → t div d) (factor⁺ dvd))
  (div-exact-multiple (quotient⁺ dvd) d)

-- § A positive divisible natural has a positive stored quotient.
divides⁺-positive-quotient : {d : ℕ⁺} {n : ℕ} → (dvd : Divides⁺ d (suc n)) → Σ ℕ (λ k → quotient⁺ dvd ≡ suc k)
divides⁺-positive-quotient {d} {n} dvd with quotient⁺ dvd | factor⁺ dvd
... | zero | ()
... | suc k | _ = k , refl

-- § Built-in addition and manuscript addition coincide on naturals.
+-to-+ℕ : (m n : ℕ) → (m + n) ≡ (m +ℕ n)
+-to-+ℕ zero n = refl
```

```
+-to-+ℕ (suc m) n = cong suc (+-to-+ℕ m n)

-- § The ℕ-view of ℕ⁺ multiplication is ordinary natural multiplication.
⁺toℕ-*⁺ : (x y : ℕ⁺) → ⁺toℕ (x *⁺ y) ≡ ⁺toℕ x *ℕ ⁺toℕ y
⁺toℕ-*⁺ (mkℕ⁺ a) (mkℕ⁺ b) = cong suc (+ℕ-comm (a *ℕ suc b) b)

-- § Divisibility lifts through multiplication by a positive factor on the right.
divides⁺-mul-right : {e : ℕ⁺} {n : ℕ} → Divides⁺ e n → (d : ℕ⁺) → Divides⁺ (e *⁺ d) (n *ℕ ⁺toℕ d)
divides⁺-mul-right {e} {n} dvd d = record
 { quotient⁺ = quotient⁺ dvd
 ; factor⁺ =
   trans
    (cong (λ t → t *ℕ ⁺toℕ d) (factor⁺ dvd))
    (trans
     (*ℕ-assoc (quotient⁺ dvd) (⁺toℕ e) (⁺toℕ d))
     (cong (λ t → quotient⁺ dvd *ℕ t) (sym (⁺toℕ-*⁺ e d))))
 }

-- § Equality after multiplying by the same positive factor cancels on the right.
*ℕ-cancelʳ-suc : {a b : ℕ} → (k : ℕ) → a *ℕ suc k ≡ b *ℕ suc k → a ≡ b
*ℕ-cancelʳ-suc {a} {b} k eq =
 ≤-antisym
  (≤-*ℕ-cancelʳ-suc k (subst (λ t → (a *ℕ suc k) ≤ t) eq (≤-refl (a *ℕ suc k))))
  (≤-*ℕ-cancelʳ-suc k (subst (λ t → (b *ℕ suc k) ≤ t) (sym eq) (≤-refl (b *ℕ suc k))))

-- § A product of two positive naturals equals one only in the trivial case.
positive-product-one : (a b : ℕ) → suc a *ℕ suc b ≡ oneNat → (a ≡ zero) × (b ≡ zero)
positive-product-one a zero eq =
 let
  aEq : suc a ≡ oneNat
  aEq = trans (sym (*ℕ-one-right (suc a))) eq
 in
 suc-injective aEq , refl
positive-product-one a (suc b) ()

-- § If a product divisor of d also divides d, the extra factor must be one.
divides⁺-product-factor-left-one : (e d : ℕ⁺) → Divides⁺ (e *⁺ d) (⁺toℕ d) → e ≡ one⁺
divides⁺-product-factor-left-one e d dvd =
 let
  qPos : Σ ℕ (λ k → quotient⁺ dvd ≡ suc k)
  qPos = divides⁺-positive-quotient dvd

  k : ℕ
  k = fst qPos

  qEq : quotient⁺ dvd ≡ suc k
  qEq = snd qPos

  factored : ⁺toℕ d ≡ ((suc k *ℕ ⁺toℕ e) *ℕ ⁺toℕ d)
  factored =
   trans
    (factor⁺ dvd)
    (trans
     (cong (λ t → t *ℕ ⁺toℕ (e *⁺ d)) qEq)
     (trans
      (cong (λ t → suc k *ℕ t) (⁺toℕ-*⁺ e d))
      (sym (*ℕ-assoc (suc k) (⁺toℕ e) (⁺toℕ d)))))

  prodOne : suc k *ℕ ⁺toℕ e ≡ oneNat
  prodOne =
   *ℕ-cancelʳ-suc
    (pred d)
```

```
    (trans
     (sym factored)
     (sym (*ℕ-one-left (⁺toℕ d))))

  ePredZero : pred e ≡ zero
  ePredZero = snd (positive-product-one k (pred e) prodOne)
 in
 cong mkℕ⁺ ePredZero
```

The factor constraints above show that divisibility by a product forces each factor to be trivial when the product divides a single copy of one factor. This is the positive-integer analogue of the familiar number-theoretic fact that if $ab \mid b$, then $a = 1$. With this in hand, the machinery compares quotients: if d divides both m and n and $m \leq n$, then the stored quotient for m is at most the stored quotient for n.

```
– § Order on divisible multiples reflects to the stored quotients.
divides⁺-quotient-≤ :
 {d : ℕ⁺} {m n : ℕ} →
 m ≤ n →
 (dm : Divides⁺ d m) →
 (dn : Divides⁺ d n) →
 Divides⁺.quotient⁺ dm ≤ Divides⁺.quotient⁺ dn
divides⁺-quotient-≤ {mkℕ⁺ p} {m} {n} m≤n dm dn =
 let
  step₁ : m ≤ (Divides⁺.quotient⁺ dn *ℕ (suc p))
  step₁ = subst (λ t → m ≤ t) (Divides⁺.factor⁺ dn) m≤n

  step₂ : (Divides⁺.quotient⁺ dm *ℕ (suc p)) ≤ (Divides⁺.quotient⁺ dn *ℕ (suc p))
  step₂ = subst (λ t → t ≤ (Divides⁺.quotient⁺ dn *ℕ (suc p))) (Divides⁺.factor⁺ dm) step₁
 in
 ≤-*ℕ-cancelʳ-suc p step₂

– § Positive divisibility survives subtraction of a smaller divisible multiple.
divides⁺-∸-≤ :
 {d : ℕ⁺} {m n : ℕ} →
 m ≤ n →
 Divides⁺ d m →
 Divides⁺ d n →
 Divides⁺ d (n ∸ m)
divides⁺-∸-≤ {d} {m} {n} m≤n dm dn = record
 { quotient⁺ = Divides⁺.quotient⁺ dn ∸ Divides⁺.quotient⁺ dm
 ; factor⁺ = factor
 }
 where
  q≤ : Divides⁺.quotient⁺ dm ≤ Divides⁺.quotient⁺ dn
  q≤ = divides⁺-quotient-≤ m≤n dm dn

  qSplit : Divides⁺.quotient⁺ dm +ℕ (Divides⁺.quotient⁺ dn ∸ Divides⁺.quotient⁺ dm) ≡ Divides⁺.quotient⁺ dn
  qSplit = ≤→+ℕ-∸-split q≤

  nAsSum : n ≡ m +ℕ ((Divides⁺.quotient⁺ dn ∸ Divides⁺.quotient⁺ dm) *ℕ ⁺toℕ d)
  nAsSum =
   trans
    (Divides⁺.factor⁺ dn)
    (trans
     (sym (cong (λ t → t *ℕ ⁺toℕ d) qSplit))
     (trans
      (*ℕ-distrib-left-+ℕ (Divides⁺.quotient⁺ dm) (Divides⁺.quotient⁺ dn ∸ Divides⁺.quotient⁺ dm) (⁺toℕ d))
      (cong (λ t → t +ℕ ((Divides⁺.quotient⁺ dn ∸ Divides⁺.quotient⁺ dm) *ℕ ⁺toℕ d)) (sym (Divides⁺.factor⁺ dm)))))
```

```
  factor : n ∸ m ≡ (Divides⁺.quotient⁺ dn ∸ Divides⁺.quotient⁺ dm) *ℕ ⁺toℕ d
  factor = subst (λ t → t ∸ m ≡ (Divides⁺.quotient⁺ dn ∸ Divides⁺.quotient⁺ dm) *ℕ ⁺toℕ d) (sym nAsSum)
   (+ℕ-∸-cancel-left m ((Divides⁺.quotient⁺ dn ∸ Divides⁺.quotient⁺ dm) *ℕ ⁺toℕ d))

-- § Adding back a divisible remainder recovers divisibility of the larger number.
divides⁺-restore-∸ :
 {d : ℕ⁺} {m n : ℕ} →
 m ≤ n →
 Divides⁺ d m →
 Divides⁺ d (n ∸ m) →
 Divides⁺ d n
divides⁺-restore-∸ {d} {m} {n} m≤n dm dnm =
 subst
  (Divides⁺ d)
  (≤→+ℕ-∸-split m≤n)
  (divides⁺-+ℕ dm dnm)

-- § The ℕ-view of sucToℕ⁺ is the expected successor.
⁺toℕ-sucToℕ⁺ : (n : ℕ) → ⁺toℕ (sucToℕ⁺ n) ≡ suc n
⁺toℕ-sucToℕ⁺ zero = refl
⁺toℕ-sucToℕ⁺ (suc n) = cong suc (⁺toℕ-sucToℕ⁺ n)

-- § The successor-coded positive natural divides its own ℕ-view.
divides⁺-suc-self : (n : ℕ) → Divides⁺ (sucToℕ⁺ n) (suc n)
divides⁺-suc-self n =
 subst
  (Divides⁺ (sucToℕ⁺ n))
  (⁺toℕ-sucToℕ⁺ n)
  (divides⁺-self (sucToℕ⁺ n))

-- § Zero/zero is a stable fixed point of gcd-fuel.
gcd-fuel-zero-zero : (f : ℕ) → gcd-fuel f zero zero ≡ zero
gcd-fuel-zero-zero zero = refl
gcd-fuel-zero-zero (suc f) = refl

-- § Positive fuel with a zero left input returns the right input.
gcd-fuel-zero-left-suc : (f n : ℕ) → gcd-fuel (suc f) zero (suc n) ≡ suc n
gcd-fuel-zero-left-suc f n = refl

-- § Positive fuel with a zero right input returns the left input.
gcd-fuel-zero-right-suc : (f m : ℕ) → gcd-fuel (suc f) (suc m) zero ≡ suc m
gcd-fuel-zero-right-suc f m = refl

-- § One Euclidean subtraction step preserves the total positive mass in the true branch.
euclid-sum-true : {m n : ℕ} → m ≤ n → (suc m) +ℕ (n ∸ m) ≡ suc n
euclid-sum-true p = cong suc (≤→+ℕ-∸-split p)

-- § One Euclidean subtraction step preserves the total positive mass in the false branch.
euclid-sum-false : {m n : ℕ} → n ≤ m → (m ∸ n) +ℕ (suc n) ≡ suc m
euclid-sum-false {m} {n} p =
 trans
  (+ℕ-comm (m ∸ n) (suc n))
  (cong suc (≤→+ℕ-∸-split p))
```

GCD engine: common-divisor preservation, output divisibility, and positivity

The Euclidean gcd is defined, but a bare recurrence carries no force. Three properties must be forged before the gcd can serve the reduction pipeline:

Common-divisor preservation. Any positive integer that divides both inputs must still divide the output. This is the "upward" direction: known divisors survive the algorithm. The proof proceeds by mutual structural recursion, tracking divisibility through each subtraction step via the already established divides⁺-∸-≤ lemma.

Output divisibility. Conversely, if the gcd output is positive, it divides both inputs. This is the "downward" direction: the output itself is a common divisor. The proof is again by structural recursion on fuel, restoring divisibility through the subtraction witness at each step.

Positivity. Whenever at least one input is positive, the gcd output is also positive. This eliminates the degenerate case and ensures that the canonical reduction divisor is always well-formed as a positive natural.

Together, these three properties force the gcd to behave as the *greatest* common divisor in the usual sense: it divides both inputs, and every other common divisor divides it.

```
– § Every natural is bounded by its own right extension.
≤-self+ℕ : (m n : ℕ) → m ≤ (m +ℕ n)
≤-self+ℕ zero n = z≤n
≤-self+ℕ (suc m) n = s≤s (≤-self+ℕ m n)

mutual
 – § One recursive Euclidean step preserves any common positive divisor.
 gcd-fuel-common-divisor-step :
  {d : ℕ⁺} →
  (f m n : ℕ) →
  (b : Bool) →
  m ≤ℕ n ≡ b →
  Divides⁺ d (suc m) →
  Divides⁺ d (suc n) →
  Divides⁺ d (gcd-fuel-step f (suc m) (suc n) b)
 gcd-fuel-common-divisor-step f m n true eq dm dn =
  gcd-fuel-common-divisor f (suc m) (n ∸ m) dm
   (divides⁺-∸-≤ (s≤s (≤ℕ-true→≤ eq)) dm dn)
 gcd-fuel-common-divisor-step f m n false eq dm dn =
  gcd-fuel-common-divisor f (m ∸ n) (suc n)
   (divides⁺-∸-≤ (s≤s (≤ℕ-false→≤ eq)) dn dm)
   dn

 – § Any common positive divisor survives every Euclidean gcd-fuel step.
 gcd-fuel-common-divisor :
  {d : ℕ⁺} →
  (f m n : ℕ) →
  Divides⁺ d m →
  Divides⁺ d n →
  Divides⁺ d (gcd-fuel f m n)
 gcd-fuel-common-divisor zero m n dm dn = dm
 gcd-fuel-common-divisor (suc f) zero zero dm dn = divides⁺-zero _
 gcd-fuel-common-divisor (suc f) zero (suc n) dm dn = dn
 gcd-fuel-common-divisor (suc f) (suc m) zero dm dn = dm
 gcd-fuel-common-divisor {d} (suc f) (suc m) (suc n) dm dn =
  subst
   (Divides⁺ d)
   (sym (gcd-fuel-suc-suc f m n))
   (gcd-fuel-common-divisor-step f m n (m ≤ℕ n) refl dm dn)

 – § Phase 2: Positive gcd outputs divide both original inputs

– § Under sufficient fuel, every positive gcd-fuel output divides both inputs.
```

```
gcd-fuel-positive-output-divides≤ :
 (fuel m n g : ℕ) →
 ((m +ℕ n) ≤ fuel) →
 (gcd-fuel fuel m n ≡ suc g) →
 ((Divides⁺ (sucToℕ⁺ g) m) × (Divides⁺ (sucToℕ⁺ g) n))
gcd-fuel-positive-output-divides≤ fuel zero zero g enough eq with trans (sym (gcd-fuel-zero-zero fuel)) eq
... | ()
gcd-fuel-positive-output-divides≤ zero zero (suc n) g () eq
gcd-fuel-positive-output-divides≤ (suc fuel) zero (suc n) g enough eq =
 divides⁺-zero (sucToℕ⁺ g) ,
 subst
  (Divides⁺ (sucToℕ⁺ g))
  (sym eq')
  (divides⁺-suc-self g)
 where
  eq' : suc n ≡ suc g
  eq' = trans (sym (gcd-fuel-zero-left-suc fuel n)) eq
gcd-fuel-positive-output-divides≤ zero (suc m) zero g () eq
gcd-fuel-positive-output-divides≤ (suc fuel) (suc m) zero g enough eq =
 subst
  (Divides⁺ (sucToℕ⁺ g))
  (sym eq')
  (divides⁺-suc-self g)
 , divides⁺-zero (sucToℕ⁺ g)
 where
  eq' : suc m ≡ suc g
  eq' = trans (sym (gcd-fuel-zero-right-suc fuel m)) eq
gcd-fuel-positive-output-divides≤ (suc fuel) (suc m) (suc n) g (s≤s enough') eq with inspect (m ≤ℕ n)
... | reveal true bEq =
 let
  p : m ≤ n
  p = ≤ℕ-true→≤ bEq

  sucn≤sum : suc n ≤ (m +ℕ suc n)
  sucn≤sum = subst (λ t → suc n ≤ t) (+ℕ-comm (suc n) m) (≤-self+ℕ (suc n) m)

  subEnough : ((suc m) +ℕ (n ∸ m)) ≤ fuel
  subEnough = subst (λ t → t ≤ fuel) (sym (euclid-sum-true p)) (≤-trans sucn≤sum enough')

  stepEq₀ : gcd-fuel-step fuel (suc m) (suc n) (m ≤ℕ n) ≡ suc g
  stepEq₀ = trans (sym (gcd-fuel-suc-suc fuel m n)) eq

  stepEq : gcd-fuel fuel (suc m) (n ∸ m) ≡ suc g
  stepEq = trans (sym (cong (gcd-fuel-step fuel (suc m) (suc n)) bEq)) stepEq₀

  rec : Divides⁺ (sucToℕ⁺ g) (suc m) × Divides⁺ (sucToℕ⁺ g) (n ∸ m)
  rec = gcd-fuel-positive-output-divides≤ fuel (suc m) (n ∸ m) g subEnough stepEq

  dm : Divides⁺ (sucToℕ⁺ g) (suc m)
  dm = fst rec

  dn-rest : Divides⁺ (sucToℕ⁺ g) (n ∸ m)
  dn-rest = snd rec
 in
 dm , divides⁺-restore-∸ (s≤s p) dm dn-rest
... | reveal false bEq =
 let
  p : n ≤ m
  p = ≤ℕ-false→≤ bEq

  sucm≤sum : suc m ≤ (m +ℕ suc n)
  sucm≤sum = subst (λ t → suc m ≤ t) (sym (+ℕ-suc-right m n)) (≤-self+ℕ (suc m) n)
```

```
  subEnough : ((m ∸ n) +ℕ (suc n)) ≤ fuel
  subEnough = subst (λ t → t ≤ fuel) (sym (euclid-sum-false p)) (≤-trans sucm≤sum enough')

  stepEq₀ : gcd-fuel-step fuel (suc m) (suc n) (m ≤ℕ n) ≡ suc g
  stepEq₀ = trans (sym (gcd-fuel-suc-suc fuel m n)) eq

  stepEq : gcd-fuel fuel (m ∸ n) (suc n) ≡ suc g
  stepEq = trans (sym (cong (gcd-fuel-step fuel (suc m) (suc n)) bEq)) stepEq₀

  rec : Divides⁺ (sucToℕ⁺ g) (m ∸ n) × Divides⁺ (sucToℕ⁺ g) (suc n)
  rec = gcd-fuel-positive-output-divides≤ fuel (m ∸ n) (suc n) g subEnough stepEq

  dm-rest : Divides⁺ (sucToℕ⁺ g) (m ∸ n)
  dm-rest = fst rec

  dn : Divides⁺ (sucToℕ⁺ g) (suc n)
  dn = snd rec
in
divides⁺-restore-∸ (s≤s p) dn dm-rest , dn
```

The inductive core of the gcd engine is established: for any fuel level sufficient to reach termination, the positive output divides both inputs. The remaining step generalises this to the canonical fuel formula $\mathrm{slack} + (m + n)$, which always provides enough iterations. This is the interface consumed by the rational reduction machinery above.

```
– § Canonical-or-greater fuel is enough to turn any positive output into a common divisor.
gcd-fuel-positive-output-divides :
 (slack m n g : ℕ) →
 (gcd-fuel (slack +ℕ (m +ℕ n)) m n ≡ suc g) →
 ((Divides⁺ (sucToℕ⁺ g) m) × (Divides⁺ (sucToℕ⁺ g) n))
gcd-fuel-positive-output-divides slack m n g eq =
 gcd-fuel-positive-output-divides≤
  (slack +ℕ (m +ℕ n))
  m
  n
  g
  (subst
   (λ t → (m +ℕ n) ≤ t)
   (+ℕ-comm (m +ℕ n) slack)
   (≤-self+ℕ (m +ℕ n) slack))
  eq

– § Phase 3: Positive total mass forces a positive gcd

– § Any common positive divisor of m and n divides gcd m n.
common-divisor-divides-gcd :
 {d : ℕ⁺} →
 (m n : ℕ) →
 Divides⁺ d m →
 Divides⁺ d n →
 Divides⁺ d (gcd m n)
common-divisor-divides-gcd {d} m n dm dn =
 subst
  (Divides⁺ d)
  (sym (cong (λ t → gcd-fuel t m n) (+-to-+ℕ m n)))
  (gcd-fuel-common-divisor (m +ℕ n) m n dm dn)

– § Under sufficient fuel, a positive total input mass forces a positive gcd-fuel output.
gcd-fuel-positive-sum≤ :
```

```
  (fuel m n s : ℕ) →
  (m +ℕ n ≡ suc s) →
  ((m +ℕ n) ≤ fuel) →
  Σ ℕ (λ g → gcd-fuel fuel m n ≡ suc g)
gcd-fuel-positive-sum≤ zero zero zero s () enough
gcd-fuel-positive-sum≤ zero zero (suc n) s sumEq ()
gcd-fuel-positive-sum≤ zero (suc m) zero s sumEq ()
gcd-fuel-positive-sum≤ zero (suc m) (suc n) s sumEq ()
gcd-fuel-positive-sum≤ (suc fuel) zero zero s () enough
gcd-fuel-positive-sum≤ (suc fuel) zero (suc n) s sumEq enough = n , gcd-fuel-zero-left-suc fuel n
gcd-fuel-positive-sum≤ (suc fuel) (suc m) zero s sumEq enough = m , gcd-fuel-zero-right-suc fuel m
gcd-fuel-positive-sum≤ (suc fuel) (suc m) (suc n) s sumEq (s≤s enough') with inspect (m ≤ℕ n)
... | reveal true bEq =
  let
    p : m ≤ n
    p = ≤ℕ-true→≤ bEq

    sucn≤sum : suc n ≤ (m +ℕ suc n)
    sucn≤sum = subst (λ t → suc n ≤ t) (+ℕ-comm (suc n) m) (≤-self+ℕ (suc n) m)

    subEnough : ((suc m) +ℕ (n ∸ m)) ≤ fuel
    subEnough = subst (λ t → t ≤ fuel) (sym (euclid-sum-true p)) (≤-trans sucn≤sum enough')

    subSum : (suc m) +ℕ (n ∸ m) ≡ suc n
    subSum = euclid-sum-true p

    stepEq₀ : gcd-fuel-step fuel (suc m) (suc n) (m ≤ℕ n) ≡ gcd-fuel fuel (suc m) (n ∸ m)
    stepEq₀ = cong (gcd-fuel-step fuel (suc m) (suc n)) bEq

    rec : Σ ℕ (λ g → gcd-fuel fuel (suc m) (n ∸ m) ≡ suc g)
    rec = gcd-fuel-positive-sum≤ fuel (suc m) (n ∸ m) n subSum subEnough
  in
  fst rec , trans (gcd-fuel-suc-suc fuel m n) (trans stepEq₀ (snd rec))
... | reveal false bEq =
  let
    p : n ≤ m
    p = ≤ℕ-false→≤ bEq

    sucm≤sum : suc m ≤ (m +ℕ suc n)
    sucm≤sum = subst (λ t → suc m ≤ t) (sym (+ℕ-suc-right m n)) (≤-self+ℕ (suc m) n)

    subEnough : ((m ∸ n) +ℕ (suc n)) ≤ fuel
    subEnough = subst (λ t → t ≤ fuel) (sym (euclid-sum-false p)) (≤-trans sucm≤sum enough')

    subSum : (m ∸ n) +ℕ (suc n) ≡ suc m
    subSum = euclid-sum-false p

    stepEq₀ : gcd-fuel-step fuel (suc m) (suc n) (m ≤ℕ n) ≡ gcd-fuel fuel (m ∸ n) (suc n)
    stepEq₀ = cong (gcd-fuel-step fuel (suc m) (suc n)) bEq

    rec : Σ ℕ (λ g → gcd-fuel fuel (m ∸ n) (suc n) ≡ suc g)
    rec = gcd-fuel-positive-sum≤ fuel (m ∸ n) (suc n) m subSum subEnough
  in
  fst rec , trans (gcd-fuel-suc-suc fuel m n) (trans stepEq₀ (snd rec))

-- § The canonical gcd of a positive denominator is itself positive.
gcd-positive-right : (m : ℕ) → (d : ℕ⁺) → Σ ℕ (λ g → gcd m (⁺toℕ d) ≡ suc g)
gcd-positive-right m d =
  let
    pack : Σ ℕ (λ g → gcd-fuel (m +ℕ ⁺toℕ d) m (⁺toℕ d) ≡ suc g)
    pack =
      gcd-fuel-positive-sum≤
```

```
    (m +ℕ ⁺toℕ d)
    m
    (⁺toℕ d)
    (m +ℕ pred d)
    (+ℕ-suc-right m (pred d))
    (≤-refl (m +ℕ ⁺toℕ d))
  in
  fst pack ,
   trans
    (cong (λ t → gcd-fuel t m (⁺toℕ d)) (+-to-+ℕ m (⁺toℕ d)))
    (snd pack)
```

Canonical reduction candidate and divisibility

The gcd engine and the divisibility theory are both in place. The canonical reduction candidate is therefore forced: given a rational $q = n/d$, compute $g = \gcd(|n|, d)$, and define the reduced numerator as $|n|/g$ and the reduced denominator as d/g. The "candidate" is not a guess; it is the unique pair obtained by dividing out the maximal common factor.

Three properties must survive. First, the canonical divisor g is itself positive—forced by the gcd-positivity theorem on the positive denominator. Second, the $\mathbb{N}$-view of the divisor equals the computed gcd—a bookkeeping identity that eliminates the successor-encoding detour. Third, the divisor divides both the numerator magnitude and the denominator—forced by the output-divisibility theorem already established for the gcd engine.

Constraint: The reduction candidate must be computable from the raw fields and must preserve the rational class up to $\simeq_{\mathbb{Q}}$. Any alternative decomposition would reintroduce presentation freedom.

Construction: Any reduction candidate not computable from the raw fields, or failing to preserve the rational class up to $\simeq_{\mathbb{Q}}$, is eliminated. The unique surviving candidate is canonical-reduction-divisor $= \mathrm{mk}\mathbb{N}^{+}(\gcd(|n|, d) - 1)$. The numerator and denominator are then forced by exact division. Positivity, value agreement, and divisibility follow from the candidate's definition.

Consequence: The candidate is well-defined and the gcd divides both fields. The factorization and coprimality proofs that follow proceed from concrete divisibility witnesses.

```
-- § The successor-coded positive natural is definitionally mkℕ⁺.
sucToℕ⁺-mkℕ⁺ : (n : ℕ) → sucToℕ⁺ n ≡ mkℕ⁺ n
sucToℕ⁺-mkℕ⁺ zero = refl
sucToℕ⁺-mkℕ⁺ (suc n) = cong suc⁺ (sucToℕ⁺-mkℕ⁺ n)

-- § The gcd used by the canonical reduction candidate.
canonical-reduction-divisor : ℚ → ℕ⁺
canonical-reduction-divisor q = mkℕ⁺ (gcd (magℤ (num q)) (⁺toℕ (den q)) ∸ 1)

-- § Phase 2: Divide both fields by the forced gcd

-- § Candidate reduced numerator obtained by dividing out the computed gcd.
canonical-reduction-num : ℚ → ℕ
canonical-reduction-num q = magℤ (num q) div canonical-reduction-divisor q

-- § Candidate reduced denominator obtained by dividing out the computed gcd.
```

```
canonical-reduction-den : ℚ → ℕ⁺
canonical-reduction-den q = mkℕ⁺ ((⁺toℕ (den q) div canonical-reduction-divisor q) ∸ 1)

-- § Package the raw gcd/division reduction candidate.
record CanonicalReductionCandidate (q : ℚ) : Set where
 field
   cand-divisor : ℕ⁺
   cand-num : ℕ
   cand-den : ℕ⁺

canonical-reduction-candidate : (q : ℚ) → CanonicalReductionCandidate q
canonical-reduction-candidate q = record
 { cand-divisor = canonical-reduction-divisor q
 ; cand-num = canonical-reduction-num q
 ; cand-den = canonical-reduction-den q
 }

-- § The canonical reduction divisor is the positive gcd itself.
canonical-reduction-divisor-positive :
 (q : ℚ) →
 Σ ℕ (λ g → canonical-reduction-divisor q ≡ sucToℕ⁺ g)
canonical-reduction-divisor-positive q =
 let
   gPack : Σ ℕ (λ g → gcd (magℤ (num q)) (⁺toℕ (den q)) ≡ suc g)
   gPack = gcd-positive-right (magℤ (num q)) (den q)

   g : ℕ
   g = fst gPack

   gcdEq : gcd (magℤ (num q)) (⁺toℕ (den q)) ≡ suc g
   gcdEq = snd gPack
 in
 g ,
   trans
    (cong (λ t → mkℕ⁺ (t ∸ 1)) gcdEq)
    (trans
     (cong mkℕ⁺ (∸-one-suc g))
     (sym (sucToℕ⁺-mkℕ⁺ g)))

-- § The ℕ-view of the canonical reduction divisor is the computed gcd.
canonical-reduction-divisor-value :
 (q : ℚ) →
 ⁺toℕ (canonical-reduction-divisor q) ≡ gcd (magℤ (num q)) (⁺toℕ (den q))
canonical-reduction-divisor-value q with gcd-positive-right (magℤ (num q)) (den q)
... | g , gcdEq =
 let
   divEq : canonical-reduction-divisor q ≡ sucToℕ⁺ g
   divEq =
    trans
     (cong (λ t → mkℕ⁺ (t ∸ 1)) gcdEq)
     (trans
      (cong mkℕ⁺ (∸-one-suc g))
      (sym (sucToℕ⁺-mkℕ⁺ g)))
 in
 trans
   (cong ⁺toℕ divEq)
   (trans
    (⁺toℕ-sucToℕ⁺ g)
    (sym gcdEq))

-- § The canonical reduction divisor divides the visible numerator magnitude.
canonical-reduction-divides-num :
```

```
 (q : ℚ) →
 Divides⁺ (canonical-reduction-divisor q) (magℤ (num q))
canonical-reduction-divides-num q with gcd-positive-right (magℤ (num q)) (den q)
... | g , gcdEq =
 let
   divEq : canonical-reduction-divisor q ≡ sucToℕ⁺ g
   divEq =
    trans
     (cong (λ t → mkℕ⁺ (t ∸ 1)) gcdEq)
     (trans
      (cong mkℕ⁺ (∸-one-suc g))
      (sym (sucToℕ⁺-mkℕ⁺ g)))

   gcdEq+ℕ : gcd-fuel (magℤ (num q) +ℕ ⁺toℕ (den q)) (magℤ (num q)) (⁺toℕ (den q)) ≡ suc g
   gcdEq+ℕ =
    trans
     (sym (cong (λ t → gcd-fuel t (magℤ (num q)) (⁺toℕ (den q))) (+-to-+ℕ (magℤ (num q)) (⁺toℕ (den q)))))
     gcdEq
 in
 subst
   (λ t → Divides⁺ t (magℤ (num q)))
   (sym divEq)
   (fst
    (gcd-fuel-positive-output-divides
     zero
     (magℤ (num q))
     (⁺toℕ (den q))
     g
     gcdEq+ℕ))

-- § The canonical reduction divisor divides the visible denominator.
canonical-reduction-divides-den :
 (q : ℚ) →
 Divides⁺ (canonical-reduction-divisor q) (⁺toℕ (den q))
canonical-reduction-divides-den q with gcd-positive-right (magℤ (num q)) (den q)
... | g , gcdEq =
 let
   divEq : canonical-reduction-divisor q ≡ sucToℕ⁺ g
   divEq =
    trans
     (cong (λ t → mkℕ⁺ (t ∸ 1)) gcdEq)
     (trans
      (cong mkℕ⁺ (∸-one-suc g))
      (sym (sucToℕ⁺-mkℕ⁺ g)))

   gcdEq+ℕ : gcd-fuel (magℤ (num q) +ℕ ⁺toℕ (den q)) (magℤ (num q)) (⁺toℕ (den q)) ≡ suc g
   gcdEq+ℕ =
    trans
     (sym (cong (λ t → gcd-fuel t (magℤ (num q)) (⁺toℕ (den q))) (+-to-+ℕ (magℤ (num q)) (⁺toℕ (den q)))))
     gcdEq
 in
 subst
   (λ t → Divides⁺ t (⁺toℕ (den q)))
   (sym divEq)
   (snd
    (gcd-fuel-positive-output-divides
     zero
     (magℤ (num q))
     (⁺toℕ (den q))
     g
     gcdEq+ℕ))
```

Factorization, coprimality, and witness stabilization

The canonical reduction divisor now divides both the numerator magnitude and the denominator. The next forced step is to show that dividing out the gcd produces a coprime pair—so that the candidate is genuinely reduced—and that the entire candidate stabilizes on any input that is already reduced.

Factorization is read directly from the exact-division infrastructure: since the gcd divides both fields, exact division recovers the quotients, and the original fields are the product of quotient times divisor. Coprimality then follows by contradiction: any common divisor of the reduced pair would lift, through multiplication by the gcd, to a common divisor of the *original* pair that exceeds the gcd itself—which contradicts the maximality of the gcd.

Stabilization completes the picture. If the input is already irreducible, the gcd is 1, division by one leaves the fields unchanged, and the candidate collapses to the original witness. This guarantees that the reduction pipeline is idempotent: applying it twice yields the same result as applying it once.

Constraint: Without coprimality, the "reduced" candidate might still hide common factors, and the uniqueness guarantee downstream would fail.

Elimination: Factor both fields through exact division; eliminate any putative common divisor by lifting it back through the gcd—where it is absorbed; eliminate instability by specializing to divisor = 1. The candidate survives all three tests.

Consequence: The canonical candidate is a genuine reduced pair. The reduced witness is idempotent. Every later reference to "the reduced form" is unambiguous.

```
-- § The candidate numerator factorization follows from exact division.
canonical-reduction-num-factor :
 (q : ℚ) →
 magℤ (num q)
 ≡ canonical-reduction-num q *ℕ ⁺toℕ (canonical-reduction-divisor q)
canonical-reduction-num-factor q =
 let
  dvd : Divides⁺ (canonical-reduction-divisor q) (magℤ (num q))
  dvd = canonical-reduction-divides-num q
 in
 trans
  (Divides⁺.factor⁺ dvd)
  (cong (λ t → t *ℕ ⁺toℕ (canonical-reduction-divisor q)) (sym (divides⁺→div dvd)))

-- § The candidate denominator factorization follows from exact division.
canonical-reduction-den-factor :
 (q : ℚ) →
 ⁺toℕ (den q)
 ≡ ⁺toℕ (canonical-reduction-den q) *ℕ ⁺toℕ (canonical-reduction-divisor q)
canonical-reduction-den-factor q =
 let
  dvd : Divides⁺ (canonical-reduction-divisor q) (⁺toℕ (den q))
  dvd = canonical-reduction-divides-den q

  qPos : Σ ℕ (λ k → quotient⁺ dvd ≡ suc k)
  qPos = divides⁺-positive-quotient dvd

  k : ℕ
  k = fst qPos
```

```
  qEq : quotient⁺ dvd ≡ suc k
  qEq = snd qPos

  denQuotEq : ⁺toℕ (canonical-reduction-den q) ≡ quotient⁺ dvd
  denQuotEq =
   let
    denEq : canonical-reduction-den q ≡ sucToℕ⁺ k
    denEq =
     trans
      (cong mkℕ⁺ (cong (λ t → t ∸ 1) (trans (divides⁺→div dvd) qEq)))
      (trans
       (cong mkℕ⁺ (∸-one-suc k))
       (sym (sucToℕ⁺-mkℕ⁺ k)))
   in
   trans
    (cong ⁺toℕ denEq)
    (trans
     (⁺toℕ-sucToℕ⁺ k)
     (sym qEq))
 in
 trans
  (Divides⁺.factor⁺ dvd)
  (cong (λ t → t *ℕ ⁺toℕ (canonical-reduction-divisor q)) (sym denQuotEq))

-- § Any common positive divisor of the canonical reduced pair is forced to be one.
canonical-reduction-common-divisor-one :
 (q : ℚ) →
 {e : ℕ⁺} →
 Divides⁺ e (canonical-reduction-num q) →
 Divides⁺ e (⁺toℕ (canonical-reduction-den q)) →
 e ≡ one⁺
canonical-reduction-common-divisor-one q {e} dnum dden =
 let
  liftedNum : Divides⁺ (e *⁺ canonical-reduction-divisor q) (magℤ (num q))
  liftedNum =
   subst
    (Divides⁺ (e *⁺ canonical-reduction-divisor q))
     (sym (canonical-reduction-num-factor q))
    (divides⁺-mul-right dnum (canonical-reduction-divisor q))

  liftedDen : Divides⁺ (e *⁺ canonical-reduction-divisor q) (⁺toℕ (den q))
  liftedDen =
   subst
    (Divides⁺ (e *⁺ canonical-reduction-divisor q))
     (sym (canonical-reduction-den-factor q))
    (divides⁺-mul-right dden (canonical-reduction-divisor q))

  gcdDiv : Divides⁺ (e *⁺ canonical-reduction-divisor q) (gcd (magℤ (num q)) (⁺toℕ (den q)))
  gcdDiv = common-divisor-divides-gcd (magℤ (num q)) (⁺toℕ (den q)) liftedNum liftedDen

  divisorDiv : Divides⁺ (e *⁺ canonical-reduction-divisor q) (⁺toℕ (canonical-reduction-divisor q))
  divisorDiv =
   subst
    (Divides⁺ (e *⁺ canonical-reduction-divisor q))
     (sym (canonical-reduction-divisor-value q))
    gcdDiv
 in
 divides⁺-product-factor-left-one e (canonical-reduction-divisor q) divisorDiv

-- § Phase 2: Eliminate every leftover common factor
```

```
-- § The canonical reduced numerator and denominator are coprime.
canonical-reduction-candidate-coprime :
 (q : ℚ) →
 gcd (canonical-reduction-num q) (⁺toℕ (canonical-reduction-den q)) ≡ 1
canonical-reduction-candidate-coprime q with gcd-positive-right (canonical-reduction-num q) (canonical-reduction-den q)
... | g , gcdEq =
 let
  gcdEq+ℕ : gcd-fuel (canonical-reduction-num q +ℕ ⁺toℕ (canonical-reduction-den q)) (canonical-reduction-num q) (⁺toℕ (canonical-reduction-den q)) ≡
  gcdEq+ℕ =
   trans
    (sym (cong (λ t → gcd-fuel t (canonical-reduction-num q) (⁺toℕ (canonical-reduction-den q))) (+-to-+ℕ (canonical-reduction-num q) (⁺toℕ (canonical-r
    gcdEq

  divisorPair : Divides⁺ (sucToℕ⁺ g) (canonical-reduction-num q) × Divides⁺ (sucToℕ⁺ g) (⁺toℕ (canonical-reduction-den q))
  divisorPair =
   gcd-fuel-positive-output-divides
    zero
    (canonical-reduction-num q)
    (⁺toℕ (canonical-reduction-den q))
    g
    gcdEq+ℕ

  oneEq : sucToℕ⁺ g ≡ one⁺
  oneEq = canonical-reduction-common-divisor-one q (fst divisorPair) (snd divisorPair)
 in
 trans
  gcdEq
  (trans
   (sym (⁺toℕ-sucToℕ⁺ g))
   (cong ⁺toℕ oneEq))

-- § A reduced witness fixes the visible quotient fields of q.
reduced-witness-fields :
 {q : ℚ} →
 (r : ReducedRationalWitness q) →
 num q ≡ fromℕℤ (ReducedRationalWitness.red-num r)
 × den q ≡ ReducedRationalWitness.red-den r
reduced-witness-fields {n / d} r =
 rational-fields-unique (n / d)
  n
  (fromℕℤ (ReducedRationalWitness.red-num r))
  d
  (ReducedRationalWitness.red-den r)
  refl
  (ReducedRationalWitness.red-value r)
```

The gcd machinery has confirmed that the canonical divisor is one, and the field-extraction lemma locks the numerator and denominator of the reduced witness to the original quotient fields. These are bookkeeping results—they do not change the mathematical content, but they allow every subsequent proof to refer to the reduced form without re-deriving the field correspondence each time.

The next step converts a reduced witness into a full irreducibility certificate. Once this is in hand, any rational that admits a reduced witness is provably in lowest terms, and no further simplification is possible.

```
-- § Every reduced witness certifies irreducibility of the represented quotient.
reduced-witness-irred : {q : ℚ} → (r : ReducedRationalWitness q) → IrreducibleQuotient q
reduced-witness-irred {q} r =
```

```
 let
   numEq = fst (reduced-witness-fields r)
   denEq = snd (reduced-witness-fields r)
   magEq : magℤ (num q) ≡ ReducedRationalWitness.red-num r
   magEq = trans (cong magℤ numEq) (magℤ-fromℕℤ (ReducedRationalWitness.red-num r))

   denNatEq : ⁺toℕ (den q) ≡ ⁺toℕ (ReducedRationalWitness.red-den r)
   denNatEq = cong ⁺toℕ denEq

   gcdEq : gcd (magℤ (num q)) (⁺toℕ (den q)) ≡ gcd (ReducedRationalWitness.red-num r) (⁺toℕ (ReducedRationalWitness.red-den r))
   gcdEq =
     trans
      (cong (λ t → gcd t (⁺toℕ (den q))) magEq)
      (cong (gcd (ReducedRationalWitness.red-num r)) denNatEq)
 in
 trans gcdEq (ReducedRationalWitness.red-coprime r)

-- § On a reduced witness, the canonical gcd collapses to one.
canonical-reduction-divisor-from-reduced :
 {q : ℚ} →
 (r : ReducedRationalWitness q) →
 canonical-reduction-divisor q ≡ one⁺
canonical-reduction-divisor-from-reduced r =
 trans
  (cong (λ t → mkℕ⁺ (t ∸ 1)) (reduced-witness-irred r))
  refl

-- § Phase 3: Stabilization on already reduced input

-- § The canonical candidate numerator stabilizes on any reduced witness.
canonical-reduction-num-from-reduced :
 {q : ℚ} →
 (r : ReducedRationalWitness q) →
 canonical-reduction-num q ≡ ReducedRationalWitness.red-num r
canonical-reduction-num-from-reduced {q} r =
 let
   numEq = fst (reduced-witness-fields r)
   magEq : magℤ (num q) ≡ ReducedRationalWitness.red-num r
   magEq = trans (cong magℤ numEq) (magℤ-fromℕℤ (ReducedRationalWitness.red-num r))

   divEq :
     magℤ (num q) div canonical-reduction-divisor q
     ≡ magℤ (num q) div one⁺
   divEq = cong (λ t → magℤ (num q) div t) (canonical-reduction-divisor-from-reduced r)
 in
 trans divEq (trans (div-one⁺ (magℤ (num q))) magEq)

-- § The canonical candidate denominator stabilizes on any reduced witness.
canonical-reduction-den-from-reduced :
 {q : ℚ} →
 (r : ReducedRationalWitness q) →
 canonical-reduction-den q ≡ ReducedRationalWitness.red-den r
canonical-reduction-den-from-reduced {q} r =
 let
   denEq = snd (reduced-witness-fields r)
   denNatEq : ⁺toℕ (den q) ≡ ⁺toℕ (ReducedRationalWitness.red-den r)
   denNatEq = cong ⁺toℕ denEq

   step :
     (⁺toℕ (den q) div canonical-reduction-divisor q)
     ≡ ⁺toℕ (ReducedRationalWitness.red-den r)
   step =
```

```
    trans
     (cong (λ t → ⁺toℕ (den q) div t) (canonical-reduction-divisor-from-reduced r))
     (trans (div-one⁺ (⁺toℕ (den q))) denNatEq)
 in
 trans
  (cong mkℕ⁺ (cong (λ t → t ∸ 1) step))
  (mkℕ⁺-⁺toℕ-minus-one (ReducedRationalWitness.red-den r))

– § The full canonical reduction candidate stabilizes on any reduced witness.
canon-red-candidate-from-reduced :
 {q : ℚ} →
 (r : ReducedRationalWitness q) →
 CanonicalReductionCandidate.cand-divisor
  (canonical-reduction-candidate q) ≡ one⁺
 × CanonicalReductionCandidate.cand-num
    (canonical-reduction-candidate q) ≡
    ReducedRationalWitness.red-num r
 × CanonicalReductionCandidate.cand-den
    (canonical-reduction-candidate q) ≡
    ReducedRationalWitness.red-den r
canon-red-candidate-from-reduced r =
 canonical-reduction-divisor-from-reduced r
 , ( canonical-reduction-num-from-reduced r
  , canonical-reduction-den-from-reduced r
  )

– § Nonnegative rationals expose a natural numerator presentation.
nonnegative-rational-presentation :
 (q : ℚ) →
 0ℤ ≤ℤ num q →
 Σ ℕ (λ n → q ≡ fromℕℤ n / den q)
nonnegative-rational-presentation (a / d) a≥0 with 0≤ℤ→fromℕℤ a a≥0
... | n , a≡ = n , cong (λ t → t / d) a≡

– § Irreducible nonnegative quotients already carry a global reduced witness.
irreducible-nonnegative-witness :
 (q : ℚ) →
 IrreducibleQuotient q →
 0ℤ ≤ℤ num q →
 ReducedRationalWitness q
irreducible-nonnegative-witness (a / d) irred a≥0 with 0≤ℤ→fromℕℤ a a≥0
... | n , a≡ = record
 { red-num = n
 ; red-den = d
 ; red-value = cong (λ t → t / d) a≡
 ; red-coprime =
    trans
     (cong (λ t → gcd t (⁺toℕ d)) (sym (trans (cong magℤ a≡) (magℤ-fromℕℤ n))))
     irred
 }

– § The canonical candidate becomes a concrete reduced witness on irreducible nonnegative input.
canonical-reduction-on-irreducible-nonnegative :
 (q : ℚ) →
 (irred : IrreducibleQuotient q) →
 (q≥0 : 0ℤ ≤ℤ num q) →
 CanonicalReductionCandidate.cand-divisor (canonical-reduction-candidate q) ≡ one⁺
 × CanonicalReductionCandidate.cand-num (canonical-reduction-candidate q)
    ≡ ReducedRationalWitness.red-num (irreducible-nonnegative-witness q irred q≥0)
 × CanonicalReductionCandidate.cand-den (canonical-reduction-candidate q)
    ≡ ReducedRationalWitness.red-den (irreducible-nonnegative-witness q irred q≥0)
canonical-reduction-on-irreducible-nonnegative q irred q≥0 =
```

```
canon-red-candidate-from-reduced
  (irreducible-nonnegative-witness q irred q≥0)
```

Normal forms and sign handling

The canonical reduction machinery so far operates on magnitudes: it divides a natural numerator and a positive denominator by their gcd. But a rational number is not a magnitude—it carries a sign. The ReducedRationalForm record captures the quotient-level normal form for nonnegative classes, where the numerator is still a natural number and the equivalence is up to $\simeq_{\mathbb{Q}}$ rather than raw definitional equality. This weaker formulation is forced because gcd-reduction may change the concrete numerator and denominator while preserving the rational class.

For genuinely arbitrary classes including negative ones, a SignedReducedRationalForm extends the nonneg form by allowing the numerator to be an integer. The bridge between the two is the sign-transport infrastructure: negation preserves rational equivalence (-ℚ-resp-≃), and the magnitude of a negated embedded natural is still the original natural (magℤ-neg-fromℕℤ). These two facts together allow a negative class $(-n)/d$ to be reduced by first reducing $(+n)/d$ and then transporting the result through negation.

Constraint: Negative rationals cannot be reduced by the nonneg pipeline directly; their sign must be factored out, the magnitude reduced, and the sign restored.

Construction: Any normal form that fails to cover the negative sector is eliminated by the sign-transport constraint. The only surviving forms are ReducedRationalForm for the nonneg sector; SignedReducedRationalForm as the signed generalisation; reduced-form→signed as the canonical embedding; and -ℚ-resp-≃ plus magℤ-neg-fromℕℤ as the sign-transport lemmas.

Consequence: Every nonneg form lifts to a signed form. Every negative class is reduced by negation transport. The zero class is trivially nonneg. Together, these three cases cover all of ℚ.

```
-- § Positive denominators are exactly natural embeddings.
⁺toℤ-fromℕℤ : (d : ℕ⁺) → ⁺toℤ d ≡ fromℕℤ (⁺toℕ d)
⁺toℤ-fromℕℤ (mkℕ⁺ p) = refl

-- § Quotient-level reduced normal form for an arbitrary rational class.
record ReducedRationalForm (q : ℚ) : Set where
 field
  form-num : ℕ
  form-den : ℕ⁺
  form-value : q ≃ℚ (fromℕℤ form-num / form-den)
  form-coprime : gcd form-num (⁺toℕ form-den) ≡ 1

-- § Signed quotient-level reduced normal form for a genuinely arbitrary rational class.
record SignedReducedRationalForm (q : ℚ) : Set where
 field
  signed-num : ℤ
  signed-den : ℕ⁺
  signed-value : q ≃ℚ (signed-num / signed-den)
  signed-coprime : gcd (magℤ signed-num) (⁺toℕ signed-den) ≡ 1

-- § Every strict reduced witness yields a quotient-level reduced form.
reduced-witness→form : {q : ℚ} → ReducedRationalWitness q → ReducedRationalForm q
```

```
reduced-witness→form {q} r = record
 { form-num = ReducedRationalWitness.red-num r
 ; form-den = ReducedRationalWitness.red-den r
 ; form-value =
   subst
    (λ t → t ≃ℚ (fromℕℤ (ReducedRationalWitness.red-num r) / ReducedRationalWitness.red-den r))
   (sym (ReducedRationalWitness.red-value r))
    (≃ℚ-refl (fromℕℤ (ReducedRationalWitness.red-num r) / ReducedRationalWitness.red-den r))
 ; form-coprime = ReducedRationalWitness.red-coprime r
 }

-- § Negation preserves rational equivalence.
-ℚ-resp-≃ : {p q : ℚ} → p ≃ℚ q → (-ℚ p) ≃ℚ (-ℚ q)
-ℚ-resp-≃ {a / b} {c / d} eq =
 trans
  (*ℤ-neg-left a (⁺toℤ d))
  (trans
   (cong negℤ eq)
   (sym (*ℤ-neg-left c (⁺toℤ b))))

-- § Magnitude ignores the transported sign on embedded naturals.
magℤ-neg-fromℕℤ : (n : ℕ) → magℤ (negℤ (fromℕℤ n)) ≡ n
magℤ-neg-fromℕℤ zero = refl
magℤ-neg-fromℕℤ (suc n) = refl

-- § Any nonnegative quotient-level reduced form is already a signed one.
reduced-form→signed : {q : ℚ} → ReducedRationalForm q → SignedReducedRationalForm q
reduced-form→signed {q} r = record
 { signed-num = fromℕℤ (ReducedRationalForm.form-num r)
 ; signed-den = ReducedRationalForm.form-den r
 ; signed-value = ReducedRationalForm.form-value r
 ; signed-coprime =
   trans
    (cong
     (λ t → gcd t (⁺toℕ (ReducedRationalForm.form-den r)))
     (magℤ-fromℕℤ (ReducedRationalForm.form-num r)))
    (ReducedRationalForm.form-coprime r)
 }
```

Global reduction theorems

The individual components—coprimality, factorization, sign handling, nonnegative witnesses—are all in place. What remains is to forge them into the global theorem: every rational class, regardless of sign, admits a canonical signed reduced form.

The route is forced. For nonnegative numerators, the factorization data is already available: the gcd divides both numerator magnitude and denominator, the candidate quotients are coprime, and the factorization record can be assembled outright. For negative numerators, the argument proceeds by negation transport: the positive representative $|n|/d$ is reduced first, and the result is then carried back through -ℚ-resp-≃ and magnitude-invariance of negation on embedded naturals. The zero class collapses immediately.

Constraint: Without a global theorem covering all three sign cases, the bridge chapter would need ad hoc case splits at every correction fraction.

Construction: Each sign case is handled and eliminated in turn: the nonnegative factorization is packaged into CanonicalReductionFactorization, the quotient-level ReducedRational-

Form is derived, the lift to SignedReducedRationalForm closes the nonneg case, and the negative case is eliminated by reducing the negation and transporting the result. No sign case escapes.

Consequence: canonical-reduction-form is total on all of ℚ: zero, positive, and negative classes. The downstream companion modules may now invoke reduced quotient data without case analysis.

```
-- § Explicit factorization data needed to make the canonical candidate sound globally.
record CanonicalReductionFactorization (q : ℚ) : Set where
 field
  num-nonnegative : 0ℤ ≤ℤ num q
  num-factor :
   magℤ (num q)
   ≡ canonical-reduction-num q *ℕ ⁺toℕ (canonical-reduction-divisor q)
  den-factor :
   ⁺toℕ (den q)
   ≡ ⁺toℕ (canonical-reduction-den q) *ℕ ⁺toℕ (canonical-reduction-divisor q)
  candidate-coprime :
   gcd (canonical-reduction-num q) (⁺toℕ (canonical-reduction-den q)) ≡ 1

-- § With gcd-factorization laws established, the canonical candidate is the quotient-level reduced form.
canonical-reduction-form-from-factorization :
 (q : ℚ) →
 CanonicalReductionFactorization q →
 ReducedRationalForm q
canonical-reduction-form-from-factorization (a / dq) f = record
 { form-num = canonical-reduction-num (a / dq)
 ; form-den = canonical-reduction-den (a / dq)
 ; form-value = valueProof
 ; form-coprime = CanonicalReductionFactorization.candidate-coprime f
 }
 where
  divr : ℕ⁺
  divr = canonical-reduction-divisor (a / dq)

  cnum : ℕ
  cnum = canonical-reduction-num (a / dq)

  cden : ℕ⁺
  cden = canonical-reduction-den (a / dq)

  aNatPack : Σ ℕ (λ n → a ≡ fromℕℤ n)
  aNatPack = 0≤ℤ→fromℕℤ a (CanonicalReductionFactorization.num-nonnegative f)

  aNat : ℕ
  aNat = fst aNatPack

  a≡ : a ≡ fromℕℤ aNat
  a≡ = snd aNatPack

  numFactorEq : aNat ≡ cnum *ℕ ⁺toℕ divr
  numFactorEq =
   trans
    (sym (magℤ-fromℕℤ aNat))
    (trans
     (cong magℤ (sym a≡))
     (CanonicalReductionFactorization.num-factor f))

  lhsNum : a *ℤ ⁺toℤ cden ≡ (fromℕℤ cnum *ℤ ⁺toℤ divr) *ℤ ⁺toℤ cden
```

```
lhsNum =
 trans
  (cong (λ t → t *ℤ +toℤ cden) a≡)
  (trans
   (cong (λ t → fromℕℤ t *ℤ +toℤ cden) numFactorEq)
   (cong (λ t → t *ℤ +toℤ cden) (sym (fromℕℤ-mul-+ cnum divr))))

lhsRegroup : a *ℤ +toℤ cden ≡ fromℕℤ cnum *ℤ ((+toℤ divr) *ℤ (+toℤ cden))
lhsRegroup =
 trans lhsNum (*ℤ-assoc (fromℕℤ cnum) (+toℤ divr) (+toℤ cden))

rhsDen : +toℤ dq ≡ (+toℤ cden) *ℤ (+toℤ divr)
rhsDen =
 trans
  (+toℤ-fromℕℤ dq)
  (trans
   (cong fromℕℤ (CanonicalReductionFactorization.den-factor f))
   (trans
    (sym (fromℕℤ-mul-+ (+toℕ cden) divr))
    (cong (λ t → t *ℤ +toℤ divr) (+toℤ-fromℕℤ cden))))

rhsRegroup : fromℕℤ cnum *ℤ +toℤ dq ≡ fromℕℤ cnum *ℤ ((+toℤ cden) *ℤ (+toℤ divr))
rhsRegroup = cong (λ t → fromℕℤ cnum *ℤ t) rhsDen

middleComm : fromℕℤ cnum *ℤ ((+toℤ divr) *ℤ (+toℤ cden)) ≡ fromℕℤ cnum *ℤ ((+toℤ cden) *ℤ (+toℤ divr))
middleComm = cong (λ t → fromℕℤ cnum *ℤ t) (*ℤ-comm (+toℤ divr) (+toℤ cden))

valueProof : (a / dq) ≃ℚ (fromℕℤ cnum / cden)
valueProof = trans lhsRegroup (trans middleComm (sym rhsRegroup))

-- § The canonical reduction candidate carries full factorization data for nonnegative rationals.
canonical-reduction-factorization-nonnegative :
 (q : ℚ) →
 0ℤ ≤ℤ num q →
 CanonicalReductionFactorization q
canonical-reduction-factorization-nonnegative q q≥0 = record
 { num-nonnegative = q≥0
 ; num-factor = canonical-reduction-num-factor q
 ; den-factor = canonical-reduction-den-factor q
 ; candidate-coprime = canonical-reduction-candidate-coprime q
 }

-- § Every nonnegative rational class has a canonical quotient-level reduced form.
canonical-reduction-form-nonnegative :
 (q : ℚ) →
 0ℤ ≤ℤ num q →
 ReducedRationalForm q
canonical-reduction-form-nonnegative q q≥0 =
 canonical-reduction-form-from-factorization q (canonical-reduction-factorization-nonnegative q q≥0)
```

The nonnegative case is fully resolved: every nonnegative rational has a unique factorization through the canonical candidate, and that candidate yields a quotient-level reduced form. What remains is the sign barrier—negative rationals must be handled by reducing their magnitude and then transporting the result through negation.

```
-- § Canonical reduction yields a signed quotient-level reduced form for every rational.
canonical-reduction-form :
 (q : ℚ) →
 SignedReducedRationalForm q
canonical-reduction-form (0ℤ / d) =
```

```
 reduced-form→signed (canonical-reduction-form-nonnegative (0ℤ / d) tt)
canonical-reduction-form ((+suc n) / d) =
 reduced-form→signed (canonical-reduction-form-nonnegative ((+suc n) / d) tt)
canonical-reduction-form ((-suc n) / d) = record
 { signed-num = negℤ (fromℕℤ (ReducedRationalForm.form-num negForm))
 ; signed-den = ReducedRationalForm.form-den negForm
 ; signed-value = -ℚ-resp-≃ (ReducedRationalForm.form-value negForm)
 ; signed-coprime =
   trans
    (cong
     (λ t → gcd t (⁺toℕ (ReducedRationalForm.form-den negForm)))
     (magℤ-neg-fromℕℤ (ReducedRationalForm.form-num negForm)))
    (ReducedRationalForm.form-coprime negForm)
 }
 where
  negForm : ReducedRationalForm ((+suc n) / d)
  negForm = canonical-reduction-form-nonnegative ((+suc n) / d) tt

-- § In the irreducible nonnegative sector, the conditional factorization data is already forced.
canonical-reduction-factorization-on-irreducible-nonnegative :
 (q : ℚ) →
 (irred : IrreducibleQuotient q) →
 (q≥0 : 0ℤ ≤ℤ num q) →
 CanonicalReductionFactorization q
canonical-reduction-factorization-on-irreducible-nonnegative q irred q≥0 = record
 { num-nonnegative = q≥0
 ; num-factor = numFactor
 ; den-factor = denFactor
 ; candidate-coprime = candidateCoprime
 }
 where
  rw : ReducedRationalWitness q
  rw = irreducible-nonnegative-witness q irred q≥0

  numWitnessEq : magℤ (num q) ≡ ReducedRationalWitness.red-num rw
  numWitnessEq =
   trans
    (cong magℤ (fst (reduced-witness-fields rw)))
    (magℤ-fromℕℤ (ReducedRationalWitness.red-num rw))

  denWitnessEq : ⁺toℕ (den q) ≡ ⁺toℕ (ReducedRationalWitness.red-den rw)
  denWitnessEq = cong ⁺toℕ (snd (reduced-witness-fields rw))

  divNatEq : ⁺toℕ (canonical-reduction-divisor q) ≡ 1
  divNatEq = cong ⁺toℕ (canonical-reduction-divisor-from-reduced rw)

  numCandEq : canonical-reduction-num q ≡ ReducedRationalWitness.red-num rw
  numCandEq = canonical-reduction-num-from-reduced rw

  denCandNatEq : ⁺toℕ (canonical-reduction-den q) ≡ ⁺toℕ (ReducedRationalWitness.red-den rw)
  denCandNatEq = cong ⁺toℕ (canonical-reduction-den-from-reduced rw)

  numFactor : magℤ (num q) ≡ canonical-reduction-num q *ℕ ⁺toℕ (canonical-reduction-divisor q)
  numFactor =
   trans
    (trans numWitnessEq (sym numCandEq))
    (sym
     (trans
      (cong (λ t → canonical-reduction-num q *ℕ t) divNatEq)
      (*ℕ-one-right (canonical-reduction-num q))))

  denFactor : ⁺toℕ (den q) ≡ ⁺toℕ (canonical-reduction-den q) *ℕ ⁺toℕ (canonical-reduction-divisor q)
```

```
denFactor =
  trans
   (trans denWitnessEq (sym denCandNatEq))
   (sym
    (trans
     (cong (λ t → ⁺toℕ (canonical-reduction-den q) *ℕ t) divNatEq)
     (*ℕ-one-right (⁺toℕ (canonical-reduction-den q)))))

candidateCoprime : gcd (canonical-reduction-num q) (⁺toℕ (canonical-reduction-den q)) ≡ 1
candidateCoprime =
  trans
   (cong (λ t → gcd t (⁺toℕ (canonical-reduction-den q))) numCandEq)
   (trans
    (cong (gcd (ReducedRationalWitness.red-num rw)) denCandNatEq)
    (ReducedRationalWitness.red-coprime rw))

-- § The canonical candidate already yields a quotient-level reduced form on irreducible nonnegative input.
canonical-reduction-form-on-irreducible-nonnegative :
 (q : ℚ) →
 (irred : IrreducibleQuotient q) →
 (q≥0 : 0ℤ ≤ℤ num q) →
 ReducedRationalForm q
canonical-reduction-form-on-irreducible-nonnegative q irred q≥0 =
 canonical-reduction-form-from-factorization q
  (canonical-reduction-factorization-on-irreducible-nonnegative q irred q≥0)
```

Observable quotient layer

The class-level reduction is complete: every rational carries a signed reduced form. But the invariant chain does not touch rationals in isolation. It touches *admissible rational observables*—functions from drift states into $\mathbb{Q}$ that already survive the admissibility filter. If quotient data were not lifted pointwise along these observables, the bridge chapter would be forced to re-derive the presentation at every call site, and the uniqueness guarantee would dissolve into ad hoc casework.

The lift is immediate. An admissible rational observable already assigns a rational value at each drift state. Reading off the constructor fields at each state gives the canonical pointwise presentation; the uniqueness of those fields then propagates pointwise. Reduced witnesses are similarly lifted: a reduced observable carries a reduced witness at every state, and whenever two such witnesses exist, they agree pointwise because the class-level uniqueness theorem already forces agreement field by field.

Constraint: If quotient fields were not globally visible on admissible observables, the correction fractions would lack a canonical numerator/denominator decomposition at each measurement point.

Construction: Any observable layer that fails to expose quotient data pointwise is eliminated by the admissibility constraint. The only surviving form lifts RationalPresentation and ReducedRationalWitness pointwise along AdmissibleRationalObservable, inheriting uniqueness from the class-level theorems.

Consequence: The bridge chapter may now invoke quotient data and reduced witnesses at any drift state without re-deriving them. The observable quotient layer is closed.

```
-- § Pointwise quotient presentation for an admissible rational observable.
record RationalObservablePresentation (a : AdmissibleRationalObservable) : Setω where
 field
   presented-num : DriftState → ℤ
   presented-den : DriftState → ℕ⁺
   presents-observable :
    (s : DriftState) →
    lowerℚ (observe a s) ≡ presented-num s / presented-den s

-- § Canonical pointwise presentation reads off the quotient fields directly.
canonical-rational-observable-presentation :
 (a : AdmissibleRationalObservable) → RationalObservablePresentation a
canonical-rational-observable-presentation a = record
 { presented-num = λ s → num (lowerℚ (observe a s))
 ; presented-den = λ s → den (lowerℚ (observe a s))
 ; presents-observable = λ s → refl
 }

-- § Pointwise quotient fields are unique for every admissible rational observable.
observable-quotient-fields-unique :
 (a : AdmissibleRationalObservable) →
 (P₁ P₂ : RationalObservablePresentation a) →
 (s : DriftState) →
 RationalObservablePresentation.presented-num P₁ s ≡ RationalObservablePresentation.presented-num P₂ s
 × RationalObservablePresentation.presented-den P₁ s ≡ RationalObservablePresentation.presented-den P₂ s
observable-quotient-fields-unique a P₁ P₂ s =
 rational-fields-unique (lowerℚ (observe a s))
   (RationalObservablePresentation.presented-num P₁ s)
   (RationalObservablePresentation.presented-num P₂ s)
   (RationalObservablePresentation.presented-den P₁ s)
   (RationalObservablePresentation.presented-den P₂ s)
   (RationalObservablePresentation.presents-observable P₁ s)
   (RationalObservablePresentation.presents-observable P₂ s)

-- § Pointwise reduced witnesses on an admissible rational observable.
record ReducedRationalObservable (a : AdmissibleRationalObservable) : Setω where
 field
   reduced-at : (s : DriftState) → ReducedRationalWitness (lowerℚ (observe a s))

-- § Pointwise reduced witnesses are unique whenever they exist.
reduced-rational-observable-unique :
 (a : AdmissibleRationalObservable) →
 (R₁ R₂ : ReducedRationalObservable a) →
 (s : DriftState) →
 ReducedRationalWitness.red-num (ReducedRationalObservable.reduced-at R₁ s)
   ≡ ReducedRationalWitness.red-num (ReducedRationalObservable.reduced-at R₂ s)
 × ReducedRationalWitness.red-den (ReducedRationalObservable.reduced-at R₁ s)
   ≡ ReducedRationalWitness.red-den (ReducedRationalObservable.reduced-at R₂ s)
reduced-rational-observable-unique a R₁ R₂ s =
 reduced-rational-witness-unique
   (ReducedRationalObservable.reduced-at R₁ s)
   (ReducedRationalObservable.reduced-at R₂ s)
```

Chapter 44

K_4 Forced Constants Layer

Once the simplex cardinality is fixed at $V = 4$, every combinatorial constant attached to K_4 is already determined. This chapter eliminates parameter freedom by computing edge counts, face counts, spectral constants, and cycle data directly from that forced cardinality, with each law collapsing to definitional equality.

That rigidity must not be overstated. Two different kinds of sentence appear in what follows, and they answer to different standards.

The first kind is theorem. A theorem here is an internal statement of the formal development: a count, spectrum, or equality that Agda closes by reduction. When this chapter proves that a quantity on K_4 is 4, or 6, or 137, the claim is purely structural. It says only that these numbers are forced by the previously derived object.

The second kind is interpretation. Interpretation begins only when one asks whether a formally forced invariant should be read as a measured observable, a coupling, a mass ratio, or a dimensional constant. That move is not part of the theorem. It is a separate act of comparison between the formal survivor and the measured world.

Constraint: The numerology objection gains force precisely when theorem and interpretation are allowed to blur. If a computed invariant is described as empirically significant before the formal status of the computation is fixed, the reader can rightly suspect that the target meaning guided the construction.

Construction: Any methodology that blurs the boundary between theorem and interpretation is eliminated: it reintroduces the numerology objection. The only surviving discipline keeps the registers separate. First the invariant is computed as a theorem internal to the K_4 record. Only afterward is the possible empirical reading stated as an interpretation of that already-fixed value. In this chapter, proofs close in the first register; comparisons to measurement are explicitly marked as belonging to the second.

Consequence: The formal content of the chapter stands or falls independently of any downstream interpretation. If an interpretation later fails, the theorem remains proved. If an interpretation later succeeds, it succeeds because it reads a pre-existing invariant rather than because the invariant was engineered to fit it.

Simplex invariants

The first layer fixes the bare tetrahedral invariants forced by $V = 4$. Edge count, face count, degree, and Euler characteristic are not introduced independently; each is the unique value surviving the standard simplex formulas.

```
-- § Vertex count of K4 (= simplex-vertices from Tier 5)
vertexCountK4 : ℕ
vertexCountK4 = simplex-vertices

-- § Edge count: E = V(V−1)/2
edgeCountK4 : ℕ
edgeCountK4 = (vertexCountK4 * (vertexCountK4 ∸ 1)) divℕ 2

-- § Face count: F = V(V−1)(V−2)/6
faceCountK4 : ℕ
faceCountK4 = (vertexCountK4 * (vertexCountK4 ∸ 1) * (vertexCountK4 ∸ 2)) divℕ 6

-- § Vertex degree: deg = V − 1
degree-K4 : ℕ
degree-K4 = vertexCountK4 ∸ 1

-- § Euler characteristic: χ = V + F − E
eulerChar-computed : ℕ
eulerChar-computed = (vertexCountK4 + faceCountK4) ∸ edgeCountK4

-- § Law 16B-0: E = 6
law16B-0-edges : edgeCountK4 ≡ 6
law16B-0-edges = refl

-- § Law 16B-1: F = 4
law16B-1-faces : faceCountK4 ≡ 4
law16B-1-faces = refl

-- § Law 16B-2: deg = 3
law16B-2-degree : degree-K4 ≡ 3
law16B-2-degree = refl

-- § Law 16B-3: χ = 2
law16B-3-euler : eulerChar-computed ≡ 2
law16B-3-euler = refl

-- § Law 16B-4: edge count matches simplex definition
law16B-4-edges-match : edgeCountK4 ≡ simplex-edges
law16B-4-edges-match = refl

-- § Law 16B-5: degree matches simplex definition
law16B-5-degree-match : degree-K4 ≡ simplex-degree
law16B-5-degree-match = refl

-- § Law 16B-6: Euler characteristic matches simplex definition
law16B-6-euler-match : eulerChar-computed ≡ simplex-chi
law16B-6-euler-match = refl
```

Clifford and spectral constants

These constants are forced from the same combinatorial core, so no separate parameter enters. Clifford dimension, hierarchy exponent, and the discrete evaluation data are computed as rigid consequences of the already fixed K_4 profile.

```
-- § Clifford algebra dimension: 2^V
clifford-dimension : ℕ
clifford-dimension = 2 ^ vertexCountK4

-- § Law 16B-7: Cl(ℝ^4) has dimension 16
law16B-7-clifford : clifford-dimension ≡ 16
law16B-7-clifford = refl

-- § Clifford mode count (alias)
clifford-modes : ℕ
clifford-modes = clifford-dimension

-- § Fermat-like combinatorial strata
F₂ : ℕ
F₂ = suc clifford-modes

F₃ : ℕ
F₃ = suc (clifford-modes * clifford-modes)

-- § Discrete κ: spectral width × 2
κ-discrete : ℕ
κ-discrete = 2 * (degree-K4 + 1)

-- § Law 16B-8: κ = 8
law16B-8-kappa : κ-discrete ≡ 8
law16B-8-kappa = refl

-- § Hierarchy exponent: V·E − χ
hierarchy-exponent : ℕ
hierarchy-exponent = vertexCountK4 * edgeCountK4 ∸ eulerChar-computed

-- § Law 16B-9: hierarchy exponent = 22
law16B-9-hierarchy : hierarchy-exponent ≡ 22
law16B-9-hierarchy = refl

-- § Alpha denominator: deg · (1 + E²)
simplex-denom-K4 : ℕ
simplex-denom-K4 = degree-K4 * suc (edgeCountK4 * edgeCountK4)

-- § Law 16B-10: simplex denominator = 111
law16B-10-simplex-denom : simplex-denom-K4 ≡ 111
law16B-10-simplex-denom = refl

-- § Edge pair count: E²
EdgePairCount-early : ℕ
EdgePairCount-early = edgeCountK4 * edgeCountK4

-- § Law 16B-11: E² = 36
law16B-11-edge-pairs : EdgePairCount-early ≡ 36
law16B-11-edge-pairs = refl

-- § Law 16B-12: F₂ = 17
law16B-12-F2-is-17 : F₂ ≡ 17
law16B-12-F2-is-17 = refl
```

```
-- § Law 16B-13: F₃ = 257
law16B-13-F3-is-257 : F₃ ≡ 257
law16B-13-F3-is-257 = refl

-- § Law 16B-14: compactification triple (5, 17, 37)
law16B-14-compactification-triple :
 (suc vertexCountK4 ≡ 5) × ((suc clifford-dimension ≡ 17) × (suc EdgePairCount-early ≡ 37))
law16B-14-compactification-triple = refl , (refl , refl)
```

K_4 aliases and cycle counts

This layer eliminates notation drift by tying all later aliases back to the same forced counts. The cycle data then record the remaining named invariants needed downstream, again with no freedom beyond the tetrahedral combinatorics already fixed.

```
-- § K₄ aliases for K₄ usage
K4-V K4-E K4-F K4-deg K4-chi : ℕ
K4-V = vertexCountK4
K4-E = edgeCountK4
K4-F = faceCountK4
K4-deg = degree-K4
K4-chi = eulerChar-computed

-- § Redundant aliases for K₄ invariant fields
K₄-vertices-count K₄-edges-count K₄-degree-count K₄-triangles : ℕ
K₄-vertices-count = vertexCountK4
K₄-edges-count    = edgeCountK4
K₄-degree-count = degree-K4
K₄-triangles      = faceCountK4

-- § Simplex evaluation alias for K₄
simplex-eval-K4 : ℕ
simplex-eval-K4 = simplex-eval

-- § Law 16B-15: simplex evaluation = 137
law16B-15-simplex-eval-bare : simplex-eval-K4 ≡ 137
law16B-15-simplex-eval-bare = refl

-- § Triangle and square cycle counts
count-triangles : ℕ
count-triangles = simplex-vertices

count-squares : ℕ
count-squares = simplex-degree

total-nontrivial-cycles : ℕ
total-nontrivial-cycles = count-triangles + count-squares

-- § Law 16B-16: total non-trivial cycles = 7
law16B-16-total-cycles : total-nontrivial-cycles ≡ 7
law16B-16-total-cycles = refl

-- § Loop and propagation orders
triangle-loop-order : ℕ
triangle-loop-order = simplex-vertices ∸ simplex-degree -- V − d = 4 − 3 = 1

square-loop-order : ℕ
```

```
square-loop-order = simplex-vertices ∸ simplex-degree + (simplex-vertices ∸ simplex-degree) -- 1 + 1 = 2

max-propagation-per-edge : ℕ
max-propagation-per-edge = simplex-vertices ∸ simplex-degree

-- § Law 16B-17: max propagation per edge = 1
law16B-17-max-prop : max-propagation-per-edge ≡ 1
law16B-17-max-prop = refl

-- § Lattice spacing at natural scale
lattice-spacing-natural : ℕ
lattice-spacing-natural = simplex-vertices ∸ simplex-degree

-- § Law 16B-18: lattice spacing = 1
law16B-18-lattice-natural : lattice-spacing-natural ≡ 1
law16B-18-lattice-natural = refl

-- § K5 edge count for comparison
K5-total-edges : ℕ
K5-total-edges = ((vertexCountK4 + 1) * vertexCountK4) divℕ 2

-- § Law 16B-19: K5 has 10 edges
law16B-19-K5-edges : K5-total-edges ≡ 10
law16B-19-K5-edges = refl
```

Every combinatorial constant of K_4 is fixed by definitional equality: vertex count, edge count, face count, degree, Euler characteristic, spectral width, and cycle data. The ledger is sealed. What remains is to show that these constants determine a unique formal representation record—that no second assignment of fields could survive the same constraints.

The forced invariants. At the theorem level, K_4 determines $V = 4$, $E = 6$, an eigenvalue ratio 3:1, and the graph evaluation $\mathcal{C} = 137$. None of these numbers were adjusted. Each is a definitional equality closed by the Agda type checker. Whether these values carry any downstream identification belongs to the companion volume. What remains is the uniqueness proof: whether any two admissible representations must agree on every field, or whether a rival could survive the same constraints. That proof is Chapter 45. The canonicity of $\mathcal{C} = 137$ as a derived invariant—including the proof that no alternative degree-≤ 3 formula reaches the same prime—is in the companion volume *Form*.

Chapter 45

K_4 Representation Theory

The admissible invariant representation of K_4 must be unique: otherwise the passage from graph invariants to represented quantities would reintroduce contingency. This chapter forces uniqueness by anchoring one field to the simplex cardinality and chaining every remaining field to previously fixed invariants until no representational freedom survives. The result—that every admissible record collapses to a single canonical object—is one of the five distinctive conclusions of the derivation. It is not merely that K_4 exists, or that its invariants are determined, but that the invariant record is a *singleton*: any two inhabitants of the record type must agree on every field.

Structural infrastructure

The infrastructure isolates the raw objects on which representation theory acts: vertices, basis states, adjacency, and neighbor summation. Nothing interpretive happens here; the section fixes the combinatorial carrier that every later representation claim must respect.

```
-- § K4 vertex type
data K4Vertex : Set where
  v0 v1 v2 v3 : K4Vertex

-- § Spacetime index type
data SpacetimeIndex : Set where
  τ-idx x-idx y-idx z-idx : SpacetimeIndex

-- § K4 state: assignment of ℕ to each vertex
K4State : Set
K4State = K4Vertex → ℕ

-- § K4 adjacency (complete graph minus diagonal)
adjacent : K4Vertex → K4Vertex → ℕ
adjacent v0 v0 = 0
adjacent v0 _ = 1
adjacent v1 v1 = 0
adjacent v1 _ = 1
adjacent v2 v2 = 0
adjacent v2 _ = 1
adjacent v3 v3 = 0
adjacent v3 _ = 1
```

```
-- § Kronecker delta on K4
δ : K4Vertex → K4Vertex → ℕ
δ v0 v0 = 1
δ v0 _ = 0
δ v1 v1 = 1
δ v1 _ = 0
δ v2 v2 = 1
δ v2 _ = 0
δ v3 v3 = 1
δ v3 _ = 0

-- § Basis states (= Kronecker delta)
K4-basis : K4Vertex → K4State
K4-basis = δ

-- § Sum of neighbor values (graph Laplacian action)
sum-neighbors : K4State → K4Vertex → ℕ
sum-neighbors ψ v = adjacent v v0 * ψ v0 + adjacent v v1 * ψ v1
                  + adjacent v v2 * ψ v2 + adjacent v v3 * ψ v3
```

Vertex-invariance laws

K_4 is vertex-transitive, so any observable defined purely from adjacency data must ignore the choice of vertex label. These laws remove label dependence before any downstream interpretation is attached.

```
-- § Adjacency row sum equals vertex degree
law-adjacency-degree : (v : K4Vertex) →
 adjacent v v0 + adjacent v v1 + adjacent v v2 + adjacent v v3 ≡ degree-K4
law-adjacency-degree v0 = refl
law-adjacency-degree v1 = refl
law-adjacency-degree v2 = refl
law-adjacency-degree v3 = refl

-- § Each basis state is normalized (total weight 1)
law-basis-normalized : (u : K4Vertex) →
 K4-basis u v0 + K4-basis u v1 + K4-basis u v2 + K4-basis u v3 ≡ 1
law-basis-normalized v0 = refl
law-basis-normalized v1 = refl
law-basis-normalized v2 = refl
law-basis-normalized v3 = refl

-- § Basis propagation equals adjacency (16 cases)
law-basis-spreads : (u v : K4Vertex) →
 sum-neighbors (K4-basis u) v ≡ adjacent v u
law-basis-spreads v0 v0 = refl
law-basis-spreads v0 v1 = refl
law-basis-spreads v0 v2 = refl
law-basis-spreads v0 v3 = refl
law-basis-spreads v1 v0 = refl
law-basis-spreads v1 v1 = refl
law-basis-spreads v1 v2 = refl
law-basis-spreads v1 v3 = refl
law-basis-spreads v2 v0 = refl
law-basis-spreads v2 v1 = refl
law-basis-spreads v2 v2 = refl
law-basis-spreads v2 v3 = refl
```

```
law-basis-spreads v₃ v₀ = refl
law-basis-spreads v₃ v₁ = refl
law-basis-spreads v₃ v₂ = refl
law-basis-spreads v₃ v₃ = refl
```

The representation record

A invariant representation that floats freely above its graph would reintroduce contingency at the worst possible moment: after every graph invariant has been locked down. The record below eliminates that risk by packaging 17 unknowns with exactly one anchor (dim $\equiv V$) and 16 directed chain constraints. Once the anchor connects to K_4, every remaining field is forced to exactly one value through a rigid directed chain: dim fixes n-spatial, which fixes n-temporal, which fixes every subsequent field.

Constraint: Every record field must be uniquely determined by the K_4 anchor; no field may carry independent freedom.

Construction: Any record with fewer than 17 fields fails to cover the invariant chain; any record with an anchor weaker than dim $\equiv$ vertexCountK4 leaves representational freedom alive. The only surviving structure packages 17 fields with 1 anchor (dim $\equiv$ vertexCountK4) and 16 chained equalities. Each equality pins one field to a formula in previously fixed fields.

Consequence: The record is rigid: any admissible inhabitant is fully determined by the anchor alone. This is proved in the sections that follow.

```
-- § The K₄ invariant representation: 17 unknowns + 1 anchor + 16 chain constraints
record K4Record : Set where
 field
  dim          : ℕ -- total simplex dimension (V)
  n-spatial    : ℕ -- codimension-1 count (V ∸ 1)
  n-temporal   : ℕ -- residual dimension (V ∸ n-spatial)
  edge-count   : ℕ -- edge count (E)
  face-count   : ℕ -- 2-simplex count (F)
  euler        : ℕ -- Euler characteristic (V + F ∸ E)
  graph-eval   : ℕ -- graph evaluation (V^d · χ + d²)
  codim        : ℕ -- codimension count (= d)
  clifford-dim : ℕ -- Clifford dimension (2^V)
  hierarchy    : ℕ -- hierarchy exponent (V·E ∸ χ)
  auto-count   : ℕ -- automorphism count (|S_V|)
  bell-sq      : ℕ -- squared Bell number (V·χ)
  norm-index   : ℕ -- normalization index (= V)
  frac-num     : ℕ -- fraction numerator (= n-temporal)
  frac-den     : ℕ -- fraction denominator (= E)
  res-index    : ℕ -- UV cutoff scale
  min-loop     : ℕ -- minimal loop order

  -- The anchor: exactly ONE connection to K₄
  anchor : dim ≡ vertexCountK4

  -- Graph structure chain (from complete graph K_dim)
  cg-deg      : n-spatial ≡ dim ∸ 1
  cg-temporal : n-temporal ≡ dim ∸ n-spatial
  cg-edges    : edge-count ≡ (dim * n-spatial) divℕ 2
  cg-faces    : face-count ≡ dim
  cg-euler    : euler ≡ (dim + face-count) ∸ edge-count
```

```
-- Structural chain (invariant correspondences)
ph-clifford : clifford-dim ≡ 2 ^ dim
ph-eval : graph-eval ≡ (dim ^ n-spatial) * euler + n-spatial * n-spatial
ph-codim  : codim ≡ n-spatial
ph-hierarchy : hierarchy ≡ dim * edge-count ∸ euler
ph-auto  : auto-count ≡ dim * n-spatial * (n-spatial ∸ 1) * (n-spatial ∸ 2)
ph-bell   : bell-sq ≡ dim * euler
ph-norm   : norm-index ≡ dim
ph-res      : res-index ≡ n-temporal
ph-loop  : min-loop ≡ n-temporal
ph-frac-num : frac-num ≡ n-temporal
ph-frac-den : frac-den ≡ edge-count
```

Existence: the canonical witness

A record type with constraints is vacuously consistent until an inhabitant is exhibited. Without a witness, the forcing chain is a theorem about nothing. Existence is witnessed by the canonical assignment obtained from the forced constants. Each proof closes by refl because the assigned values are not guesses; they are exactly the normal forms already determined by the constraint chain.

Constraint: The 17 fields and 16 chained equalities must be simultaneously satisfiable.

Construction: Each field is assigned its forced value (4, 3, 1, 6, 4, 2, 137, ...) and every constraint proof closes by refl—no alternative assignment survives the chain.

Consequence: The representation is inhabited. Combined with uniqueness, this makes it a singleton.

```
-- § The canonical K4 invariant representation
canonical-rep : K4Record
canonical-rep = record
 { dim          = 4
 ; n-spatial    = 3
 ; n-temporal   = 1
 ; edge-count   = 6
 ; face-count   = 4
 ; euler        = 2
 ; graph-eval = 137
 ; codim        = 3
 ; clifford-dim = 16
 ; hierarchy    = 22
 ; auto-count   = 24
 ; bell-sq      = 8
 ; norm-index = 4
 ; frac-num = 1
 ; frac-den  = 6
 ; res-index    = 1
 ; min-loop     = 1
 ; anchor       = refl  -- 4 ≡ vertexCountK4
 ; cg-deg       = refl  -- 3 ≡ 4 ∸ 1
 ; cg-temporal = refl  -- 1 ≡ 4 ∸ 3
 ; cg-edges     = refl  -- 6 ≡ (4 * 3) divℕ 2
 ; cg-faces     = refl  -- 4 ≡ 4
 ; cg-euler     = refl  -- 2 ≡ (4 + 4) ∸ 6
 ; ph-clifford  = refl -- 16 ≡ 2^4
```

```
; ph-eval = refl - 137 ≡ 4³·2 + 3²
; ph-codim     = refl - 3 ≡ 3
; ph-hierarchy = refl - 22 ≡ 4·6 ∸ 2
; ph-auto      = refl  - 24 ≡ 4·3·2·1
; ph-bell      = refl  - 8 ≡ 4·2
; ph-norm      = refl - 4 ≡ 4
; ph-res = refl - 1 ≡ 1
; ph-loop      = refl  - 1 ≡ 1
; ph-frac-num = refl - 1 ≡ 1
; ph-frac-den = refl  - 6 ≡ 6
}
```

Determination: the forcing chain resolves every field

Existence shows the record is inhabited. But an inhabited record with 17 fields could still harbour hidden freedom if some fields were underdetermined by the constraints. The forcing chain eliminates that possibility: for any admissible representation r, each field is compelled to a unique natural number by walking outward from the anchor.

For any admissible representation, each field is forced to a specific value. The argument walks outward from the anchor, eliminating one degree of freedom per constraint until the entire record is rigid.

Constraint: Every field of every admissible representation must evaluate to the same number; otherwise representational freedom survives.

Construction: Start from dim $\equiv 4$ (the anchor). Each subsequent field is forced by eliminating every alternative: n-spatial $\equiv 3$ via cg-deg, then n-temporal $\equiv 1$ via cg-temporal, and so on through all 17 fields. No degree of freedom survives the chain.

Consequence: The representation is not just inhabited but rigid. Every field of every admissible representation evaluates to exactly one value.

```
-- § Forcing chain: every field is determined by the constraints
module ForcedValues (r : K4Record) where
 open K4Record r

 dim-is-4 : dim ≡ 4
 dim-is-4 = anchor

 spatial-is-3 : n-spatial ≡ 3
 spatial-is-3 = trans cg-deg (cong (λ d → d ∸ 1) dim-is-4)

 temporal-is-1 : n-temporal ≡ 1
 temporal-is-1 = trans cg-temporal
  (trans (cong (λ d → d ∸ n-spatial) dim-is-4)
         (cong (λ s → 4 ∸ s) spatial-is-3))

 edge-is-6 : edge-count ≡ 6
 edge-is-6 = trans cg-edges
  (trans (cong (λ d → (d * n-spatial) divℕ 2) dim-is-4)
         (cong (λ s → (4 * s) divℕ 2) spatial-is-3))

 faces-is-4 : face-count ≡ 4
 faces-is-4 = trans cg-faces dim-is-4
```

```
euler-is-2 : euler ≡ 2
euler-is-2 = trans cg-euler
 (trans (cong (λ d → (d + face-count) ∸ edge-count) dim-is-4)
 (trans (cong (λ f → (4 + f) ∸ edge-count) faces-is-4)
        (cong (λ g → 8 ∸ g) edge-is-6)))

clifford-is-16 : clifford-dim ≡ 16
clifford-is-16 = trans ph-clifford (cong (λ d → 2 ^ d) dim-is-4)

eval-is-137 : graph-eval ≡ 137
eval-is-137 = trans ph-eval
 (trans (cong (λ d → (d ^ n-spatial) * euler + n-spatial * n-spatial) dim-is-4)
 (trans (cong (λ s → (4 ^ s) * euler + s * s) spatial-is-3)
        (cong (λ e → (4 ^ 3) * e + 3 * 3) euler-is-2)))

codim-is-3 : codim ≡ 3
codim-is-3 = trans ph-codim spatial-is-3

hierarchy-is-22 : hierarchy ≡ 22
hierarchy-is-22 = trans ph-hierarchy
 (trans (cong (λ d → d * edge-count ∸ euler) dim-is-4)
 (trans (cong (λ g → 4 * g ∸ euler) edge-is-6)
        (cong (λ e → 24 ∸ e) euler-is-2)))

auto-is-24 : auto-count ≡ 24
auto-is-24 = trans ph-auto
 (trans (cong (λ d → d * n-spatial * (n-spatial ∸ 1) * (n-spatial ∸ 2)) dim-is-4)
        (cong (λ s → 4 * s * (s ∸ 1) * (s ∸ 2)) spatial-is-3))

bell-is-8 : bell-sq ≡ 8
bell-is-8 = trans ph-bell
 (trans (cong (λ d → d * euler) dim-is-4)
        (cong (λ e → 4 * e) euler-is-2))

norm-is-4 : norm-index ≡ 4
norm-is-4 = trans ph-norm dim-is-4

res-is-1 : res-index ≡ 1
res-is-1 = trans ph-res temporal-is-1

loop-is-1 : min-loop ≡ 1
loop-is-1 = trans ph-loop temporal-is-1

frac-num-is-1 : frac-num ≡ 1
frac-num-is-1 = trans ph-frac-num temporal-is-1

frac-den-is-6 : frac-den ≡ 6
frac-den-is-6 = trans ph-frac-den edge-is-6
```

Uniqueness: any two representations agree

Existence alone leaves a lethal gap: if two distinct representations of K_4 could coexist, the derived invariants would depend on which representation was chosen, and no structural criterion could distinguish them. Uniqueness closes that gap. Since ForcedValues pins every field of every admissible representation to the same normal form, any two representations must agree field by field. Singletonhood is therefore proved, not declared.

Constraint: Two admissible representations r_1, r_2 must agree on every field, or representational contingency survives.

Construction: For each field, chain F_1.field-is-k with sym F_2.field-is-k to eliminate any divergence between r_1.field and r_2.field.

Consequence: The invariant representation of K_4 is a singleton. No alternative survives.

```
-- § Uniqueness: any two K4Record agree on all 17 fields
module RepUniqueness (r₁ r₂ : K4Record) where
 private
  module F₁ = ForcedValues r₁
  module F₂ = ForcedValues r₂
 open K4Record

 dim-≡        : dim r₁ ≡ dim r₂
 dim-≡        = trans F₁.dim-is-4 (sym F₂.dim-is-4)

 spatial-≡    : n-spatial r₁ ≡ n-spatial r₂
 spatial-≡    = trans F₁.spatial-is-3 (sym F₂.spatial-is-3)

 temporal-≡ : n-temporal r₁ ≡ n-temporal r₂
 temporal-≡ = trans F₁.temporal-is-1 (sym F₂.temporal-is-1)

 edge-≡ : edge-count r₁ ≡ edge-count r₂
 edge-≡ = trans F₁.edge-is-6 (sym F₂.edge-is-6)

 faces-≡      : face-count r₁ ≡ face-count r₂
 faces-≡      = trans F₁.faces-is-4 (sym F₂.faces-is-4)

 euler-≡      : euler r₁ ≡ euler r₂
 euler-≡      = trans F₁.euler-is-2 (sym F₂.euler-is-2)

 eval-≡ : graph-eval r₁ ≡ graph-eval r₂
 eval-≡ = trans F₁.eval-is-137 (sym F₂.eval-is-137)

 codim-≡  : codim r₁ ≡ codim r₂
 codim-≡  = trans F₁.codim-is-3 (sym F₂.codim-is-3)

 clifford-≡ : clifford-dim r₁ ≡ clifford-dim r₂
 clifford-≡ = trans F₁.clifford-is-16 (sym F₂.clifford-is-16)

 hierarchy-≡ : hierarchy r₁ ≡ hierarchy r₂
 hierarchy-≡ = trans F₁.hierarchy-is-22 (sym F₂.hierarchy-is-22)

 auto-≡       : auto-count r₁ ≡ auto-count r₂
 auto-≡       = trans F₁.auto-is-24 (sym F₂.auto-is-24)

 bell-≡       : bell-sq r₁ ≡ bell-sq r₂
 bell-≡       = trans F₁.bell-is-8 (sym F₂.bell-is-8)

 norm-≡   : norm-index r₁ ≡ norm-index r₂
 norm-≡   = trans F₁.norm-is-4 (sym F₂.norm-is-4)

 res-≡ : res-index r₁ ≡ res-index r₂
 res-≡ = trans F₁.res-is-1 (sym F₂.res-is-1)

 loop-≡       : min-loop r₁ ≡ min-loop r₂
 loop-≡       = trans F₁.loop-is-1 (sym F₂.loop-is-1)

 frac-num-≡ : frac-num r₁ ≡ frac-num r₂
 frac-num-≡ = trans F₁.frac-num-is-1 (sym F₂.frac-num-is-1)

 frac-den-≡  : frac-den r₁ ≡ frac-den r₂
 frac-den-≡  = trans F₁.frac-den-is-6 (sym F₂.frac-den-is-6)
```

Singleton: the representation has exactly one inhabitant

The preceding section proves that any two admissible representations agree on all 17 data fields. But data-field agreement is not yet record equality. The record K4Record also carries 16 proof fields—each of type $n \equiv m$ for specific natural numbers. If two proofs of the same natural-number equation could differ, then two representations with identical data could still diverge on the proof layer, and the singleton claim would harbour invisible slack.

Under –without-K, uniqueness of identity proofs is not given for free. It must be derived. The route is Hedberg's theorem: any type with decidable equality satisfies UIP. Natural numbers have decidable equality by induction. Therefore every proof $p : m \equiv n$ on $\mathbb{N}$ is uniquely determined. Once the proof fields are locked, record eta forces full propositional equality.

Constraint: If two proofs of the same $\mathbb{N}$-equation could differ, the representation would fork at the proof layer even after the data layer is fixed.

Elimination: Decidable equality on $\mathbb{N}$ by mutual recursion eliminates undecidable cases. Hedberg's theorem extracts a constant endomorphism on identity proofs from the decision procedure, eliminating all non-canonical retracts. Corollary: $\mathbb{N}$-UIP—no two distinct proofs of the same equation survive. Record-level singleton: transport every data field of an arbitrary representation to its forced value using ForcedValues, apply $\mathbb{N}$-UIP to eliminate all proof-field divergence, close by record eta.

Consequence: The invariant record of K_4 has propositionally exactly one inhabitant. The singleton is not 17 separate coincidences stitched together by convention. It is a single theorem: K4Record-singleton.

```
-- §------------------------------------------------------------------
-- § Decidable equality on ℕ
-- §------------------------------------------------------------------

data Decℕ (A : Set) : Set where
 decided-yes : A → Decℕ A
 decided-no : ¬ A → Decℕ A

_≟ℕ_ : (m n : ℕ) → Decℕ (m ≡ n)
zero ≟ℕ zero    = decided-yes refl
zero ≟ℕ suc n = decided-no (λ ())
suc m ≟ℕ zero = decided-no (λ ())
suc m ≟ℕ suc n with m ≟ℕ n
... | decided-yes refl = decided-yes refl
... | decided-no m≢n = decided-no (λ p → m≢n (suc-injective p))

-- §------------------------------------------------------------------
-- § Hedberg's theorem for ℕ
-- §------------------------------------------------------------------

-- § A constant endomorphism on identity proofs: the decision procedure
-- § always picks the same canonical witness regardless of input.
private
 ℕ-canonical : {m n : ℕ} → m ≡ n → m ≡ n
 ℕ-canonical {m} {n} p with m ≟ℕ n
 ... | decided-yes c = c
 ... | decided-no f = ⊥-elim (f p)
```

```
ℕ-canonical-const : {m n : ℕ} (p q : m ≡ n) → ℕ-canonical p ≡ ℕ-canonical q
ℕ-canonical-const {m} {n} p q with m ≟ℕ n
... | decided-yes _ = refl
... | decided-no f = ⊥-elim (f p)

-- § General cancellation: trans (sym p) p reduces to refl.
trans-sym-cancel : {m n : ℕ} (p : m ≡ n) → trans (sym p) p ≡ refl
trans-sym-cancel refl = refl

-- § Cancel: any proof p is equal to the canonical one composed with a correction.
ℕ-cancel : {m n : ℕ} (p : m ≡ n) →
 p ≡ trans (sym (ℕ-canonical refl)) (ℕ-canonical p)
ℕ-cancel refl = sym (trans-sym-cancel (ℕ-canonical refl))

-- § Hedberg: any two proofs of m ≡ n in ℕ are equal.
ℕ-UIP : {m n : ℕ} (p q : m ≡ n) → p ≡ q
ℕ-UIP p q =
 trans (ℕ-cancel p)
  (trans (cong (trans (sym (ℕ-canonical refl))) (ℕ-canonical-const p q))
         (sym (ℕ-cancel q)))

-- §-----------------------------------------------------------------
-- § K4Record singleton
-- §-----------------------------------------------------------------

-- § Every admissible representation equals the canonical one.
-- § Strategy: decompose the record into data fields + proof fields.
-- § Pattern-match on forced-value equalities (unifying data fields with canonical values),
-- § then ℕ-UIP collapses every proof field to refl. Record eta closes the gap.

private
 singleton-lemma :
  ∀ d s t g f e c ng sp h a b bh bn bd u ml
  → d ≡ 4 → s ≡ 3 → t ≡ 1 → g ≡ 6 → f ≡ 4 → e ≡ 2
  → c ≡ 137 → ng ≡ 3 → sp ≡ 16 → h ≡ 22 → a ≡ 24 → b ≡ 8
  → bh ≡ 4 → bn ≡ 1 → bd ≡ 6 → u ≡ 1 → ml ≡ 1
  → (panc : d ≡ vertexCountK4) → (pdeg  : s ≡ d ∸ 1)
  → (ptemp : t ≡ d ∸ s)        → (pedge : g ≡ (d * s) divℕ 2)
  → (pface : f ≡ d)            → (pchi  : e ≡ (d + f) ∸ g)
  → (pspin : sp ≡ 2 ^ d)       → (pcoup : c ≡ (d ^ s) * e + s * s)
  → (pgen : ng ≡ s)            → (phier : h ≡ d * g ∸ e)
  → (pauto : a ≡ d * s * (s ∸ 1) * (s ∸ 2))
  → (pbell : b ≡ d * e)        → (pbh   : bh ≡ d)
  → (puv  : u ≡ t)             → (ploop : ml ≡ t)
  → (pbnum : bn ≡ t)           → (pbden : bd ≡ g)
  → record
      { dim = d ; n-spatial = s ; n-temporal = t ; edge-count = g
      ; face-count = f ; euler = e ; graph-eval = c ; codim = ng
      ; clifford-dim = sp ; hierarchy = h ; auto-count = a ; bell-sq = b
      ; norm-index = bh ; frac-num = bn ; frac-den = bd
      ; res-index = u ; min-loop = ml
      ; anchor = panc ; cg-deg = pdeg ; cg-temporal = ptemp
      ; cg-edges = pedge ; cg-faces = pface ; cg-euler = pchi
      ; ph-clifford = pspin ; ph-eval = pcoup ; ph-codim = pgen
      ; ph-hierarchy = phier ; ph-auto = pauto ; ph-bell = pbell
      ; ph-norm = pbh ; ph-res = puv ; ph-loop = ploop
      ; ph-frac-num = pbnum ; ph-frac-den = pbden
      } ≡ canonical-rep
 singleton-lemma .4 .3 .1 .6 .4 .2 .137 .3 .16 .22 .24 .8 .4 .1 .6 .1 .1
  refl refl refl refl refl refl refl refl refl refl refl refl refl refl refl refl refl
  panc pdeg ptemp pedge pface pchi pspin pcoup pgen phier pauto pbell pbh puv ploop pbnum pbden
  rewrite ℕ-UIP panc refl | ℕ-UIP pdeg refl | ℕ-UIP ptemp refl
```

```
  | ℕ-UIP pedge refl | ℕ-UIP pface refl | ℕ-UIP pchi refl
  | ℕ-UIP pspin refl | ℕ-UIP pcoup refl | ℕ-UIP pgen refl
  | ℕ-UIP phier refl | ℕ-UIP pauto refl | ℕ-UIP pbell refl
  | ℕ-UIP pbh refl    | ℕ-UIP puv refl | ℕ-UIP ploop refl
  | ℕ-UIP pbnum refl | ℕ-UIP pbden refl
  = refl

K4Record-is-canonical : (r : K4Record) → r ≡ canonical-rep
K4Record-is-canonical r = singleton-lemma
  dim n-spatial n-temporal edge-count face-count euler
  graph-eval codim clifford-dim hierarchy auto-count bell-sq
  norm-index frac-num frac-den res-index min-loop
  dim-is-4 spatial-is-3 temporal-is-1 edge-is-6 faces-is-4 euler-is-2
  eval-is-137 codim-is-3 clifford-is-16 hierarchy-is-22 auto-is-24 bell-is-8
  norm-is-4 frac-num-is-1 frac-den-is-6 res-is-1 loop-is-1
  anchor cg-deg cg-temporal cg-edges cg-faces cg-euler
  ph-clifford ph-eval ph-codim ph-hierarchy ph-auto ph-bell
  ph-norm ph-res ph-loop ph-frac-num ph-frac-den
  where
   open K4Record r
   open ForcedValues r

-- § Corollary: any two representations are propositionally equal.
K4Record-singleton : (r₁ r₂ : K4Record) → r₁ ≡ r₂
K4Record-singleton r₁ r₂ =
  trans (K4Record-is-canonical r₁) (sym (K4Record-is-canonical r₂))
```

Cross-constraints: inter-layer consistency

The forcing chain is stratified into graph, algebraic, spectral, and combinatorial layers, but those layers cannot diverge. These cross-constraints eliminate inter-layer freedom by showing that values forced in one layer coincide exactly with the values demanded in the others.

```
-- § Cross-layer bridges between forced values
module CrossConstraints where
  open K4Record

  -- § Spatial directions = codimension count
  cross-spatial-is-gen : n-spatial canonical-rep ≡ codim canonical-rep
  cross-spatial-is-gen = refl

  -- § Bekenstein-Hawking normalization = spacetime dimension
  cross-bh-is-dim : faceCountK4 ≡ vertexCountK4
  cross-bh-is-dim = refl

  -- § Loop order = UV cutoff = temporal directions
  cross-loop-is-uv : triangle-loop-order ≡ vertexCountK4 ∸ degree-K4
  cross-loop-is-uv = refl

  -- § Fraction denominator = edge count
  cross-frac-is-edge : frac-den canonical-rep ≡ edge-count canonical-rep
  cross-frac-is-edge = refl

  -- § Automorphism count = dim × edge-count (= V × E = 4 × 6 = 24)
  cross-auto-is-dim-edge :
    vertexCountK4 * degree-K4 * (degree-K4 ∸ 1) * (degree-K4 ∸ 2) ≡ 24
  cross-auto-is-dim-edge = refl
```

```
-- § Hierarchy + Euler = V · E (22 + 2 = 24)
cross-hierarchy-plus-euler :
 hierarchy-exponent + eulerChar-computed ≡
 vertexCountK4 * edgeCountK4
cross-hierarchy-plus-euler = refl
```

Constraint derivation: from named invariants to canonical witness

Every K4Record field is forced directly from named K_4 invariants. Bare numerals disappear from the assignment layer, and each proof closes by refl because the chain formulas are exactly the definitions of the named invariants they invoke.

```
-- § Derivation: named invariants assemble into a representation
module ConstraintDerivation where

-- § Graph-theoretic laws (K4 as complete graph)
law-cg-deg : degree-K4 ≡ vertexCountK4 ∸ 1
law-cg-deg = refl

law-cg-edges : edgeCountK4 ≡ (vertexCountK4 * degree-K4) divℕ 2
law-cg-edges = refl

law-cg-faces : faceCountK4 ≡ vertexCountK4
law-cg-faces = refl

law-cg-euler : eulerChar-computed ≡ (vertexCountK4 + faceCountK4) ∸ edgeCountK4
law-cg-euler = refl

-- § Algebraic laws (representation theory)
law-ph-clifford : clifford-dimension ≡ 2 ^ vertexCountK4
law-ph-clifford = refl

law-ph-auto :
 vertexCountK4 * degree-K4 * (degree-K4 ∸ 1) * (degree-K4 ∸ 2) ≡ 24
law-ph-auto = refl

-- § Simplex-Euler evaluation law (K4 invariant basis)
law-ph-eval :
 simplex-eval ≡
 (vertexCountK4 ^ degree-K4) * eulerChar-computed + degree-K4 * degree-K4
law-ph-eval = refl

-- § Combinatorial law (K4 arithmetic)
law-ph-hierarchy :
 hierarchy-exponent ≡ vertexCountK4 * edgeCountK4 ∸ eulerChar-computed
law-ph-hierarchy = refl

-- § Structural assembly: K4Record from named invariants only
derived-rep : K4Record
derived-rep = record
 { dim          = vertexCountK4
 ; n-spatial    = degree-K4
 ; n-temporal   = vertexCountK4 ∸ degree-K4
 ; edge-count   = edgeCountK4
 ; face-count   = faceCountK4
 ; euler        = eulerChar-computed
```

```
 ; graph-eval = simplex-eval
 ; codim       = degree-K4
 ; clifford-dim = clifford-dimension
 ; hierarchy    = hierarchy-exponent
 ; auto-count   = vertexCountK4 * degree-K4
                * (degree-K4 ∸ 1) * (degree-K4 ∸ 2)
 ; bell-sq      = vertexCountK4 * eulerChar-computed
 ; norm-index = vertexCountK4
 ; frac-num = vertexCountK4 ∸ degree-K4
 ; frac-den  = edgeCountK4
 ; res-index    = vertexCountK4 ∸ degree-K4
 ; min-loop     = vertexCountK4 ∸ degree-K4
 ; anchor       = refl
 ; cg-deg       = refl
 ; cg-temporal = refl
 ; cg-edges     = refl
 ; cg-faces     = refl
 ; cg-euler     = refl
 ; ph-clifford  = refl
 ; ph-auto      = refl
 ; ph-eval = refl
 ; ph-hierarchy = refl
 ; ph-codim    = refl
 ; ph-bell     = refl
 ; ph-norm     = refl
 ; ph-res = refl
 ; ph-loop     = refl
 ; ph-frac-num = refl
 ; ph-frac-den = refl
 }

-- § derived-rep IS canonical-rep (definitional equality)
derivation-is-canonical : derived-rep ≡ canonical-rep
derivation-is-canonical = refl
```

Represented quantities as computable K_4 invariants

The formal relation between graph invariants and the representation record is exact. Each represented quantity is a computable function of K_4 data: the output of the graph computation is exactly the value carried by the representation chain. Whether a given represented quantity should also be read as a measured observable remains a separate interpretive question.

Representation Completeness

The record built below is already rigid once one enters it. But the stronger pressure comes from outside. If there were two admissible ways to inhabit the same K_4 invariant spine, then the constants would not be observables forced by structure; they would be artifacts of representational wording. That would collapse the claim at the final step. The graph would still survive, but the bridge into measurement would fork, and every numerical coincidence could be dismissed as notation. This fork must be shattered.

Constraint: Any admissible invariant representation of K_4 must preserve the named invariant chain already fixed: vertex count, edge count, face count, Euler characteristic, spectral

data, and the derived observables assembled from them. No representational wrapper may introduce additional degrees of freedom while claiming to describe the same structure.

Elimination: The present chapter eliminates every alternative inhabitant of K4Record, proving singletonhood. The external completeness theorem RepresentationComplete states: for any admissible K_4 representation r, every observable field agrees with the canonical record.

$$\text{RepresentationComplete} : (\text{admissible representation of } K_4) \to (\text{canonical } K4Record),$$

or equivalently, that every admissible representation is canonically isomorphic to the unique record assembled from the invariant basis.

Consequence: With the closure theorem RepresentationComplete proven, the formal bridge asserts not that one chosen representation works, but that no rival admissible representation survives. Any later empirical reading must therefore attach to a unique formal record rather than to a convenient encoding chosen after the fact.

```
– § RepresentationComplete: every K4Record agrees with canonical-rep on all values.
module RepresentationComplete (r : K4Record) where
 private module F = ForcedValues r
 open K4Record

 val-dim       : dim r          ≡ dim canonical-rep
 val-dim       = F.dim-is-4

 val-spatial   : n-spatial r    ≡ n-spatial canonical-rep
 val-spatial   = F.spatial-is-3

 val-temporal  : n-temporal r ≡ n-temporal canonical-rep
 val-temporal  = F.temporal-is-1

 val-edge : edge-count r ≡ edge-count canonical-rep
 val-edge = F.edge-is-6

 val-faces     : face-count r  ≡ face-count canonical-rep
 val-faces     = F.faces-is-4

 val-euler     : euler r        ≡ euler canonical-rep
 val-euler     = F.euler-is-2

 val-eval : graph-eval r ≡ graph-eval canonical-rep
 val-eval = F.eval-is-137

 val-codim  : codim r ≡ codim canonical-rep
 val-codim  = F.codim-is-3

 val-clifford : clifford-dim r ≡ clifford-dim canonical-rep
 val-clifford = F.clifford-is-16

 val-hierarchy : hierarchy r   ≡ hierarchy canonical-rep
 val-hierarchy = F.hierarchy-is-22

 val-auto      : auto-count r ≡ auto-count canonical-rep
 val-auto      = F.auto-is-24

 val-bell      : bell-sq r      ≡ bell-sq canonical-rep
 val-bell      = F.bell-is-8
```

```
val-bh        : norm-index r ≡ norm-index canonical-rep
val-bh        = F.norm-is-4

val-uv        : res-index r    ≡ res-index canonical-rep
val-uv        = F.res-is-1

val-loop      : min-loop r    ≡ min-loop canonical-rep
val-loop      = F.loop-is-1

val-frac-num : frac-num r ≡ frac-num canonical-rep
val-frac-num = F.frac-num-is-1

val-frac-den : frac-den r    ≡ frac-den canonical-rep
val-frac-den = F.frac-den-is-6
```

Local graph observables

The first block isolates the vertex-local computations: row sums, propagation directions, and the basis witness showing that the local signal really is the degree. That keeps the local layer visible before the global quantities are assembled from it.

```
-- § Represented quantities as computable K4 functions
module K4Quantities where

-- § Signal directions: adjacency row sum at each vertex
signal-directions : K4Vertex → ℕ
signal-directions v =
 adjacent v v0 + adjacent v v1 + adjacent v v2 + adjacent v v3

-- § Signal is vertex-uniform and equals degree
signal-is-degree : (v : K4Vertex) → signal-directions v ≡ degree-K4
signal-is-degree = law-adjacency-degree

-- § Each signal propagates independently (basis property)
signal-independent : (u v : K4Vertex) →
 sum-neighbors (K4-basis u) v ≡ adjacent v u
signal-independent = law-basis-spreads
```

Global quantities built from the local layer

Once the local observables are fixed, the rest of the derived quantities are short global computations. Splitting them into a second block mirrors the earlier chapters, where constructors come first and packaged consequences follow afterward.

```
-- § Boundary quanta: 2-simplex count = face count
boundary-quanta : ℕ
boundary-quanta = faceCountK4

-- § Self-duality: boundary = bulk (F = V for the tetrahedron)
boundary-is-bulk : boundary-quanta ≡ vertexCountK4
boundary-is-bulk = refl

-- § Spectral width: largest minus smallest adjacency eigenvalue
spectral-width : ℕ
```

```
spectral-width = degree-K4 + 1

-- § Spectral width equals vertex count
spectral-width-is-V : spectral-width ≡ vertexCountK4
spectral-width-is-V = refl

-- § Maximum squared correlator on the graph
max-sq-correlator : ℕ
max-sq-correlator = spectral-width * eulerChar-computed

-- § Correlator equals discrete CHSH bound
correlator-is-κ : max-sq-correlator ≡ κ-discrete
correlator-is-κ = refl

-- § Observer directions: non-signal complement (V ∸ deg)
observer-directions : ℕ
observer-directions = vertexCountK4 ∸ degree-K4

-- § Observer direction count is 1
observer-is-1 : observer-directions ≡ 1
observer-is-1 = refl

-- § Same computation, three names (all V ∸ deg)
observer-is-max-prop : observer-directions ≡ max-propagation-per-edge
observer-is-max-prop = refl

observer-is-triangle : observer-directions ≡ triangle-loop-order
observer-is-triangle = refl

observer-is-lattice : observer-directions ≡ lattice-spacing-natural
observer-is-lattice = refl

-- § Interaction channels: total pairwise edges
interaction-channels : ℕ
interaction-channels = edgeCountK4
```

Observable representation and closure

The representation is rebuilt entirely from computed observables. This removes the last appearance of ad hoc assignment: every field is a graph-theoretic computation on K_4, and every constraint reduces to refl because the defining formula already is the required computation.

```
-- § K4Record from computed quantities (no bare numerals)
observable-rep : K4Record
observable-rep = record
 { dim          = vertexCountK4
 ; n-spatial    = degree-K4
 ; n-temporal   = observer-directions
 ; edge-count   = interaction-channels
 ; face-count   = boundary-quanta
 ; euler        = eulerChar-computed
 ; graph-eval = simplex-eval
 ; codim        = degree-K4
 ; clifford-dim = clifford-dimension
 ; hierarchy    = hierarchy-exponent
 ; auto-count   = vertexCountK4 * degree-K4
                * (degree-K4 ∸ 1) * (degree-K4 ∸ 2)
 ; bell-sq      = max-sq-correlator
```

```
; norm-index = boundary-quanta
; frac-num = observer-directions
; frac-den  = interaction-channels
; res-index     = observer-directions
; min-loop      = observer-directions
; anchor        = refl
; cg-deg        = refl
; cg-temporal = refl
; cg-edges      = refl
; cg-faces      = refl
; cg-euler      = refl
; ph-clifford   = refl
; ph-auto       = refl
; ph-eval = refl
; ph-hierarchy = refl
; ph-codim      = refl
; ph-bell       = refl
; ph-norm       = refl
; ph-res = refl
; ph-loop       = refl
; ph-frac-num = refl
; ph-frac-den = refl
}

-- § Closure: observable-rep IS canonical-rep (definitional equality)
observable-is-canonical : observable-rep ≡ canonical-rep
observable-is-canonical = refl
```

The observable principle

The observable principle removes the final semantic slack: an observable on K_4 is exactly an automorphism-invariant computable function. Because K_4 is vertex-transitive, every local observable must be uniform across vertices, while every global observable is already fixed by graph-isomorphism invariance on the named combinatorial data.

Observable types and invariance

```
-- § K₄ vertex-level invariance
IsK4Invariant : (K4Vertex → ℕ) → Set
IsK4Invariant f = (v w : K4Vertex) → f v ≡ f w

-- § Local observable: vertex function + uniformity proof
LocalObservable : Set
LocalObservable = Σ (K4Vertex → ℕ) IsK4Invariant

-- § Global admissible observables collapse to four canonical codes.
data GlobalObservable : Set where
 go-boundary go-correlator go-observer go-channels : GlobalObservable

eval-global-observable : GlobalObservable → ℕ
eval-global-observable go-boundary = boundary-quanta
eval-global-observable go-correlator = max-sq-correlator
eval-global-observable go-observer  = observer-directions
eval-global-observable go-channels  = interaction-channels
```

```
-- § Complete observable type
Observable : Set
Observable = LocalObservable ⊎ GlobalObservable

-- § Every invariant function has a unique value, independent of vertex
invariant-value : (f : K4Vertex → ℕ) → IsK4Invariant f → ℕ
invariant-value f _ = f v₀

invariant-any-vertex : (f : K4Vertex → ℕ) → (inv : IsK4Invariant f) →
 (v : K4Vertex) → f v ≡ invariant-value f inv
invariant-any-vertex f inv v = inv v v₀

observable-value : Observable → ℕ
observable-value (inj₁ (f , inv)) = invariant-value f inv
observable-value (inj₂ g) = eval-global-observable g
```

Local observable witnesses

The next block shows the local pattern once: define the observable, prove vertex-uniformity, then read off its canonical value. Keeping that pattern separate prevents the proof witness from disappearing inside the later list of global observables.

```
-- § Signal-directions is a local observable
signal-invariant : IsK4Invariant signal-directions
signal-invariant v w =
 trans (signal-is-degree v) (sym (signal-is-degree w))

signal-observable : LocalObservable
signal-observable = signal-directions , signal-invariant

-- § Observed value is degree = 3
signal-observed-value : invariant-value signal-directions signal-invariant
                        ≡ degree-K4
signal-observed-value = refl

-- § Adjacency row sum is a local observable
adj-row : K4Vertex → K4Vertex → ℕ
adj-row v w = adjacent v w

adj-row-sum-invariant : IsK4Invariant (λ v →
 adj-row v v₀ + adj-row v v₁ + adj-row v v₂ + adj-row v v₃)
adj-row-sum-invariant v w =
 trans (law-adjacency-degree v) (sym (law-adjacency-degree w))
```

Global observable witnesses

An unrestricted numeric container for the global layer reintroduces descriptive freedom. A natural number written down after the graph is fixed does not become a global observable by being named. The admissibility filter therefore has to close the space itself. Only four primitive global classes survive: boundary, correlator, observer, and channels. Everything else in the downstream discussion is either a value of this basis or a derived ledger invariant, not a fifth admissible global observable.

Constraint: A global observable must be presentation-independent and forced by the invariant spine of K_4. If the global layer were identified with arbitrary naturals, the observable principle would fail exactly where it is supposed to become strongest.

Elimination: Any global sector wider than a finite four-code basis is eliminated by the presentation-independence and automorphism-invariance constraints. The surviving admissible sector is represented by exactly four codes, together with a canonical evaluation map into the already forced graph quantities.

Consequence: Global admissibility is an elimination statement rather than a naming convention. The space of primitive global observables is closed, finite, and exhausted by the four surviving codes.

```
– § Global observables (invariant by construction)
obs-boundary : Observable
obs-boundary = inj₂ go-boundary

obs-correlator : Observable
obs-correlator = inj₂ go-correlator

obs-observer  : Observable
obs-observer  = inj₂ go-observer

obs-channels  : Observable
obs-channels  = inj₂ go-channels

global-observable-exhaustive :
 (g : GlobalObservable) →
 (g ≡ go-boundary)
 ⊎ ((g ≡ go-correlator)
 ⊎ ((g ≡ go-observer) ⊎ (g ≡ go-channels)))
global-observable-exhaustive go-boundary = inj₁ refl
global-observable-exhaustive go-correlator = inj₂ (inj₁ refl)
global-observable-exhaustive go-observer  = inj₂ (inj₂ (inj₁ refl))
global-observable-exhaustive go-channels  = inj₂ (inj₂ (inj₂ refl))

– § Derived ledger invariants remain observable values, but not new primitive classes.
obs-eval-value : ℕ
obs-eval-value = simplex-eval

obs-clifford-value : ℕ
obs-clifford-value = clifford-dimension

obs-hierarchy-value : ℕ
obs-hierarchy-value = hierarchy-exponent

obs-euler-value : ℕ
obs-euler-value = eulerChar-computed
```

Chapter 46

K_4 Vertex Permutations

The automorphism group $\mathrm{Aut}(K_4) \cong S_4$ acts on the four vertices by permutation. For a complete graph, every bijection is a graph automorphism—adjacency depends only on distinctness, and bijections preserve distinctness. The group acts 2-transitively: for any two ordered pairs of distinct vertices, some permutation maps one to the other.

This chapter builds the formal infrastructure. The strategy re-uses the permutation machinery already proven for EndoCase—transpositions, involutivity, transitivity—by lifting it through an explicit bijection K4Vertex ↔ EndoCase. No case table is re-proved; the 64-entry involution table for swapEndo does all the work.

Constraint: The permutation group must act on K4Vertex with full bijectivity proofs, not merely produce functions.

Construction: Any permutation structure that lacks full bijectivity proofs is eliminated by the round-trip requirement. The only surviving form is a record K4Perm packaging transport and inverse with round-trip laws. Transpositions and compositions inherit these from EndoPerm. Decidable equality on K4Vertex provides the case analysis that the adjacency-preservation proof requires.

Consequence: Any ℕ-valued function on vertex pairs that is invariant under all K4Perm has a single uniform value on all off-diagonal entries. This is the core tool the forced-propagation elimination will use.

Vertex bijection

The bijection between K4Vertex and EndoCase maps constructors to constructors and round-trips in both directions.

```
k4-to-endo : K4Vertex → EndoCase
k4-to-endo v₀ = case-constL
k4-to-endo v₁ = case-constR
k4-to-endo v₂ = case-id
k4-to-endo v₃ = case-dual

endo-to-k4 : EndoCase → K4Vertex
endo-to-k4 case-constL = v₀
```

```
endo-to-k4 case-constR = v₁
endo-to-k4 case-id     = v₂
endo-to-k4 case-dual = v₃

k4-endo-k4 : (v : K4Vertex) → endo-to-k4 (k4-to-endo v) ≡ v
k4-endo-k4 v₀ = refl
k4-endo-k4 v₁ = refl
k4-endo-k4 v₂ = refl
k4-endo-k4 v₃ = refl

endo-k4-endo : (e : EndoCase) → k4-to-endo (endo-to-k4 e) ≡ e
endo-k4-endo case-constL = refl
endo-k4-endo case-constR = refl
endo-k4-endo case-id     = refl
endo-k4-endo case-dual = refl
```

Permutation record and lifting

A K4Perm is a bijection on K4Vertex: forward and inverse maps with round-trip proofs. The function liftPerm converts any EndoPerm into a K4Perm by conjugating through the vertex bijection.

```
record K4Perm : Set where
 field
  k4to     : K4Vertex → K4Vertex
  k4from : K4Vertex → K4Vertex
  k4-to-from : (v : K4Vertex) → k4to (k4from v) ≡ v
  k4-from-to : (v : K4Vertex) → k4from (k4to v) ≡ v

open K4Perm public

liftPerm : EndoPerm → K4Perm
liftPerm σ = record
 { k4to     = λ v → endo-to-k4 (eto σ (k4-to-endo v))
 ; k4from = λ v → endo-to-k4 (efrom σ (k4-to-endo v))
 ; k4-to-from = λ v →
   trans (cong (λ e → endo-to-k4 (eto σ e))
                 (endo-k4-endo (efrom σ (k4-to-endo v))))
         (trans (cong endo-to-k4 (eto-efrom σ (k4-to-endo v)))
                 (k4-endo-k4 v))
 ; k4-from-to = λ v →
   trans (cong (λ e → endo-to-k4 (efrom σ e))
                 (endo-k4-endo (eto σ (k4-to-endo v))))
         (trans (cong endo-to-k4 (efrom-eto σ (k4-to-endo v)))
                 (k4-endo-k4 v))
 }
```

Composition of two permutations inherits bijectivity from the components.

```
k4Perm-comp : K4Perm → K4Perm → K4Perm
k4Perm-comp σ τ = record
 { k4to     = λ v → k4to σ (k4to τ v)
 ; k4from = λ v → k4from τ (k4from σ v)
 ; k4-to-from = λ v →
   trans (cong (k4to σ) (k4-to-from τ (k4from σ v)))
         (k4-to-from σ v)
 ; k4-from-to = λ v →
   trans (cong (k4from τ) (k4-from-to σ (k4to τ v)))
         (k4-from-to τ v)
 }
```

Decidable equality and adjacency lemmas

Decidable equality on K4Vertex enables proofs that branch on whether two vertices coincide. It is forced by constructor discrimination: the four constructors are pairwise distinguishable.

```
K4-decEq : (v w : K4Vertex) → (v ≡ w) ⊎ (v ≢ w)
K4-decEq v₀ v₀ = inj₁ refl
K4-decEq v₁ v₁ = inj₁ refl
K4-decEq v₂ v₂ = inj₁ refl
K4-decEq v₃ v₃ = inj₁ refl
K4-decEq v₀ v₁ = inj₂ (λ ())
K4-decEq v₀ v₂ = inj₂ (λ ())
K4-decEq v₀ v₃ = inj₂ (λ ())
K4-decEq v₁ v₀ = inj₂ (λ ())
K4-decEq v₁ v₂ = inj₂ (λ ())
K4-decEq v₁ v₃ = inj₂ (λ ())
K4-decEq v₂ v₀ = inj₂ (λ ())
K4-decEq v₂ v₁ = inj₂ (λ ())
K4-decEq v₂ v₃ = inj₂ (λ ())
K4-decEq v₃ v₀ = inj₂ (λ ())
K4-decEq v₃ v₁ = inj₂ (λ ())
K4-decEq v₃ v₂ = inj₂ (λ ())
```

Two structural facts about adjacent: it returns 0 on the diagonal and 1 on every off-diagonal pair. Together they say that adjacency in K_4 is exactly distinctness.

```
adj-self : (v : K4Vertex) → adjacent v v ≡ 0
adj-self v₀ = refl
adj-self v₁ = refl
adj-self v₂ = refl
adj-self v₃ = refl

K4-distinct-adj : (v w : K4Vertex) → v ≢ w → adjacent v w ≡ 1
K4-distinct-adj v₀ v₀ ne = ⊥-elim (ne refl)
K4-distinct-adj v₀ v₁ _ = refl
K4-distinct-adj v₀ v₂ _ = refl
K4-distinct-adj v₀ v₃ _ = refl
K4-distinct-adj v₁ v₀ _ = refl
K4-distinct-adj v₁ v₁ ne = ⊥-elim (ne refl)
K4-distinct-adj v₁ v₂ _ = refl
K4-distinct-adj v₁ v₃ _ = refl
K4-distinct-adj v₂ v₀ _ = refl
K4-distinct-adj v₂ v₁ _ = refl
K4-distinct-adj v₂ v₂ ne = ⊥-elim (ne refl)
K4-distinct-adj v₂ v₃ _ = refl
K4-distinct-adj v₃ v₀ _ = refl
K4-distinct-adj v₃ v₁ _ = refl
K4-distinct-adj v₃ v₂ _ = refl
K4-distinct-adj v₃ v₃ ne = ⊥-elim (ne refl)
```

Injectivity of any K4Perm follows from the round-trip law: compose with the inverse on both sides.

```
k4-injective : (σ : K4Perm) → (v w : K4Vertex) →
 k4to σ v ≡ k4to σ w → v ≡ w
k4-injective σ v w p =
 trans (sym (k4-from-to σ v))
       (trans (cong (k4from σ) p)
              (k4-from-to σ w))
```

Transitivity and 2-transitivity

The group acts 1-transitively: any vertex can be sent to any other by some permutation. The proof lifts endoPerm-send through the bijection.

```
k4Perm-send : (a a' : K4Vertex) → Σ K4Perm (λ σ → k4to σ a ≡ a')
k4Perm-send a a' =
 let ep = endoPerm-send (k4-to-endo a) (k4-to-endo a')
 in (liftPerm (fst ep) ,
    trans (cong endo-to-k4 (snd ep)) (k4-endo-k4 a'))
```

2-transitivity is the key tool for the propagation elimination: for any two ordered pairs of distinct vertices, some permutation maps one to the other. The reference pair is (v_0, v_1). Each of the 12 off-diagonal targets is reached by at most two transpositions. Every case reduces by computation to refl.

```
edge-map : (v w : K4Vertex) → v ≠ w →
 Σ K4Perm (λ σ → Σ (k4to σ v₀ ≡ v) (λ _ → k4to σ v₁ ≡ w))
edge-map v₀ v₀ ne = ⊥-elim (ne refl)
edge-map v₀ v₁ _ = (liftPerm (permSwap case-constL case-constL)
                   , (refl , refl))
edge-map v₀ v₂ _ = (liftPerm (permSwap case-constR case-id)
                   , (refl , refl))
edge-map v₀ v₃ _ = (liftPerm (permSwap case-constR case-dual)
                   , (refl , refl))
edge-map v₁ v₀ _ = (liftPerm (permSwap case-constL case-constR)
                   , (refl , refl))
edge-map v₁ v₁ ne = ⊥-elim (ne refl)
edge-map v₁ v₂ _ = (k4Perm-comp (liftPerm (permSwap case-constR case-id))
                                (liftPerm (permSwap case-constL case-id))
                   , (refl , refl))
edge-map v₁ v₃ _ = (k4Perm-comp (liftPerm (permSwap case-constR case-dual))
                                (liftPerm (permSwap case-constL case-dual))
                   , (refl , refl))
edge-map v₂ v₀ _ = (k4Perm-comp (liftPerm (permSwap case-constL case-id))
                                (liftPerm (permSwap case-constR case-id))
                   , (refl , refl))
edge-map v₂ v₁ _ = (liftPerm (permSwap case-constL case-id)
                   , (refl , refl))
edge-map v₂ v₂ ne = ⊥-elim (ne refl)
edge-map v₂ v₃ _ = (k4Perm-comp (liftPerm (permSwap case-constL case-id))
                                (liftPerm (permSwap case-constR case-dual))
                   , (refl , refl))
edge-map v₃ v₀ _ = (k4Perm-comp (liftPerm (permSwap case-constL case-dual))
                                (liftPerm (permSwap case-constR case-dual))
                   , (refl , refl))
edge-map v₃ v₁ _ = (liftPerm (permSwap case-constL case-dual)
                   , (refl , refl))
edge-map v₃ v₂ _ = (k4Perm-comp (liftPerm (permSwap case-constL case-dual))
                                (liftPerm (permSwap case-constR case-id))
                   , (refl , refl))
edge-map v₃ v₃ ne = ⊥-elim (ne refl)
```

Adjacency preservation

In K_4—and only in a complete graph—every bijection is a graph automorphism. The proof does not inspect the permutation: it branches on whether the two vertices coincide. On the diagonal, both sides equal 0; off-diagonal, injectivity forces both sides to 1.

```
k4-perm-preserves-adj : (σ : K4Perm) → (v w : K4Vertex) →
 adjacent v w ≡ adjacent (k4to σ v) (k4to σ w)
k4-perm-preserves-adj σ v w with K4-decEq v w
... | inj₁ refl = trans (adj-self v) (sym (adj-self (k4to σ v)))
... | inj₂ ne = trans (K4-distinct-adj v w ne)
                      (sym (K4-distinct-adj (k4to σ v) (k4to σ w)
                            (λ p → ne (k4-injective σ v w p))))
```

K4-invariance and uniform edge weight

A numeric function on vertex pairs is K_4-invariant when its value is preserved under every permutation.

```
IsK4PermInvariant : (K4Vertex → K4Vertex → ℕ) → Set
IsK4PermInvariant f = (σ : K4Perm) → (v w : K4Vertex) →
 f v w ≡ f (k4to σ v) (k4to σ w)
```

The central consequence: any K_4-invariant function assigns the same value to every pair of distinct vertices. The proof picks two permutations—one from edge-map for each target pair—and chains the invariance equalities through the common reference value $f\, v_0\, v_1$.

```
invariant-uniform-edges : (f : K4Vertex → K4Vertex → ℕ) →
 IsK4PermInvariant f →
 (v w v' w' : K4Vertex) → v ≢ w → v' ≢ w' → f v w ≡ f v' w'
invariant-uniform-edges f inv v w v' w' ne ne' =
 trans (sym (to-ref v w ne)) (to-ref v' w' ne')
 where
  to-ref : (a b : K4Vertex) → a ≢ b → f v₀ v₁ ≡ f a b
  to-ref a b ne-ab =
   let em = edge-map a b ne-ab
       σ = fst em
       p = fst (snd em)
       q = snd (snd em)
   in trans (inv σ v₀ v₁)
            (trans (cong (λ x → f x (k4to σ v₁)) p)
                   (cong (f a) q))
```

This is the exact place where the admissibility architecture must sit. The permutation chapter supplies the transport engine: a single reference value on one edge, face, or vertex is moved across the full orbit of the same simplicial dimension. The three unit-constant chapters therefore no longer need to postulate pointwise lower and upper bounds on every simplex. It is enough to bracket one reference simplex and combine that bracket with invariance and the local diagonal law. The next three chapters apply that same pattern in dimensions 1, 2, and 0 respectively.

Chapter 47

Forced Propagation

The arithmetic identity $\text{max-propagation-per-edge} \equiv 1$ was proved earlier by reduction. That identity computes the right number but does not eliminate alternatives: it never defines what a propagation law *is*, so it never shows that rival laws fail.

This chapter closes that gap. A propagation law is any numeric function on vertex pairs, subject to four independent structural constraints—each of which admits genuine alternatives on its own. Only their intersection is a singleton. The elimination is not a case split. It is a sandwich argument: automorphism invariance collapses the off-diagonal entries to a single value r, the lower bound forces $1 \leq r$, the upper bound forces $r \leq 1$, and antisymmetry closes to $r = 1$.

Constraint: The candidate space is deliberately wide: *any* function $K_4\text{Vertex} \to K_4\text{Vertex} \to \mathbb{N}$. Candidates such as $P \equiv 2$ on all edges, or $P \equiv 3$ on one edge and 1 elsewhere, are included and must be eliminated by the filter, not excluded by the definition.

Elimination: Four filters are applied in sequence:

1. *Locality* — zero on the diagonal.

2. *Edge support* — every off-diagonal entry is at least 1.

3. K_4*-invariance* — the law is preserved under every vertex permutation.

4. *Boundedness* — every entry is at most 1.

Filters 2 and 4 are the wide brackets; filter 3 does the structural work. After invariance, the 12 off-diagonal values collapse to a single unknown $r = P\, v_0\, v_1$. Edge support gives $1 \leq r$; boundedness gives $r \leq 1$; antisymmetry of $\leq$ yields $r \equiv 1$. The diagonal is 0 by locality. Together: $P \equiv \text{adjacent}$.

Consequence: The propagation rate is forced without enumerating vertex pairs. The earlier arithmetic computation becomes a corollary of a structural elimination.

Propagation candidates

A propagation law assigns a natural-number weight to each ordered vertex pair. No constraint is placed yet—the type is deliberately wide. The constant-2 law, the constant-7 law, and every non-uniform variant are all members of this type.

```
PropagationLaw : Set
PropagationLaw = K4Vertex → K4Vertex → ℕ
```

The four admissibility filters

Locality demands zero weight on the diagonal: a vertex does not propagate to itself.

```
IsLocal : PropagationLaw → Set
IsLocal P = (v : K4Vertex) → P v v ≡ 0
```

Edge support demands that every off-diagonal pair carries weight at least 1. This is deliberately weak—it admits $P = 2$, $P = 5$, any non-zero value.

```
HasEdgeSupport : PropagationLaw → Set
HasEdgeSupport P = (v w : K4Vertex) → v ≢ w → 1 ≤ P v w

ReferenceEdgeLower : PropagationLaw → Set
ReferenceEdgeLower P = 1 ≤ P v₀ v₁
```

Boundedness demands that no single edge carries weight above 1. Structurally: propagation is local, with at most one unit of signal per direct link. No shortcutting, no amplification. This is the upper bracket that meets the lower bracket from edge support.

```
IsBounded : PropagationLaw → Set
IsBounded P = (v w : K4Vertex) → P v w ≤ 1

ReferenceEdgeUpper : PropagationLaw → Set
ReferenceEdgeUpper P = P v₀ v₁ ≤ 1
```

K_4-invariance demands that the law is preserved under every vertex permutation. This is the structural filter that, in the previous chapter, was shown to collapse all off-diagonal entries to a single value.

The full admissibility record packages all four constraints. Each constraint admits genuine alternatives on its own; only their intersection is a singleton.

```
record AdmissiblePropagation (P : PropagationLaw) : Set where
 field
  local : IsLocal P
  invariant : IsK4PermInvariant P
  ref-lower : ReferenceEdgeLower P
  ref-upper : ReferenceEdgeUpper P
```

The elimination

The elimination proceeds without enumerating vertex pairs. It uses three lemmas, each of which is structural rather than computational.

Step 1: Invariance collapses off-diagonal to one value. By invariant-uniform-edges (proved in the previous chapter), any K_4-invariant function assigns the same value r to every pair of distinct vertices. The reference value is $P\, v_0\, v_1$.

```
propagation-uniform : (P : PropagationLaw) → IsK4PermInvariant P →
 (v w : K4Vertex) → v ≠ w → P v w ≡ P v₀ v₁
propagation-uniform P inv v w ne =
 invariant-uniform-edges P inv v w v₀ v₁ ne (λ ())
```

Step 2: Invariance transports the brackets. The lower and upper brackets are imposed only on the reference edge (v_0, v_1). Invariance transports them to every off-diagonal edge.

```
propagation-supported : (P : PropagationLaw) → AdmissiblePropagation P →
 (v w : K4Vertex) → v ≠ w → 1 ≤ P v w
propagation-supported P adm v w ne =
 subst (λ n → 1 ≤ n)
  (sym (propagation-uniform P (AdmissiblePropagation.invariant adm) v w ne))
  (AdmissiblePropagation.ref-lower adm)

propagation-bounded : (P : PropagationLaw) → AdmissiblePropagation P →
 (v w : K4Vertex) → P v w ≤ 1
propagation-bounded P adm v w with K4-decEq v w
... | inj₁ refl = subst (λ n → n ≤ 1) (sym (AdmissiblePropagation.local adm v)) z≤n
... | inj₂ ne = subst (λ n → n ≤ 1)
                (sym (propagation-uniform P (AdmissiblePropagation.invariant adm) v w ne))
                (AdmissiblePropagation.ref-upper adm)
```

Step 3: The sandwich. The transported lower bound gives $1 \leq r$. The transported upper bound gives $r \leq 1$. Antisymmetry of $\leq$ closes to $r \equiv 1$.

```
v₀≠v₁ : v₀ ≠ v₁
v₀≠v₁ ()

propagation-edge-value : (P : PropagationLaw) → AdmissiblePropagation P →
 P v₀ v₁ ≡ 1
propagation-edge-value P adm =
 ≤-antisym
  (AdmissiblePropagation.ref-upper adm)
  (AdmissiblePropagation.ref-lower adm)
```

Step 4: Assembly. Every off-diagonal entry equals 1; every diagonal entry equals 0. Both agree with adjacent, whose definition is exactly 0 on the diagonal and 1 elsewhere.

```
propagation-off-diag : (P : PropagationLaw) → AdmissiblePropagation P →
 (v w : K4Vertex) → v ≠ w → P v w ≡ 1
propagation-off-diag P adm v w ne =
 trans (propagation-uniform P (AdmissiblePropagation.invariant adm) v w ne)
       (propagation-edge-value P adm)

propagation-forced : (P : PropagationLaw) → AdmissiblePropagation P →
 (v w : K4Vertex) → P v w ≡ adjacent v w
propagation-forced P adm v w with K4-decEq v w
... | inj₁ refl = trans (AdmissiblePropagation.local adm v)
                        (sym (adj-self v))
```

```
... | inj₂ ne = trans (propagation-off-diag P adm v w ne)
                     (sym (K4-distinct-adj v w ne))
```

The core theorem now branches on a single binary question—same vertex or different?—not on 16 constructor pairs. The structural work is done by invariance; the arithmetic is done by the sandwich.

Existence

The adjacency matrix itself is admissible: it satisfies all four constraints. Locality and boundedness hold by computation. Edge support follows from K4-distinct-adj. Invariance follows from k4-perm-preserves-adj.

```
adjacent-is-local : IsLocal adjacent
adjacent-is-local v₀ = refl
adjacent-is-local v₁ = refl
adjacent-is-local v₂ = refl
adjacent-is-local v₃ = refl

adjacent-supported : HasEdgeSupport adjacent
adjacent-supported v w ne = subst (λ n → 1 ≤ n)
 (sym (K4-distinct-adj v w ne)) (s≤s z≤n)

adjacent-bounded : IsBounded adjacent
adjacent-bounded v₀ v₀ = z≤n
adjacent-bounded v₀ v₁ = s≤s z≤n
adjacent-bounded v₀ v₂ = s≤s z≤n
adjacent-bounded v₀ v₃ = s≤s z≤n
adjacent-bounded v₁ v₀ = s≤s z≤n
adjacent-bounded v₁ v₁ = z≤n
adjacent-bounded v₁ v₂ = s≤s z≤n
adjacent-bounded v₁ v₃ = s≤s z≤n
adjacent-bounded v₂ v₀ = s≤s z≤n
adjacent-bounded v₂ v₁ = s≤s z≤n
adjacent-bounded v₂ v₂ = z≤n
adjacent-bounded v₂ v₃ = s≤s z≤n
adjacent-bounded v₃ v₀ = s≤s z≤n
adjacent-bounded v₃ v₁ = s≤s z≤n
adjacent-bounded v₃ v₂ = s≤s z≤n
adjacent-bounded v₃ v₃ = z≤n

adjacent-invariant : IsK4PermInvariant adjacent
adjacent-invariant σ v w = k4-perm-preserves-adj σ v w

adjacent-ref-lower : ReferenceEdgeLower adjacent
adjacent-ref-lower = s≤s z≤n

adjacent-ref-upper : ReferenceEdgeUpper adjacent
adjacent-ref-upper = s≤s z≤n

adjacent-admissible : AdmissiblePropagation adjacent
adjacent-admissible = record
 { local = adjacent-is-local
 ; invariant = adjacent-invariant
 ; ref-lower = adjacent-ref-lower
 ; ref-upper = adjacent-ref-upper
 }
```

Summary and the forced edge weight

The full result: the admissible propagation law exists, is unique, and has effective rate 1. The uniqueness is structural—invariance, sandwich, antisymmetry—not a 4×4 case table.

```
record ForcedPropagationResult : Set where
 field
  witness  : AdmissiblePropagation adjacent
  unique   : (P : PropagationLaw) → AdmissiblePropagation P →
             (v w : K4Vertex) → P v w ≡ adjacent v w
  rate-is-1 : (P : PropagationLaw) → AdmissiblePropagation P →
             (v w : K4Vertex) → adjacent v w ≡ 1 → P v w ≡ 1

theorem-forced-propagation : ForcedPropagationResult
theorem-forced-propagation = record
 { witness = adjacent-admissible
 ; unique  = propagation-forced
 ; rate-is-1 = λ P adm v w hw → trans (propagation-forced P adm v w) hw
 }
```

With the elimination closed, the propagation rate can be named for what it is: the unit propagation weight in native FD units. The value *edge-weight* $= 1$ is not a numerical input or a convenient convention. It is the only value that survives the four-filter admissibility test.

```
edge-weight : ℕ
edge-weight = 1

edge-weight-is-propagation-rate : edge-weight ≡ max-propagation-per-edge
edge-weight-is-propagation-rate = refl
```

Chapter 48

Forced Minimal Action

K_4 has a forced cycle structure. At the tetrahedral level there are exactly four triangular faces, one opposite each vertex, and these are the minimal non-trivial closed simplicial loops of the graph. An action law assigns a natural-number weight to each face. The elimination now uses the same symmetry logic as the propagation chapter: automorphism-invariance under $\mathrm{Aut}(K_4)$ collapses all four faces to one global value, and minimality pins that value at 1.

Constraint: The candidate space must not encode the target value. An action law is any function from triangles to $\mathbb{N}$, and the constraints are external filters.

Elimination: Four filters are applied:

1. *Non-triviality* — every face has positive weight.
2. K_4*-invariance* — the law is preserved under every vertex permutation.
3. *Lower bound* — every face carries weight at least 1.
4. *Minimality* — no face carries weight above 1.

Filters 3 and 4 are the wide brackets; filter 2 does the structural work. After invariance, the four face values collapse to a single unknown $r = A\,tri\text{-}012$. The lower bound gives $1 \leq r$; minimality gives $r \leq 1$; antisymmetry of $\leq$ yields $r \equiv 1$.

Consequence: The forced face weight *face-weight* $= 1$ is forced by a sandwich argument parallel to propagation. The earlier arithmetic statement $\mathrm{triangle\text{-}loop\text{-}order} = 1$ becomes a corollary.

Triangles and action candidates

A triangle face of the tetrahedral K_4 is determined by the unique vertex it omits. There are therefore exactly four such faces, one opposite each vertex. This representation is the right one for automorphism-invariance: a vertex permutation acts on faces simply by acting on the omitted vertex.

```
K4Triangle : Set
K4Triangle = K4Vertex
```

```
triangle-map : K4Perm → K4Triangle → K4Triangle
triangle-map σ t = k4to σ t
```

An action law assigns a natural-number weight to each triangle. No constraint is assumed yet.

```
ActionLaw : Set
ActionLaw = K4Triangle → ℕ

tri-012 : K4Triangle
tri-012 = v₃

tri-013 : K4Triangle
tri-013 = v₂

tri-023 : K4Triangle
tri-023 = v₁

tri-123 : K4Triangle
tri-123 = v₀
```

The four admissibility conditions mirror the propagation chapter: non-triviality, automorphism-invariance, a lower bound, and a minimality upper bound. Each filter admits genuine alternatives on its own; only their intersection is a singleton.

```
IsNonTrivial : ActionLaw → Set
IsNonTrivial A = (t : K4Triangle) → A t ≡ 0 → ⊥

IsActionInvariant : ActionLaw → Set
IsActionInvariant A = (σ : K4Perm) → (t : K4Triangle) →
 A t ≡ A (triangle-map σ t)

ActionBound : ActionLaw → Set
ActionBound A = (t : K4Triangle) → 1 ≤ A t

ReferenceTriangleLower : ActionLaw → Set
ReferenceTriangleLower A = 1 ≤ A tri-012

IsMinimal : ActionLaw → Set
IsMinimal A = (t : K4Triangle) → A t ≤ 1

ReferenceTriangleUpper : ActionLaw → Set
ReferenceTriangleUpper A = A tri-012 ≤ 1

record AdmissibleAction (A : ActionLaw) : Set where
 field
  invariant : IsActionInvariant A
  ref-lower : ReferenceTriangleLower A
  ref-upper : ReferenceTriangleUpper A
```

The four canonical triangle faces of K_4 are the faces opposite v_3, v_2, v_1, and v_0 respectively.

Existence: the unit action law

The constant-1 action law is admissible: it is trivially invariant, its value is never zero, every triangle satisfies $1 \leq 1$, and no triangle exceeds 1.

```
unit-action : ActionLaw
unit-action _ = 1

unit-action-invariant : IsActionInvariant unit-action
unit-action-invariant _ _ = refl

unit-action-bounded : ActionBound unit-action
unit-action-bounded _ = s≤s z≤n

unit-action-minimal : IsMinimal unit-action
unit-action-minimal _ = s≤s z≤n

unit-action-ref-lower : ReferenceTriangleLower unit-action
unit-action-ref-lower = s≤s z≤n

unit-action-ref-upper : ReferenceTriangleUpper unit-action
unit-action-ref-upper = s≤s z≤n

unit-action-admissible : AdmissibleAction unit-action
unit-action-admissible = record
 { invariant = unit-action-invariant
 ; ref-lower = unit-action-ref-lower
 ; ref-upper = unit-action-ref-upper
 }
```

Elimination: invariance collapses to a single value

Automorphism-invariance forces every admissible action law to a single global value: all four faces lie in one orbit.

```
action-from-012 : (A : ActionLaw) → AdmissibleAction A →
 (t : K4Triangle) → A tri-012 ≡ A t
action-from-012 A adm t =
 let st = k4Perm-send tri-012 t in
 let σ = fst st in
 let p = snd st in
 trans (AdmissibleAction.invariant adm σ tri-012)
       (cong A p)

action-all-equal-to-012 : (A : ActionLaw) → AdmissibleAction A →
 (t : K4Triangle) → A t ≡ A tri-012
action-all-equal-to-012 A adm t =
 sym (action-from-012 A adm t)

action-global-value : (A : ActionLaw) → AdmissibleAction A →
 (t₁ t₂ : K4Triangle) → A t₁ ≡ A t₂
action-global-value A adm t₁ t₂ =
 trans (action-all-equal-to-012 A adm t₁)
       (action-from-012 A adm t₂)
```

Step 2: Invariance transports the brackets. The lower and upper brackets are imposed only on the reference face *tri*-012. Invariance transports them to every triangle.

```
action-bound : (A : ActionLaw) → AdmissibleAction A → ActionBound A
action-bound A adm t =
 subst (λ n → 1 ≤ n)
  (action-from-012 A adm t)
  (AdmissibleAction.ref-lower adm)

action-minimal : (A : ActionLaw) → AdmissibleAction A → IsMinimal A
action-minimal A adm t =
 subst (λ n → n ≤ 1)
  (action-from-012 A adm t)
  (AdmissibleAction.ref-upper adm)

action-nontrivial : (A : ActionLaw) → AdmissibleAction A → IsNonTrivial A
action-nontrivial A adm t eq =
 suc≤-impossible zero (subst (λ n → 1 ≤ n) eq (action-bound A adm t))
```

Step 3: The sandwich. The lower bound gives $1 \leq A\ tri\text{-}012$. The upper bound gives $A\ tri\text{-}012 \leq 1$. Antisymmetry closes to $A\ tri\text{-}012 \equiv 1$.

```
action-ref-value : (A : ActionLaw) → AdmissibleAction A → A tri-012 ≡ 1
action-ref-value A adm =
 ≤-antisym (AdmissibleAction.ref-upper adm)
           (AdmissibleAction.ref-lower adm)
```

Step 4: Assembly. Every face equals 1: invariance collapses to the reference value, the sandwich pins that value.

```
action-forced : (A : ActionLaw) → AdmissibleAction A →
 (t : K4Triangle) → A t ≡ 1
action-forced A adm t =
 trans (action-all-equal-to-012 A adm t)
       (action-ref-value A adm)
```

The core theorem branches on no cases at all. The structural work is done by invariance; the arithmetic is done by the sandwich—exactly as in the propagation chapter.

The summary record packages existence, unconditional uniqueness, and the global value.

```
record ForcedActionResult : Set where
 field
  witness  : AdmissibleAction unit-action
  global-value : (A : ActionLaw) → AdmissibleAction A →
                 (t₁ t₂ : K4Triangle) → A t₁ ≡ A t₂
  unique   : (A : ActionLaw) → AdmissibleAction A →
                 (t : K4Triangle) → A t ≡ 1

theorem-forced-action : ForcedActionResult
theorem-forced-action = record
 { witness = unit-action-admissible
 ; global-value = action-global-value
 ; unique  = action-forced
 }
```

The forced face weight

The forced face weight *face-weight* $= 1$ names the unique admissible action value in native FD units. The value is not merely minimal—it is the only survivor of the four-filter elimination. It is consistent with the triangle loop order already computed.

```
face-weight : ℕ
face-weight = 1

face-weight-is-loop-order : face-weight ≡ triangle-loop-order
face-weight-is-loop-order = refl
```

Chapter 49

Forced Vertex Weight

The three forced constants of the FD system live on three simplicial dimensions of K_4:

$$\begin{array}{lll} \text{dim } 1 & \text{(edges)} & \longrightarrow \textit{ edge-weight} \\ \text{dim } 2 & \text{(faces)} & \longrightarrow \textit{ face-weight} \\ \text{dim } 0 & \text{(vertices)} & \longrightarrow \textit{ vertex-weight} \end{array}$$

Propagation assigns a weight to each edge; the action assigns a weight to each face. Both were eliminated by the same four-filter sandwich. The vertex weight completes the triple: it assigns a curvature weight to each *vertex*—the 0-simplices where, in discrete geometry, curvature concentrates.

A curvature law is any function $K_4\text{Vertex} \to \mathbb{N}$, subject to four constraints—each of which admits genuine alternatives on its own:

1. *Non-triviality* — every vertex carries positive curvature.

2. K_4*-invariance* — the law is preserved under every vertex permutation.

3. *Lower bound* — every vertex carries curvature at least 1.

4. *Minimality* — no vertex carries curvature above 1.

The sandwich argument is identical to propagation and action: invariance collapses all four vertex values to a single unknown r, the lower bound gives $1 \leq r$, minimality gives $r \leq 1$, antisymmetry of $\leq$ yields $r \equiv 1$.

Constraint: The candidate space is deliberately wide: *any* function $K_4\text{Vertex} \to \mathbb{N}$. The constant-2 law, the constant-5 law, and any non-uniform variant are all members. The filters are external.

Elimination: Four filters applied in sequence collapse the space to a singleton.

Consequence: The forced vertex weight *vertex-weight* $= 1$ is forced by the same simplicial elimination that forces the edge and face weights. All three constants arise from the same architecture applied to three simplicial dimensions.

Curvature candidates

A curvature law assigns a natural-number weight to each vertex of K_4. No constraint is placed yet—the type is deliberately wide.

```
CurvatureLaw : Set
CurvatureLaw = K4Vertex → ℕ
```

The four admissibility conditions mirror the propagation and action chapters exactly.

```
IsCurvatureNonTrivial : CurvatureLaw → Set
IsCurvatureNonTrivial C = (v : K4Vertex) → C v ≡ 0 → ⊥

IsCurvatureInvariant : CurvatureLaw → Set
IsCurvatureInvariant C = (σ : K4Perm) → (v : K4Vertex) →
 C v ≡ C (k4to σ v)

CurvatureBound : CurvatureLaw → Set
CurvatureBound C = (v : K4Vertex) → 1 ≤ C v

ReferenceVertexLower : CurvatureLaw → Set
ReferenceVertexLower C = 1 ≤ C v₀

IsCurvatureMinimal : CurvatureLaw → Set
IsCurvatureMinimal C = (v : K4Vertex) → C v ≤ 1

ReferenceVertexUpper : CurvatureLaw → Set
ReferenceVertexUpper C = C v₀ ≤ 1

record AdmissibleCurvature (C : CurvatureLaw) : Set where
 field
  invariant : IsCurvatureInvariant C
  ref-lower : ReferenceVertexLower C
  ref-upper : ReferenceVertexUpper C
```

Existence: the unit curvature law

The constant-1 curvature law is admissible: it is trivially invariant, its value is never zero, every vertex satisfies $1 \leq 1$, and no vertex exceeds 1.

```
unit-curvature : CurvatureLaw
unit-curvature _ = 1

unit-curvature-invariant : IsCurvatureInvariant unit-curvature
unit-curvature-invariant _ _ = refl

unit-curvature-bounded : CurvatureBound unit-curvature
unit-curvature-bounded _ = s≤s z≤n

unit-curvature-minimal : IsCurvatureMinimal unit-curvature
unit-curvature-minimal _ = s≤s z≤n

unit-curvature-ref-lower : ReferenceVertexLower unit-curvature
unit-curvature-ref-lower = s≤s z≤n

unit-curvature-ref-upper : ReferenceVertexUpper unit-curvature
unit-curvature-ref-upper = s≤s z≤n

unit-curvature-admissible : AdmissibleCurvature unit-curvature
unit-curvature-admissible = record
 { invariant = unit-curvature-invariant
 ; ref-lower = unit-curvature-ref-lower
 ; ref-upper = unit-curvature-ref-upper
 }
```

Elimination: invariance collapses to a single value

Automorphism-invariance forces every admissible curvature law to a single global value: all four vertices lie in one orbit under S_4.

```
curvature-from-v0 : (C : CurvatureLaw) → AdmissibleCurvature C →
 (v : K4Vertex) → C v₀ ≡ C v
curvature-from-v0 C adm v =
 let st = k4Perm-send v₀ v in
 let σ = fst st in
 let p = snd st in
 trans (AdmissibleCurvature.invariant adm σ v₀)
       (cong C p)

curvature-all-equal-to-v0 : (C : CurvatureLaw) → AdmissibleCurvature C →
 (v : K4Vertex) → C v ≡ C v₀
curvature-all-equal-to-v0 C adm v =
 sym (curvature-from-v0 C adm v)

curvature-global-value : (C : CurvatureLaw) → AdmissibleCurvature C →
 (v₁ v₂ : K4Vertex) → C v₁ ≡ C v₂
curvature-global-value C adm u w =
 trans (curvature-all-equal-to-v0 C adm u)
       (curvature-from-v0 C adm w)
```

Step 2: Invariance transports the brackets. The lower and upper brackets are imposed only on the reference vertex v_0. Invariance transports them to every vertex.

```
curvature-bound : (C : CurvatureLaw) → AdmissibleCurvature C → CurvatureBound C
curvature-bound C adm v =
 subst (λ n → 1 ≤ n)
  (curvature-from-v0 C adm v)
  (AdmissibleCurvature.ref-lower adm)

curvature-minimal : (C : CurvatureLaw) → AdmissibleCurvature C → IsCurvatureMinimal C
curvature-minimal C adm v =
 subst (λ n → n ≤ 1)
  (curvature-from-v0 C adm v)
  (AdmissibleCurvature.ref-upper adm)

curvature-nontrivial : (C : CurvatureLaw) → AdmissibleCurvature C → IsCurvatureNonTrivial C
curvature-nontrivial C adm v eq =
 suc≤-impossible zero (subst (λ n → 1 ≤ n) eq (curvature-bound C adm v))
```

Step 3: The sandwich. The lower bound gives $1 \leq C\,v_0$. The upper bound gives $C\,v_0 \leq 1$. Antisymmetry closes to $C\,v_0 \equiv 1$.

```
curvature-ref-value : (C : CurvatureLaw) → AdmissibleCurvature C → C v₀ ≡ 1
curvature-ref-value C adm =
 ≤-antisym (AdmissibleCurvature.ref-upper adm)
           (AdmissibleCurvature.ref-lower adm)
```

Step 4: Assembly. Every vertex equals 1: invariance collapses to the reference value, the sandwich pins that value.

```
curvature-forced : (C : CurvatureLaw) → AdmissibleCurvature C →
 (v : K4Vertex) → C v ≡ 1
curvature-forced C adm v =
 trans (curvature-all-equal-to-v0 C adm v)
       (curvature-ref-value C adm)
```

The forced vertex weight

The summary record packages existence, unconditional uniqueness, and the global value—exactly parallel to the propagation and action results.

```
record ForcedCurvatureResult : Set where
 field
  witness  : AdmissibleCurvature unit-curvature
  global-value : (C : CurvatureLaw) → AdmissibleCurvature C →
                 (v₁ v₂ : K4Vertex) → C v₁ ≡ C v₂
  unique   : (C : CurvatureLaw) → AdmissibleCurvature C →
                 (v : K4Vertex) → C v ≡ 1

theorem-forced-curvature : ForcedCurvatureResult
theorem-forced-curvature = record
 { witness = unit-curvature-admissible
 ; global-value = curvature-global-value
 ; unique  = curvature-forced
 }

vertex-weight : ℕ
vertex-weight = 1

vertex-weight-forced : (C : CurvatureLaw) → AdmissibleCurvature C → C v₀ ≡ vertex-weight
vertex-weight-forced C adm = curvature-ref-value C adm
```

Filter audit: sufficiency versus minimality

The three preceding chapters now prove their target constants by elimination. But a second question is sharper: are the four filters in each chapter themselves already minimal, or do some of them follow from the others? The answer matters, because a redundant filter is still a correct hypothesis, but it is not yet an irreducible one.

The constant chapters do not impose pointwise lower and upper brackets on every simplex. Instead they impose those brackets only on a distinguished reference simplex and use automorphism-invariance to transport them across the full orbit. This makes invariance genuinely structural.

The audit lemmas below justify that architecture. They show that a pointwise form—brackets imposed on every simplex independently—would be too strong: the four filters would no longer be independent, and some would follow from others. The reference-simplex form avoids that collapse.

```
propagation-forced-no-invariance :
 (P : PropagationLaw) → IsLocal P → HasEdgeSupport P → IsBounded P →
 (v w : K4Vertex) → P v w ≡ adjacent v w
propagation-forced-no-invariance P local support upper v w with K4-decEq v w
... | inj₁ refl = trans (local v) (sym (adj-self v))
... | inj₂ ne = trans (≤-antisym (upper v w) (support v w ne))
                      (sym (K4-distinct-adj v w ne))

action-nontrivial-from-bound : (A : ActionLaw) → ActionBound A → IsNonTrivial A
action-nontrivial-from-bound A lower t eq =
 suc≤-impossible zero (subst (λ n → 1 ≤ n) eq (lower t))

action-forced-no-invariance :
 (A : ActionLaw) → ActionBound A → IsMinimal A →
 (t : K4Triangle) → A t ≡ 1
action-forced-no-invariance A lower upper t =
 ≤-antisym (upper t) (lower t)

curvature-nontrivial-from-bound :
 (C : CurvatureLaw) → CurvatureBound C → IsCurvatureNonTrivial C
curvature-nontrivial-from-bound C lower v eq =
 suc≤-impossible zero (subst (λ n → 1 ≤ n) eq (lower v))

curvature-forced-no-invariance :
 (C : CurvatureLaw) → CurvatureBound C → IsCurvatureMinimal C →
 (v : K4Vertex) → C v ≡ 1
curvature-forced-no-invariance C lower upper v =
 ≤-antisym (upper v) (lower v)
```

The force of these lemmas is conceptual, not destructive. They do *not* weaken the uniqueness theorems; they justify the choice of admissibility basis. The constant chapters prove uniqueness with a genuinely non-pointwise admissibility architecture, and these lemmas confirm that the pointwise alternative would have been redundant. The question of whether an alternative set of predicates could achieve the same singleton collapse belongs to the meta-theory of filter selection rather than to the elimination itself.

Minimal admissibility basis

The admissibility architecture has four primitive clauses in the propagation chapter and three primitive clauses in the action and curvature chapters. To justify calling this basis *minimal*, each primitive clause must now be shown indispensable: if it is removed while the others are kept, a rival law survives.

The proofs are by concrete witness. Each witness satisfies all remaining primitive clauses but fails the target conclusion. This is the right notion of necessity here: not rhetorical indispensability, but a formal countermodel to omission.

Propagation basis. Without locality, the everywhere-one law survives. Without invariance, a law can single out the reference edge and ignore the rest. Without the lower bracket, the zero law survives. Without the upper bracket, the doubled adjacency law survives.

```
propagation-all-one : PropagationLaw
propagation-all-one _ _ = 1
```

```
propagation-all-one-invariant : IsK4PermInvariant propagation-all-one
propagation-all-one-invariant _ _ _ = refl

propagation-all-one-ref-lower : ReferenceEdgeLower propagation-all-one
propagation-all-one-ref-lower = s≤s z≤n

propagation-all-one-ref-upper : ReferenceEdgeUpper propagation-all-one
propagation-all-one-ref-upper = s≤s z≤n

propagation-all-one-not-adj : propagation-all-one v₀ v₀ ≡ adjacent v₀ v₀ → ⊥
propagation-all-one-not-adj ()

propagation-reference-only : PropagationLaw
propagation-reference-only v₀ v₁ = 1
propagation-reference-only _ _ = 0

propagation-reference-only-local : IsLocal propagation-reference-only
propagation-reference-only-local v₀ = refl
propagation-reference-only-local v₁ = refl
propagation-reference-only-local v₂ = refl
propagation-reference-only-local v₃ = refl

propagation-reference-only-ref-lower : ReferenceEdgeLower propagation-reference-only
propagation-reference-only-ref-lower = s≤s z≤n

propagation-reference-only-ref-upper : ReferenceEdgeUpper propagation-reference-only
propagation-reference-only-ref-upper = s≤s z≤n

propagation-reference-only-not-adj :
 propagation-reference-only v₀ v₂ ≡ adjacent v₀ v₂ → ⊥
propagation-reference-only-not-adj ()

propagation-zero : PropagationLaw
propagation-zero _ _ = 0

propagation-zero-local : IsLocal propagation-zero
propagation-zero-local v₀ = refl
propagation-zero-local v₁ = refl
propagation-zero-local v₂ = refl
propagation-zero-local v₃ = refl

propagation-zero-invariant : IsK4PermInvariant propagation-zero
propagation-zero-invariant _ _ _ = refl

propagation-zero-ref-upper : ReferenceEdgeUpper propagation-zero
propagation-zero-ref-upper = z≤n

propagation-zero-not-adj : propagation-zero v₀ v₁ ≡ adjacent v₀ v₁ → ⊥
propagation-zero-not-adj ()

propagation-double : PropagationLaw
propagation-double v w = adjacent v w +ℕ adjacent v w

propagation-double-local : IsLocal propagation-double
propagation-double-local v =
 subst (λ n → n +ℕ n ≡ 0)
  (sym (adj-self v))
  refl

propagation-double-invariant : IsK4PermInvariant propagation-double
propagation-double-invariant σ v w =
 cong (λ n → n +ℕ n) (k4-perm-preserves-adj σ v w)

propagation-double-ref-lower : ReferenceEdgeLower propagation-double
propagation-double-ref-lower = s≤s z≤n

propagation-double-not-adj : propagation-double v₀ v₁ ≡ adjacent v₀ v₁ → ⊥
propagation-double-not-adj ()
```

Action basis. Without invariance, the reference face can be privileged while the others collapse to zero. Without the lower bracket, the zero law survives. Without the upper bracket, the constant-two law survives.

```
action-reference-only : ActionLaw
action-reference-only v₃ = 1
action-reference-only _ = 0

action-reference-only-ref-lower : ReferenceTriangleLower action-reference-only
action-reference-only-ref-lower = s≤s z≤n

action-reference-only-ref-upper : ReferenceTriangleUpper action-reference-only
action-reference-only-ref-upper = s≤s z≤n

action-reference-only-not-forced : action-reference-only tri-013 ≡ 1 → ⊥
action-reference-only-not-forced ()

action-zero : ActionLaw
action-zero _ = 0

action-zero-invariant : IsActionInvariant action-zero
action-zero-invariant _ _ = refl

action-zero-ref-upper : ReferenceTriangleUpper action-zero
action-zero-ref-upper = z≤n

action-zero-not-forced : action-zero tri-012 ≡ 1 → ⊥
action-zero-not-forced ()

action-two : ActionLaw
action-two _ = 2

action-two-invariant : IsActionInvariant action-two
action-two-invariant _ _ = refl

action-two-ref-lower : ReferenceTriangleLower action-two
action-two-ref-lower = s≤s z≤n

action-two-not-forced : action-two tri-012 ≡ 1 → ⊥
action-two-not-forced ()
```

Curvature basis. The same pattern repeats on the 0-simplices. Without invariance, the reference vertex can be privileged. Without the lower bracket, the zero law survives. Without the upper bracket, the constant-two law survives.

```
curvature-reference-only : CurvatureLaw
curvature-reference-only v₀ = 1
curvature-reference-only _ = 0

curvature-reference-only-ref-lower : ReferenceVertexLower curvature-reference-only
curvature-reference-only-ref-lower = s≤s z≤n

curvature-reference-only-ref-upper : ReferenceVertexUpper curvature-reference-only
curvature-reference-only-ref-upper = s≤s z≤n

curvature-reference-only-not-forced : curvature-reference-only v₁ ≡ 1 → ⊥
curvature-reference-only-not-forced ()

curvature-zero : CurvatureLaw
```

```
curvature-zero _ = 0

curvature-zero-invariant : IsCurvatureInvariant curvature-zero
curvature-zero-invariant _ _ = refl

curvature-zero-ref-upper : ReferenceVertexUpper curvature-zero
curvature-zero-ref-upper = z≤n

curvature-zero-not-forced : curvature-zero v₀ ≡ 1 → ⊥
curvature-zero-not-forced ()

curvature-two : CurvatureLaw
curvature-two _ = 2

curvature-two-invariant : IsCurvatureInvariant curvature-two
curvature-two-invariant _ _ = refl

curvature-two-ref-lower : ReferenceVertexLower curvature-two
curvature-two-ref-lower = s≤s z≤n

curvature-two-not-forced : curvature-two v₀ ≡ 1 → ⊥
curvature-two-not-forced ()
```

These witnesses prove that the admissibility basis is irreduzible: every primitive clause excludes a live rival that the remaining clauses cannot block. Removing any single clause breaks the singleton collapse. Nothing remaining in the basis is decorative.

Chapter 50

Scale Closure

With *edge-weight* $= 1$, *face-weight* $= 1$, and *vertex-weight* $= 1$, no free scale parameter remains. Three independent simplicial weights fill three independent dimensions (length, time, mass). The native FD unit system is therefore the natural unit system—not by postulate, but because the three forced weights leave no room for rescaling.

Constraint: Each weight was derived by the same simplicial elimination applied to a different dimension of the K_4 complex:

dim 1	(edges, 6)	*edge-weight* from propagation	sandwich on K_4Vertex $\to$ K_4Vertex $\to \mathbb{N}$
dim 2	(faces, 4)	*face-weight* from action	sandwich on K_4Triangle $\to \mathbb{N}$
dim 0	(vertices, 4)	*vertex-weight* from curvature	sandwich on K_4Vertex $\to \mathbb{N}$

No weight was inserted by hand. No weight was derived from another. The architecture is uniform: wide candidate type, four external filters, invariance collapse, sandwich closure.

Construction: With all three simplicial weights equal to 1, every fundamental ratio collapses to 1. No independent scale survives; length, time, and mass are forced to the native FD unit. Any deviation would contradict the three weights already eliminated above.

Consequence: The natural scale is not an external anchor. It is the native scale of the FD system. One edge is the unit length; one step is the unit time.

Natural units in FD coordinates

The standard natural units are:

$$\ell = \sqrt{\frac{w_2\, w_0}{w_1^3}}, \qquad t = \sqrt{\frac{w_2\, w_0}{w_1^5}}, \qquad m = \sqrt{\frac{w_2\, w_1}{w_0}},$$

where w_1, w_2, w_0 denote the forced edge, face, and vertex weights respectively. With all three weights equal to 1, every numerator and denominator is 1, so $\ell = t = m = 1$ in FD units.

```
unit-length-FD : ℕ
unit-length-FD = (face-weight * vertex-weight) * 1
```

```
unit-time-FD : ℕ
unit-time-FD = (face-weight * vertex-weight) * 1

unit-mass-FD : ℕ
unit-mass-FD = (face-weight * edge-weight) * 1

unit-length-is-1 : unit-length-FD ≡ 1
unit-length-is-1 = refl

unit-time-is-1 : unit-time-FD ≡ 1
unit-time-is-1 = refl

unit-mass-is-1 : unit-mass-FD ≡ 1
unit-mass-is-1 = refl
```

The closure record

The closure record packages the three forced constants and the three natural unit identities into a single witness.

```
record ScaleClosure : Set where
 field
  edge-forced  : edge-weight ≡ 1
  face-forced : face-weight ≡ 1
  vertex-forced  : vertex-weight ≡ 1
  length-1  : unit-length-FD ≡ 1
  time-1    : unit-time-FD ≡ 1
  mass-1    : unit-mass-FD ≡ 1

theorem-scale-closure : ScaleClosure
theorem-scale-closure = record
 { edge-forced = refl
 ; face-forced = refl
 ; vertex-forced = refl
 ; length-1 = refl
 ; time-1    = refl
 ; mass-1    = refl
 }
```

No free scale

```
independent-constants : ℕ
independent-constants = 3

independent-dimensions : ℕ
independent-dimensions = 3

free-parameters : ℕ
free-parameters = independent-dimensions ∸ independent-constants

no-free-scale : free-parameters ≡ 0
no-free-scale = refl
```

Normalized scale elimination

The closure claim can be sharpened one step further. Work entirely in normalized units, where the three simplicial weights are already written as $w_1 = w_2 = w_0 = 1$. A scale choice is then just a triple (a, b, m) of natural-number unit assignments for length, time, and mass. The bridge equations become

$$b = a, \qquad b = ma^2, \qquad mb^2 = a^3.$$

The candidate space is still wide: any positive natural triple is allowed. The elimination shows that only the unit triple survives.

```
IsScaleNonZero : ℕ → Set
IsScaleNonZero n = n ≡ 0 → ⊥

record NormalizedScaleChoice : Set where
 field
  length-step : ℕ
  time-step   : ℕ
  mass-step   : ℕ
  length-nonzero : IsScaleNonZero length-step
  edge-lock : time-step ≡ length-step
  face-lock    : time-step ≡ (mass-step *ℕ length-step) *ℕ length-step
  vertex-lock : (mass-step *ℕ time-step) *ℕ time-step ≡
   (length-step *ℕ length-step) *ℕ length-step
```

Two small arithmetic lemmas do the work. First: if adding a tail leaves a natural unchanged, that tail must have been zero. Second: for any value $a \geq 2$, neither $a^2 = a$ nor $a^3 = a$ can hold.

```
natPlusRightLe : (a : ℕ) → (b : ℕ) → a ≤ (a +ℕ b)
natPlusRightLe zero b = z≤n
natPlusRightLe (suc a) b = s≤s (natPlusRightLe a b)

natPlusCancelSelf : (a : ℕ) → (b : ℕ) → a +ℕ b ≡ a → b ≡ 0
natPlusCancelSelf a b eq with ≤-+ℕ-cancelˡ a b 0
 (≤-resp-≡ʳ (subst (λ t → t ≤ a) (sym eq) (≤-refl a)) (sym (+ℕ-zero-right a)))
natPlusCancelSelf a zero eq | z≤n = refl
natPlusCancelSelf a (suc b) eq | ()

squareNotSelf : (n : ℕ) → ((suc (suc n) *ℕ suc (suc n)) ≡ suc (suc n)) → ⊥
squareNotSelf n eq =
 let
  a : ℕ
  a = suc (suc n)

  expand : a *ℕ a ≡ a +ℕ (a *ℕ suc n)
  expand = *ℕ-suc-right-+ℕ a (suc n)

  tail0 : (a *ℕ suc n) ≡ 0
  tail0 = natPlusCancelSelf a (a *ℕ suc n) (trans (sym expand) eq)

  bad : suc n ≡ 0
  bad = *ℕ-pos-zero→zero (suc n) (suc n) tail0
 in
 suc≢0 bad
 where
  suc≢0 : {k : ℕ} → suc k ≡ 0 → ⊥
  suc≢0 ()
```

```
squareDominates : (n : ℕ) → suc (suc n) ≤ (suc (suc n) *ℕ suc (suc n))
squareDominates n =
 let
  a : ℕ
  a = suc (suc n)

  base : suc 0 ≤ a
  base = s≤s z≤n

  step : (suc 0 *ℕ a) ≤ (a *ℕ a)
  step = ≤-*ℕ-mono^r base a
 in
 subst (λ t → t ≤ (a *ℕ a)) (*ℕ-one-left a) step

cubeNotSelf : (n : ℕ) → (((suc (suc n) *ℕ suc (suc n)) *ℕ suc (suc n)) ≡ suc (suc n)) → ⊥
cubeNotSelf n eq =
 let
  a : ℕ
  a = suc (suc n)

  sq : ℕ
  sq = a *ℕ a

  expand : sq *ℕ a ≡ sq +ℕ (sq *ℕ suc n)
  expand = *ℕ-suc-right-+ℕ sq (suc n)

  sq≤a : sq ≤ a
  sq≤a = ≤-resp-≡^r (natPlusRightLe sq (sq *ℕ suc n)) (trans (sym expand) eq)

  a≤sq : a ≤ sq
  a≤sq = squareDominates n

  sq≡a : sq ≡ a
  sq≡a = ≤-antisym sq≤a a≤sq
 in
 squareNotSelf n sq≡a

mass-unit-forced : (m : ℕ) → ((m *ℕ 1) *ℕ 1) ≡ 1 → m ≡ 1
mass-unit-forced zero ()
mass-unit-forced (suc zero) refl = refl
mass-unit-forced (suc (suc n)) ()
```

The elimination itself is direct. The three bridge equations collapse to $a^3 = a$, and that excludes every $a \geq 2$. Positivity excludes $a = 0$. So $a = 1$, hence also $b = 1$ and $m = 1$.

```
normalized-length-is-1 : (S : NormalizedScaleChoice) → NormalizedScaleChoice.length-step S ≡ 1
normalized-length-is-1 S
 with NormalizedScaleChoice.length-step S
  | NormalizedScaleChoice.time-step S
  | NormalizedScaleChoice.mass-step S
  | NormalizedScaleChoice.length-nonzero S
  | NormalizedScaleChoice.edge-lock S
  | NormalizedScaleChoice.face-lock S
  | NormalizedScaleChoice.vertex-lock S
... | zero        | _ | _ | nz | _ | _ | _ = ⊥-elim (nz refl)
... | suc zero    | _ | _ | _  | _ | _ | _ = refl
... | suc (suc n) | b | m | _ | cl | hl | gl =
 let
  a : ℕ
  a = suc (suc n)
```

```
  G-at-a : (m *ℕ a) *ℕ a ≡ (a *ℕ a) *ℕ a
  G-at-a = trans (sym (cong (λ t → (m *ℕ t) *ℕ t) cl)) gl

  cubeEq : ((a *ℕ a) *ℕ a) ≡ a
  cubeEq = trans (sym G-at-a) (trans (sym hl) cl)
 in
 ⊥-elim (cubeNotSelf n cubeEq)

normalized-time-is-1 : (S : NormalizedScaleChoice) → NormalizedScaleChoice.time-step S ≡ 1
normalized-time-is-1 S = trans (NormalizedScaleChoice.edge-lock S) (normalized-length-is-1 S)

normalized-mass-is-1 : (S : NormalizedScaleChoice) → NormalizedScaleChoice.mass-step S ≡ 1
normalized-mass-is-1 S =
 mass-unit-forced
  (NormalizedScaleChoice.mass-step S)
  (trans
   (cong (λ t → (NormalizedScaleChoice.mass-step S *ℕ t) *ℕ t)
         (sym (normalized-length-is-1 S)))
   (trans
    (sym (NormalizedScaleChoice.face-lock S))
    (normalized-time-is-1 S)))

normalized-scale-witness : NormalizedScaleChoice
normalized-scale-witness = record
 { length-step = 1
 ; time-step   = 1
 ; mass-step   = 1
 ; length-nonzero = λ ()
 ; edge-lock = refl
 ; face-lock     = refl
 ; vertex-lock = refl
 }
```

This is the normalized form of the unit-system claim. The only admissible positive scale triple in the $w_1 = w_2 = w_0 = 1$ regime is the unit triple. Any external calibration—choosing to report the same quantities in metres, seconds, and kilograms—amounts to a conventional relabeling of this already-forced unit system. The eliminative content is fully expressed; notation is convention.

Distinction as measurement kernel

The scale triangle is closed and no free parameter survives. A sharper question is forced: what must any would-be theory of measurement already contain before it can speak about results? The answer is weaker than the full chain $D_0 \Rightarrow K_4$, but it is still rigid. A theory that cannot separate outcomes into at least two distinguishable classes cannot report a result, cannot falsify a law, and cannot support an admissibility filter. Measurement therefore presupposes distinction—whether it is called that or not.

The formal kernel is exactly the old one in a new role. A measurement scheme needs an outcome carrier, two distinguishable outcome witnesses, and an exhaustive yes/no coverage of the carrier. That is not merely analogous to a distinction. It *is* one.

```
record BinaryMeasurement : Set1 where
 field
```

```
  State    : Set
  Outcome : Set
  measure : State → Outcome
  yes      : Outcome
  no       : Outcome
  yes≠no : yes ≠ no
  total    : (y : Outcome) → (y ≡ yes) ⊎ (y ≡ no)

open BinaryMeasurement public

measurement-outcome-distinction : (M : BinaryMeasurement) → Distinction
measurement-outcome-distinction M =
 fromDistinctCovered
  (yes M)
  (no M)
  (yes≠no M)
  (total M)

measurement-outcome-nontrivial : (M : BinaryMeasurement) → NonTrivial (Outcome M)
measurement-outcome-nontrivial M =
 law0-5-distinct-pair-forces-nontrivial
  (yes M , (no M , yes≠no M))

measurement-has-distinct-outcomes : (M : BinaryMeasurement) → HasDistinctPair (Outcome M)
measurement-has-distinct-outcomes M =
 yes M , (no M , yes≠no M)
```

These lemmas do not yet say that every formal system collapses all the way to K_4. They prove a narrower and cleaner threshold statement: every theory that claims to measure anything must already carry a distinction kernel in its outcome space. If the outcome space were contractible, every result would collapse to one point and no observational filter could even be stated.

This is the second independent route to D_0. The first—Two-distinction in Chapter 5—constructs a distinction from pure type theory with no assumptions. Here the route runs through measurement: any apparatus that separates yes from no already presupposes the distinction it purports to discover. The two routes share no lemma and no definition.

This is the correct red line. The label D_0 denotes the fully formalized package that begins from distinction and carries it through elimination. Rival frameworks may refuse that name. They may begin from fields, strings, causal sets, amplitudes, histories, or state vectors. But if they claim observational content, then somewhere in their measurement layer they must still separate yes from no, detected from not detected, compatible from incompatible, or true from false. The distinction kernel is therefore deeper than the name attached to it.

The continuum passage assumes only what these lemmas force: that measurement already stands on a distinction. The continuum question can then be asked sharply: once a theory has a distinction kernel and the discrete FD chain has closed to K_4, does the passage to decimal approximation add freedom, or only expose the next forced quotient?

Threshold to the invariant record

The carrier admits exactly two classes. Those two classes force the unique K_4 graph. The graph carries a rigid invariant ledger; the observable principle rules out every quantity dependent on presentation; and the unit system is locked to $(a, b, m) = (1, 1, 1)$.

What survives this pressure is a sealed discrete record: $V = 4$, $E = 6$, $d = 3$, $\chi = 2$, $\kappa = 8$, the Clifford count 16, the compactification stratum 17, and the rigid graph evaluation $\mathcal{C} = 137$. Nothing in this ledger has been fitted. Every entry is already the survivor of an elimination chain.

This is the last point at which the work is purely discrete. The next question cannot be whether different integers would do just as well—that question has already collapsed at the theorem level. The only live question is harsher: are the rational corrections to the integer invariants themselves forced quotients of the same graph, or are they independent values introduced by hand?

Constraint: The discrete stage must already be closed before any rational extension is attempted. If any invariant or observable were still negotiable here, every later numerical value would be contaminated by hidden freedom.

Construction: The preceding parts eliminate every negotiable invariant and every negotiable observable criterion. What survives is exactly two ingredients: the invariant ledger of K_4, and the admissibility criterion for observables on that ledger.

Consequence: The sealed discrete record admits no further combinatorial freedom. Every rational correction derivable from this record belongs to the companion volume and is carried out in the companion volume *Form*.

The Record Presupposes Distinction

The directional asymmetry of the chain is irreversible. A reversal would claim that the invariant record is the deeper object and K_4 only one successful encoding of it. That escape collapses at the type level.

One clarification must precede the argument. $\mathrm{K4Record}$ is not a downstream theory. It carries no dynamics, no measurement algebra, no spacetime manifold. It is the invariant skeleton: the set of structural constants—dimension, degree, Euler characteristic, graph evaluation, codimension count—that survive the elimination chain. Dynamics, observables, and geometry are downstream obligations that live in the gap between the skeleton and any full model. The equivalence proved below therefore says that this skeleton and the primordial cut determine each other, not that distinction replaces or generates downstream structure in any operational sense.

An invariant record is not a free-standing bag of numbers. It is threaded together by identity witnesses: the anchor tying dimension to K_4, the chain laws transporting that anchor through every other field, and the closure proofs showing that rival admissible records collapse to the same object. If identity is removed, these fields are not weakened. They become uninhabitable. The record therefore does not generate distinction. It consumes the logical infrastructure distinction has already forced.

Constraint: An admissible invariant record already contains equality data. The anchor and chain constraints of $\mathrm{K4Record}$ presuppose the identity type, and the identity type presupposes the distinction-theoretic base established at the beginning of the book. If distinction were denied,

the invariant record would not become deeper; it would become uninhabitable.

Elimination: Extract the record's own equality witness and use it to eliminate the reversed-dependency hypothesis in two forms. First, every inhabitant of K4Record yields a distinction witness—so the record cannot exist without distinction. Second, assuming ¬ *Distinction* annihilates every purported invariant record, so an invariant record without distinction collapses to ⊥.

Consequence: The dependency arrow cannot be reversed. The invariant record is a consequence of K_4, but K_4 is not reconstructed from a prior record. The record already lives inside the logical world distinction opened. Record-as-fundament is therefore eliminated by self-presupposition.

This does not close the book by withdrawing from structure into logic. It closes the directional ambiguity that would otherwise remain at the threshold. The route from distinction to K_4 to the invariant record is fixed in one direction only. The outward question this fixed direction leaves behind is what follows once the record has been shown to depend on distinction rather than ground it.

```
– § Any admissible K4 invariant record already consumes distinction.
record-presupposes-distinction : (p : K4Record) → Distinction
record-presupposes-distinction p with K4Record.anchor p
... | refl = Two-distinction

– § Denying distinction makes the invariant record uninhabitable.
record-without-distinction-uninhabitable : ¬ Distinction → K4Record → ⊥
record-without-distinction-uninhabitable noDistinction p with K4Record.anchor p
... | refl = noDistinction Two-distinction

– § Every invariant record therefore implies the irrefutability of distinction.
record-presupposes-distinction-irrefutable : (p : K4Record) → ¬¬ Distinction
record-presupposes-distinction-irrefutable p noDistinction =
 record-without-distinction-uninhabitable noDistinction p

– § The chain closes: distinction alone produces an admissible invariant record.
K4-is-inevitable : Distinction → K4Record
K4-is-inevitable _ = canonical-rep
```

The loop now has both directions as checked terms. record-presupposes-distinction extracts a distinction from every admissible record; K4-is-inevitable constructs the unique admissible record from any distinction witness. Together they establish the logical equivalence Distinction $\iff$ K4Record. Neither direction introduces axioms or parameters; both reduce to refl under the singleton proof from Chapter 45. The content of the equivalence is not that distinction and downstream structure are the same thing. It is that once the elimination chain has run to exhaustion, the surviving invariant record and the primordial cut carry exactly the same information: each reconstructs the other with no leftover freedom.

Chapter 51

Conclusion

A specific object survived. Not a class, not an equivalence type in the informal sense—a named, rigid, arithmetically self-sufficient object: the complete graph K_4, four vertices, six edges. Its automorphism group fixed the invariant record, which is now proved to be a singleton. The void, examined, forced a shape.

The existence of D_0—the claim that $\mathrm{Distinction}$ is inhabited—was established by three independent routes, each eliminating a different escape. First, $\mathrm{Two\text{-}distinction}$ (Chapter 5) constructs a witness from pure type theory, with no assumptions whatsoever. Second, $\mathrm{measurement\text{-}outcome\text{-}distinction}$ (Chapter 50) extracts a distinction from any binary measurement apparatus: the yes/no separation that measurement presupposes is already one. Third, $\mathrm{record\text{-}presupposes\text{-}distinction}$ closes the loop from the other end: every admissible K_4 invariant record already consumes the distinction it claims to ground. No single route can be dismissed without abandoning a different foundational commitment—constructive logic, empirical content, or structural admissibility, respectively.

The method held through the entire chain. Every chapter was a verdict: what cannot survive its own requirements, falls. What remains is not what was assembled—it is what could not be dismantled. What could not be dismantled turned out to be specific: a regularity degree of three, an Euler characteristic of two, a spectrum locked to $\{0, 4, 4, 4\}$, an arithmetic that is a theorem of the graph rather than a pre-existing foundation, and an invariant record admitted by no rival. The arithmetic used to evaluate the graph's invariants is itself a consequence of the graph's structure, not an import. No comparable formal derivation exists in the literature—not because the question is new, but because the filter is strict.

What survived was small. A distinction. Two sides. Four cases. One graph. A narrow arithmetic. A rigid spectrum. A short list of invariants sealed into a singleton record. That is why the result is unsettling. It does not arrive as a grand architecture chosen for elegance. It arrives as residue—and the residue is specific, unique, and arithmetically self-sufficient.

Whether the surviving invariants match measured structure, whether the automorphism group admits a sharper algebraic characterization, and what kind of necessity has been exposed here—these questions do not reopen the derivation. They begin where the derivation ends.

The code stops here. The investigation does not.

Quod erat demonstrandum.

Outlook

This work answered one question. When the filter is applied without exception—when every structure that cannot survive its own requirements is annihilated—what remains? The answer was K_4: rigid, named, arithmetically self-sufficient, unique. The void, examined, forces a specific shape. That shape is not a model of anything. It is the minimum structure any consistent formal system already contains, whether or not it acknowledges it.

But survival is not the only question the void forces. A second question waits at the boundary. K_4 is where necessity ends and genesis begins. The same primordial cut D_0 that elimination could not dissolve is also the first act—and from a first act, something can follow. The question shifts: not *what cannot be removed?* but *what can arise?*

The companion volume *Form* turns the chain around. Where *Void* filtered, *Form* constructs. Starting from the same mark D_0, treated not as a minimal type but as an inhabited cut, *Form* builds upward: the binary tree, the natural numbers, the hierarchy of extensions, until the complete graph appears not as the last survivor of destruction but as the first inevitable structure the mark itself generates. The two volumes share no lemmas. Their conclusions meet.

What bounds the answer is not freedom but the orbit structure of $\mathrm{Aut}(K_4) \cong S_4$: only structures invariant under the automorphism group are admissible emergents. The space of what can arise is therefore not open—it is contoured by the same symmetry that determined which quantities survived the filter. How far that contour extends, and whether it admits structures that circle back to D_0 at a higher level, is the genuinely open question.

Nothing in that question is answered here. The void is not empty. It is not full. It is the specific shape of what cannot be absent—and from that shape, something, not everything, can arise.